



**UNIFIED
DEVELOPMENT
CONTROL AND
PROMOTION
REGULATIONS
FOR
MAHARASHTRA
STATE**

(Updated as on 30th January, 2025)

**Applicable to all Planning Authorities and Regional Plan Areas
except Municipal Corporation of Greater Mumbai, Other Planning Authorities /
Special Planning Authorities / Development Authorities within the limit of
Municipal Corporation of Greater Mumbai, MIDC, NAINA, Jawaharlal Nehru Port Trust,
Hill Station Municipal Councils, Eco-sensitive / Eco-fragile region notified by MoEF & CC
and Lonavala Municipal Council, in Maharashtra.**

**GOVERNMENT OF MAHARASHTRA
URBAN DEVELOPMENT DEPARTMENT**

1. These Unified Development Control and Promotion Regulations are sanctioned by the State Government under Section 37(1AA)(c) and Section 20(4) of the Maharashtra Regional & Town Planning Act, 1966 vide Notification No.TPS-1818/C.R.236/18/DP&RP/Sec.37(1AA)(c) & Sec.20(4)/UD-13, Dated 02nd December, 2020.
2. These Unified Development Control and Promotion Regulations are published by the State Government under Section 20(3) of the Maharashtra Regional & Town Planning Act, 1966 vide Notice No.TPS-1818/C.R.236/18/ Sec.20(3)/UD-13, Dated 02nd December, 2020.
3. Directives under Section 154 of the Maharashtra Regional & Town Planning Act, 1966 issued by the State Government vide Resolution No.TPS-1818/C.R.236/18/Sec.20(3)/UD-13, Dated 02nd December, 2020.
4. These Unified Development Control and Promotion Regulations are published by the State Government under Section 37(1AA) of the Maharashtra Regional & Town Planning Act, 1966 vide Notification No.TPS-1818/C.R.236/18/ Sec.37(1AA)/UD-13, Dated 02nd December, 2020.
5. Directives under Section 154 of the Maharashtra Regional & Town Planning Act, 1966 issued by the State Government vide Resolution No.TPS-1818/C.R.236/18/Sec.37(1AA)/UD-13, Dated 02nd December, 2020.
6. *Corrigendum under section 37(1AA)(c) & 20(4) of the Maharashtra Regional & Town Planning Act, 1966 issued by the State Government vide Resolution No.TPS-1818/C.R.236/18/D.P. and R.P./Sec.37(1AA)(c)/Sec.20(4)/Corrigendum/UD-13, Dated 9th December, 2020.*
7. *Notification under Regulation No.1.10 of the Unified Development control and Promotion Regulations issued by the State Government vide Resolution No.TPS-1818/C.R.236/18/Sec.37(1AA) & Sec.20(3)(Part 1)/Addendum/UD-13, Dated 14th January, 2021.*
8. *Government Order No.TPS-1818/C.R.236/18/(Part 1)/UD-13, Dated 1st March, 2021.*
9. *Notification under Section 37(1AA)(c) & 20(4) of the Maharashtra Regional & Town Planning Act, 1966 issued by the State Government vide Resolution No.TPS-1818/C.R.236/18(Part3)/Sec.37(1AA)(c) & Sec.20(4)/Modification/UD-13, Dated 16th June, 2021.*
10. *Notification under Regulation No.1.10 of the Unified Development control and Promotion Regulations issued by the State Government vide Resolution No.TPS-1818/C.R.236/18(Part1)/Addendum/UD-13, Dated 23rd June, 2021.*
11. *Government Order No.TPS-1818/C.R.236/18(Part1)/UD-13, Dated 26th July, 2021.*
12. *State Government Resolution No.TPS-1818/C.R.236/18(Part1)/Addendum/UD-13, Dated 8th October, 2021.*
13. *Addendum under Regulation No.1.10 of Unified Development Control and Promotion Regulations issued by State Government vide Addendum No.TPS-1821/575/C.R.121/21/Addendum/UD-13, Dated 27th October, 2021.*
14. *Guidelines issued by the State Government vide Order No.TPS-1818/C.R.236/18(Part-1)/UD-13, Dated 02nd December 2021.*
15. *Notification under Section 37(1AA)(c) & 20(4) of the Maharashtra Regional & Town Planning Act, 1966 issued by the State Government vide Resolution No.TPS-1818/C.R.236/18(Part-3)/Sec.37(1AA)(c) & Sec.20 (4)/Modification/UD-13, Dated 02nd December, 2021.*
16. *Corrigendum / Addendum under Regulation No.1.10 of Unified Development Control and Promotion Regulations issued by State Government vide Corrigendum / Addendum No.TPS-1820/614/C.R.79/2021/UD-13, Dated 02nd December, 2021.*
17. *Corrigendum / Addendum under Regulation No.1.10 of Unified Development Control and Promotion Regulations issued by the State Government vide Corrigendum / Addendum No.TPS-1821/575/C.R.121/21/UD-13, Dated 02nd December, 2021.*


 (Kishor Gokhale)
 Under Secretary
 Government of Maharashtra




 (N. R. Shende)
 Director of Town Planning and Joint Secretary
 Government of Maharashtra

18. Notice under Section 20(3) of the Maharashtra Regional & Town Planning Act, 1966 issued by the State Government vide Resolution No.TPS-1216/3196/C.R.421/16/UD-12, Dated 21st December, 2021 & Directives under Section 154 of the Maharashtra Regional & Town Planning Act, 1966 issued by the State Government vide Resolution Dated 21st December, 2021
19. Notification under Section 20(4) of the Maharashtra Regional & Town Planning Act, 1966 issued by the State Government vide Resolution No.TPS-1919/436/C.R.83/19/Sec.20(4)/UD-13, Dated 23rd December, 2021.
20. Notification under Section 37(1AA)(c) & Section 20(4) of the Maharashtra Regional & Town Planning Act, 1966 issued by the State Government vide Resolution No.TPS-1818/C.R.236/18(Part-3)/Section 37(1AA)(c) & Section 20(4)/Modification/UD-13, Dated 3rd February, 2022.
21. Order issued by Director of Town Planning under Note below Regulation No.4.2 vide No.URC/1939, Dated 7th April, 2022.
22. Notice under Section 37(1) & Section 20(3) with Directives under Section 154 of the Maharashtra Regional & Town Planning Act, 1966 issued by the State Government vide Resolution No.TPS-1822/C.R.04/2022/UD-13, Dated 2nd June, 2022.
23. Directives under Section 154 of the Maharashtra Regional & Town Planning Act, 1966 issued by the State Government vide Resolution No.TPS-1222/1089/C.R.70/22/UD-12, Dated 27th June, 2022.
24. Notification under Section 37(1AA)(c) & Section 20(4) of the Maharashtra Regional & Town Planning Act, 1966 issued by the State Government vide Resolution No.TPS-1818/950/C.R.158/19/Sec.37(1AA)(c) & Sec.20(4)/UD-13, Dated 10th October, 2022.
25. Notification under Section 37(1AA)(c) of the Maharashtra Regional & Town Planning Act, 1966 issued by the State Government vide Resolution No.TPS-1818/C.R.236/18/Section 37(1AA)(C)/UD-13(Part-6), Dated 12th October, 2022.
26. Notification under Section 37(2) of the Maharashtra Regional & Town Planning Act, 1966 issued by the State Government vide Resolution No.TPS-1818/C.R.236/18(Part-5)/Section 37(2)/UD-13, Dated 16th December, 2022.
27. Directives under Section 154 of the Maharashtra Regional & Town Planning Act, 1966 issued by the State Government vide Resolution No.TPS-1818/C.R.236/18(Part-5)/UD-13, Dated 16th December, 2022.
28. Notification under Section 37(1AA)(c) & Section 20(4) of the Maharashtra Regional & Town Planning Act, 1966 issued by the State Government vide Resolution No.TPS-1818/C.R.236/18(Part-4)/Sec.37(1AA)(c) & Section 20(4)/Modification/UD-13, Dated 28th December, 2022.
29. Corrigendum for Notification Dated 28th December, 2022 vide Government Resolution No.TPS-1818/C.R.236/18 (Part-4)/Sec.37(1AA)(c) & Sec.20(4)/Modification/UD-13, Dated 11th January, 2023.
30. Corrigendum for Notification Dt.28th December, 2022 vide Government Resolution No.TPS-1818/C.R.236/18 (Part-4)/Sec.37(1AA)(c) & Sec.20(4)/Corrigendum/UD-13, Dated 12th January, 2023.
31. Directives under Section 154 of the Maharashtra Regional & Town Planning Act, 1966 issued by the State Government vide Resolution No.TPS-1823/CR.07/2023/UD-13, Dated 27th February, 2023 regarding Class – 2 lands.
32. Order issued by Director of Town Planning under Note below Regulation No.4.2 vide No. परिपत्रक क्र.1/२०२३/नासंघ/4274, Dated 25th August, 2023.
33. Directives under Section 154 of the Maharashtra Regional & Town Planning Act, 1966 issued by the State Government vide Resolution No.TPS-1822/1818/C.R.179/2022/UD-13, Dated 25th August, 2023 regarding inclusion of Addendum to Model Building Bye-Laws – 2016.
34. Notification under Section 37(1AA)(c) & Section 20(4) of the Maharashtra Regional & Town Planning Act, 1966 issued by the State Government vide Resolution No.TPS-1818/C.R.236/18(Part-3)/Section 37(1AA)(c) & Section 20(4)/Modification/UD-13, Dated 27th October, 2023.
35. Notification under Section 37(2) of the Maharashtra Regional & Town Planning Act, 1966 issued by the State Government vide Resolution No.TPS-1822/251/C.R.09/2023/UD-13, Dated 05th December, 2023.
36. Notification under Section 37(1AA)(c) & Section 20(4) of the Maharashtra Regional & Town Planning Act, 1966 issued by the State Government vide Resolution No.TPS-1823/UOR-54/CR.97/2023/UD-13, Dated 12th January, 2024.
37. Directives under Section 154 of the Maharashtra Regional & Town Planning Act, 1966 issued by the State Government vide Resolution No.TPS-1823/VIP-53/C.R.94/2023/Directives/UD-13, Dated 01st March, 2024 regarding applicability of UDCPR to Ratnagiri District.
38. Revised Addendum No.TPS-1823/VIP-53/C.R.94/2023/UD-13, Dated 01st March, 2024 issued by the State Government to Addendum No.TPS-1818/C.R.236/18/Sec.37(1AA) & Sec.20(3)(Part-1)/Addendum/UD-13, Dated 14th January, 2021.
39. Notification under Section 37(1AA)(c) of the Maharashtra Regional & Town Planning Act, 1966 issued by the State Government vide Resolution No.TPS-1219/2172/C.R.110/19/UD-12, Dated 15th March, 2024.

40. Notice under Section 37(1AA)(a) with Directives under Section 154 of the Maharashtra Regional & Town Planning Act, 1966 issued by the State Government vide Resolution No.TPS-1824/1075/C.R.87/2024/UD-13, Dated 23rd July, 2024 regarding Regulation No.3.8.2(b).
41. Notification under Section 37(1AA)(c) & Section 20(4) of the Maharashtra Regional & Town Planning Act, 1966 issued by the State Government vide Resolution No.TPS-1824/225/C.R.96/2024/UD-13, Dated 05th September, 2024 regarding Regulation No.11.2.5.
42. Notification under Section 37(1AA)(c) & Section 20(4) of the Maharashtra Regional & Town Planning Act, 1966 issued by the State Government vide Resolution No.TPS-1821/452/C.R.105/2022/(Part-2)/UD-13, Dated 05th September, 2024 regarding ITP Policy.
43. Order issued by Director of Town Planning under Note below Regulation No.4.2 vide No.Order No.1/Equivalency of Zones/2024/TPV-7/4946, Dated 10th September, 2024.
44. Notice under Section 37(1AA)(a) & Section 20(3) alongwith Directives under Section 154 of the Maharashtra Regional & Town Planning Act, 1966 issued by the State Government vide Resolution No.TPS-1824/UOR-31/2024/C.R.100/2024/UD-13, Dated 25th September, 2024 regarding Regulation No.6.10.1.
45. Notification under Section 37(1AA)(c) of the Maharashtra Regional & Town Planning Act, 1966 issued by the State Government vide Resolution No.TPS-1224/1175/C.R.53/24/Sec.37(1AA)(c)/UD-12, Dated 04th October, 2024 regarding Regulations No.10.3, 10.4, 11.2.
46. Notification under Section 37(1AA)(c) of the Maharashtra Regional & Town Planning Act, 1966 issued by the State Government vide Resolution No.TPS-1224/1018/C.R.15/24/UD-12, Dated 07th October, 2024 regarding New Regulation No.10.16.
47. Notice under Section 37(1AA)(a) & Section 20(3) alongwith Directives under Section 154 of the Maharashtra Regional & Town Planning Act, 1966 issued by the State Government vide Resolution No.TPS-1824/UOR-38/C.R.118/2024/UD-13, Dated 07th October, 2024 regarding Regulation No.7.6.
48. Notification under Section 37(1AA)(c) of the Maharashtra Regional & Town Planning Act, 1966 issued by the State Government vide Resolution No.TPB-4322/10/C.R.45/2022/UD-11, Dated 10th October, 2024 regarding New Regulation No.13.6.
49. Corrigendum issued by the State Government vide Resolution No.TPS-1824/1264/C.R.116/2024/UD-13, Dated 11th October, 2024 regarding Regulation No.11.2.5.
50. Order No.TPS-1824/1264/C.R.116/2024/(Part-2)/Order/UD-13, Dated 11th October, 2024 under clause (c) - RoD in Notification under Section 37(2) of the Maharashtra Regional & Town Planning Act, 1966 issued by the State Government vide Resolution No.TPS-1822/251/C.R.09/2023/UD-13, Dated 05th December, 2023 regarding Regulation No.14.6.
51. Notice under Section 37(1AA)(a) alongwith Directives under Section 154 of the Maharashtra Regional & Town Planning Act, 1966 issued by the State Government vide Resolution No.TPS-1824/1264/C.R.116/2024/UD-13, Dated 11th October, 2024 regarding Regulation No.14.6.16(2).
52. Notice under Section 37(1AA)(a) & Section 20(3) alongwith Directives under Section 154 of the Maharashtra Regional & Town Planning Act, 1966 issued by the State Government vide Resolution No.TPS-1824/1159/C.R.94/2024/UD-13, Dated 11th October, 2024 regarding Regulation No.2.2.14.
53. Notification under Section 37(1AA)(c) & Section 20(4) of the Maharashtra Regional & Town Planning Act, 1966 issued by the State Government vide Resolution No.TPS-1823/C.R.35/2023/UD-13, Dated 27th November, 2024 regarding New Regulation No.6.15.

-*_**_*-*

INDEX		
Regulation No.	Particulars	Page No.
	CHAPTER - 1 ADMINISTRATION	
1.0	Short Title, Extent and Commencement	1
1.1 *	Extent and Jurisdiction	1
1.2	Commencement of Regulations	1
1.3 * #	Definitions	1
1.4	Applicability of Regulations	16
1.5 **	Saving	17
1.6	Applicability of Other Regulations	18
1.7 *	Power to Prescribe the Proformas	19
1.8	Power to Decide Charges	19
1.9	Meanings as in Acts, Rules & Interpretations	19
1.10	Removal of Difficulties	20
	CHAPTER - 2 DEVELOPMENT PERMISSION AND COMMENCEMENT CERTIFICATE	
2.1	Permission from the Planning Authority is Mandatory	21
	2.1.1 Necessity of Obtaining Permission	21
	2.1.2 *** Permission Not Necessary	21
	2.1.3 Development Undertaken on Behalf of Government	22
	2.1.4 Operational Constructions	22
	2.1.5 Constructions not Covered Under the Operational Constructions	23
	2.1.6 Temporary Constructions	23
	2.1.7 Repairs to Building	24
2.2	Procedure for Obtaining Development Permission / Building Permission / Commencement Certificate	24
	2.2.1 Notice / Application	24
	2.2.2 Information Accompanying Notice / Application	24
	2.2.3 * # Ownership Title and Area	24
	2.2.4 Key Plan or Location Plan	25
	2.2.5 (a) Sub-division Layout Plan	25
	2.2.5 (b) Amalgamation Plan	26
	2.2.6 Site Plan	26
	2.2.7 Building Plan	26
	2.2.8 # Building Plans for Special Buildings	27
	2.2.9 Service Plan	28
	2.2.10 Supervision	28
	2.2.11 # Clearance From Other Departments	28
	2.2.12 # Building / Layout Permission Scrutiny Fee	29
	2.2.13 * # Development Charges	29

	2.2.14 * #	Premium Charges and Fire Infrastructure Charges.	30
	2.2.15	Structural Stability Certificate	31
	2.2.16	Signing the Plan	31
	2.2.17	Size of Drawing Sheets	31
	2.2.18	Colouring Notations for Plans	32
	2.2.19	Qualification and Competence of the Architect / Licensed Engineer / Structural Engineer / Town Planner / Supervisor	32
2.3 #		Discretionary Powers - Interpretation	33
2.4		Discretionary Powers - Relaxations in Specific Cases	33
2.5 #		Drafting Error	34
2.6		Grant or Refusal of Permission	34
	2.6.1	General	34
	2.6.2	Deemed Permission	34
	2.6.3	Approval of building permission on Risk Based Classification	35
	2.6.4	Display of Sanctioned Permissions on Authority's Web-Site.	35
2.7		Commencement of Work	35
	2.7.1 * #	Commencement	35
	2.7.2	Development of Land Subdivision / Group Housing Schemes	35
2.8		Procedure During Construction	36
	2.8.1	Owner / Developer / Architect / Town Planner / Engineer / Structural Engineer / Supervisor or any licensed technical person's Responsibilities in Their Respective Domain.	36
	2.8.2	Results of Test	36
	2.8.3 *	Display Board	36
	2.8.4	Plinth Checking	37
	2.8.5	Deviation during Construction	37
2.9		Completion Certificate	37
2.10		Occupancy Certificate	37
2.11		Part Occupancy Certificate	37
2.12		Inspection	38
2.13		Unsafe Buildings	38
2.14 *		Offences and Penalties	38
2.15		Revocation of Permission	38
		CHAPTER - 3	
		GENERAL LAND DEVELOPMENT REQUIREMENTS	
3.1		Requirements of Site	39
	3.1.1	Site Not Eligible For Construction of Building	39
	3.1.2 *	Distance of Site From Electric Lines	40
	3.1.3	Construction Within Blue and Red Flood Line	41
	3.1.4	Development Within 30 m. Distance From Railway Boundary	41
	3.1.5	Environmental Clearance	41
	3.1.6 * #	Development Along Highways / Classified Roads.	41
	3.1.7	Development Within Certain Distance from the Prison Premises	41

	3.1.8	Distances from Land Fill Sites	41
	3.1.9	Restrictions in the Vicinity of Airport	41
	3.1.10	Restrictions in the Vicinity of Ancient Monuments	42
	3.1.11	Restriction under the Works of Defense Act, 1903	42
	3.1.12	Distance from Natural Lake and Dam.	42
	3.1.13	Authorities to Supply Complete Information about Restrictions to the Authority	42
3.2		Means of Access	43
3.3		Regulations for Land Sub-division and Layout	43
	3.3.1	Obligation to Prepare Layout	43
	3.3.2	Roads / Streets in Land Sub-division or Layout	43
	3.3.3	Length of Internal Roads, How to be Measured	44
	3.3.4	Co-ordination of Roads in Adjoining Lands	45
	3.3.5	Narrow Roads in Congested Areas (Core area in case of Nashik Municipal Corporation)	45
	3.3.6	Development of Street	45
	3.3.7	Development of Private Street, if neglected	45
	3.3.8 * #	Access from the Highways / Classified Roads	45
	3.3.9 *	Access Provision for Special Buildings of Regulation No.1.3(93)(xiv)	46
	3.3.10	Cul-de-sacs	46
	3.3.11	Handing Over of Layout Roads	46
	3.3.12 #	Intersection of Roads	46
	3.3.13	Acute Angled Junctions	47
	3.3.14	Land-locked Plot	47
	3.3.15	Approach by Underpass or Over Bridge for Adjoining Properties.	47
3.4		Recreational Open Spaces	48
	3.4.1 * #	Recreational Open Space	48
	3.4.2	Recreational Open Space - Owner's Undertaking	49
	3.4.3	Recreational Open Space - Rearrangement	50
	3.4.4	Recreational Open Space - Exclusive	50
	3.4.5	Recreational Open Space in Green Belt	50
	3.4.6	Minimum Dimensions	50
	3.4.7	Structures Permitted in Open Space	50
	3.4.8	Recreational Open Space and Means of Access	51
3.5		Provision for Amenity Space	51
	3.5.1 * #	In the areas of Local Authorities, Special Planning Authorities and Metropolitan Region Authorities	51
	3.5.2	In case of Regional Plan Areas.	52
	3.5.3	Development of Amenity Spaces in Earlier Sanctioned Layout	52
3.6		Provision for Electric Sub-station	52
3.7		Minimum Plot Area for Various Uses	53
3.8 *		Provision for Inclusive Housing	54

3.9	Net Plot Area and Computation of FSI	56
3.10	Transfer of DP Sites (other than DP road) in lieu of FSI	57
3.11	Relocation of DP-RP Sites / Roads	57
3.12	Amalgamation of Plots	58
3.13	Development of Cycle Track Along River and Nallah	58
	3.13.1 For Nashik Municipal Corporation.	58
	3.13.2 For Other Municipal Corporations.	58
	CHAPTER - 4	
	LAND USE CLASSIFICATION AND PERMISSIBLE USES	
4.1	General	59
4.2 * +	Land Use Classification and Equivalency of Zones	59
4.3	Residential Zone - R-1	61
4.4 *	Residential Zone - R-2	63
4.5	Low Density Residential Zone	65
4.6	Future Urbanisable Zone	65
4.7	Commercial Zone	65
4.8	Industrial Zone	65
	4.8.1* Allowing Residential / Commercial Uses in Industrial Zone	66
4.9	Loom Industry cum Residential Zone.	69
4.10	Public / Semi Public Zone	69
4.11 * #	Agricultural Zone	70
4.12 *	Green Belt Zone / River Protection Belt	75
4.13	Traffic and Transportation Zone	76
4.14	Regional Park Zone.	76
4.15	Tourism Development Zone	77
4.16 *	Afforestation Zone	77
4.17	Hill Top - Hill Slope Zone / Hilly Area	77
4.18	Green Zone-2	77
4.19	Forest Zone	77
4.20	Defense Zone	77
4.21	Mines and Quarry Zone	78
4.22	Public Utility Zone	78
4.23	Woodland Corridor	78
4.24	Special Economic Zone.	78
4.25	Airport and Allied Activities / Service Zone.	78
4.26	Additional Uses.	78
4.27 *	Uses Permissible in Development Plan Reservations.	79
	CHAPTER - 5	
	ADDITIONAL PROVISIONS FOR REGIONAL PLAN AREAS	
5.0	General	83
5.1	For all Regional Plan Areas	83
	5.1.1 * Development Permissible Adjacent to Gaathan.	83

	5.1.2	Regulations for Development of Tourist Resorts / Holiday Homes / Township in Hill Stations Type Areas under Hill Station Policy.	84
	5.1.3	Committed Development	84
	5.1.4	Rectification of Draftsman's Error.	84
	5.1.5	Highways notified by State / Central Government.	85
	5.1.6 *	Station Area Development.	85
	5.1.7	Modification Proposals Already Sanctioned.	85
	5.1.8 *	Provision of Amenity Space.	85
	5.1.9	Residential Zone with Payment of Premium	86
5.2	For Thane - Raigad - Palghar Regional Plan.		86
	5.2.1 ***	Development in Tarapur - Boisar Area.	86
5.3	For Ratnagiri - Sindhudurg Regional Plan		87
	5.3.1	Area within Ratnagiri District	87
	5.3.2	Area within Sindhudurg District	87
5.4	For Kolhapur Regional Plan		89
5.5 *	For Satara Regional Plan		90
5.6	For Hingoli, Buldhana, Washim, Yawatmal, Nanded Regional Plan		100
5.7	For Raigad Regional Plan		101
5.8	For Solapur Regional Plan		101
5.9	For Pune Regional Plan		101
5.10	Certain Regulations cease to operate in future.		103
5.11 *	Board of Appeals		103
5.12 *	Aurangabad Regional Plan		103
	CHAPTER - 6		
	GENERAL BUILDING REQUIREMENTS - SETBACK, MARGINAL DISTANCE, HEIGHT AND PERMISSIBLE FSI		
6.0	General		105
6.1	Regulations for Congested Area in Development Plans / Gaothan of Village Settlements in Metropolitan Region Development Authorities and Regional Plans		105
	6.1.1 *	Residential Buildings / Residential Buildings with mixed-use	105
	6.1.2	Other buildings like Public / Semi-Public, Educational, Medical, Institutional, Commercial, Mercantile, etc.	107
	6.1.3	Width of Pathway	107
	6.1.4	Front Setback	107
6.2	Regulations for Outside Congested Area (Non-Congested Area).		107
	6.2.1 *	Marginal Distances and Set-back for Residential Buildings and Mixed Use	107
	6.2.2 #	Other Building.	110
	6.2.3 * #	Marginal Distances for Buildings of Higher Heights	114
	6.2.4	In the cases of layouts of two or more buildings in a plot for any uses	115
	6.2.5	In case of group housing scheme	115

	6.2.6	Building Abutting Two or More Streets	115
6.3 * #		Permissible FSI	115
6.4		Industrial Buildings	119
6.5 *		FSI of Green Belt	119
6.6		Calculation of Built-up area for the Purposes of FSI	120
6.7		Permissible Projections in Marginal Open Spaces / Distances	120
6.8 *		Exclusion of Structures / Projections for FSI Calculation	121
6.9 *		Interior and Exterior chowk	122
6.10 *		Height of Building	122
6.11		Height Exemptions	123
6.12		Requirements in case of Building more than 70 m. Height	123
6.13		FSI of Lands Affected by HEMRL or Other Restrictions	123
6.14		Provision of Recreational Floor	123
6.15		Provision of Hirkani Kaksha (Ladies Room)	124
		CHAPTER - 7	
		HIGHER FSI FOR CERTAIN USES	
7.0		General	125
7.1 *		Higher F.S.I.	126
7.2		Entitlement of FSI for Road Widening or Construction of New Roads / Surrender of Reserved Land	129
7.3		Development / Redevelopment of Staff Quarters of the State Government or its Statutory Bodies or Planning Authority	129
7.4*		Development / Redevelopment of Housing Schemes of Maharashtra Housing and Area Development Authority	131
7.5		Protection of FSI in Redevelopment of Existing Buildings	134
7.6		Redevelopment of Old Dilapidated / Dangerous Buildings	134
	7.6.1*	Redevelopment of Multi-dwelling Buildings of Owner / Owners	135
	7.6.2	Redevelopment of Tenanted Buildings	135
7.7 *		Development of Housing for EWS / LIG	136
7.8		Regulations for Development of Information Technology Establishment	137
	7.8.1	For Municipal Corporation, Area Development Authority and Special Planning Authority area.	137
	7.8.2	For Municipal Council, Nagar Panchayat and Non-Municipal Town Development Plan Area	139
	7.8.3	For Regional Plan Area	139
7.9		Regulation for Development of Biotechnology Parks	140
7.10 *		Incentive for Green Buildings	141
7.11		Development of Public Toilet	142
7.12		Buildings of Smart Fin-Tech Centre	142
7.13		Commercial Building in CBD, Commercial, Residential Zone in Planning Authorities Area.	143

	CHAPTER - 8	
	PARKING, LOADING AND UNLOADING SPACES	
8.1 *	Parking Spaces	145
8.2	Off Street Parking Requirement	146
	8.2.1 * Off Street Parking Requirement	146
	8.2.2 Off Street Parking Requirement for Various Planning Authorities / Areas.	152
	CHAPTER - 9	
	REQUIREMENTS OF PART OF BUILDING	
9.0	Standard Requirement of Various Parts of Buildings	153
9.1	Plinth	153
9.2	Habitable Rooms	153
9.3	Kitchen	154
9.4	Bath Rooms, Water Closets, Combined Bath Room and Water Closet	154
9.5	Ledge or Tand / Loft	154
9.6	Cupboard	155
9.7 *	Mezzanine Floor	155
9.8	Store Room	156
9.9	Garage	156
9.10	Roofs	156
9.11	Basements	157
9.12 *	Ramp	158
9.13 #	Podium	158
9.14	Balcony	159
9.15	Supported Double Height Terraces	159
9.16	Stilt	159
9.17	Chimneys	159
9.18	Letter Box	160
9.19	Meter Room	160
9.20	Lighting and Ventilation of Room	160
9.21	Overhead Tanks	161
9.22	Parapet	161
9.23	Cabin	161
9.24	Wells	161
9.25	Septic Tanks	161
9.26	Boundary / Compound Wall	161
9.27 #	Provision of Lift	162
9.28 * #	Exit Requirements	162
9.29 *	Other Requirements of Individual Exit at Each Floor	165
9.30	Architectural Projections.	169
9.31 *	Additional Requirements in case of Housing Schemes	169
9.32	Fire Protection Requirement	169
9.33	Service Floor	170

	CHAPTER - 10	
	CITY SPECIFIC REGULATIONS	
10.0	General	171
10.1	Pune City Municipal Corporation.	171
10.2 *	Thane Municipal Corporation area.	174
10.3	Nagpur Municipal Corporation	180
10.4 * #	Nagpur Metropolitan Region Development Authority	181
10.5 *	Nashik Municipal Corporation	185
10.6	Vasai-Virar City Municipal Corporation	185
10.7	Mira-Bhayandar Municipal Corporation	186
10.8	Ulhasnagar City Municipal Corporation	186
10.9 *	Kolhapur Municipal Corporation	186
10.10 #	Navi Mumbai Municipal Corporation	192
10.11	National Park and Tungreshwar Eco Sensitive Zone.	198
10.12	Maharashtra Airport Development Company Notified Area.	198
10.13	Bhiwandi Surrounding Notified Area	198
10.14	CIDCO Area Excluding NAINA Area	202
10.14 A	CIDCO Area within Panvel Municipal Corporation	204
10.15 *	Certain Regulations Cease to Operate in Future.	204
10.16	Area Within Panvel Municipal Corporaton	204
	CHAPTER - 11	
	ACQUISITION AND DEVELOPMENT OF RESEVED SITES IN DEVELOPMENT PLANS	
11.0	General	205
11.1 *	Manner of Development of Reserved Site in Development Plan (Accommodation Reservation Principle)	205
11.2	Regulations for Grant of Transferable Development Rights	219
	11.2.1 Transferable Development Rights	219
	11.2.2 Cases Eligible for Transferable Development Rights (TDR)	219
	11.2.3 Cases not Eligible for Transferable Development Rights (TDR)	219
	11.2.4 * Generation of the Transferable Development Rights (TDR)	220
	11.2.5 # Transferable Development Rights (TDR) against Construction of Amenity	221
	11.2.6 Utilisation of Transferable Development Rights (TDR)	223
	11.2.7 * Utilisation of Transferable Development Rights (TDR) and Road Width Relation	223
	11.2.8 Areas Restricted from Utilisation of Transferable Development Rights (TDR)	223
	11.2.9 * General Stipulation	224
	11.2.10 Transfer of DRC	224
	11.2.11 Infrastructure Improvement Charges	225
	11.2.12 Vesting of Land	225
	11.2.13 Effect of this Regulation	225

11.3	Reservation Credit Certificate (RCC)	225
	CHAPTER - 12 STRUCTURAL SAFETY, WATER SUPPLY, DRAINAGE AND SANITARY REQUIREMENTS, OUTDOOR DISPLAY AND OTHER SERVICES.	
12.1	Structural Design	227
12.2	Quality of Materials and Workmanship	227
12.3	Alternative Materials, Methods of Design & Construction and Tests	227
12.4	Building Services	228
12.5 *	Water Supply, Drainage and Sanitary Requirements	228
12.6	Drainage and Sanitation Requirements	230
	12.6.1 General	230
	12.6.2 For Residences	230
	12.6.3 For Buildings other than Residences	230
12.7	Signs and Outdoor Display Structures	237
	CHAPTER - 13 SPECIAL PROVISIONS FOR CERTAIN BUILDINGS	
13.0	General	237
13.1	Provisions for Barrier Free Access	237
	13.1.1 Definitions	237
	13.1.2 Scope	237
	13.1.3 Site Development	237
	13.1.4 Building Requirements	238
13.2	Installation of Solar Assisted Water Heating (SWH) System / Roof Top Photovoltaic (RTPV) System	240
13.3	Rain Water Harvesting	241
13.4	Grey Water Recycling and Reuse	242
13.5	Solid Waste Management	244
	CHAPTER – 14 SPECIAL SCHEMES	
14.1	Integrated Township Project (ITP)	247
	14.1.1 * For Regional Plan Area	247
	14.1.2 For Development Plan Area	247
14.2	Transit Oriented Development (TOD)	265
	14.2.1 # For Pune Municipal Corporation Area	265
	14.2.2 Pune Metropolitan Region Development Authority area.	270
	14.2.3 * For Nagpur Municipal Corporation and Nagpur Metropolitan Region Development Authority.	270
	14.2.4 For Other Municipal Corporations and Other Metropolitan Region Development Authority Area	275
	14.2.5 Regulations for BRT Corridor in Pimpri-Chinchwad Municipal Corporation.	275
14.3 *	Affordable Housing Scheme	276
14.4	Pradhan Mantri Awas Yojana	278

	14.4.1 #	For Development Plan Area.	278
	14.4.2	For Regional Plan Area.	280
14.5		Conservation of Heritage Buildings / Precincts / Natural Features	280
14.6		Slum Rehabilitation Scheme for Pune, PCMC, PCNTDA and Nagpur.	286
14.7 *		Slum Rehabilitation Scheme for Other Municipal Corporations.	318
14.8 * #		Urban Renewal Scheme	333
14.9		Development of Tourism and Hospitality Services under Community Nature Conservancy Around Wild Life Sanctuaries and National Parks.	349
14.10		Integrated Information Technology Township (IITP)	350
14.11		Integrated Logistic Park (ILP)	354
14.12		Industrial Township Under Aerospace and Defense Manufacturing Policy	357
14.13		Development of Integrated Industrial Area	357
		CHAPTER - 15	
		REGULATIONS FOR SPECIAL ACTIVITIES / PLANS	
15.1		Quarrying Operations	359
15.2 ***		Erection of Mobile Towers	360
15.3		Preparation of Local Area Plan	360
15.4 *		Guidelines for Street Design in City / Town.	360
		APPENDICES	
Appendix A-1 *		Form for Construction of Building or Layout of Buildings / Group Housing	363
Appendix A-2 *		Form for Sub-Division of Land as Plotted Layout	372
Appendix B *		Form for Supervision	378
Appendix C * # +		Qualification, Competence, Duties and Responsibilities etc. of Licensed Technical Personnel or Architect for Development Permission and Supervision.	379
Appendix D-1 *		Form for Sanction of Building Permission and Commencement Certificate	387
Appendix D-2		Form for Tentative Approval for Demarcation of Land / Sub-Division Layout	388
Appendix D-3		Form for Final Approval to the Land Sub-Division / Layout	389
Appendix E-1		Form for Refusal of Building Permit / Commencement Certificate	390
Appendix E-2		Form for Refusal of Land Sub-Division / Layout	391
Appendix F		Form for Intimation of Completion of Work up to Plinth Level	392
Appendix G *		Form for Completion Certificate	393
Appendix H		Form for Full / Part Occupancy Certificate	394
Appendix I		Form for Refusal of Occupancy Certificate	395
Appendix J		Form of Indemnity for Part Occupancy Certificate	396
Appendix K		Approvals of Building Permission Based on Risk Based Categorization	397
Appendix K-1		Form for Permission of Construction of Building on a plot upto 150 sq.m.	399
Appendix K-2		Approvals of Building Permission for Construction Upto 8 Rooms for Agro Tourism Center and Allied Activities as per Tourism Policy - 2016	400

Appendix L	Heritage List Card (Town & Region)	402
Appendix M	Typical Plans & Cross-section of the Road.	407
	PLANS	
Plan - A	Nallahs Identified for Cycle Track in Nashik Municipal Corporation Area.	420
	Clarifications & Directions by Government	
14/01/2021	क्र.टिपीएस-१८१८/प्र.क्र.२३६/१८(भाग-२)/नवि-१३ - मंजूर नियमावलीमधील विनियम क्र.१४.२.१ संदर्भात स्पष्टीकरण देणेबाबत.	422
10/05/2021	क्र.टिपीएस-१८२१/३४०/प्र.क्र.६८/२०२१/नवि-१३ - विनियम क्र.६.२.२ मधील Table No.6E(6) नुसार वर्गीकृत रस्त्यावरील पेट्रोल पंपाचेसाठी जंक्शनपासून सोडावयाच्या अंतराबाबत.	423
10/06/2021	क्र.टिपीएस-१२२१/९९०/प्र.क्र.४४/२१/नवि-१२ - विनियम क्र.११.२.५ नुसार बांधीव सुविधांतर्गत विकास हक्क हस्तांतरण संदर्भातील बाबींच्या अंमलबजावणीकामी मार्गदर्शन.	425
14/06/2021	क्र.टिपीएस-१२२१/१०३९/प्र.क्र.४२/२१/नवि-१२ - सिडको प्राधिकरणाकडून पनवेल महानगरपालिकेकडे वर्ग झालेल्या भूखंडावर मंजूर एकत्रिकृत विकास नियंत्रण व प्रोत्साहन नियमावलीनुसार (UDCPR) बांधकाम परवानगी देतेवेळी अनुसरावयाच्या पद्धतीचे मार्गदर्शन.	427
02/08/2021	क्र.टिपीएस-१८२१/प्र.क्र.१०३/२०२१/नवि-१३ - विनियम क्र.२.२.१४(ii) तरतुदीनुसार Fire Infrastructure Charges संदर्भात आदेश.	432
17/09/2021	क्र.टिपीएस-१८१८/प्र.क्र.२३६/१८(भाग-२)/नवि-१३ - मंजूर एकत्रिकृत विकास नियंत्रण व प्रोत्साहन नियमावलीप्रमाणे भूखंडाच्या कमाल बांधकाम क्षमतेच्या गणनेसंदर्भात येणाऱ्या अडचणीबाबत मार्गदर्शन.	434
08/12/2021	क्र.UDCPR/Appendix-C/परवाना/५७२९ - मंजूर नियमावलीतील Appendix-C, C-7.1 Technical personnel to be licensed या तरतुदीच्या अनुषंगाने अधिकार प्रत्यायोजन आदेश.	436
23/12/2021	क्र.टिपीएस-१८१८/प्र.क्र.२३६/१८(भाग-२)/नवि-१३ - विनियम क्र.१.९(v) अन्वये स्पष्टीकरण.	438
23/12/2021	क्र.टिपीएस-१८२१/९३३/नवि-१३ - विनियम क्र.२.५ -आरेखकीय त्रुटीसंदर्भाने चुक दुरुस्ती करण्याचे अधिकारांबाबत स्पष्टीकरण.	451
06/09/2022	क्र.टिपीएस-२४२२/७३१/प्र.क्र.६७/२०२२/नवि-०९ - नागपूर महानगर प्रदेश विकास प्राधिकरणासाठी लागू असलेल्या विनियम क्र.१०.४.३ बाबत मार्गदर्शन.	453
26/09/2022	आदेश क्र.८ - क्र.टिपीएस-१८१८/प्र.क्र.२३६/१८(भाग-२)/नवि-१३ - विनियम क्र.२.३(vi) बाबत स्पष्टीकरण.	455
26/09/2022	क्र.टिपीएस-१२२२/१५४४/प्र.क्र.१२८/२२/नवि-१२ - विनियम क्र.२.३(vi) बाबत स्पष्टीकरण.	458
26/09/2022	शासन निदेश क्र.टिपीएस-१८१८/प्र.क्र.२३६/१८(भाग-२)/नवि-१३ - विनियम क्र.२.३(vi) बाबत कलम १५४ चे निदेश.	460

12/10/2022	आदेश क्र.९ - टिपीएस-१८१८/प्र.क्र.२३६/१८(भाग-२)/नवि-१३ - नवनगर विकास प्राधिकरण या नात्याने सिडको क्षेत्रासाठी आणि विशेष नियोजन प्राधिकरण या नात्याने MADCP क्षेत्रासाठी UDCPR लागू करणेबाबत.	463
12/10/2022	आदेश क्र.१० - टिपीएस-१८१८/प्र.क्र.२३६/१८(भाग-२)/नवि-१३ - विनियम क्र.१०.१०.१, नोट क्र.३ बाबत स्पष्टीकरण.	466
29/11/2022	आदेश क्र.११ - टिपीएस-१८२१/२०२३/प्र.क्र.१०४/२०२२/नवि-३० -विनियम क्र.३.४.१ व विनियम क्र.३.५.१ बाबत स्पष्टीकरण.	469
27/02/2023	क्र.टिपीएस-१८२३/प्र.क्र.०७/२०२३/नवि-१३ - भोगवटा वर्ग-२ जमिनी भोगवटा वर्ग-१ मध्ये रुपांतरित करण्यासंदर्भात - राज्यातील ज्या नियोजन प्राधिकरणांना UDCPR लागू आहे, अशा सर्व नियोजन प्राधिकरणांना कलम १५४ अन्वये निदेश.	473
02/06/2023	शुध्दीपत्रक क्र.टिपीएस-१८२१/२०२३/प्र.क्र.१०४/२०२२/नवि-३० - विनियम क्र.३.४.१ व विनियम क्र.३.५.१ बाबत स्पष्टीकरणासंदर्भात आदेश क्र.११ ला शुध्दीपत्रक	477
24/07/2023	क्र.टिपीएस-१८२३/प्र.क्र.३१/२०२३/नवि-१३ - विनियम क्र.१०.१०.१, नोट क्र.३ व विनियम क्र.१०.१०.१(b) बाबत स्पष्टीकरण.	480
25/08/2023	आदेश क्र.१२ - टिपीएस-१२२३/६०३/प्र.क्र.७२/२३/नवि-१२ - विनियम क्र.४.८.१(b)(xvi) बाबत स्पष्टीकरण.	481
25.08.2023	आदेश क्र.टिपीएस-१८२२/१८१८/प्र.क्र.१७९/२०२२/नवि-१३ - विनियम क्र.१५.२ बाबत निदेश	483
28/08/2023	आदेश क्र.१२ - टिपीएस-१८१८/प्र.क्र.५४/२०२३/नवि-१३ - विनियम क्र.१४.२.१.२.४(ii) बाबत स्पष्टीकरण.	488
04/09/2023	आदेश क्र.१३ - टिपीएस-१२२१/२१७४/प्र.क्र.५८/२२/नवि-१२ - विनियम क्र.११.२.५ बाबत स्पष्टीकरण.	491
18/10/2023	आदेश क्र.१४ - टिपीएस-१२२३/९०५/प्र.क्र.१००/२३/नवि-१२ - विनियम क्र.७.७ बाबत स्पष्टीकरण.	493
26/10/2023	स्पष्टीकरण क्र.टिपीएस-१२२३/१४८०/प्र.क्र.१२२/२३/नवि-१२ - विनियम क्र.३.४.५ व विनियम क्र.४.१२ बाबत स्पष्टीकरण.	495
21/02/2024	आदेश क्र.१५ - टिपीएस-१२२३/१३१२/प्र.क्र.१४०/२३/नवि-१२ - विनियम क्र.१०.१४.२(ii) बाबत स्पष्टीकरण.	497
03/04/2024	पत्र क्र. टिपीएस -१८२३/१७२/प्र.क्र.४२/२०२३/नवि-१३ - विनियम क्र.१०.१५ बाबतच्या निदेशास स्थगितीबाबत.	499
22/08/2024	आदेश क्र.१६ - टिपीएस-१२२२/१३९८/प्र.क्र.११७/२२/नवि-१२ - विनियम क्र.५.१.१(vi) व ५.१.६ बाबत स्पष्टीकरण.	501
26/09/2024	आदेश क्र.१७ - टिपीएस-१२२४/१२०५/प्र.क्र.७०/२४/नवि-१२ - विनियम क्र.५.१.४(ii) बाबत स्पष्टीकरण.	504

10.10.2024	अधिसूचना क्र.टिपीबी-४३२२/१०/प्र.क्र.४५/२०२२/नवि-११ - विनियम क्र.१३.६ बाबतची परिशिष्टे.	507
<i>Note –</i> (*) Indicates Corrigendum / Addendum sanctioned by the Government from time to time under Regulation No. 1.10. (**) Indicates Guidelines issued by the Government from time to time under Regulation No 1.5. (***) Indicates Notice published by the Government under Section 20(3) & 37(1) with Directives issued under section 154. (#) Indicates the Clarifications issued by the Government from time to time. (+) Indicates the order issued by the Director of Town Planning, Maharashtra State, Pune.		

CHAPTER - 1

ADMINISTRATION

1.0 SHORT TITLE, EXTENT & COMMENCEMENT

These regulations shall be called as “Unified Development Control and Promotion Regulations for Maharashtra” (hereinafter called “These Regulations” or “Unified Development Control and Promotion Regulations” - ‘UDCPR’)

1.1 Extent and Jurisdiction

- i) These regulations shall apply to the building activities and development works on lands within the jurisdiction of all Planning Authorities and Regional Plan areas except Municipal Corporation of Greater Mumbai, other Planning Authorities / Special Planning Authorities / Development Authorities within the limit of Municipal Corporation of Greater Mumbai, MIDC, NAINA, Jawaharlal Nehru Port Trust, Hill Station Municipal Councils, ⁽¹⁾ Chikhaldara notified area (consisting Chikhaldara Hill Station M.C. & four villages) Eco-sensitive / Eco-fragile region notified by MoEF & CC, and Lonavala Municipal Council in Maharashtra.
- ii) These Regulations shall also be applicable to the Town Planning Scheme area. However this will not bar the Development Permission to be granted as per the Regulations of the Town Planning Scheme intoto.

1.2 Commencement of Regulations

These regulations shall come into force with effect from the date of publication of notification in the official Gazette. All the Development Control Regulations / special Regulations which are in operation shall cease to operate.

1.3 DEFINITIONS

In these Regulations, unless the context otherwise requires, the definitions given hereunder, shall have meaning indicated against each of them.

Words and expressions which are not defined in these Regulations, shall have the same meaning or sense as in the :-

- i) Maharashtra Regional and Town Planning Act, 1966;
- ii) Maharashtra Municipal Corporations Act, 1949;
- iii) Nagpur Improvement Trust Act, 1936;
- iv) Maharashtra Municipal Councils, Nagar Panchayats and Industrial Townships Act, 1965;
- v) Maharashtra Metropolitan Region Development Authority Act, 2016;
- vi) Maharashtra Land Revenue Code, 1966;
- vii) Real Estate (Regulation and Development) Act, 2016;
- viii) National Building Code of India, 2016;
- ix) Maharashtra Housing and Area Development Act, 1976;
- x) Maharashtra Slum Areas (Improvement, Clearance And Redevelopment) Act, 1971.



- 1 **Act** - means the Maharashtra Regional & Town Planning Act, 1966 as may be amended from time to time.

⁽¹⁾ Inserted vide Corrigendum / Addendum No.CR.121/21, dt.02nd December, 2021


- 2 **Addition / Alteration** - means any change in existing authorized building or change from one occupancy to another, or a structural change, such as an addition to the area or height, or the removal of part of a building, or any change to the structure, such as the construction of, cutting into or removal of any wall, partition, column, beam, joist, floor, roof or other support or a change to or closing of any required means of ingress or egress or a change to the fixtures of equipment as provided under these regulations. However, modification in regards to gardening, white washing, painting, plastering, pointing, paving and retiling shall not be deemed to be alteration.
- 3 **Advertising Sign** - means any surface or structure with characters, letters or illustrations applied thereto and displayed outdoor in any manner whatsoever for purposes of advertising or to give information regarding or to attract the public to any place for public performance, article or merchandise whatsoever, or is attached to, or forms a part of building, or is connected with any building or is fixed to a tree or to the ground or to any pole, screen, fence or hoarding or displayed in space, or in or over any water body.
- 4 **Air-conditioning** - means the process of treating air so as to control simultaneously its temperature, humidity, cleanliness and distribution to meet the requirement of conditioned space.
- 5 **Accessory Building** - means a building separate from the main building on a plot and containing one or more rooms for accessory use such as servant quarters, garage, store rooms etc.
- 6 **Accessory / Ancillary Use** - means any use of the premises subordinate to the principal use and incidental to the principal use.
- 7 **Amenity Space** - for the purpose of these regulations, amenity space means a statutory space kept in any layout to be used for any of the amenity such as open spaces, parks recreational grounds, playgrounds, sports complex, gardens, convenience shopping, parking lots, primary and secondary schools, nursery, health club, Dispensary, Nursing Home, Hospital, sub post-office, police station, electric substation, ATM of banks, electronic cyber library, open market, garbage bin, assisted living and hospice together, senior citizen housing and orphanage together, project affected persons' housing, auditorium, conventional centre, water supply, electricity supply and includes other utilities, services and conveniences.
- 8 **Annual Statements of Rates** - means the Annual Statements of Rates (ASR) published by the Inspector General of Registration, Maharashtra State, Pune.
- 9 **Architectural projection** - means a chajja, cornice etc. which is a protrusion from the building facade or line of the building only for aesthetic purpose and not used for any habitable purpose.
- 10 **Access** - means a clear approach to a plot or a building.
- 11 **Architect** - An Architect who is a member of the Indian Institute of Architects and duly registered with the Council of Architecture under the Architects Act, 1972.
- 12 **Apartment** - means whether called block, chamber, dwelling unit, flat, office, showroom, shop, godown, premises, suit, tenement, unit or by any other name, means a separate and self-contained part of any immovable property, including one or more rooms or enclosed spaces, located on one or more floors or any part thereof, in a building or on a plot of land, used or intended to be used for any residential or commercial use such as residence, office, shop, showroom or godown or for carrying on any business, occupation, profession or trade, or for any other type of use ancillary to the purpose specified.
- 13 **Applicant** - means any person who is an owner or a person having an irrevocable registered Power of Attorney of an owner and any other document as acceptable to the Authority.

14 Authority means :

- i) in the case of a Municipal Corporation, the Municipal Commissioner or such other officer as he may appoint in this behalf;
- ii) in the case of a Zilla Parishad, the Chief Executive Officer or such other officers as he may appoint in this behalf;
- iii) in the case of a Municipal Council, the Chief Officer of the Council; and
- iv) in the case of any other local authority, Special Planning Authority, New Town Development Authority or Area Development Authority, the Chief Executive Officer or person exercising such powers under Acts applicable to such authorities;
- v) in the area of a Regional Plan, the Collector of the District;
- vi) in case of Development Authorities established under the Metropolitan Region Development Authorities Act, Metropolitan Commissioner or such other officer as he may appoint in this behalf;
- vii) in case the land is situated in the gaathan, within the meaning of clause (10) of section 2 of the Maharashtra Land Revenue Code, 1966, the village Panchayat concerned.

15 Atrium - means a sky lighted and naturally/mechanically ventilated area in a building, with no intermediate floors and used as circulation space or entrance foyer.**16 Balcony** - means a horizontal cantilever projection, including parapet, handrail or balustrade to serve as a passage or sitting out place with at least one side open, except for the railing or parapet wall for safety.

Also, non-cantilever balcony shown in the illustration below shall be treated as balcony.




- 17 **Basic FSI** - means floor Space Index permissible without levy of premium or loading of TDR on any parcel of land as per the provisions of these regulations.
- 18 **Basement / Cellar** - means the lower storey of a building below or partly below the ground level with one or more than one levels.
- 19 **Biotechnology Unit / Park** - means a Unit or a Park which is certified as such by the Development Commissioner (Industries).
- 20 **Building** - means any structure for whatsoever purpose and of whatsoever materials constructed and every part thereof whether used as human habitation or not and includes foundation, plinth, walls, floors, roofs, chimneys, wells, door steps, fencing, plumbing and building services, fixed - platforms, varandahs, balcony; cornice or projection, part of a building or anything affixed thereto or any wall fence enclosing or intended to enclose any land or space and signs and outdoor display structures. However, tents, shamiyanas and the tarpaulin shelters erected for temporary and ceremonial occasions with the permission of the Authority shall not be considered as building.
- 21 **Built up Area** - means the area covered by a building on all floors including cantilevered portion, mezzanine floors, if any, but excluding the areas specifically exempted from computation of Floor Space Index (F.S.I.) under these Regulations.
- 22 **Building Line** - means the line up to which the plinth of a building adjoining a street or an extension of a street or on a future street may lawfully extend. It includes the lines prescribed, if any, in any scheme and / or development plan / Regional Plan, or under any other law in force.
- 23 **Building Height** - means the vertical distance measured in the case of flat roofs, from the average level of the ground around and contiguous to the building or as decided by the Authority to the terrace of last floor of the building adjacent to the external walls; to the highest point of the building and in the case of pitched roofs, up to the point where the external surface of the outer wall intersects the finished surface of the sloping roof; and in the case of gable facing road, the mid-point between the eaves level and the ridge. Architectural features serving no other function except that of decoration, terrace water tank, staircase roof and parapet wall shall be excluded for the purpose of measuring heights.
- 24 **Cabin** - means a non-residential enclosure constructed of non-load bearing, non-masonry partitions.
- 25 **Carpet area** - means the net usable floor area of an apartment, excluding the area covered by the external walls, areas under services shafts, exclusive balcony or veranda area and exclusive open terrace area, but includes the area covered by the internal partition walls of the apartment.


Explanation (1) - The expression "exclusive balcony or veranda area" means the area of the balcony or veranda, as the case may be, which is appurtenant to the net usable floor area of an apartment, meant for the exclusive use of the allottee; and "exclusive open terrace area" means the area of open terrace which is appurtenant to the net usable floor area of an apartment, meant for the exclusive use of the allottee.

Explanation (2) - If in any regulation of these regulations, carpet area is defined different than what is mentioned here, then carpet area as mentioned in that regulation, shall be applicable

- 26 **Chajja** - means a sloping or horizontal structural overhang usually provided over openings on external walls to provide protection from sun and rain and for purpose of architectural appearance.
- 27 **Chief Fire Officer** - means a Chief Fire Officer as specified in the Maharashtra Fire Prevention and Life Safety Measures Act, 2006 and Rules there under as amended from time to time.
- 28 **Chimney** - means an upright shaft containing one or more flues provided for the conveyance to the outer air of any product of combustion resulting from the operation of heat producing appliance or equipment employing solid, liquid or gaseous fuel.
- 29 **Cluster** - means any area of land so defined, under these regulations.
- 30 **Combustible Material** - means a material which when burnt adds heat to a fire when tested for combustibility in accordance with IS 3808-1979 : Method of test for non-combustibility of building materials (first revision) given in the National Building Code.
- 31 **Congested Area** - In case of Regional Plan area, a land included within the gaathan as determined under Maharashtra Land Revenue Code, 1966, and in case of other areas as specifically earmarked in the Development Plan / Planning Proposal. (In case of Nashik Municipal Corporation, congested area is referred to as Core area).
- 32 **Control Line** - means a line on either side of a highway or part of highway beyond the building line fixed in respect of such highway by the Highway Authority from time to time.
- 33 **Courtyard or Chowk** - means a space permanently open to sky enclosed on sides fully or partially by buildings and may be at ground level or any other level within or adjacent to a building.
- 34 **Canopy** - means a cantilevered projection over any entrance to a building



- 35 **Convenience Shops** - means shops for day-to-day domestic needs, as distinguished from wholesale trade or departmental store.
- 36 **Corridor** - means a common passage or circulation space including a common entrance space.



- 37 **Curb Cut** - means a small solid (usually concrete) ramp that slopes down from the top surface of a sidewalk or footpath to the surface of an adjoining street. It is designated for ease of access for pedestrians, bicyclists and differently abled people.


- 38 **Detached Building** - means a building whose walls and roofs are independent of any other building with marginal distances on all sides as may be specified.
- 39 **Development** - Development with its grammatical variations means the carrying out of buildings, engineering, mining or other operations in or over, or under land or the making of any material change, in any building or land or in the use of any building or land or any material or structural change in any Heritage building or its precinct and includes demolition of any existing building, structure or erection of part of such building, structure or erection and reclamation, redevelopment and layout or sub-division of any land and to develop shall be construed accordingly.
- 40 **Development Rights** - means right to carryout development or to develop the land or building or both and shall include the transferable development right in the form of right to utilize the floor space index of land utilizable either on the reminder of the land partially reserved for public purpose or elsewhere as the development control & promotion regulations in this behalf provide.
- 41 **Dharmashala** - means a building used as a place of religious assembly, rest house, a place in which charity is exercised with religious or social motives, or a place where in a certain section of people have a right of residence or are granted residence without payment or on nominal payment.
- 42 **Development Plan** - means a plan for the development or re-development of the area within the jurisdiction of a Planning Authority and includes revision of a Development Plan and Planning Proposals of a Special Planning Authority for development of land within its jurisdiction.
- 43 **Drain** - means a system or a line of pipes, with their fittings and accessories, such as manholes, inspection chambers, traps, gullies, floor traps used for the drainage of building, or number of building or land appurtenant to the buildings within the same cartilage. A drain shall also include open channel for conveying surface water or a system for the removal of any liquid.
- 44 **Dwelling Unit / Tenement** - means an independent housing unit with separate facilities for living, cooking and sanitary requirements.
- 45 **Eating House** - means any premises where any kind of food is prepared or supplied for consumption by public for a profit or gain of any person owning or having an interest in or managing such premises.
- 46 **Enclosed Stair case** - means a stair case separated by fire resistant walls and door(s) from the rest of the building.
- 47 **Energy Efficient Building** - means a building compliant with the provisions of Energy Conservation Building Code (ECBC).
- 48 **Existing Building or use** - means a building, structure or premises or its use existing on ground.
- 49 **Exit** - means a passage, channel or means of egress from any building, storeys or floor area to a street or other open space of safety.
- i) **“Horizontal Exit”** means a protected opening through or around a firewall or a bridge connecting two or more buildings;
- ii) **“Outside Exit”** means an exit from a building to a public way, or to an open area leading to a public way, or to an enclosed fire resistant passage leading to a public way;
- iii) **“Vertical Exit”** means an exit used for ascension or dissension between two or more levels including stairways, smoke-proof towers, ramps, escalators and fire escapes;
- 50 **External Wall** - means an outer wall of a building not being a party wall even though adjoining to a wall of another building and also means a wall abutting on an interior open space of any building.

-
- 51 **Escalator** - means a power-driven, inclined, continuous stairway used for ascending or descending between floors or bridge over a road / railway line.
- 52 **Escape Route** - means any well-ventilated corridor, staircase or other circulation space, or any combination of the same, by means of which a safe place in the open air at ground level can be reached.
- 53 **Fire and / or Emergency Alarm System** - means an arrangement of call points or detectors, sounders and other equipment's for the transmission and indication of alarm signals, for testing of circuits and, whenever required, for the operation of auxiliary services. This device may be workable automatically or manually to alert the occupants in the event of fire or other emergency.
- 54 **Fire Lift** - means a special lift designed for a use of fire service personnel in the event of fire or other emergency.
- 55 **Fire Proof Door** - means a door or shutter fitted to a wall opening made of fire resistant material to prevent the transmission and spread of heat, smoke and fire for a specified period.
- 56 **Fire Pump** - means a machine driven by external power of transmitting energy to fluids by coupling the pump to a suitable engine or motor, which may have varying outputs / capacity but shall be capable of having a pressure of 3.2 kg/cm^2 at the topmost level of a multi-storied or high rise building.
- 57 **Fire Resistance** - means the time during which a material fulfils its function of contributing to the fire safety of a building when subjected to prescribed conditions of heat and load or restraint. The fire resistance test of structures shall be done in accordance with "IS 3809 (1979) : Fire resistance test for structures"
- 58 **Fire Resisting Material** - means a material which has certain degree of fire resistance.
- 59 **Fire Separation** - means the distance in meters measured from any other building on the site, or from other site, or from the opposite side of a street or other public space to the building.
- 60 **Fire Service Inlet** - means a connection provided at the base of a building for pumping up water through in-built fire-fighting arrangements by fire service pumps in accordance with the recommendations of the Chief Fire Officer.
- 61 **Fire Tower** - means an enclosed staircase which can only be approached from the various floors through landings or lobbies separated from both, the floor areas and the staircase by fire resisting doors and open to the outer air.
- 62 **Floor** - means the lower surface in a storey on which one normally walks in a building. The general term floor, unless otherwise specifically mentioned, shall not refer to a mezzanine floor.
- Note** - The sequential numbering of floors shall be determined by its relation to the determining entrance level. For floor at or above ground level, with direct entrance from / to road or street shall be termed as ground floor. The other floors above ground floor shall be numbered in sequence as Floor 1, Floor 2, etc., with the number increasing upwards. The stilt shall be termed as stilt floor or Stilt floor 1, Stilt floor 2 etc. and floors above shall be numbered as Floor 1, Floor 2, etc.
- 63 **Floor space index (F.S.I.)** - means the quotient obtained by dividing the area covered by P line as mentioned in Regulation No.6.6 by the net area of the plot.
- F.S.I.** = Area covered by P line as mentioned in Regulation No.6.6 on all floors / Net Plot area
- “Premium FSI”** means the FSI that may be available on payment of premium as may be prescribed under these regulations.
-

- 64 **Footing** - means a foundation unit constructed in brick work, masonry or concrete, steel or any other material permissible as per IS Code under the base of a wall or column for the purpose of distributing the load over a large area.
- 65 **Foundation** - means that part of the structure which is in direct contact with transmitting loads to the ground.
- 66 **Front Open Space / Margin / Setback** - means the distance between the boundary line of plot abutting the means of access / road / street and the building line. In case of plots facing two or more means of accesses / roads / streets, the plot shall be deemed to front on all such means of accesses / roads / streets.
- 67 **Gallery** - means an intermediate floor or platform projecting from a wall of an auditorium of a hall providing extra floor area, additional seating accommodation etc. These shall also include the structures provided for seating in stadia.
- 68 **Garage - A) Private Garage** - means a building or portion thereof having a roof and walls on three sides, designed and used for parking of privately owned motor driven or other vehicles within a project. A private garage is not operated for gain and not designed or used for repairing, servicing, hiring, selling etc. of such vehicles. It does not include an unenclosed or uncovered parking space such as open parking areas.
- B) Public Garage** - means a building or portion thereof designed as a garage operated for gain, and used for repairing, servicing, hiring, selling or storing or parking of motor driven or other vehicles.
- 69 **Grey Water** - means waste water from kitchen sink, bathrooms, tubs, showers, wash basins, washing machines and dish washers excluding the waste water from water closets (W.C.).
- 70 **Group Housing Scheme** - means a building or a group of buildings constructed or to be constructed with one or more floors, consisting of more than one dwelling units and having common service facilities. Common service facilities means facilities like stair case, balcony, corridor and varandahs, lift, etc.
- 71 **Ground Level** - means the average level of the ground in a plot.
- 72 **Habitable Room** - means a room constructed or intended for human habitation and uses incidental thereto, including kitchen if used as a living room but excluding a bathroom, water closet compartment, laundry, serving and storing pantry, corridor, cellar, attic and spaces not frequently used.
- 73 **Hazardous Material means -**
- i) Radioactive substances;
 - ii) Material which is highly combustible or explosive and / or which may produce poisonous fumes or explosive emanations or storage, handling, processing or manufacturing of which may involve highly corrosive, toxic or noxious alkalis or acids or other liquids;
 - iii) Other liquids or chemicals producing flame, explosives, poisonous irritant or corrosive gases or which may produce explosive mixtures of dust or fine particles capable of spontaneous ignition.
- 74 **High-rise Building** - means a building having a height of 24 m. or more above the average surrounding ground level. Excluding chimneys, cooling towers, boiler, rooms / lift machine rooms, cold storage and other non-working areas in case of industrial buildings, and water tanks, and architectural features in respect of other buildings.
- 75 **Home Occupation** - means customary home occupation other than the conduct of an eating or a drinking place offering services to the general public, customarily carried out by a member of the

family residing on the premises without employing hired labour, and for which there is no display to indicate from the exterior of the building that it is being utilised in whole or in part for any purpose other than a residential or dwelling use, and in connection with which no article or service is sold or exhibited for sale except that which is produced therein, which shall be non-hazardous and not affecting the safety of the inhabitants of the building and the neighbourhood, and provided that no mechanical equipment is used except that as is customarily used for purely domestic or household purposes and / or employing licensable goods. Home Occupation may also include such similar occupations as may be specified by the Authority.

- 76 Layout Open Space / Recreational Open Space** - means a statutory common open space kept in any layout, sub-division or group housing scheme or campus planning exclusive of margins and approaches.
- 77 Ledge or Tand** - means a shelf like projection, supported in any manner whatsoever, except by vertical supports within a room.
- 78 Licensed Engineer / Structural Engineer / Supervisor** - means a qualified Engineer / Structural Engineer / Town Planner / Supervisor licensed by the Authority.
- 79 Lift** - means an appliance designed to transport persons or materials between two or more levels in vertical or substantially vertical directions, by means of a guided car platform.
- 80 Lift Lobby** - means a space from which people directly enter lift car(s) and in to which people directly enter upon exiting lift car(s).
- 81 Lift Machine** - means part of the lift equipment comprising the motor(s) and the control gear there with, reduction gear (if any), brakes and winding drum or sheave, by which the lift car is raised or lowered.
- 82 Lift Well** - means unobstructed space within an enclosure provided for the vertical movement of the lift car(s) and any counter weights, including the lift pit and the space for top clearance.
- 83 Loft** - means an intermediate floor between two floors which is constructed for storage purpose and as defined in these regulations.
- 84 Mall** - means a large enclosed area comprising of shopping, entertainment and eating facilities and facilities incidental thereto.
- 85 Side and Rear Marginal Open Space / Marginal Distance** - means a minimum distance required to be left open to sky between the boundary of the building plot and the building line on respective sides.
- 86 Masonry** - means an assemblage of masonry units properly bound together with mortar.
- 87 Mezzanine floor** - means an intermediate floor between two floors of any story, forming an integral part of floor below, overhanging or overlooking a floor beneath, not being a loft between the floor and ceiling of any storey.



- 88 **Means of Access** - means the road / street / vehicular access way, pathway upto the plot and to the building within a plot.
- 89 **Multiplex / Multiplex Theatre Complex (MTC)** - means a place of public entertainment for the purpose of exhibition of motion pictures with multiple screens and / or dramas and other social or cultural programmes as described in Maharashtra Entertainment Duty Act, 1923.
- 90 **Net Plot Area** - means area of the plot as defined in these regulations.
- 91 **Non-conforming User** - means any lawful use / building existed on the site but which does not conform to the zoning shown on the Development Plan / Planning Proposal/Regional Plan in force.
- 92 **Noise Barrier** - means an exterior structure / part of structure designed to protect inhabitants of sensitive land use areas from noise pollution.
- 93 **Occupancy or Use Group** - means the principal occupancy or use for which a building or a part of a building is used, or intended to be used. Occupancy shall be deemed to include subsidiary occupancies which are contingent upon principal occupancy or use. Buildings with mixed occupancies are those in which, more than one, occupancy is present in different portions of the building. The occupancy classification shall have the meaning given in this regulation, unless otherwise spelt out in any plan under the Act.
- i) **Residential Building** means any building in which sleeping accommodation is provided for normal residential purposes with or without cooking or dining or both facilities. It includes one or two or multi-family dwellings, lodging or rooming houses, residential hotels, hostels, dormitories, Dharmashala, apartment houses, flats, service apartments, studio apartments and private garages incidental thereto;
- ii) **Educational Building** means a building exclusively used for a school or college recognized by the appropriate Board or University, or any other competent authority involving assembly for instruction, education or recreation incidental to educational use, and including a building for such other uses incidental thereto such as library, multi-purpose hall, auditorium or a research institution. It shall also include quarters for essential staff required to reside on the premises and a building used as a hostel attached or independent to an educational institution whether situated on or off its campus and also includes buildings used for day-care purposes for more than 8 hours per week;
- iii) **Institutional Building** means a building constructed or used for research in education, health and other activities, for medical or other treatment, hostel for working women / persons / students but not for lodging, an auditorium or complex for cultural and allied activities or for an hospice, care of persons suffering from physical or mental illness, handicap, disease or infirmity, care of orphans, abandoned women, children and infants, convalescents, destitute or aged persons and for penal or correctional detention with restricted liberty of the inmates ordinarily providing sleeping accommodation, and includes hospitals, sanatoria, custodial and penal institutions such as jails, prisons, mental hospitals, houses for correctional detention and reformatories;
- iv) **Assembly Building** means any building or part of a building where groups of people congregate or gather for amusement, recreation or social, religious, patriotic, civil, travel and similar purposes, e.g. theatres, motion picture houses, drive-in-theatres, multiplexes, assembly halls, city halls, town halls, auditoria, exhibition halls, museums, mangal-karyalayas, cultural centres, skating rinks, places of worship, dance theatres, clubs & gymkhanas, malls, passenger stations and terminals of air, surface and other public transportation services, recreation piers and stadia;
- v) **Business Building** means any building or part thereof which is used for transaction of business for the keeping of accounts and records for similar purposes; offices, banks, professional establishments, I.T. establishments, call centres, offices for private entrepreneurs etc. shall be


classified in this group in so far as principal function of these is transaction of public business and the keeping of books and records;

- vi) Office Building / Premises** means the premises whose sole or principal use is to be used as an office or for office purpose; “office purposes” shall include the purpose of administration, clerical work, handling money, telephone / telegraph / computer operations; and ‘clerical work’ shall include writing, book-keeping, sorting papers, typing, filing, duplicating, drawing of matter for publication and the editorial preparation of matter for publication and such other activities;
- vii) Mercantile (Commercial) Building** means any building or part of a building which is used as shops, stores, market, malls for display and sale of merchandise, either wholesale or retail, including office, storage and service facilities incidental to the sale of merchandise and located in the same building;
- viii) Public / Semi-public Building** means a building used or intended to be used, either ordinarily or occasionally by the public such as (a) offices of State or Central Government, any public sector undertaking or statutory or local Authority or Semi Government Organization (b) a place for public worship, etc.;
- ix) Wholesale Establishment** means an establishment, wholly or partly engaged in wholesale trade, manufacturers’ wholesale outlets including related storage facilities, A.P.M.C. establishments, warehouses and establishments engaged in truck transport including truck transport booking agencies;
- x) Industrial Buildings** means any building or part of a building or structure, in which products or materials of all kinds and properties are fabricated, assembled or processed like assembling plants, laboratories, power plants, smoke houses, refineries, gas plants, mills, dairies, factories etc.;
- xi) Storage Buildings** means any building or part of a building used primarily for the storage or sheltering of goods, wares or merchandise, like warehouses, cold storages, freight depots, transit sheds, godowns, store houses, public garages, hangars, truck terminals, grain elevators, barns and stables;
- xii) Hazardous Building** means any building or part of a building which is used for the storage, handling, manufacture or processing of radioactive, highly combustible or explosive materials or products which are liable to burn with extreme rapidity and / or which may produce poisonous fumes or explosive emanations during storage, handling, manufacturing or processing, which involve highly corrosive, toxic or noxious alkalis, acids or other liquids or chemicals producing flames, fumes and explosive mixtures of dust or which result in the division of matter into fine particles capable of spontaneous ignition;
- xiii) Information Technology Building / Establishment (ITE)** means an establishment which is in the business of developing either software or hardware relating to computers or computer technology as approved by Director of Industries.
- (#)xiv) Special Building means** - i) any multi-storeyed building which is more than 24 m. in height measured from ground level, or
 - ii) buildings for educational, assembly, mercantile, institutional, industrial, storage and hazardous occupancies having built-up area 500 Sq.m. or more on any floor irrespective of height of such building , or
 - iii) Any building with mixed occupancies with any of the aforesaid occupancies in (ii) above with built-up area 500 sq.m. or more on any floor irrespective of height of such building.
- (1) Note :** Any building for residential or mix occupancy with height upto 24 m. but built up area upto 750 Sq.m. on any floor and sprinkler system is provided and travel distance is maintained as per these regulations, shall not be considered as special building, subject to fire NOC.
- xv) Yatri Niwas** means a building used for accommodation of tourist, traveller etc.


⁽¹⁾ Inserted vide Corrigendum / Addendum No. CR 121/21, dt. 02nd December, 2021.

^(#) Clarifications issued vide letter - CR 44/21 dt, 10th June, 2021 & CR 42/21/UD 12, dt. 14th June, 2021.


- 94 **Owner** - means a person who has legal title to land or building and includes any person for the time being receiving or entitled to receive, whether on his own account or as agent, trustee, guardian, manager or receiver for another person or for any religious or charitable purposes the rents or profits of the property in connection with which it is used;
- 95 **Parapet** - means low wall or railing built along the edge of a roof, terraces, balcony, varandah etc.
- 96 **Parking Space** - means an enclosed or unenclosed, covered or open area or area provided by mechanical means sufficient in size to park vehicle. Parking spaces shall be served by a driveway connecting them with a street or alley and permitting ingress or egress of vehicles.




- 97 **Partition** - means an interior non-load-bearing barrier, one storey or part-storey in height.



- 98 **Permit / Permission** - means permission or authorization in writing by the Authority to carry out the work regulated by these regulations.
- 99 **Plinth** - means the portion of a structure between the surface of the surrounding ground and surface of the floor immediately above the ground.
- 100 **Plot / Site** - means a parcel or piece of land enclosed by definite boundaries.
- 101 **Pandals / Shamiyanas** - means a temporary structure with roof or walls made of canvas, cloth other like material which is not adopted for permanent or continuous occupancy.
- 102 **Porch** - means a covered surface supported on pillars or otherwise, for the purpose of pedestrian or vehicular approach to an entrance in a building.




- 103 Podium** - means a floor of a building extending beyond building line/s and used for parking, recreational open space, recreation, fire and building services / utilities and incidental purposes, as specified in these regulations.



- 104 Reconstruction** - means a reconstruction in whole or part of a building which has ceased to exist due to an accidental fire, natural collapse or demolition after having been declared unsafe by the Authority, or which is likely to be demolished by or under the order of the Authority / Other Competent Municipal Officer.

- 105 Refuge Area** - means an unenclosed space in a multi-storied building specifically provided to serve as fire-proof space to gather easily for evacuation of the occupants.



- 106 Refuge chute** - means a vertical pipe system passing from floor to floor provided with ventilation and inlet openings for receiving refuge from successive flats and ending at ground floor on top of the collecting chamber.


- 107 Road / Street** - means any high way, street, lane, pathway, alley, stair way, passage way, carriage way, footway, square place or bridge, tunnel, underpass, elevated road, whether a thoroughfare or not, over which the public have a right of passage or access or have passed and had access uninterruptedly for a specified period, whether existing or proposed in any scheme, and includes all bunds, channels, ditches, storm-water drains, culverts, sidewalks, traffic islands, roadside trees, hedges, retaining walls, fences, barriers and railings within the street lines.

- 108 Road / Street Line** - means the line defining the side limit of a road / street.

- 109 Road width or Width of road/street** - means the whole extent of space within the boundaries of a road when applied to a new road / street, as laid down in the city survey or development plan or prescribed road lines by any act or law and measured at right angles to the course or intended course or direction of such road.


- 110 Room Height** - means the vertical distance measured from the finished floor surface to the

finished slab surface of a room. In case of pitched roofs, the room height shall be the average height between bottom of the eaves and bottom of the ridge from the finished floor surface.



- 111 **Roof Top Photovoltaic (RTPV) System** - means any of the two Photovoltaic Systems installed on the roof of any building, i.e. (i) RTPV System with storage facility using battery, and (ii) Grid Connected RTPV System.
- 112 **Row Housing** - means a row of houses with only front and rear open spaces except end houses which shall be with side open spaces.
- 113 **Semi Detached Building** - means a building detached on three sides with marginal distances as specified and on the fourth side attached to a building in an adjoining plot.
- 114 **Service Apartment** - means premises other than a lodge or hotel, in which furnished rooms or a suite of rooms are let out on short / long term basis.
- 115 **Service Floor** - means a non-habitable floor with a height not more than 1.8 m. from floor level to soffit of beam, generally provided in special buildings, wherever required, wherefrom services like water supply, sewage disposal system, electricity etc. are co-coordinated / maintained.
- 116 **Service Road** - means a local road on a continuous alignment that normally runs adjacent and parallel to main roads like National or State Highways and provides access to properties bordering it.
- 117 **Site corner** - means the side at the junctions of and fronting on two or more intersecting streets.
- 118 **Site, Depth of Site** - means the mean horizontal distance between the front and rear side boundaries.
- 119 **Solar Assisted Water Heating (SWH) System** - means a device to heat water using solar energy as heat source.
- 120 **Double Frontage** - means a site, having a frontage on two streets other than a corner plot.
- 121 **Site, Interior or Tandem** - means a site, access to which is by a passage from a street whether such passage forms part of the site or not.
- 122 **Smoke Stop Door** - means a door for preventing or checking the spread of smoke from one area to another.
- 123 **Stair Cover / Staircase Room** - means a structure with a covering roof over a staircase and its landing built to enclose only the stair and its landings for the purpose of providing protection from weather which should not be used for human habitation.
- 124 **Stall** - means a small shop, floor area of which does not exceed 5.0 sq.m.

- 125 **Storage** - means a place where goods are stored.
- 126 **Store Room** - means a room used as storage space.
- 127 **Storey** - means the portion of a building included between the surface of any floor and the surface of the floor next above it, or if there be no floor above it, then the space between any floor and the ceiling next above it.
- 128 **Stilts or Stilt Floor** - means the portion of a building above ground level consisting of structural columns supporting the super-structure with at least two sides open and without any enclosures and used for the purpose of parking vehicles like cars, scooters, cycles, etc. and other services as may be permitted under these Regulations.
- 129 **Sub-station (Electric)** - means a station for transforming or converting electricity for the transmission or distribution thereof and includes transformers, converters, switchgears, capacitors, synchronous condensers, structures, cables and other appurtenant equipment and any buildings used for that purpose and the site thereof.
- 130 **Supported Double Height Terraces** - means open terraces, unenclosed on at-least one side with railing and lying wholly within building line with supports underneath and having minimum height of two floors.
- 131 **Tenement** - means an independent dwelling unit with a kitchen or cooking alcove.
- 132 **Terrace** - means an open-to-sky flat roof of a building or part of a building, provided with a parapet for safety and with or without any cantilevered portion.
- 133 **Theatre** - means a place of public entertainment for the purposes of exhibition of motion picture and/or dramas and other social or cultural programs
- 134 **Travel Distance** - means the distance from the remotest point on a floor of a building to a place of safety, be it a vertical exit, horizontal exit or an outside exit measured along the line of travel.



- 135 **Tower like structure** - means a structure in which the height of the tower like portion is at least twice the width of the broader base.
- 136 **Unsafe Building** - means buildings which are structurally unsafe, unsanitary or not provided with adequate means of ingress or egress which constitute a fire hazard or are otherwise dangerous to human life or which in relation to existing use constitute a hazard to safety or health or public welfare, by reason of inadequate maintenance, dilapidation or abandonment.
- 137 **Varandah** - means a covered area with at least one side open to the outside with the exception of 1.0 m. high parapet on the upper floors to be provided on the open side.
- 138 **Water Closet (WC)** - means a privy with arrangement for flushing the pan with water. It does not

include a bathroom.

- 139 Water Course** - means a natural channel meant for carrying storm water and includes an artificial one formed by training or diversion of a natural channel;
- i) **“Major Water Course”** means a river.
- ii) **“Minor Water Course”** means a nallah.
- 140 Window** - means an opening to the outside other than the door which provides all or part of the required natural light, ventilation or both, to the interior space.
- 141 Wing of a Building** - means a part of a building with independent access, staircase and lift connected to other parts with common basement / stilt / podium / terrace / common wall and connecting passages.

1.4 APPLICABILITY OF REGULATIONS

- i) **Development and Construction** : Except as hereinafter otherwise provided, these regulations shall apply to all development, redevelopment, erection and / or re-erection of a building, change of user etc. as well as to the design, construction or reconstruction, additions and alterations to a building.
- ii) **Part Construction** : Where the whole or part of a building is demolished or altered or reconstructed or removed, except where otherwise specifically stipulated, these Regulations apply only to the extent of the work involved.
- iii) **Change of Occupancy / Use** : Where the occupancy or the user of a building is changed, except where otherwise specifically stipulated, these regulations shall apply to all parts of the building affected by the change.
- iv) **Reconstruction** : The reconstruction in whole or part of a building which has ceased to exist due to an accidental fire, natural collapse or demolition, having been declared unsafe, or which is likely to be demolished by or under an order of the Authority and for which the necessary certificate has been given by the Authority shall be allowed subject to the provisions in these regulations.
- v) **Development of sites or / and subdivision or amalgamation of land** : Where land is to be developed, subdivided, or two or more plots are to be amalgamated, or a lay-out is to be prepared; these Regulations shall apply to the entire area under development, sub-division, amalgamation and layout. Provided that, where a developed land, an existing lay-out / sub-division plan is being altered, these Regulations shall apply only to that part which is being altered.
- vi) **Revised permission** : Any development permission granted earlier may be revised provided that, third party interest established in pursuance of such permissions, if any, are not adversely affected. In such case, consent of the adversely affected persons shall be necessary, if required under RERA. While granting the revised permission, the approved plans and commencement certificate of the earlier permission with office, shall be stamped as ‘SUPERSEDED’ by the Authority.
- vii) **Exclusions** : Nothing in these regulations shall require the removal, alteration or abandonment or prevent the continuance of the lawfully established use or occupancy of an existing building or its use, unless in the opinion of the Authority, such a building is unsafe or constitutes a hazard to the safety of adjacent property.

1.5 SAVINGS

Notwithstanding anything contained in these regulations, any development permission granted or any development proposal for which any action is taken under the erstwhile regulations shall be valid and continue to be so valid, unless otherwise specified in these regulations.

Provided that, the words 'action taken' in this regulation shall also include the issuance of letter for payment of Development and other Charges issued after approval of the proposal in principle.

Provided further that if any development permission has been issued before the date of coming into force of these regulations and if work is not commenced within validity period and such permission is not renewed ⁽¹⁾ in time i.e. before expiry of validity period of one year, then the said development permission shall be deemed to have been lapsed. ⁽¹⁾ However, there is no bar to further renew the valid permission from year to year; but such extended period shall in no case exceed three years.

Provided further that, it shall be permissible for the owner to -

- a) Either continue to develop the project as approved under the erstwhile regulations in toto; and for that limited purpose erstwhile regulation shall remain in force.
 - ⁽¹⁾ In case the commencement certificate is issued and the construction is in progress / part occupancy issued, and if plans for additional built up area ⁽²⁾ as per erstwhile regulations are submitted to the Authority ⁽²⁾ either before or after ⁽¹⁾ coming into force of these regulations by consuming / utilising FSI / TDR as per the erstwhile regulations; but could not be sanctioned due to the pandemic situation arisen out of COVID-19, the same may be allowed to be permitted as per the erstwhile regulations in toto including the payment of premium / charges, if the applicant so desires. However, such cases shall be disposed by the authority before ⁽³⁾ 31st January, 2022; ⁽¹⁾ else such applicants will have to submit the fresh proposal as per these regulations.
 - ⁽¹⁾ Provided further that, if any development proposal ⁽²⁾ as per erstwhile regulations is ⁽¹⁾ submitted before the date of coming into force of these regulations ⁽²⁾ either upto maximum building potential or part of maximum building potential ⁽¹⁾ for which any action is not taken under the erstwhile regulations, due to the pandemic situation arisen out of COVID-19, it shall be permissible for the owner to continue the project as per the erstwhile regulations in toto ⁽²⁾ upto maximum building potential as per erstwhile regulations, if applicant so desire ⁽¹⁾ and for that limited purpose the erstwhile regulations shall remain in force. However, such cases shall be disposed by the authority before ⁽³⁾ 31st January, 2022 ⁽¹⁾ else such applicants will have to submit the fresh proposal as per these regulations or
- b) Apply for grant of revised permission under the new regulations, if the project is on-going and the occupation certificate has not been granted fully. In such cases, charges/premium etc. paid earlier ⁽¹⁾ against the FSI sanctioned / exemptions granted in side margins, allowing Residential / Commercial use on the Industrial Zone as per erstwhile regulations shall be deemed to have been paid against such earlier sanctioned FSI / exemptions / allowance of use. ⁽³⁾ In such cases ⁽¹⁾ the charges / premium under these ⁽¹⁾ regulations shall be leviable ⁽²⁾ against the revised permission and the charges / premium paid earlier shall be adjusted against the revised charges / premium under these regulations. Provided that no refund is permissible in any case.

⁽¹⁾ Inserted Vide Order No. CR 236/18 (Part-1), dt. 01st March 2021.

⁽²⁾ Inserted Vide Order No. CR 236/18 (Part-1), dt. 26th July 2021.

⁽³⁾ Inserted Vide Order No. CR 236/18 (Part 1), dt. 02nd December 2021.

- c) In case the development is started with due permission before these regulations have come into force, and if the owner / developer, at his option, thereafter seeks further development of plot / layout / buildings as per these regulations, then the provision of these regulations shall apply to the balance development. The development potential of such entire plot shall be computed as per these regulations from which the sanctioned FSI of buildings / part of buildings which are proposed to be retained as per approved plan shall be deducted to arrive at the balance development potential of such plot ⁽¹⁾ and ancillary FSI shall be permissible only on such balance potential. Such balance potential can be distributed on one or more existing, earlier / newly proposed building/s in a group housing scheme.
- ⁽¹⁾ In case of approved layouts in group housing scheme with buildings having height between 15.0 m. to 24.0 m., and complying with provisions mentioned in Regulation No.1.3(93)(xiv), NOC from Chief Fire Officer shall not be necessary, if the applicant is applying for revised permission under these regulations.
- d) The existing marginal distances including front margin may be allowed for higher floor / floors subject to step margin as per these regulations. ⁽¹⁾ In case of a building sanctioned under the erstwhile regulations as non-special one with a height of 16 m. with 3.0 m. setbacks and the construction work is in progress, then while revising the plan under these regulations, for height up to 16.0 m., the setbacks as per the erstwhile regulations shall be allowed to be continued and for the height above 16.0 m. (instead of 15.0 m.), setback as per H / 5 requirement shall be insisted in the form of step-margin.
- e) For the on-going buildings for which passages, stairs, lifts, lift rooms etc. are allowed as free of FSI by charging premium, in such cases these free of FSI items are allowed to that extent only and for the remaining balance potential, provisions for free of FSI items of these regulations shall be applicable.
- f) For the on-going buildings for which balconies are allowed to be enclosed as free of FSI by charging premium, these free of FSI items are allowed to that extent only and for the remaining balance potential balcony shall only be allowed as mentioned in these regulations.
- g) For the cases where occupation certificate is fully granted, revised permission as per these regulations, may be granted subject to provisions of Real Estate (Regulations and Development) Act, 2016, as may be applicable.
- ⁽¹⁾ Provisions mentioned in (b) to (f) shall be applicable mutatis-mutandis to the proposals to be sanctioned under this provision.
- h) If the project proponent applies for occupation with minor amendments in plans approved prior to this UDCPR, then amendment ⁽¹⁾ permitted as per the erstwhile regulations in terms of internal / locational changes, amendment to the extent of 5% in the built-up area / dimensions per floor within the permissible FSI as per then regulations may be considered.
- ⁽¹⁾ **Note** - The State Government may issue guidelines from time to time, if necessary, for smooth implementation and removal of difficulties in transitional proposals.

- 1.5 (i)** Megacity Project approved under Regulation No.15.4.3 of Mumbai Metropolitan Regional Plan shall remain valid till completion of the said project as per said regulation.

1.6 APPLICABILITY OF OTHER REGULATIONS

- i) **CRZ Regulations** - Any development within CRZ areas shall be governed by the Coastal Regulation Zone Notification No.S.O.19(E) dt. 6th January, 2011 and No.G.S.R. 37(E), dated 18th January, 2019 as amended or replaced from time to time, wherever applicable.

⁽¹⁾ Inserted Vide Order No.CR 236/18 (Part-1), dt. 01st March 2021.

⁽²⁾ Inserted Vide Order No.CR 236/18 (Part 1), dt. 02nd December 2021.

- ii) **Restriction in Western Ghat Eco Sensitive Area** - The restrictions in the Western Ghat Eco Sensitive Area imposed by the notification issued from time to time by Ministry of Environment, Forest and Climate Change, Government of India, shall be followed.
- iii) **Other Regulations** - Any other Restrictions imposed under the relevant regulations / Rules / Acts shall also be applicable, wherever applicable.

1.7 POWER TO PRESCRIBE THE PROFORMAS

⁽¹⁾ Notwithstanding anything contained in any Appendices / Proformas, provision in respective regulations shall prevail. The Authority, with the approval of Government, shall have the powers to prescribe proformas / appendices and/or make amendments in the contents of such proformas / Appendices **A to M** attached with these regulations.

1.8 POWER TO DECIDE CHARGES

The charges mentioned in these regulations for additional FSI, premium FSI, rate of interest or for any other matter shall be subject to amendment by the Government from time to time. Wherever the rate of premium is to be decided based on rates mentioned in ASR, rate in the ASR shall be of the year of granting the permission.

1.9 MEANINGS AS IN ACTS, RULES & INTERPRETATIONS

- i) Terms and expressions not defined in these regulations shall have the same meaning or sense as in the Maharashtra Regional and Town Planning Act, 1966 (Maharashtra Act No.XXXVII of 1966) or the Maharashtra Municipal Corporations Act, 1949 or National Building Code, 2005, as amended from time to time, and the rules or bye-laws framed there under, as the case may be, unless the context otherwise requires.
- ii) The Maharashtra General Clauses Act, as amended from time to time, shall be applicable in case of standard terms and phrases as defined and interpreted therein,
- iii) In these regulations, the use of the present tense includes the future tense, the masculine gender includes the feminine and neutral genders, the singular includes the plural and plural includes singular. The word "person" includes a corporation as well as an individual; "writing" includes printing, typing, e-communication and "signature" includes e-signature, digital signature and thumb impression of a person unable to sign, provided that his name is written below such impression.
- iv) Whenever sizes and dimensions of rooms and spaces within buildings are specified, they shall mean clear dimensions unless otherwise specified in these regulations. However, sizes and dimensions may not be disputed with reference to finished/unfinished surfaces unless they affect overall dimensions of the building.
- v) If any question or dispute arises with regard to interpretation of any of these regulations the matter shall be referred to the State Government, who, after considering the matter and, if necessary, after giving hearing to the parties, shall give a decision on the interpretation of the provisions of these regulations. The decision of the Government on the interpretation of these regulations shall be final and binding on the concerned party or parties.
- vi) In the case of provisions of other Acts / Rules / Regulations which are incorporated in these regulations, the amendments made subsequently in parent Acts / Rules / Regulations, will automatically be applicable, wherever applicable, to these regulations.
- vii) If a Marathi version of these Regulations exists and if there is a conflict in interpretation of any clause between English & Marathi versions of these Regulations, then the interpretation of English version shall prevail.

⁽¹⁾ Inserted vide Corrigendum / Addendum No. CR 121/21, dt. 02nd December, 2021.

1.10 REMOVAL OF DIFFICULTIES.

If any difficulty arises in giving effect to the provisions of this Unified Development Control and Promotion Regulations, the State Government may, by order published in the official Gazette, give such directions, as may appear to it to be necessary or expedient for the purpose of removing the difficulty.

Provided that, no such order shall be made after the expiry of a period of 1 years from the date of coming in to force of this Unified Development Control and Promotion Regulations.

_*_*_*_*_*_

CHAPTER - 2

DEVELOPMENT PERMISSION AND COMMENCEMENT CERTIFICATE

2.1 PERMISSION FROM THE PLANNING AUTHORITY IS MANDATORY

2.1.1 Necessity of Obtaining Permission : No person shall carry out any development work including development of land by laying out into suitable plots or amalgamation of plots or development of any land as group housing scheme or to erect, re-erect or make alterations or demolish any building or cause the same to be done without first obtaining a separate building permit / development permission / commencement certificate for each such development work / building from the Authority. As stipulated in section 18 / 46 of the Maharashtra Regional and Town Planning Act, 1966, no such permission shall be in contravention of the Regional Plan, Development Plan proposals as the case may be.

2.1.2 Permission Not Necessary - No such permission shall be necessary for :-

- i) carrying out of works in compliance with any order or direction made by any Authority under any law for the time being in force.
- ii) carrying out of works by any Authority in exercise of its powers under any law for the time being in force.
- iii) the excavation (including excavation of wells) made in the ordinary course of agricultural operation.
- iv) the construction of a road intended to give access to land solely for agricultural purpose.
- v) normal use of land which has been used temporarily for other purposes like marriage pandals or for festive occasions etc. on private land;
- vi) provision of safety grills to window / ventilator,
- vii) distribution / receiving substation of the electric supply company.
- viii) installation of solar panels having base of solar panel at height upto 1.8 m. from terrace, ensuring structural stability from the Licensed Structural Engineer.
- ix) providing internal lightweight partitions / cabins in the commercial building / establishment with certificate of structural stability from the Licensed Structural Engineer.
- x) temporary structures for godowns / storage of construction materials within the site.
- xi) temporary site offices, sample flats and watchman chowkys within the site only during the phase of construction of the main building.
- xii) temporary structures for storage of machinery before installation for factories in industrial lands within the site.
- xiii) labour camps for construction sites, provided adequate water supply and sanitation facilities are provided and safety is ensured;
- xiv) construction of temporary sets for film / TV serial / advertisement shooting and like activities for a period not more than one year, subject to intimation to the authority.
- xv) building on plot area upto 150 sq.mt. (low risk category) and on plot area more than 150 sq.mt. upto 300 sq.mt. (moderate risk category) subject to compliance as per APPENDIX - K.
- xvi) ⁽¹⁾ Construction upto 8 rooms for Agro Tourism Centre and allied activities as per Tourism Policy - 2016 in Agricultural Zone, subject to compliance as per APPENDIX-K-2

⁽¹⁾ Inserted vide Government Resolution No.CR.04/022, dt.02nd June, 2022

2.1.3 Development undertaken on behalf of Government

As per the provisions of Section 58 of the Maharashtra Regional and Town Planning Act, 1966 the office in-charge of the Government Department shall inform in writing to the Authority of the intention to carry out its purpose along with details of such development or construction as specified below and as certified by the Government Architect / Architect / Technical personnel :-

- i) An official letter by the authorized officer of Government Department addressed to the Authority, giving full particulars of the development work or any operational construction.
- ii) Ownership document and measurement plan issued by the Competent Authority of Land Records Department.
- iii) Development / building plans conforming to the provisions of Development Plan / Regional Plan and these Regulations for the proposed development work to the scale specified in these Regulations.
- iv) The proposals of the Development Plan or Town Planning Scheme or Regional Plan affecting the land.
- v) A Site Plan (of required copies) of the area proposed to be developed to the scale.
- vi) Detailed plan (of required copies) showing the plan, sections and elevations of the proposed development work to the scale, including existing building specifying either to be retained or to be demolished.

2.1.4 Operational Constructions

No permission shall be necessary for operational construction of the Government or Government undertaking, whether of temporary or permanent nature, which is necessary for the operation, maintenance, development or execution of any of the following services :

- a) Railways;
- b) National Highway;
- c) National Waterway;
- d) Airway and Aerodromes and Major Ports;
- e) Posts and Telegraphs, Telephones, Wireless, Broadcasting and other like forms of Communication excluding Mobile Towers;
- f) Regional grids, towers, gantries, switchyards, control room, relay room for transmission, distribution, etc. of electricity;
- g) Defence Authorities;
- h) Any other essential public service as may be notified by the State/ Central Government;
- i) The following constructions for operational purposes of new railway lines or tracks by the Metro Rail Administration (MRA) / Project Implementing Agency designated by the Government for the Metro rail and Mono rail / light Rail Transit (LRT) Project.

"Operation Control Centre, Playback Training Room. Administration Building, Stabling Yards, Maintenance Workshop and Training Centre, Auto Car Wash Plant and Auto Wash Plant, Auxiliary Rail Vehicle Building, Under Floor Wheel Lathe and Blow Down Plant, Cooling Tower, Generator Area, Auxiliary Sub-station, Traction Sub-station, Transformer Area, Water Treatment Plant, Waste Water Treatment Plant, Depot Control Centre, sump Area, Parking, Check Post, Loading and unloading areas, Fouling Points, DG set Rooms, Metro and Mono stations (underground and elevated), Viaduct and tunnel, Ventilation

Shaft, Entry / Exit Blocks, Passages, Underground passage to Station box, Lifts, Staircases, Escalators, Transit accommodation / Guest rooms, Metro Stations / Depots on property owned by it in all Use Zones, Air Handling Unit, Fire staircase, Fire lift and fire passages, Refuge area, thereto."

- j) Facilities & services such as Roads, Water Supply, Sewerage, Storm Water Disposal and any other essential public services carried out by State / Central Government or its undertakings / Bodies or the Local Bodies including :-
 - (a) maintenance or improvement of highway, road or public street, being works carried out on land within the boundaries of such highway, road or public street; or
 - (b) inspecting, repairing or renewing any drains, sewers mains, pipes including gas pipes, telephone and electric cables, or other apparatus including the breaking open of any street, or other land for the purpose.

Provided that the concerned authority shall inform the Planning Authority in writing at the earliest and pay the necessary restoration charges to the Planning Authority within a month. The restoration charges shall not be more than the expenditure to be incurred by the Authority to restore the road etc. along with supervision charges, if any.

All such constructions shall, however, conform to the prescribed requirements for the provision of essential services, water supply connections, drains, etc. to the satisfaction of the Authority.

2.1.5 Constructions Not Covered under the Operational Constructions

The following constructions of the Government Departments do not come under the purview of operational construction for the purpose of exemption. In such cases intimation to the authority as mentioned in above regulation shall be necessary.

- a) New residential building (other than gate lodges, quarters for limited essential operational staff and the like), roads and drains in railway colonies, hospitals, clubs, institutes and schools in case of railways;
- b) A new building, new construction or new installation or any extension thereof, in case of any other services other than those mentioned in these regulations.

2.1.6 Temporary Constructions

Permission shall be necessary for carrying out temporary construction. The Authority may grant permission for temporary construction for a period not exceeding six months at a time and in the aggregate not exceeding a period of one year. Such permission may be given by him for the construction of the following, viz. :-

- (i) Structures for protection from the rain or covering of the terraces during monsoon only.
- (ii) Pandals for fairs, ceremonies, religious functions, etc. on public land.
- (iii) Structures of exhibitions / circuses etc.
- (iv) Structures for ancillary works for quarrying operations in conforming zones.
- (v) Government milk booths, telephone booths, MAFFCO stall and ATM Centres.
- (vi) Transit accommodation for persons to be rehabilitated in a new construction.
- (vii) Structures for educational and medical facilities within the site of the proposed building during the phase of planning and constructing the said permanent buildings.
- (viii) Ready mix concrete plant.

Provided that, necessary documents along with necessary scrutiny fees shall be submitted by the applicant along with the application for temporary construction.

Provided that, temporary constructions for structures etc. mentioned at (vi), (vii) and (viii) may be permitted to be continued temporarily by the Authority, but in any case not beyond completion of construction of the main structure or building and that, structure in (iv) and (v) may be continued on annual renewal basis by the Authority beyond a period of one year.

Provided further that approval of the Chief Fire Officer of the authority shall be obtained, wherever necessary.

2.1.7 Repairs to Building

The permission shall not be required for the following types of repairs to existing authorised building, which do not amount to additions or alternations. Only intimation to the Authority by the owner alongwith the certificate of licensed personnel shall be given.

- i) Changing of doors and windows in the same position.
- ii) Strengthening of existing walls, existing roof in the same position.
- iii) Any other items similar to above.

2.2 PROCEDURE FOR OBTAINING DEVELOPMENT PERMISSION / BUILDING PERMISSION / COMMENCEMENT CERTIFICATE

2.2.1 Notice / Application

Every person who intends to carry out development or redevelopment, erect or re-erect or make alterations in any place in a building or demolish any building, shall give notice / application in writing, through registered Architect, Town Planner or Licensed Engineer / Supervisor, to the Authority of his said intention in the prescribed form (See Appendix A1 or A2). It will be mandatory to submit complete information in the form accompanied with Appendix A-1 and A-2. Such notice shall be accompanied by the payment receipt of required scrutiny fee and any other fee / charges prescribed by the Authority from time to time and the plans and statements in sufficient copies (See Regulation No.2.2.2), and as per the requirements under Regulation No.2.2.2 to 2.2.19. One set of plans shall be retained in the office of the Authority for record after the issue of permission or refusal. The plans may be submitted in electronic form as may be specified by the Authority from time to time. The Authority may set a date after which all submissions, approvals and communication in regard to development permission shall be online.

2.2.2 Information Accompanying Notice / Application

The Notice / Application shall be accompanied with the ownership title, key (location) plan, site plan, sub-division layout plan/ building plan, plans for services, specifications and certificate of supervision etc., as prescribed in these regulations. Ordinarily four copies of plans and statements shall be made available along with the notice; however, the number of such copies required shall be as decided by the Authority.

2.2.3 ^(#) Ownership title and area

Every application for development permission and commencement certificate shall be accompanied by the following documents for verifying the ownership and area etc. of the land -

- i) Latest 7/12 extracts or property register card of a date not earlier than six months prior to the date of submission of development proposal, power of attorney, wherever applicable or attested copy of lease deed of the concerned lessor authority, enabling ownership of the document. In case of Ulhasnagar, conveyance deed and/or sanad issued by the Revenue Authority may also be considered.

^(#) Clarification issued vide letter – CR.42/21 dt.14th June, 2021

- ii) Original measurement plan / city survey sheet of the land or lands under development proposal issued by Land Record Department.
- (1) Provided that, where City Survey of the whole gaothan area is not done by the City Survey Department, in that case the measurement plan authenticated by the Architect having signatures of adjacent plot / land holders may be acceptable.
- iii) Statement of area of the holding by triangulation method / CADD (Computer Aided Design and Drafting Software) from the qualified licensed technical personnel or architect with an affidavit from the owner in regard to the area in the form prescribed by the Authority.
- iv) Any other document prescribed by the Authority.
- v) In case of revised permission, wherever third party interest is created by way of registered agreement to sale or lease etc. of the apartment, consent of such interested party / persons as specified under RERA Act shall be submitted.
- vi) A self-attested copy of sub-division / amalgamation / layout of land approved by the concerned authority, if any.
- vii) In the case of land leased by the Government or Local Authorities, No Objection Certificate of Government or such Authorities shall be obtained if there is deviation from lease conditions and shall be attached to the application for development permission in respect of such land. Such No Objection Certificate shall also be necessary, where, development proposal proposes to utilise FSI more than mentioned in the lease deed.

2.2.4 Key Plan or location plan

The key plan drawn to a scale of not less than 1:4000 shall be submitted along with the application for a Building Permit and Commencement Certificate showing the boundary locations of the site with respect to neighbourhood landmarks or features within the radius of 200 m. from the site whichever is more.

2.2.5 (a) Sub-division / Layout plan

In the case of development of land, the notice shall be accompanied by the sub-division / layout plan which shall be drawn to a scale of not less than 1:500, however, for layout having areas 4.0 ha. and above, the plan shall be drawn at a scale of not less than 1:1000, containing the following :-

- i) Scale including a graphical scale used and north point;
- ii) The location within the land of all proposed and existing roads with their existing / proposed widths and all the proposals of the Development Plan / Town Planning Scheme, if any;
- iii) Dimension of plots;
- iv) The location of drains, sewers, public facilities and services, electrical lines, Natural water courses, water bodies and streams etc.;
- v) Table indicating size, area and use of all plots in the sub-division / layout plan;
- vi) The statement indicating the total area of the site, area utilized under roads, recreational open spaces, playground, amenity space, and development plan reservation / roads, schools, shopping and other public places along with their percentage with reference to the total area of the site proposed to be sub-divided / laid out;
- vii) In case of plots which are sub-divided in built-up areas in addition to the above, the means of access to each sub divided plot from existing streets.
- viii) Contour plan of site, wherever necessary.

⁽¹⁾ Inserted vide Corrigendum / Addendum No. CR 121/21, dt. 02nd December, 2021.

(b) Amalgamation Plan

Where two or more plots / holdings of same or different owners are to be amalgamated, an amalgamation plan showing such amalgamation drawn to a scale of not less than 1:500 shall accompany the application. Instead of submitting a separate plan, such amalgamation may be allowed to be shown on building / layout-plan itself.

2.2.6 Site Plan

The site plan shall be submitted with an application for building permission drawn to a scale of 1:500 or more as may be decided by the Authority. This plan shall be based on the measurement plan duly authenticated by the appropriate officer of the Department of Land Records. This plan shall have the following details :-

- i) Boundaries of the site and of any contiguous land belonging to the neighbouring owners;
- ii) Position of the site in relation to neighbouring streets;
- iii) Name of the street, if any, from which the building is proposed to derive access;
- iv) All existing buildings contained in the site with their names (where the buildings are given names) and their property numbers;
- v) Position of the building and of other buildings, if any, which the applicant intends to erect, upon his contiguous land referred to in (i) above;
- vi) Boundaries of the site and, in a case where the site has been partitioned, boundaries of the portions owned by others;
- vii) All adjacent streets, buildings (with number of storey and height) and premises within a distance of 12.0 m. of the work site and of the contiguous land (if any) referred to in (i). If there is no street within a distance of 12.0 m. of the site, the nearest existing street with its name;
- viii) Means of access from the street to the building and to all other buildings (if any) which the applicant intends to erect upon;
- ix) Space to be left around the building to secure free circulation of air, admission of light and access;
- x) The width of the street (if any) in front and the street (if any) at the side or near of the building, including proposed roads;
- xi) The direction of north line relative to the plan of the building;
- xii) Any existing physical features, such as wells, tanks, drains, pipe lines, high tension line, railway line, trees, etc.;
- xiii) Overhead electric supply lines, if any, including space for electrical transformer / substation according to these Regulations or as per the requirements of the electric distribution company;
- xiv) Any water course existing on site or adjacent to site;
- xv) Existing alignments of water supply and drainage lines;
- xvi) Such other particulars as may be prescribed by the Authority.

2.2.7 Building plan

The plans of the buildings and elevation and section to be sent with the application accompanying the notice shall be drawn to a scale of 1:100. The building plan shall :

- i) Include floor plans of all floors together with the built up area clearly indicating the sizes of rooms and the position and width of staircase, ramps and other exit ways, lift wells, lift machine room and lift pit details, meter room and electric sub-station and also include ground floor plan as well as basement plan and shall indicate the details of parking space and loading and unloading spaces provided around and within the building as also the access ways and the appurtenant open spaces with projections in dotted lines, distance from any building existing on the plot in figured dimensions along with accessory building. These plans will also contain the details of FSI calculations;
- ii) Show the statement of carpet area of every apartment or any unit along with areas of balconies and double height terraces, if any, attached to the said unit;
- iii) Show the use or occupancy of all parts of the buildings;
- iv) Show exact location of essential services, such as water closet (W.C.), bath, sink and the like;
- v) Include sectional drawings showing clearly the thickness of basement wall, wall construction, size and spacing of framing members, floors, slabs, roof slabs with the materials. The section shall indicate the height of the building, rooms and parapet, drainage and slope of the roof. At least one section should be taken through the staircase;
- vi) Show relative levels of street;
- vii) Give dimensions of the projected portion beyond the permissible building line;
- viii) Include terrace plan indicating the drainage and the slope of the roof;
- ix) Give indication of the north line relative to the plan;
- x) Details of parking spaces provided;
- xi) Give dimensions and details of doors, windows and ventilators;
- xii) Give the area statement with detailed calculation chart of each floor of the building or area as per periphery line of construction (P-line) excluding ducts and voids;
- xiii) Show the pump rooms, rain water harvesting system, sewage treatment plant, if any;
- xiv) Certificate of Structural Engineer about structural and earthquake safety in case of building above G + 2 or stilt + 2 structure;
- xv) Give such other particulars as may be required to explain the proposal clearly as prescribed by the Authority.

2.2.8 ^(#) Building plans for Special Buildings

The following additional information shall be furnished / indicated in the Building Plans in addition to the items (i) to (xv) of Regulation No.2.2.7;

- a) Access to fire appliances / vehicles with details of vehicular turning circle and clear motorable access way around the building of minimum 6.0 m. width;
- b) Size (width) of main and alternate staircases, wherever necessary, along with balcony approach, corridor, ventilated lobby approach;
- c) Location and details of lift enclosures;
- d) Location and size of fire lift;
- e) Smoke stop lobby / door, where provided;
- f) Refuge chutes, refuse chamber, service duct, etc.;

^(#) Clarification issued vide Order - CR 236/18 (Part 2), dt. 23rd December, 2021

- g) Vehicular parking spaces;
- h) Refuge area, if any;
- i) Details of Building Services :- Air-conditioning system with position of fire dampers, mechanical ventilation system, electrical services, boilers, gas pipes etc. ;
- j) Details of exits including provision of ramps, etc. for hospitals and buildings requiring special fire protection measures;
- k) Location of generator, transformer and switch gear room;
- l) Smoke exhaust system, if any;
- m) Details of fire alarm system network;
- n) Location of centralized control, connecting all fire alarm systems, built in fire protection arrangements and public address system etc.;
- o) Location and dimensions of static water storage tank and pump room along with fire service inlets for mobile pump and water storage tank;
- p) Location and details of fixed fire protection installations such as sprinklers, wet risers, hose reels, drenchers, CO2 installation etc.;
- q) Location and details of first aid, fire-fighting equipment's / installations;
- r) Certificate of structural engineer about structural and earthquake safety;
- s) Clearance certificate from the Chief Fire Officer of the Authority or Director of Fire services, as the case may be.

2.2.9 Service plan - Plans, elevations and sections of water / grey-water supply, sewage disposal system and details of building services, where required by the Authority, shall be made available on a scale not less than 1:100 and for layouts 1:1000.

2.2.10 Supervision

The notice shall be further accompanied by a certificate of supervision in the prescribed form as given in Appendix B, by Architect / Licensed Engineer / Supervisor / Town Planner, as the case may be. In the event of the said licensed technical personnel ceasing to be employed for the development work, further development work shall stand suspended till a new licensed technical person is appointed.

2.2.11 ^(#) Clearance from other Departments

In case of development / construction of buildings requiring clearance from the Authorities like Civil Aviation Authority, Railways, Directorate of Industries, Maharashtra Pollution Control Board, District Magistrate, Inspectorate of Boilers and Smoke Nuisance, Defence Department, Maharashtra Coastal Zone Management Authority, Archaeological Department etc., the relevant No Objection Certificates from these Authorities, whichever applicable, shall also accompany the application, where such information is not received by the authority as mentioned in Regulation No.3.1.13.

In case of building identified in Regulation No.1.3(93)(xiv), the building scheme shall also be cleared by the Fire Officer of the Authority or in absence of such Officer, by Director of Maharashtra Fire Services or an Officer authorised by him.

^(#)Clarification issued vide letter - CR 42/21/UD 12, dt. 14th June, 2021.

2.2.12 ^(#) Building / Layout Permission Scrutiny Fee

The notice shall be accompanied by a self-attested copy of receipt of payment of building / layout permission Scrutiny Fee. These fees shall be as mentioned below and shall be subject to Government orders, if any. Provided that, such fees shall not be applicable for the development proposals implemented by Government / Government Departments or Public Authorities of State or Central Government.

Sr. No.	Type of Authority	Scrutiny fee for plotted Layout	Scrutiny fee for Building Constructions.
1	For Pune, Pimpri-Chinchwad, Nagpur, Nashik, Municipal Corporations in MMR and Metropolitan Authorities area. ⁽²⁾ Special Planning Authorities, NTDA, ADA within these areas.	Rs. 2,000/- per 0.4 hector or part thereof .	Rs. 5/- Per Sq.m. of built-up area.
2	Remaining all Municipal Corporations area, A Class Municipal Councils and Mumbai Metropolitan Regional Plan area.	Rs. 1,500/- per 0.4 hector or part thereof.	Rs. 4/- Per Sq.m. of built-up area.
3	B and C Class Municipal Councils, Nagar Panchayats, Non Municipal Council D.P. and Regional Plan areas.	Rs. 500/- per 0.4 hector or part thereof.	Rs. 2/- Per Sq.m. of built-up area.

Note -

- No scrutiny fee shall be levied if the proposal is received after compliance of the objections raised by the authority.
- In case of revised permission, the scrutiny fee shall be applicable.
- In case of revised permission, where additional development work is proposed without disturbing the already approved development work, then the scrutiny fee shall be levied for additional development work.
- The charges mentioned above may be revised by the Authority with prior approval of the Government.
- The charges mentioned above shall also be subject to Government orders from time to time.

2.2.13 ^(#) Development Charges

Development charges as required under Section 124 A ⁽¹⁾ to 124 L of the Maharashtra Regional and Town Planning Act, 1966 shall be deposited with the Authority before issue of development permission / commencement certificate. Such charges shall be calculated for area of each land parcel included in the development permission considering the rates in ASR and provisions mentioned in the said Act.

Provided that,

- in case of revised permission, where no development is carried out in pursuance of the earlier permission and permission is lapsed, amount of difference of development charges, if any, shall be levied and recovered.

^(#) Clarification issued vide Order No.CR.236/18, dt.23rd December, 2021

⁽¹⁾ Inserted vide Corrigendum / Addendum No.CR.121/21, dt.02nd December, 2021

⁽²⁾ Inserted vide Notification No.CR.236/18 (Part 6), dt.12th October, 2022

- ii) in case of revised permission, where development is commenced in pursuance of earlier permission, development charges shall be levied on the land and built-up area, over and above the area covered in the earlier permission.
- iii) no such charges shall be levied for renewal of permission.
- iv) in case where minor amendment to the plotted layout approved prior to 10/8/1992 are proposed or where development charge for land development has already been collected in past, no development charge should be levied for such amendment of plotted layout provided no construction was proposed in the said layout i.e. only plotted layout was approved.
- v) construction of compound wall is meant for protection of property and as such no development charge shall be levied for construction of compound wall or for repairs of compound wall.
- vi) no development charge shall be recovered in respect of maintenance work, internal repairs of buildings, or for strengthening the existing building provided such works do not involve consumption of additional floor space.
- vii) for any reconstruction work, development charge shall be levied in full which involves demolition of existing building and reconstruction of new building.
- viii) in case a cooperative housing society is authorised by Maharashtra Housing and Area Development Authority or Bombay Housing and Area Development Board to undertake reconstruction of old / dilapidated building (which work would otherwise, have been undertaken by MHADA), no development charge shall be recovered from that co-operative housing society, provided the FSI does not exceed the existing or permissible FSI whichever is lower. Provided further that, it accommodates existing tenants only. Further in reconstruction involving consumption of additional FSI and accommodation of additional members other than existing tenants, proportionate development charges shall be recovered.
- ix) In case no development work is carried out in pursuance of permission and permission is lapsed or permission is cancelled on the request of the owner, the development charges paid, shall be adjusted in permission that may be granted in future.
- x) ⁽¹⁾ Where development permission is granted and development charges are already collected by any Authority in their jurisdiction and thereafter such area is included in the jurisdiction of other Authority in such cases, the provisions mentioned in Sr.No.(i) to (ix) above shall be applicable mutatis and mutandis, as the case may be.

2.2.14 ^(#) **Premium Charges and Fire Infrastructure Charges.**

- i) **Premium Charges** - Premium charges as may be required to be recovered under these regulations shall be paid to the Authority before issue of development permission / commencement certificate. The 50% Premium share of the Government shall be deposited by the Authority in a specified head of account of the Government. The amount of premium collected by the Authority shall be kept in a separate account and it shall be utilized for development of civic amenities and infrastructure.

In case of Regional Plan area, 100% premium charges shall be paid to Government through the District offices of Town Planning and Valuation Department.

The aforesaid premium charges except the premium leviable under Chapter 5 of these regulations shall be allowed to be paid in the instalments with interest @ 8.5% per annum in the following manner and subject to following conditions.

⁽¹⁾ Inserted vide Corrigendum / Addendum No.CR.121/21, dt.02nd December, 2021

^(#) Clarifications issued vide letter CR.42/21/UD-12, dt.14th June, 2021 & CR.236/18 (Part 2), dt.23rd December, 2021

A) Option - 1

a) Building below 70.0 m. height.

Initial Payment	At the end of Month with interest			
	12 th	24 th	36 th	48 th
1 st Instalment	2 nd Instalment	3 rd Instalment	4 th Instalment	5 th Instalment
10%	22.5%	22.5%	22.5%	22.5%

b) Building having height of 70.0 m. and above.

Initial Payment	At the end of Month with interest				
	12 th	24 th	36 th	48 th	60 th
1 st Instalment	2 nd Instalment	3 rd Instalment	4 th Instalment	5 th Instalment	6 th Instalment
10%	18%	18%	18%	18%	18%

B) Option - 2

The instalment of 20% shall be paid at the time of granting development permission / commencement certificate and remaining 80% amount at the time of occupation certificate. The remaining amount shall be liable for interest @ 8.5% per annum.

Notes :

- i) The instalment shall be granted with the interest at the rate of 8.5% p.a. on reducing outstanding balance premium.
- ii) The owner / developer shall deposit post-dated cheques for instalment amount with an interest due drawn on scheduled bank, as per the scheduled date of payment.
- iii) Occupation Certificate shall be granted in proportion to the payments made.
- iv) The first instalment shall not be less than 50 lakhs in case of A, B, C Class Municipal Corporations and 25 lakhs in case of other areas. ⁽²⁾ However the Planning Authority may reduce the first instalment limit as a policy by considering local conditions. ⁽²⁾ In such case, the remaining amount shall be apportioned in remaining instalments.
- ⁽²⁾ v) (Deleted). ⁽²⁾
- ii) ^(#) **Fire Infrastructure Charges** - These charges shall be decided by the Government from time to time

2.2.15 Structural Stability Certificate

In case of special buildings, the application shall be accompanied by structural stability certificate signed by the licensed Structural Engineer to the effect that the building is safe against various loads, forces and effects including due to natural disasters, such as, earthquake, landslides, cyclones, floods, etc. as per Part 11 'Structural Design' and other relevant Codes.

2.2.16 Signing the Plan

All the plans shall be duly signed by the owner, co-owner, if any, and the Architect or Town Planner or Licensed Engineer / Supervisor and shall indicate his name, address and Registration / license number (allotted by the Authority).

2.2.17 Size of Drawing sheets

The size of drawing sheets shall be any of those specified in Table 2-A.

⁽¹⁾ Inserted vide Corrigendum / Addendum No.CR.121/21, dt.02nd December, 2021

^(#) Clarification issued vide Order No.CR.103/2021, dt.2nd August, 2021

⁽²⁾ Modified / Deleted vide Directives alongwith Notice u/s.37(1AA) & 20(3) bearing No.CR.94/2024/UD-13, dt.11th October, 2024

Table 2-A - Drawing Sheet Sizes		
Sr. No.	Designation	Trimmed Size, mm
1.	A0	841 X 1189
2.	A1	594 X 841
3.	A2	420 X 594
4.	A3	297 X 420
5.	A4	210 X 297

Note : If necessary, submission of plans on sheets bigger than A0 size is also permissible. All dimensions shall be indicated only in metric units.

2.2.18 Colouring Notations for Plans

The plan shall be coloured as specified in Table No.2-B given below and prints of plan shall be on one side of the paper only.

Table No.2-B - Colouring Notations for Plans							
Sr. No.	Item	Site Plan			Building Plan		
		White Plan	Blue Print	Ammonia Print	White Plan	Blue Print	Ammonia Print
1	Plot lines	Thick Black	Thick Black	Thick Black	Thick Black	Thick Black	Thick Black
2	Existing street	Green	Green	Green			
3	Future street, if any	Green dotted	Green dotted	Green dotted			
4	Permissible building lines	Thick dotted black	Thick dotted black	Thick dotted black			
6	Existing work	Black (Outline)	White	Blue	Black	White	Blue
7	Work proposed to be demolished	Yellow Hatched	Yellow Hatched	Yellow Hatched	Yellow Hatched	Yellow Hatched	Yellow Hatched
8	Proposed work	Red filled in	Red	Red	Red	Red	Red
9	Drainage & Sewerage work	Red dotted	Red dotted	Red dotted	Red dotted	Red dotted	Red dotted
10	Water supply work	Black dotted thin	Black dotted thin	Black dotted thin	Black dotted thin	Black dotted thin	Black dotted thin
11	Deviations	Red hatched	Red hatched	Red hatched	Red hatched	Red hatched	Red hatched

Note : For land development / Sub-Division / layout / building plan, suitable colouring notations shall be used which shall be indexed.

2.2.19 Qualification and Competence of the Architect / Licensed Engineer / Structural Engineer / Town Planner / Supervisor

Architect / Engineer / Town Planner / Supervisor referred to in Regulation No.2.2.16 shall be registered / licensed by the Authority as competent to plan and carry out various works as given

in Appendix “C”. The qualification and procedure for registration and licensing of the Engineer / Structural Engineer / Town Planner / Supervisor shall be as given in Appendix-“C”. An Architect registered with the Council of Architecture shall not be required to register with the Authority.

2.3 DISCRETIONARY POWERS - INTERPRETATION

In conformity with the intent and spirit of these Regulations, the Authority may by order in writing -

- i) Decide on matters where it is observed that there is an error in any order, requirement decision, and determination of interpretation made by him or by an Officer authorized by him in the application of these Regulations.
- ii) Decide the extent of the proposal of Development Plan / Regional plan with respect to S.No. / Gut No. / CTS No. / Block No. / Barrack No. / Unit No., where boundaries shown on Development Plan / Regional plan varies with the boundaries as per revenue record / measurement plan / City Survey sheets etc.
- iii) Determine and establish the location of zonal boundaries in cases of doubt or controversy;
- iv) Decide the alignment of Development Plan road / Regional plan road where the street layout actually on the ground varies from the street layout as shown on the Development Plan / Regional plan;
- v) Correct the alignment of Blue and Red flood line on Development Plan / Regional plan where it varies with the said lines given by the Irrigation Department or any other Govt. institutions dealing with the subject, from time to time;
- (#) vi) Modify the limit of a zone where the boundary line of the zone divides a plot. In such cases, the zone covering area more than 50% shall be considered;
- vii) Authorize the erection of a building or use of premises for a public service undertaking for public utility propose only, where he finds such an authorization to be reasonably necessary for the public convenience and welfare even if it is not permitted in any Land Use Classification.
- viii) Interpret the provisions of these Regulations where there is clerical, grammatical mistake, if any.

2.4 DISCRETIONARY POWERS - RELAXATIONS IN SPECIFIC CASES

In specific cases where clearly demonstrable hardship is caused, the Authority may permit any of the dimensions / provisions prescribed by these regulations to be modified provided the relaxation sought does not violate the health safety, fire safety, structural safety, and public safety of the inhabitants of the buildings and the neighbourhood. No relaxation in the setback required from the road boundary or FSI or parking requirements shall be granted under any circumstances, unless otherwise specified in these Regulations.

While granting permission under these regulations, conditions / restrictions / limitations may be imposed on size, cost or duration of the structure, abrogation of claim of compensation, payment of deposit and its forfeiture for non-compliance and payment of premium, as may be prescribed by the Authority, if required.

In areas of Municipal Councils and Regional plan, such relaxation shall be granted in consultation with concerned Divisional Joint Director of Town Planning.

Notwithstanding anything contained in any Government Order, Government Resolution, Government Notification, etc. issued from time to time regarding powers of relaxation in Development Control and Promotional regulations, the above provision shall prevail.

^(#) Directives issued by Govt. u/s.154 vide Order CR.No.236/18 (Part 2), dt.26th September, 2022 & Clarifications issued vide Order No.CR.236/18 (Part 2) & Order No.CR.128/22, dt.26th September, 2022

2.5 ^(#) DRAFTING ERROR

Drafting errors in Development / Regional Plan which are required to be corrected as per actual situation on site or as per the city survey record or sanctioned layout etc. may be corrected by the Authority, after due verification, in case of Municipal Councils Regional Plan areas, this shall be done after consultation with the Divisional Joint Director of Town Planning.

2.6 GRANT OR REFUSAL OF PERMISSION

2.6.1 General

- i) After receipt of the notice / application as mentioned in Regulation No.2.2.1 above, the Authority may either sanction or refuse the plans or may sanction them with such modifications or directions as it may deem necessary after having recovered the necessary charges / fees and there upon shall communicate its decision to the person giving the notice in the prescribed form given in Appendix D1 / D2 / D3 and E1 / E2, as the case may be.
- ii) In the case of special buildings, the building scheme shall also be subject to the scrutiny of the Chief Fire Officer of the Local / Planning Authority or Director of Fire Services, as the case may be, and the sanction development permission shall be issued by the Authority after the clearance from him.
- iii) In the case of land subdivision or plotted layout, tentative layout shall be recommended for demarcation at first instance. After having demarcated the layout, the owner shall submit the layout as measured by the Land Records Department for final approval to the Authority. The Authority shall examine and grant final approval to the measured layout if it conforms to the regulations and is broadly in accordance with the tentative layout without any departures of substantial nature. This shall also be mandatory for Group Housing Schemes where roads in the adjoining layouts / Development Plan roads / Regional Plan roads are to be coordinated and / or amenity space/s are to be earmarked.
- iv) After the plan has been scrutinized and objections have been pointed out, the owner giving notice shall modify the plan, comply with the objections raised and resubmit it. The prints of plans submitted for final approval, shall not contain superimposed corrections. The authority shall grant or refuse the commencement certificate / building permit within 60 days from the date of resubmission. No new objections may generally be raised when they are resubmitted after compliance of earlier objections, except in circumstances to be quoted for additional compliances.
- v) After the development permission is granted by the Authority, it shall be displayed alongwith the plans on the website of the Authority, wherever such website is available.

2.6.2 Deemed Permission

If within sixty (60) days of receipt of the notice, along with necessary permission fees under the regulations, the Authority fails to intimate in writing to the person, who has given the notice; of its refusal or sanction or sanction with such modifications or directions, the notice with its plan and statements shall be deemed to have been sanctioned, provided nothing shall be construed to authorize any person to do anything on the site of the work in contravention or against the terms of lease or titles of the land.

Provided that, the development proposal, for which the permission was applied, is strictly in conformity with the requirements of these regulations or regulations framed in this behalf under any law for the time being in force and the same in no way violates either provisions of any draft or final Development / Regional Plan / Planning Proposal or proposals published by means of notice, submitted for sanction under the Act. Provided further that any development carried out in

^(#) Clarification issued vide Letter No. CR 18/21, dt. 23rd December, 2021.

pursuance of such deemed permission which is in contravention of the above provisions, shall be deemed to be an unauthorized development for purposes of Section 52 to 57 of the Maharashtra Regional and Town Planning Act, 1966 and other relevant Acts.

Provided further that, upon receipt of intimation of any claim for deemed permission the Authority shall within fifteen days from the date of receipt of such claim, communicate its remarks, if any, regarding deemed permission to the applicant, failing which, the proposal shall be approved and commencement certificate along with one set of duly approved plans for proposed development shall be issued to the applicant within fifteen days thereafter.

Provided further that, necessary explanation shall be called from the concerned officers of the Planning Authority for not processing and disposing of the proposal within 60 days and necessary action as per relevant provisions of Act / Rules shall be initiated against the defaulter officer.

2.6.3 Approval of Building Permission on Risk Based Classification

Notwithstanding Anything contained in this UDCPR, the approval to the Low or Moderate Risk category of constructions shall be governed as per the procedure given in Appendix - K.

2.6.4 Display of Sanctioned Permissions on Authority's Web-Site

After sanction of development permission, the authority shall make available all plans relating to such permission on its web-site, if available. Such documents shall be kept on web-site till one month from the date of issuance of last occupation certificate.

2.7 COMMENCEMENT OF WORK

2.7.1 ^(#) Commencement

The commencement certificate / development permission, as approved, shall remain valid for 4 years in the aggregate but shall have to be renewed every year from the date of its issue. The application for renewal shall be made before expiry of one year if the work is not already commenced. Such renewal can be done for three consecutive terms of one year after which proposals shall have to be submitted to obtain development permission afresh. If application for renewal is made after expiry of the stipulated period during which commencement certificate is valid, then the Authority may condone the delay for submission of application for renewal by charging ⁽¹⁾ fees at the rate of 1/3 of amount as per Regulation No.2.2.12 per year, but in any case, commencement certificate shall not be renewed beyond 4 years from the date of commencement certificate / development permission.

Provided that, no such renewal shall be necessary if the work is commenced within the period of valid permission and such permission shall remain valid till the work is completed.

For the purpose of this regulation, "**Commencement**" shall mean as under :-

For a building work including additions and alterations	Upto plinth level or where there is no plinth upto upper level of lower basement or stilt as the case may be.
For bridges and overhead tanks construction	Foundation and work up to the base floor/ underground floor
For underground works/	Foundation and work upto floor of underground floor.
For layout, sub-division and amalgamation	Final demarcation and provision of water bound macadam roads complete.

2.7.2 Development of Land Sub-division / Group Housing Schemes

In case of land subdivision / group housing schemes, it shall be the responsibility of the owner / developer to construct all infrastructure including roads with storm water drains, sewer lines, water supply lines, development of recreational open spaces etc.

^(#) Clarification issued vide Order No.CR.236/18, dt.23rd December, 2021

⁽¹⁾ Inserted vide Corrigendum / Addendum No.CR.121/21, dt.02nd December, 2021

In case of land subdivision, these works shall generally be completed within two years and phase wise building permission shall be granted depending upon the percentage of infrastructure work completed. The layout plots should be released for construction in stages according to infrastructure work completed. The condition to that effect shall be incorporated in the development permission / commencement certificate.

In case of group housing scheme, these works shall be completed before completion of the project and occupancy certificate shall be granted phase wise as per completion of infrastructure work.

After handing over roads and infrastructure to the Authority on completion of scheme, the responsibility of maintenance of such roads and infrastructure shall lie with the Authority. However, internal roads and infrastructure in the group housing scheme shall be maintained by the owner / society.

2.8 PROCEDURE DURING CONSTRUCTION

2.8.1 Owner / Developer / Architect / Town Planner / Engineer / Structural Engineer / Supervisor or any licensed technical person's Responsibilities in their respective domain.

- i) Neither granting of the development permission nor the approval of the drawings and specifications, nor the inspections, made by the Authority during erection of the building shall, in any way relieve the Owner / Developer / Architect / Town Planner / Engineer / Structural Engineer / Supervisor or any licensed technical person, of such building / development from full responsibility for carrying out the work in accordance with the requirements of these regulations and safety norms as prescribed by the bureau of Indian Standards.
- ii) Every owner / developer shall :
 - a) permit the Authority or his representative to enter the building or premises for which the permission has been granted at any reasonable time for the purpose of enforcing these Regulations.
 - b) submit the certificate for execution of work as per structural safety requirements and give written notice to the Authority regarding completion of work.
 - c) give written notice to the Authority in case of termination of services of a Technical professional engaged by him.

2.8.2 Results of Test

Where tests of any materials are made to ensure conformity with the requirements of these regulations, records of the test data shall be kept available for inspection during the construction of the building and for such period thereafter as may be required by the Authority.

2.8.3 Display Board

As soon as the development / building permission is obtained, the owner / developer shall install "Display Board" on conspicuous place on site indicating following details :-

- i) Name and address of owner, developer, all concerned licensed persons;
- ii) Survey number / city survey number of land under reference;
- iii) Order number and date of grant of development / building permission / redevelopment permission issued by the Authority;
- iv) Built up area permitted;
- v) RERA registration no;
- ⁽¹⁾ vi) Software QR Code for the Project generated in online building permission.

Such Display Board shall not be required for individual plot holder's individual building.

⁽¹⁾ Inserted vide Corrigendum / Addendum No. CR 121/21, dt. 02nd December, 2021.

2.8.4 Plinth Checking

The owner shall give intimation in the prescribed form in Appendix - F to the Authority after the completion of work upto plinth level. This shall be certified by Architect / licensed Engineer / Supervisor with a view to ensure that the work is being carried out in accordance with the sanctioned plans. After such intimation, the construction work shall be carried out further. The officers of the Authority, who are empowered to grant development permission and subordinate officers to him, shall each, inspect about 10% of such plinth certified cases.

2.8.5 Deviation During Construction

If during construction of a building, any deviation of a substantial nature from the sanctioned plans is intended by way of internal or external additions, sanction of the Authority shall be necessary. A revised plan showing the deviation shall be submitted and the procedure laid down for the original plans shall apply to all such amended plans. Any work done in contravention of the sanctioned plans, without prior approval of the Authority, shall be deemed as un-authorised. However, any changes made within the internal layout of a residential or commercial unit, which do not violate FSI or other regulations, shall not be treated as unauthorised. Such changes shall be incorporated in plan along with completion certificate. Provided that revised permission may also be granted after completion of work before obtaining full occupancy certificate.

2.9 COMPLETION CERTIFICATE

The owner through his Architect / licensed engineer / town planner / supervisor, as the case may be, who has supervised the construction, shall furnish a building completion certificate to the Authority in the form in Appendix - G. This certificate shall be accompanied by three sets of plans of the completed development, the certificate about the operation of the lift from consultant and certificate of structural stability, wherever necessary.

In case of special buildings, the Completion Certificate shall also be accompanied with the NOC from Chief Fire Officer of respective Authority or Director of Fire services, as the case may be.

2.10 OCCUPANCY CERTIFICATE

The Authority after inspection of the work and after satisfying himself that there is no deviation from the sanctioned plans as mentioned in Regulation No.2.8.5, issue an occupancy certificate in the form in Appendix – H or refuse to sanction the occupancy certificate in Appendix - I within 21 days from the date of receipt of the said completion certificate, failing which the work shall be deemed to have been approved for occupation, provided the construction conforms to the sanctioned plans. One set of plans, certified by the Authority, shall be returned to the owner along with the occupancy certificate. Where the occupancy certificate is refused or rejected, the reasons for refusal or rejection shall be given in intimation of the rejection or the refusal. The applicant may request for Deemed Occupancy Certificate, if eligible, as above. The Authority shall issue the Deemed Occupancy Certificate within 15 (fifteen) days of the application.

In case of Special buildings, the occupancy certificate shall be issued by the Authority only after the clearance from the Chief Fire Officer regarding the completion of work from fire protection point of view.

2.11 PART OCCUPANCY CERTIFICATE

When requested by the holder of the development permission, the Authority may issue a part occupancy certificate for a building, or part thereof, before completion of the entire work as per development permission, provided sufficient precautionary measures are taken by the holder of the development permission to ensure public safety and health of the occupants and users of the

said portion of the building. The part occupancy certificate shall be subject to the owners indemnifying the Authority in the form in Appendix 'J'.

2.12 INSPECTION

The Authority shall have the power to carry out inspection of the work under the provisions of the Act, at various stages to ascertain whether the work is proceeding as per the provisions of regulations and sanctioned plan.

2.13 UNSAFE BUILDINGS

All unsafe buildings shall be considered to constitute danger to public safety and hygiene and sanitation and shall be restored by repairs or demolished or dealt with as otherwise directed by the Authority. The relevant provisions of the regulations / Act shall apply for procedure of actions to be taken by the Authority for unsafe buildings.

2.14 OFFENCES AND PENALTIES

- i) Any person who contravenes any of the provisions of these regulations, any requirements or obligations imposed on him by virtue of the Act or these regulations, shall :-
 - (a) be guilty of an offence and upon conviction, shall be punished as stipulated in Section 52 of the Act;
 - (b) be subject to further suitable actions including demolition of unauthorised works, as stipulated under Section 53 and 54 of the Act;
 - (c) where such person is a Licensed Engineer / Structural Engineer / Town Planner / Supervisor, be subject to suitable action against him which may include cancellation of license and debarring him from further practice/ business for a period as may be decided by the Authority. ⁽¹⁾ Thereupon such Licensed Engineer / Structural Engineer / Town Planner / Supervisor shall be considered debarred for respective district;
 - (d) where such person is a registered Architect, be subject to action of the Council of Architecture as per the provisions of the Architects Act, 1972 based on the report of the Authority and debarring him from further practice/ business for a period as may be decided by the Authority.
- ii) Any person who neglects any requirements or obligations imposed on him including the maintenance of fire protection services, appliances and lifts in working order or who interferes with or obstructs any person in the discharge of his duties shall be guilty of an offence as specified in Section 36 of the Maharashtra Fire Prevention and Life Safety Measures Act, 2006 and, upon conviction, shall be subject to penalties and other consequences spelt out in said Act.

2.15 REVOCATION OF PERMISSION

- i) Without prejudice to the powers of revocation conferred by Section 51 of the Act the Authority may, after giving the opportunity of being heard, revoke any development permission issued under these regulations where it is noticed by it that there had been any false statement or any misrepresentation of material fact in the application on the basis of which the development permission was issued and thereupon the whole work carried out in pursuance of such permission shall be treated as unauthorised.
- ii) In the case of revocation of the permission under sub-regulation (i), no compensation shall be paid.

_*_*_*_*_*_*_

⁽¹⁾ Inserted vide Corrigendum / Addendum No.CR.121/21, dt.02nd December, 2021

CHAPTER - 3

GENERAL LAND DEVELOPMENT REQUIREMENTS.

3.1 REQUIREMENTS OF SITE

3.1.1 Site not Eligible for Construction of Building

No piece of land shall be used as a site for the construction of building,

- i) If the Authority considers that the site is insanitary, incapable of being well drained or is dangerous to construct a building on it;
- ii) If the entire site is within a distance of 6.0 m. from the edge of water mark of a minor water course (like nallah, canal) and 15.0 m. from the edge of water mark of a major water course (like river) shown on Development Plan / Regional Plan or village / city survey map or otherwise;

Provided that where a minor water course passes through a low lying land without any well-defined banks, the owner of the property may be permitted by the Authority to canalise water course within the same land without changing the overall alignment and the position of the inlet and outlet of the water course according to cross section as determined by the Authority. In such case, marginal open space shall be as stipulated under these regulation and shall be measured from edge of the trained nallah;

- iii) If the site is hilly and having gradient more than 1:5;
- iv) If the site is not drained properly or is incapable of being well drained;
- v) If the owner of the building has not proposed appropriate measures required to safeguard the construction from constantly getting damp to the satisfaction of the Authority;
- vi) In case the building is proposed on any area filled up with carcasses, excreta, filth and offensive matter, then certificate from the Authority to the effect that it is safe from the health and sanitary point of view, to be built upon, is required;
- vii) If the use of the site is for the purpose, which in the opinion of the Authority will be a source of annoyance to the health and comfort of the inhabitants of the neighbourhood;
- viii) If the proposed occupancy of the building on the site does not conform to the land use proposals in the development plans / Regional Plan or Zoning Regulations;
- ix) If the level of the site is less than prescribed datum level depending on topography and drainage aspects;
- x) If it doesn't derive access from an authorized street/means of access of adequate width as described in these Regulations;
- xi) If it is within the river and blue flood line of the river (prohibitive zone), unless otherwise specified in these regulations;
- xii) If the site is within the boundary of Coastal Regulation Zone where CRZ Regulation does not allow development;
- xiii) If the site is not developable by virtue of restrictions imposed under any law or guidelines of any Government Department;
- xiv) If the entire site is within a distance of 50.0 m. from the mean high flood level of a wetland. The mean shall be calculated as per the provisions of Wetlands (Conservation and Management) Rules, 2017.

3.1.2 Distance of Site from Electric Lines

No structure including varandah or balcony shall be allowed to be erected or re-erected or any additions or alterations made to a building on a site within the distance quoted in Table No.3 below in accordance with the prevailing Indian Electricity Rules and its amendments from time to time between the building and any overhead electric supply line.

Table No. ⁽¹⁾ 3 - Distance of site from Electric Lines		
Electric Lines	Vertical (Meters)	Horizontal (Meters)
Low and medium voltage Lines	2.50	1.20
High voltage lines up to and including 33000 V.	3.70	2.00
Extra High voltage lines beyond 33,000 V.	3.70	2.00
	(Plus 0.3 m. for every additional 33,000 V. or part thereof)	
Note - The minimum clearance specified above shall be measured from maximum sag for vertical clearance and from maximum deflection due to wind pressure for horizontal clearance.		

3.1.3 Construction within Blue and Red Flood Line

i) Where Blue and Red flood line are marked on the Development Plan / Regional Plan or received from the Irrigation Department.

- a) The Red Flood Line and Blue Flood Line shall be considered as per the plan prepared by the Irrigation Department. The area between the river bank and blue flood line (Flood line near the river bank) shall be prohibited zone for any construction except parking, open vegetable market, garden, lawns, open space, cremation and burial ground, sewage treatment plant, water / gas / drainage pipe lines, public toilet or like uses, provided the land is feasible for such utilization.

Provided that, redevelopment of the existing authorised properties, within river bank and blue flood line, may be permitted at a plinth height of 0.45 m. above red flood line level.

- b) Area between blue flood line and red flood line shall be restrictive zone for the purposes of construction. The construction within this area may be permitted at a height of 0.45 m. above the red flood line level.
- c) If the area between the river bank and blue flood line forms part of the entire plot in Development Zone, then, FSI of such part of land may be allowed to be utilised on the remaining land.
- d) The red and blue flood line, if shown on the Development / Regional Plan / Planning Proposal shall stand modified as and when it is modified by the Irrigation Department.

ii) Where Blue and Red flood line is not marked on the Development Plan / Regional Plan or not received from the Irrigation Department.

Where Blue and Red flood line is not marked on the Development Plan / Regional Plan or not received from the Irrigation Department, the tentative Blue line shall be earmarked taking into consideration maximum observed flood level records available locally and also interacting with the residence in the area. The plan showing such tentative Blue line shall be got approved from Chief Engineer, Irrigation Department. The distance of 50.0 m. on landward side from this tentative Blue line shall be treated as No Construction Zone.

⁽¹⁾ Substituted vide Corrigendum / Addendum No.CR.121/21, dt.02nd December, 2021

In such cases, provisions of Regulation No.3.1.3(i)(a,b,c,d) shall be applicable to that extent.
Till such tentative Blue line is prepared and marked on the plan, the development permission shall be governed by the provisions of Regulation No.3.1.1(ii).

3.1.4 Development within 30.0 m. Distance from Railway Boundary

For any construction within 30.0 m. from railway boundary, No Objection Certificate from Railway Authority shall be necessary.

3.1.5 Environmental Clearance

Environmental clearance certificate shall be submitted for the project as may be prescribed by the Ministry of Environment from time to time.

3.1.6 ^(#) Development along Highways / Classified Roads

The development along the highways shall be subject to the provisions of State Highways Act, 1965 and National Highway Act, 1956 and orders issued by Public Works Department, directives issued by Urban Development Department vide Resolution No.TPS-1819/UOR-36/19/UD-13, dated 5.8.2019 in this regard, from time to time. ⁽¹⁾ All the classified roads passing through the ⁽¹⁾ ULBs i.e. Municipal Corporations / Municipal Councils / Nagar Panchayats shall be treated as city roads.

A service road as specified in Regulation No.3.3.8 shall be provided along State and National Highways on both sides. Where service road of 12.0 m. width is already provided in adjoining land, such service road of the same width may be continued in the development permission. Such service roads may not be insisted if it has no continuity from junction to junction due to existing authorised development / construction.

3.1.7 Development within certain distance from the Prison Premises

The development within 150 m., 100 m., 50 m. from the perimeter wall of Central Prison, District Prison and any Sub Prison respectively shall be regulated and may be permitted with prior consent of the committee constituted in this regard by the Home Department. This provision shall be subject to the orders issued by the Government from time to time.

3.1.8 Distances from land fill sites

For any residential development, segregating distance from the land fill site shall be observed as specified under Solid Waste Management Rules in force from time to time or as specified by competent authority.

3.1.9 Restrictions in the vicinity of Airport

For structure, installations or buildings including installations in the vicinity of aerodromes,

- i) The height shall be restricted to permissible top elevation as mentioned on Colour Coded Zoning Maps (CCZM) prepared by the Airport Authority of India (AAI) published on its web site.
- ii) For any additional height beyond that mentioned in i) above, prior NOC from AAI shall be submitted.
- iii) For the areas depicted in red colour on CCZM, prior NOC from AAI shall be submitted.

Note -

- a) The height permitted by CCZM is indicated Above Mean Sea Level i.e. AMSL.
- b) Building height permitted i.e. Above Ground level (AGL) shall be calculated as CCZM height minus the site elevation of the plot.

Height of building (AGL) = CCZM height - site elevation.

⁽¹⁾ Inserted vide Corrigendum / Addendum No.CR.121/21, dt.02nd December, 2021

^(#) Clarification issued vide Order No.CR.236/18 (Part -2), dt.23rd December, 2021

- c) In absence of aforesaid map, no objection certificate of Airport Authority of India shall be required.

Explanation

- i) Irrespective of their distance from the aerodrome, even beyond the 20 km. limit from the aerodrome reference point, no building, radio masts or similar installation exceeding 150 m. in height shall be erected without prior permission of the Civil Aviation Authorities.
- ii) The location of a slaughter house / abattoir / butcher house or other areas for activities like depositing of garbage which may encourage the collection of high flying birds, like eagles and hawks, shall not be permitted within 10 km. from the aerodrome reference point.

3.1.10 Restrictions in the Vicinity of Ancient Monuments

- 1) The Restrictions for Development in the vicinity of the protected monuments of national importance as prescribed under the Ancient Monuments and Archaeological Sites and Remains Act, 1958 shall be observed.
- 2) The Restrictions for Development in the vicinity of the protected monuments of state importance as prescribed under Ancient Monuments and Archaeological Sites and Remains Act, 1960 shall be observed.

3.1.11 Restriction under the Works of Defence Act, 1903

The restrictions imposed under the Work of Defense Act, 1903 shall be applicable and no development in contravention with the notification shall be permissible.

Whether the area affected by the notification under Works of Defense Act - 1903, is earmarked in Development Plan / Regional Plan or not, it shall be permissible to treat the area under such restrictive zone as marginal distance at the time of construction of any building proposed on contiguous unaffected area.

Provided that, it shall be permissible to utilise the FSI and also the receiving potential of the land under this zone, as otherwise permissible, on the remaining contiguous unaffected land of the same land owner.

3.1.12 Distance from Natural Lake and Dam

In Regional Plan area, no construction shall be allowed within 100 m. from the high flood line of natural lake.

In Development Plan area, development around natural lake shall be governed by the provisions made in such plan. In absence of the provisions in such plan the distance as may be specified by Irrigation Department shall be followed.

The regulation regarding clear distances from the High flood line while carrying out any development of any land around dam and foothill areas as notified and the norms regarding distance as prescribed in Government of Maharashtra, Water Resources Department Marathi Circular No.संकिर्ण-२०१२/(प्र.क्र.२०/२०१२) सि.व्य.(महसूल), dt.08/03/2018 and amendments therein, from time to time, will be applicable henceforth, subject to following condition.

Condition :- The concerned land owners/users are prohibited to discharge any Garbage / Water Sewage / Wastage in the reservoir, generating from its premises. It will be compulsory and binding on the land owner / user to make necessary arrangements within the premises for Water and sewage disposal management and to maintain the Zero Discharge condition at his own cost.

3.1.13 Authorities to Supply Complete Information about Restrictions to the Authority

The concerned authority putting restrictions as per their respective legislations / regulations / rules as mentioned above shall make available to the Authority full details of restrictions (including graded restrictions, if any) along with the relevant map detailing restrictions. In the interest of

increasing ease of doing business, no individual applicant should be required to approach the concerned departments for NOC. However it is the duty of the applicant to ensure that restrictions informed by the above said authorities are followed scrupulously. The Authority shall make a reference to this effect to the concerned authorities and ensure compliance with the restriction informed by them while sanctioning the development permission.

Such information shall be published by the Authority on its notice board/ website and also update it as and when it is updated by the concerned department.

3.2 MEANS OF ACCESS

3.2.1 Every plot / land shall have means of access like street / road irrespective of its width.

3.2.2 In case of plot not abutting on a public means of access like street / roads etc., the plot shall have access from spaces directly connected from the street by a hard surface approach as given below :-

(a) The width of such access ways in non-congested areas shall be as follows :-

Min width of access ways	Max. Length of such access ways
6.0 m.	75.0 m.
9.0 m.	150.0 m.

(b) In congested areas, the width of such access ways shall not be less than 4.5 m.

3.2.3 Every person who intends to erect a building shall not at any time erect or cause or permit to erect or re-erect any building which in any way encroaches upon or diminishes the area set apart as means of access.

3.3 REGULATIONS FOR LAND SUB-DIVISION AND LAYOUT

3.3.1 Obligation to Prepare Layout

Building Layout or Sub-division proposal shall be submitted for the following :-

- When more than one building, except for accessory buildings in case of residential building is proposed on any land, the owner of the land shall submit proposal for proper layout of building or sub-division of his entire contiguous holding.
- When development and / or redevelopment of any tract of land which includes division and sub-division or amalgamation of plots for various land uses is proposed.
- When group housing scheme or campus / cluster planning of any use is proposed.
- A two-stage approval process as specified in Regulation No.2.6.1 will be followed for such proposals, wherever necessary.

3.3.2 Roads / streets in Land Sub-division or Layout

A) For Residential Development - The minimum width of internal road in any layout or subdivision of land shall be as given in Table No.3A.

Table No.3A - Internal Roads for Residential Development		
Sr. No.	Length of Internal Road in Layout / Sub division (m.)	Width of Internal Road in Layout / Sub Division (m.)
i	Upto 150	9.00
ii	Above 150 and upto 300	12.00
iii	Above 300	15.00

Note - For layout or part of layout where plots of 100 Sq.m. or less are proposed for Economical weaker Sections (EWS), 4.5 m. wide road of length upto 60.0 m. and 6.0 m. wide road of length upto 100 m. may be permitted so that EWS plots shall abut on both sides of such roads.

B) For Other than Residential Development : The minimum width of internal road in any layout or subdivision of land shall be as given in Table No.3B.

Table No.3B - Internal Roads for non-residential Development		
Sr. No.	Length of Internal Road in Layout / Sub division (m.)	Width of Internal Road in Layout / Sub Division (m.)
i	Upto 150	12.0
ii	Above 150 and upto 300	15.0
iii	Above 300	18.0 or more

C) Group Housing Scheme : In case of group housing schemes, minimum width of internal roads shall be as given in Table No.3C.

Table No.3C - Internal Roads for Group Housing Scheme		
Sr. No.	Length of Internal Road (m.)	Width of Internal Road (m.)
i	Upto 150	7.50
ii	Above 150 and upto 300	9.00
iii	Above 300 and upto 600	12.00
iv	Above 600	15.00

Note : It shall be necessary to provide through roads in group housing scheme of area more than 2.0 Hectares, so as to coordinate the adjoining major road links (15.0 m. and above) or give way to new road link for adjoining area. The width required for such road link shall be as per Table No.3A. This shall not bar coordination of smaller width roads approaching from adjoining area, if owners so desire. Further the Authority may insist on coordination of smaller width roads from adjoining area, if required from planning point of view.

D) Pathways

In case of Group Housing Scheme / Campus planning / Layout of Buildings, a pedestrian approach to the buildings from road / street / internal means of access, wherever necessary, shall be through paved pathway of width not less than 2.0 m., 3.0 m. & 4.5 m. provided its length measured from exit way of the building is not more than 40 m., 60 m. and 100 m. respectively from the main / internal means of access. If the length is more than 100 m., then width of the road as provided in Table No.3C shall be necessary. The marginal distances shall not be required from such pathways. However, distance between two buildings shall be maintained which will include width of such pathway.

3.3.3 Length of Internal Roads, How to be Measured

The length of Internal road shall be measured from the farthest plot (or building) to the public street. The length of the subsidiary access way shall be measured from the point of its origin to the next wider road on which it meets.

Provided that in the interest of general development of an area, the Authority may insist the means of access to be of larger width than that required under Regulation No.3.3.2.

3.3.4 Co-ordination of Roads in adjoining lands

While granting the development permission for land sub-division or group housing / campus planning, it shall be necessary to co-ordinate the roads in the adjoining lands subject to provisions mentioned in Regulation No.3.3.2.C - Note. Also, proper hierarchy of roads shall be maintained while deciding width of road.

3.3.5 Narrow Roads in Congested Areas (Core area in case of Nashik Municipal Corporation)

In congested areas, plots facing street / means of access less than 4.5 m. in width, the plot boundary shall be shifted to be away by 2.25 m. from the central line of the street / means of access way to give rise to a new street / means of access way of width of 4.5 m. clear from the structural projections. However, this will not be applicable for lane of any length serving single plot / property. In these cases, no separate setback from revised plot boundary shall be required.

3.3.6 Development of Street

Means of access / internal road shall be levelled, metalled, flagged, paved, sewer, drained, channelled, lighted, laid with water supply line and provided with trees for shade (wherever necessary), free of encroachment and shall be maintained in proper condition.

3.3.7 Development of Private Street, if neglected

If any private street or any other means of access to a building is not constructed & maintained as specified above, the authority may by written notice require the owner or owners of the several premises fronting or adjoining the said street or other means of access or abutting thereon or to which access is obtained through such street or other means of access or which shall benefit by works executed to carry out any or more of the aforesaid requirements in such manner and within such time as the authority shall direct. If the owner or owners fail to comply with this direction, the authority may arrange for its execution and recover the expenses incurred from the owner/ owners.

3.3.8 Access from the Highways / Classified Roads

(a) Generally, plots / buildings along Highways and classified roads shall derive access from service roads. However, highway amenities like petrol pump, fuel station, hotel, etc. may have a direct access from Highways and this shall be subject to the provisions of National Highway Act, 1956 and State Highways Act, 1955.

^(#) (b) Width of roads to be considered while granting development permissions, unless indicated otherwise in Development Plan / Regional Plan / Planning Proposal / T.P. Scheme shall be as mentioned in table below :-

Sr. No.	Category of Road	Width of Right of Way of Road (m.)	Remarks
1	National Highway	60.0	Width inclusive of 12.0 m. service roads on both sides
2	State Highway	45.0	Width inclusive of 9.0 m. service roads on both sides
4	Major Dist. Road	24.0	No Service road required.
5	Other Dist. Road	18.0	No Service road required.
6	Village Road	15.0	No Service road required.

^(#) Clarification issued vide Order No.CR.236/18, dt.23rd December, 2021

Notes :

- 1) If the width of any existing road is more than what is specified in above table then the greater width shall prevail.
 - 2) If the service roads are provided beyond the right of way in permission granted earlier then such service roads may be continued further in adjoining land.
 - 3) The above widths of roads may vary according to guidelines or circulars issued by the respective department.
- ⁽¹⁾ This provision shall be applicable to Area Development Authorities / Metropolitan Region Development Authorities / Special Planning Authorities / New Town Development Authorities and Regional Plan Areas.

3.3.9 Access Provisions for Special buildings in Regulation No.1.3(93)(xiv)

For special buildings as mentioned in 93(xiv) under Regulation No.1.3, the following additional provisions of means of access shall be ensured;

- (a) The width of the main street on which the plot abuts shall not be less than 12.0 m. in non-congested area and shall not be less than 9.0 m. in congested area, and one end of this street shall join another street of width not less than at least 9.0 m. ⁽¹⁾ in congested area and 12.0 m. in non-congested area.
- (b) The marginal distances on all its sides shall be minimum 6.0 m. and the layout for the same shall be approved taking into consideration the requirements of fire services, and the margins shall be of hard surface capable of taking the weight of fire engine, weighing up to 45 tonnes. The said marginal distances shall be kept free of obstructions and shall be motorable.
- (c) Main entrances to the plot shall be of adequate width to allow easy access to the fire engine and in no case it shall measure less than 6.0 m. The entrance gate shall fold back against the compound wall of the premises, thus leaving the exterior access way within the plot free for movement of fire engine / fire service vehicles. If main entrance at boundary wall is built over, the minimum clearance (headroom) shall be 4.5 m.

3.3.10 Cul-de-sacs

In addition to the provisions of Regulation No.3.3.2, Cul-de-sacs giving access to plots and extending up to 150 m. normally and 275 m. maximum with an additional turning space at 150 m. may be allowed only in residential area, provided that Cul-de-sacs would be permissible only on straight roads and provided further that cul-de-sac ends shall be higher in level than the level of starting point. The turning space, in any case shall be not less than 81 sq.m. in area with no dimension being less than 9.0 m.

3.3.11 Handing Over of Layout Roads

Whenever called upon by the Authority to do so, areas under internal layout roads shall be handed over to the Planning Authority by way of deed after development of the same, within such period as may be specified in commencement letter / development permission, for which no compensation shall be paid by the Planning Authority.

3.3.12 Intersection of Roads

At junctions of roads meeting at right angles, the rounding off at the intersection shall be done with the tangent length from the point of intersection to the curve being half the road width across the direction of tangent as shown in Fig.3A. The building shall also set back at required marginal distance from this rounding off.

⁽¹⁾ Inserted vide Corrigendum / Addendum No.CR.121/21, dt.02nd December, 2021




Fig.3A - Rounding off at junctions of right angled intersections




Fig.3B - Rounding off at junctions at acute / obtuse intersections.

3.3.13 Acute Angled Junctions

For junctions of roads meeting at less than 60 degree, the rounding off or cut-off or similar treatment shall have tangent length of U and V from the intersection point as shown in Fig.3B. The tangent length at obtuse angle junction shall be equal to half the width of the road from which the vehicle enters as shown in Fig.3B. Provided, however, that the radius for the junction rounding shall not be less than 6 m. for both types.

3.3.14 Land-locked Plot

In case of a plot surrounded on all sides by other plots or reservation, if any, i.e. a land locked plot which has no access to any street or road, the Authority may require access through an adjoining plot or plots and shall, as far as possible be nearest to the street or road, to the land locked plot, at the cost of owner of the land-locked plot & such other conditions as the Authority may specify. If the Plot is land locked by any reservation, then access may be made available by adjusting reservation within owners' land without reduction in area. Such land locked plot, upto 100 m. shall be considered as fronting on the main road from which the access of minimum 9.0 m. width is made available.

3.3.15 Approach by underpass or Over Bridge for adjoining properties

In case adjoining properties of an owner or different owner are separated by road, river, nallah etc. then the Authority may allow the owner to construct underpass or over bridge or foot over bridge

of required size at his cost so as to ease the movement of people / vehicle across the properties.

3.4 RECREATIONAL OPEN SPACES

3.4.1 Recreational Open Space

In any layout or subdivision or any development of land for any land use / zone admeasuring 0.4 ha. or more (after deducting area under D.P. / R.P. road, D.P. Reservation including deemed reservation under these regulations, if any, from the total area under development), 10% of the area under layout shall be earmarked as recreational open space which shall, as far as possible, be provided in one place. In case of land admeasuring more than 0.8 ha, such recreational open space may be allowed to be earmarked at different locations in the same layout, provided that the size and other dimensions conform to the provisions herein below. However, the owner shall be at liberty to provide recreational open space more than 10%.

^(#) i) The above-mentioned area of 0.4 ha., shall be measured with reference to original holding as on 11th January, 1967 and not with reference to sub-divided holding in revenue / city survey record thereafter without the permission under the Maharashtra Regional & Town Planning Act, 1966. However, this provision shall not be applicable to plots compulsorily got subdivided below 0.4 ha. due to the D.P./ R.P. Roads / Road widening / reservations / deemed reservations or any other proposal of the Authority.

For the lands which are sub-divided after 11th January, 1967 without taking prior permission from the Authority and having plot area below 0.4 ha., the applicant may opt for any of the options from :-

- a) providing 10% open space subject to a minimum of 200 sq.m., or
 - b) availing the reduced FSI of 75% of the basic FSI as otherwise permissible on such land. In such cases, loading of TDR shall be permissible to the extent of 50% mentioned in Chapter-6.
 - c) avail full basic FSI and other permissible FSI / TDR by paying 10% value of the land under proposal as per Annual Statement of Rates for that year, without considering guidelines therein.
- (ii) For the plots having area upto 0.4 ha. regularised under the Maharashtra Gunthewari Development (Regularisation, Upgradation and Control) Act, 2001, no such open space shall be required for the development permission: ^(u) However, for plots having area 0.4 ha. or more regularised under this Act, all the provisions of UDCPR including Recreational Open Space, Amenity space, shall be applicable.
- (iii) Not more than 50% of such recreational open space may be provided on the terrace of a podium in congested / non congested area subject to Regulation No.9.13.
- Notwithstanding anything contained in the definition of “Recreational Open Space” in these regulations, such recreational open space to the extent of 100% may be allowed to be provided on the terrace of a podium if owner / developer provides 1.5 m. strip of land along plot boundary, exclusive of marginal distances, for plantation of trees.
- (iv) In case of lands declared surplus or retainable under Urban Land (C. & R.) Act, 1976, if the entire retainable holding or entire surplus holding independently admeasures 0.4 ha or more, then 10% recreational open space shall be necessary in respective holding.
- (v) Such recreational open space shall also be necessary for group housing scheme or campus / cluster planning for any use / zone.
- (vi) Such open space shall not be necessary :-
- a) in cases of layout or subdivision of plots from a layout already sanctioned by the Authority irrespective of percentage of open space left therein.

⁽¹⁾ Inserted vide Corrigendum / Addendum No.CR.121/21, dt.02nd December, 2021

⁽⁹⁾ Clarification issued vide Order No.CR.104/2022, dt.29th November, 2022

- b) for development of the reservations in the Development Plans designated for the purpose other than residential.
 - c) for the uses other than Residential, Industrial and Educational permissible in Agricultural zone.
- (vii) In the case of development of land for educational purpose, in lieu of 10% recreational open space, following percentage of the gross area (or as decided by the Government from time to time), excluding the area under Development / Regional Plan road and Development Plan reservations, shall be earmarked for play ground. Notwithstanding anything contained in this regulation, the shape and location of such open space shall be such that it can be properly used as a playground. The area of such play ground shall not be deducted for computation of FSI. The independent play ground of the institution attached with the school building shall also be entitled for computation of FSI.

Provided that, in case of area more than 1.0 ha. such area to be earmarked for playground shall be as under :-

Sr. No.	Gross Area of Land	Percentage of Playground
1	Upto 1 ha.	40%
2	Above 1 ha. and upto 2 ha.	area as per 1 + 35% of remaining area
3	Above 2 ha. and upto 3 ha.	area as per 2 + 30% of remaining area
4	Above 3 ha. and upto 4 ha.	area as per 3 + 25% of remaining area
5	Above 4 ha.	area as per 4 + 20% of remaining area

Provided further that, in cases where space for such playground is not available because of development permissions already granted by the Authority for education purpose and work is completed, such space for playground may not be insisted.

- viii) Such recreational open space shall not be entirely proposed in marginal distances / set back or major part of it shall not be proposed in marginal distances / set back. However, such recreational open space, bigger than marginal distances and conforming to the Regulation No.3.4.6, may include part of marginal distances / set back area, if such recreational open space is proposed adjoining to plot boundary.

3.4.2 Recreational Open Space - Owner's Undertaking

The owner shall give an undertaking that the recreational open space shall be for the common use of all the residents or occupants of the layout / building unit.

- i) On sanction of the development permission, the recreational open space shall be deemed to have been vested in the society / association of the residents / occupants of the layout / building unit except as specified otherwise. In case such society or association is yet to be formed, the owner shall give undertaking to the Authority at the time of occupation certificate in case of Group Housing Scheme and at the time of final approval in case of plotted layout, that he will transfer the recreational open space at a nominal cost of Re.1/- to the society / association whenever it is formed. The recreational open space shall not be sold / leased out / allotted / transferred for any purpose, to any other person and it shall not be put to any other use except for the common use of society / association of the residents/ occupants as mentioned in Regulation No.3.4.7.
- ii) If the Authority is convinced that, either the owner has failed to abide by the undertaking or such open space is being used in violation of the provisions as prescribed in these regulations, then the Authority shall take over possession of such land of recreational open

space for maintaining it for the uses permissible in these regulations, subject to condition that it shall not be further handed over or allotted to any person / institute / authority other than the society / association of the residents / occupants.

Provided that, it shall not bar the return of the possession of such open space to the original society / association of plot owners, after taking due undertaking to that effect.

Provided further that the cost incurred by the Planning Authority on maintenance of such Recreational Open Space shall be recovered as arrears of dues to the Authority from the owner / society / association of the residents / occupants till reversion of the possession.

3.4.3 Recreational Open Space - Rearrangement

No permission shall be granted to delete / reduce open spaces of the existing sanctioned layout / subdivision. However, while revising the layout, such recreational open space may be rearranged without decrease in area subject to minimum prescribed area under these Regulations with the consent of plot / tenement holders / co-owners, but such revision of recreational open space shall ordinarily not be allowed after a period of 4 years from 1st final sanction. However, such revision of open spaces may be allowed after 4 years also, where plots in the layout are not sold or transferred.

3.4.4 Recreational Open Space - Exclusive

The open spaces shall be exclusive of means of accesses / internal roads / designations or reservations, roads and areas for road widening in Development Plan / Regional Plan.

3.4.5 ^(#) Recreational Open Space in Green Belt

Such recreational open space may be allowed to be earmarked, partly or fully, in green belt area shown on the Development Plan after leaving distance of 15.0 m. from river and 9.0 m. from nallah, provided, such recreational space is sizable as required under these regulations. Provided that, the only use and structures permissible under the Regulation No.4.11 in respect of Green belt, may be permitted in such open space.

3.4.6 Minimum Dimensions

The minimum dimension of such recreational open space shall not be less than 10.0 m. and if the average width of such recreational open space is less than 20 m., the length thereof shall not exceed 2 ½ times the average width.

3.4.7 Structures permitted in Open Space

If required, structure and uses which can be permitted without counting in FSI in the recreational open spaces shall be as under :-

- i) There may be maximum two storeyed structure with maximum 15% built up area of recreational open space, out of which, built up area on ground floor shall not exceed 10%. In case of stilt, additional floor may be allowed.
- ii) The structures used for the purpose of pavilion, gymnasium, fitness centre, club house, vipashyana and yoga centre, crèche, kindergarten, library or other structures for the purpose of sports and recreational activity (indoor or outdoor stadiums, etc. as per availability of area) may be permitted. Utilities such as water tank (underground or elevated), electric substation, generator set, pump houses, garbage treatment, public health out post/ centre may be permitted only with the consent of the society of residents. Religious structure may be allowed with the permission of competent Authority as decided by Government from time to time.
- iii) No detached toilet block shall be permitted.

^(#) Clarification issued by the Govt. vide letter No.CR.122/23/UD-12, dt.26th October, 2023

- iv) A swimming pool may also be permitted in such a recreational open space. The ownership of such structures and other appurtenant users shall vest in all the owners on account of whose cumulative holdings the recreational open space is required to be kept in the land.
- v) The proposal for the construction of such structure should come as a proposal from the owner/s, owners' society / societies or federation of owners' societies and shall be meant for the beneficial use of the owners/ members of such society / societies / federation of societies.
- vi) The remaining area of the recreational open space shall be kept open to sky and properly accessible to all members as a place of recreation, garden or a playground.
- vii) The owners' society / societies, the federation of the owners' societies shall submit to the Authority, a registered undertaking agreeing to the conditions in (v) & (vi) above while obtaining permission for the above said construction.

3.4.8 Recreational Open Space and Means of Access

Every plot meant for a recreational open space shall have an independent means of access. In case of group housing scheme, if such recreational open space is surrounded by or located along buildings and is meant for use by the occupants of those buildings, then independent means of access may not be insisted upon.

3.5 PROVISION FOR AMENITY SPACE

- 3.5.1** ^(#)In the areas of Local Authorities, Special Planning Authorities and Metropolitan Region Development Authorities, Amenity Space as mentioned below on gross area after deducting area under reservations / roads in Development Plan including proposals of road widening therein, shall have to be provided in any layout or sub division of land or proposal for development.

Area of Land	Minimum Amenity Space to be provided.
⁽¹⁾ a) less than 20000 Sq.m.	Nil
b) 20000 Sq.m. or more	5% of the total area.

These amenity spaces shall be developed by the owner for the uses mentioned in the definition of amenity. However, the Authority may insist for handing over the amenity space to the Authority, if it is required for the following ⁽²⁾ six purposes only. If it is not required for the following ⁽²⁾ six purposes and required for other purposes, it may be taken over by the Authority with the consent of the owner.

- i) Garden.
- ii) Playground.
- iii) Municipal School.
- iv) Municipal Hospital.
- v) Fire Brigade.
- vi) Housing for Project affected Persons.

In such circumstances, amenity space shall deem to be reservations / proposals in Development Plan and Floor Space Index (FSI) in lieu thereof may be made available in-situ on remaining land. The calculation of this in-situ FSI shall be shown on the layout / building plan. If the owner desires to have TDR against it, instead of in-situ FSI, then he may be awarded TDR. The in-situ FSI or TDR shall be granted only after transfer of the amenity space to the Authority. The generation of TDR or in-situ FSI shall be equivalent to the quantum mentioned in Regulation No.11.2 of Transferable Development Rights.

⁽¹⁾ Substituted Vide Notification No.CR.236/18 (Part-3), dt. 16th June 2021

⁽²⁾ Substituted vide Corrigendum / Addendum No.CR.121/21, dt.02nd December, 2021

^(#) Clarifications issued vide Order No.CR.104/2022, dt.29th November, 2022 & CR.104/2022, dt.02nd June, 2023

Provided that:-

- i) this regulation shall not be applicable where separate amenity space is mandated by the Government, while sanctioning modification proposal under section 37 or 20 of the Act. In such cases, development of the amenity shall be governed by the conditions mentioned in the said notification.
- ii) amenity space shall be approachable by minimum 12.0 m. wide road except the cases where 12.0 m. approach road to the site is not available. If in case of B & C Class Municipal Councils, Nagarpanchayats and R.P. areas, such amenity space may be located on 9 m. road, however, in such case, special building on amenity plot shall not be allowed.
- iii) this regulation shall not be applicable to Regulation No.4.8.1, (i.e.Regulation for allowing Residential / Commercial user in Industrial Zone), wherein separate provision of land for public amenities / utilities is made.
- iv) this regulation shall not be applicable where entire development permission is for amenities specified in definition of amenity space in these Regulations and also for uses other than residential permissible in agricultural zone. This regulation shall also not be applicable, if construction on entire plot is for hotel building or IT establishment / building.
- v) this regulation shall not be applicable to the Town Planning Scheme area under M. R. & T. P. Act, 1966 or similar scheme permitted in agricultural zone.
- vi) this regulation shall not be applicable for revision of earlier sanctioned development permissions granted under the regulations in force prior to these regulations and work is commenced, where no such amenity space has been provided in development permission sanctioned earlier.
- viii) if some amenity space is provided in the earlier permission, then the quantum of such amenity space in the revised permission :-
 - a) shall be limited to the area provided in earlier permission.
 - b) shall not be reduced even though area of such amenity space is more than what is specified in this regulation.
- ix) if owner agrees to construct the amenity and hands it over to the Authority with consent of the Authority, then he shall be entitled for amenity TDR / in-situ FSI as per Regulation No.11.2.
- x) the development in amenity space shall be allowed upto building potential mentioned in Regulation No.6.1 or 6.3.
- xi) any other use, not mentioned in these regulations, may be allowed to be developed by the Authority similar to the uses defined as amenity.

3.5.2 In case of Regional Plan areas, the percentage of amenity space to be provided shall be as mentioned in Regulation No.5.1.8.

3.5.3 Development of Amenity Spaces in Earlier Sanctioned Layout

Amenity spaces, which are earmarked in the layout sanctioned tentatively or finally earlier and not so far developed, may also be allowed to be developed for any of the uses mentioned in this regulation. Such amenity building may be allowed to be developed on the road on which such amenity space is located in the sanctioned layout. However, special building shall require a front road as specified in Regulation No.3.3.9.

3.6 PROVISION FOR ELECTRIC SUB-STATION

In case of development / re-development of any land, building or premises mentioned below, provision for electric sub-station shall be made as under, if the requirement for the same is considered necessary by the concerned power supply authority.

Sr. No.	Plot Area	Maximum requirements
1	Plot above 2000 sq.m.	One single transformer sub-station of the size of 5.0 m. x 5.0 m. and height of not more than 5.0 m.
2	Layout or sub-division of a plot measuring 2 .0 ha. or more.	A suitable site for an electric sub-station as required by the Power Supply Company.

Provided that the sub-station is constructed in such a manner that it is away from main building at a distance of at least 3.0 m. and in general does not affect the required side marginal distances or prescribed width of internal access or recreational open space.

3.7 MINIMUM PLOT AREA FOR VARIOUS USES

Minimum plot area for various uses shall be as given in Table No.3D below :-

Table No.3D				
Sr. No.	Uses	Min. Plot area (in sq.m.)	Min. Plot Width (in m.)	Type of Development
1	Residential and Commercial	Min 30	As per Table No. 6 D	Row / Semi-detached / detached development as specified / anticipated in earlier approved layout or layout to be approved in future. In other cases, as per permissibility of the construction area taking into consideration the marginal distances.
2	Plots in EWS Housing / High Density Housing / Sites and Services / Slum Upgradation / Reconstruction Scheme by Public Authority.	Min 20 Sq.m. or as specified in the respective scheme.		Row / Semi-detached / detached.
3	Vehicle fuel Filling station including LPG / CNG / Ethanol / Public Charging Stations for Electric Vehicles -			
	(a) Without service bay	As required by the concerned authority.	As required by the concerned authority.	Detached.
	(b) With service bay	--do --	-- do --	Detached.
4.	Industrial (other than service industries)	300	10 m.	Detached.
5	Other uses (other than 1 to 4 above)	Required plot size and development shall be governed by permissibility of construction under these regulations.		
Note -				
i) In case of plotted layout, the plot width to depth ratio shall be 1:1.5 to 1:2.5; as far as possible.				

- | |
|---|
| ii) In case of Ulhasnagar, plot sizes and development shall be considered as per the lease or sanad or patta granted by Government / Authority. |
| iii) In case of Sr.No.1 above, pattern of development permissible within a plot shall be shown in dotted line while approving the layout. However, change in pattern may be permitted in future, if it fits into above pattern of development and does not disturb the overall pattern of development already approved. |

3.8 PROVISION FOR INCLUSIVE HOUSING

3.8.1 This regulation shall be applicable only to Municipal Corporations having population 10 lacs or more as per the latest Census, as mentioned in Regulation No.3.8.2.

3.8.2 Inclusive Housing

Provision for inclusive housing shall be applicable in following cases :-

(a) For the sub-division or layout of the land :-

For the sub-division or layout of the land admeasuring 4000 Sq.m. or more (after deducting area under D.P. / R.P. Roads, D.P. Reservations including deemed reservations under these regulations, if any) for residential purpose, minimum 20% of the plot area shall have to be provided either :-

- i) in the form of developed plots of 30.0 to 50.0 sq.m. size for Economically Weaker Sections / Low Income Groups (EWS / LIG), (hereinafter referred to as “affordable plots”) for allotment to the allottees as per the list provided by MHADA, **OR**
- ii) in the form of plot / plots equivalent to 20% plot area for constructing EWS / LIG tenements to be handed over to MHADA. Within this 20% area, proportionate road and recreational open space area of this 20% space, shall be included, **OR**
- iii) Land owner / Developer can exercise an option to construct EWS / LIG tenements on the said 20% plot area as per provisions specified in subsequent Regulation No.(b).
Provided that the affordable Housing Plots / tenements as mentioned in (i, ii and iii) above can also be provided at some other location(s) within 1.0 km. from original location or within same ward, **OR**
- iv) The Land owner / Developer may handover the affordable plots to MHADA at one place in lieu of FSI / DR as per TDR regulations to be utilised on the remaining plots.
Provided that in case the Landowner / Developer desires not to utilize such additional FSI / DR in the same land, fully or partly, then he shall be awarded TDR in lieu of such unutilized additional FSI. The utilization of this TDR shall be subject to the provisions of TDR regulations.

(b) For Group Housing Scheme :-

For a plot of land, admeasuring 4000 Sq.m. or more (after deducting area under D.P. / R.P. Roads, D.P. Reservations including deemed reservations under these regulations, if any) to be developed for a Housing Scheme consisting of one or more buildings (hereinafter referred to as 'the said Scheme'), EWS / LIG Housing in the form of tenements of size ranging between 30.0 and 50.0 Sq.m. ⁽¹⁾ carpet area (hereinafter referred to as 'affordable housing tenements') shall be constructed at least to the extent of 20% of the basic FSI subject to the following conditions :-

- i) The built up area of the EWS / LIG tenements constructed under the Scheme shall not be counted towards FSI and such built-up area of EWS / LIG tenements (20%) shall be over and above the permissible FSI / TDR as per UDCPR.

⁽¹⁾ Substituted vide Corrigendum / Addendum No.CR.121/21, dt.02nd December, 2021

- ii) The Land owner / Developer shall construct the stock of the affordable housing tenements in the same plot and the Authority shall ensure that the Occupation Certificate for the rest of the development under the said scheme is not issued till the occupation certificate is issued for the Affordable Housing tenements under the scheme. Provided further that the Affordable Housing tenements can also be provided at some other location(s) within 1.0 km. from the original location or within same ward to the extent of 40% of basic permissible FSI over and above permissible built up area of the receiving \ alternative plot and such area shall be free of FSI on such alternative plot. However, Affordable Housing tenements to be constructed on such alternative plot shall be increased in proportion to the land rate of the respective lands for that year.
- iii) The Owner / Developer, after getting commencement certificate of Affordable Housing component as mentioned above shall immediately intimate to MHADA regarding the numbers of tenement to be disposed by them to the allottees. Upon such intimation, MHADA within a period of six months, from the date of receipt of such intimation, after following procedure, shall send the list of allottees and forward it to the Owner / Developer. The Owner / Developer shall allot such tenements to the allottees at the construction cost mentioned in ASR applicable of the year of disposal (date of occupancy certificate) plus 25% additional cost. Out of this 25% additional cost, 1% shall be paid to MHADA towards administration charges by the Owner / Developer.

If the allottees fails to deposit the amount in the phased manner as specified in the agreement within specified time limit, then the allotment shall stand cancelled and in such case the owner / developer shall dispose of such tenements in the market at the construction cost in ASR applicable to the land of the year of disposal plus 25% additional cost ⁽²⁾ to the persons belonging to the EWS / LIG category as determined by Government in Housing Department. This shall also be applicable for plots mentioned in (a) above.

If MHADA fails to send the list within the period of six months as specified above, ⁽²⁾ concerned Planning Authority, after following procedure as that of MHADA shall send the list of allottees within six months. If such Authority also fails to send the list as specified above, the Owner / Developer shall be at liberty to dispose of the tenements in the manner mentioned in the para above.

Provided that these regulations shall not be applicable :-

- a) in case of individual bungalow irrespective of plot area, redevelopment of existing buildings of Co-operative societies / development of buildings of Government / Semi-Government / Government controlled bodies including BOT / PPP projects or projects under taken through agency development under Regulation No.7.3, development of MHADA colony under Regulation No.7.4, Development of housing for EWS / LIG under Regulation No.7.7, Development of PMAY under Regulation No.14.4, any development in agriculture (or equivalent) zone.
- b) in case of development of reservation for Public Housing, Housing the Dis-housed, Public Housing / High Density Housing and the EWS / LIG tenements constructed under the provisions of any other Act, land exempted and developed for weaker section housing scheme under section 20 of ULC Act and allowing Residential / Commercial user in Industrial zone.
- c) if company / factory establishment proposes to construct staff quarters for their staff on their own land and such construction which is meant to be used for only staff quarters and not for sale of tenements / flats.

⁽²⁾ Inserted vide Corrigendum / Addendum No.CR.121/21, dt.02nd December, 2021

- d) lands reserved in Development Plan which are being developed under Accommodation Reservation policy.
- e) For any Housing Scheme or residential development project wherein, owing to the relevant provisions of the Development Control Regulations / Laws, 20% or more of the basic FSI is required to be utilized towards construction of residential tenements for the EWS / LIG.
- iv) The Land owner / Developer may also be permitted to utilise 1/4th of the total 20% FSI earmarked for Affordable Housing towards construction of Affordable Housing Tenements in the form of service quarters in the same or separate building which shall have to be sold as service quarters only to the purchasers of free sale flats under the said scheme.
 - ⁽¹⁾ Provided that, in case of development of erstwhile existing industries or industrial plots in Residential Zone having existing quarters for factory workers / staff / tenants, the land owner / developer shall be permitted to utilise the Affordable Housing Units for rehabilitation of such existing factory workers / staff / tenants. Also remaining Affordable Housing Units, if any, after this rehabilitation, shall be offered to MHADA for allotment. The developer shall allot such Affordable Housing tenements at the rates which can extend maximum upto rates as mentioned in Regulation No.3.8.2(b)(iii). ⁽¹⁾
- v) Affordable Housing tenements to be constructed to the extent of 20% of basic FSI only and shall not be required on additional FSI / TDR wherever permissible as per UDCPR.
- vi) Amalgamation of affordable plots / affordable tenements shall not be allowed.
- vii) The Government may nominate any other Authority instead of MAHADA mentioned in the above Regulation, if required in future.
- (c) **Prospective Applicability** : These Provisions shall be applicable prospectively and shall not be applicable to revised permission of any Layout, Housing Scheme or residential development project wherein Commencement Certificate has been issued prior to the date of coming into force of these provisions and is valid on such date. However, this provision shall be applicable to revised permission where revised permission is sought including additional area more than 4000. In such case, this provision shall be applicable to additionally included area.

Provided that, earlier permission wherein provision for affordable housing is made in accordance with the then prevailing regulations, shall also be entitled for revision under this regulation.

3.8.3 If owner / developer desires to construct inclusive housing, even though it is not mandatory, inclusive housing may be provided with prior NOC from MHADA with respect to requirement of EWS / LIG housing, then in addition to basic entitlement he shall be entitled for, additional 25% FSI of the land covered under Inclusive Housing on his remaining land.

3.8.4 Provision of Inclusive Housing shall not be applicable, if the plots are auctioned by public authorities without the condition of providing Inclusive Housing before coming into force of these regulations. However, it shall be mandatory on public authorities to stipulate the condition of providing Inclusive Housing as per provision of this regulation, while auctioning the plots hereinafter, wherever applicable.

3.9 NET PLOT AREA AND COMPUTATION OF FSI

For the purpose of computing FSI / Built-up area, the net area of the plot shall be as under :-

- i) In case of a plotted layout / sub-division / group housing scheme / any development, net area shall be the balance plot area after deducting the area covered by amenity space under

⁽¹⁾ Inserted vide Directives u/s.154 with Notice u/s.37(1AA) No.CR.87/2024, Dt.23rd July, 2024

Regulation No.3.5 and Development / Regional Plan proposals including new roads and road widening, if any, from the total area of plot.

- ii) For the purpose of computation of FSI / built-up area, the net area of the plot shall only be considered.
- iii) In case of plotted layout, the basic FSI of such net area shall be distributed on all plots on pro-rata basis or on certain plots as land owner desires, subject to maximum receiving potential prescribed in these regulations. However, such entitlement of FSI on certain plots shall be clearly mentioned on the layout plan.
- iv) In case of plots from already approved layouts, the plot area shall be treated as net plot area.
- v) The above regulations in respect of net plot area and computation of FSI shall apply to proposals in all land use zones.

3.10 TRANSFER OF LAND UNDER D.P. SITES (OTHER THAN D.P. ROAD) IN LIEU OF FSI

If in any development proposal, owner desires to hand over the reserved site / area free of cost to the Authority, then FSI of such reserved site / area equivalent to the TDR may be allowed to be utilized on the remaining land. Transfer deed to that effect shall be executed and FSI calculation shall be mentioned on the plans of development proposal. In case of plotted layout, distribution of FSI on plots in pursuance of such transfer shall be as desired by the owner and upto maximum building potential according to road width as mentioned in Regulation No.6.3. It may differ from plot to plot, however the receiving plot shall front on road having minimum 9.0 m. width. If some FSI remains unutilized, the owner shall be entitled for TDR against the remaining FSI. In such cases where in-situ FSI is proposed to be used, the procedure of DRC shall not be insisted.

3.11 RELOCATION OF D.P. / R.P. SITES / ROADS

If the land proposed to be laid out for any development is affected by any reservations of public purposes, the Authority may allow adjusting the location of such reservation to suit development without altering the area of such reservation. Provided that such shifting of the reservations shall not be permitted :-

- a) If the reservation proposed to be relocated is in parts;
- b) If the reservation proposed to be relocated is beyond 500 m. from the original location in the Development Plan;
- c) If the reservation proposed to be relocated is beyond the holding of the same owner;
- d) Unless the alternative location and size is at least similar to the location and size of the Development Plan as regards access, levels, etc.;
- e) If the reservation is already relocated under these regulations;
- f) If the land is reserved considering its geographical location like Bio-Diversity Proposal, Nallah training reservation etc. and;
- g) Unless the relocation is within area covered by the layout or development permission under sanction.

All such relocation of the reservations shall be carried out by the Authority and shall be reported to the Government and Director of Town Planning, Maharashtra State at the time of sanctioning the development permission. The Development Plan is deemed to be modified to that extent.

Notwithstanding anything contained in this regulation, the relocation of the reservation from a land may also be permitted on any land within 300 meters belonging to other owner's land if the said other owner consents (by way of registered deed) to such relocation of reservation on his land and consents to hand over his land to the Planning Authority where reservation is proposed to be relocated in lieu of TDR and also subject to restrictions mentioned in above sub Regulation

No.(d), (e), and (f). In such case, the other owner may not be insisted to submit the layout or development proposal for his land.


In case of shifting of road alignment, the same shall be allowed without change in the inlet & outlet points and also, without affecting smooth flow of traffic.

Provided that such shifting shall be carried out by the Authority in consultation with Divisional Joint Director of Town Planning in case of D class Municipal Corporations, Municipal Councils, NagarPanchayats and Regional Plan areas.

In such case of shifting, the Development Plan / Regional Plan shall be deemed to be modified to that extent.

3.12 AMALGAMATION OF PLOTS

- i) Amalgamation of plots / lands shall be permissible if they form a sizable plot from planning point of view and are contiguous. Amenity and layout plot shall also be entitled for amalgamation provided amenity is developed on proportionate area.
- ii) The amalgamation of plots from approved layout which is not desirable from planning point of view (e.g. as shown in below) shall not be permitted.



- iii) Land separated by minor water course or nallah or road may be entitled for amalgamation provided connecting over bridge or under pass of sufficient width and strength is constructed by the owner with the approval of the Authority.

3.13 DEVELOPMENT OF CYCLE TRACK ALONG RIVER AND NALLAH

3.13.1 A regulation in respect of development of cycle track along river and nallah for Nashik Municipal Corporation area is given at Regulation No.10.5.2.

3.13.2 For other Municipal Corporations, following regulations shall be applicable.

A cycle track shall be developed in green belt areas earmarked on Development Plan along the rivers. Also, cycle track be developed along the major nallah.

A distance of 6.0 m. from the edge of minor water course (nallah) is to be left as marginal distance for construction of any building. A 3.0 m. strip of land from the edge of such water course out of this 6.0 m. distance to be left shall be available for use as cycle track for general public. The compound wall shall be constructed excluding this distance of 3 m. strip for cycle track. The owner shall be entitled for FSI of this strip of land for cycle track, in-situ. This 3.0 m. wide strip shall be handed over to Municipal Corporation for which, owner shall be entitled for TDR or in-situ FSI equivalent to 35% of the area of 3.0 m. wide strip. This regulation shall be applicable for development of land along Nallahs and Green Belt areas as and when it is notified by the Municipal Commissioner after identifying such green belt and Nallahs. Where development is already taken place and it is not possible to make provision for such 3.0 m. wide cycle track, then Municipal Commissioner shall not identify such green belt / Nallahs.

CHAPTER - 4

LAND USE CLASSIFICATION AND PERMISSIBLE USES

4.1 GENERAL

- i) In case of development / re-development of any land, building or premises, the intended use shall conform to the land use or, as the case may be, purpose of designation, allocation or reservation assigned to it in the Development Plan / Regional Plan/ Planning Proposal, unless specified otherwise.
- ii) **Non-Conforming Uses Existing Lawfully** - Any lawful non-conforming use of premises existing prior to the date of coming in to force of the Development Plan / Regional Plan / Planning Proposal shall continue and may be allowed to be expanded within the holding in the original sanctioned permission and that when a building containing non-conforming use is pulled down or has fallen down, the use of the new building shall be in conformity with these regulations or with lawful existing use.
- iii) **Existing features shown on the plan** - The existing features shown on Development / Regional Plan are indicative and shall stand modified on Development / Regional Plan / Planning Proposal as per actual situation. Mention of particular use on Development / Regional Plan shall not bar the owner from permission to develop land as allowed in the zone shown for such land. Also, boundaries of S.No., alignment of existing road / nallah and other physical features of land shall be as per measurement plan of Land Records Department and the land unaffected by such physical features shall be allowed to be developed for the uses permissible under the adjoining predominant land use zone.
- iv) **Development of Parking** - The Authority may develop any land, owned by or in possession of the Authority, for public parking in any of the forms - single or multi-storeyed, underground or above ground, irrespective of its existing use or proposed use in Development / Regional Plan / Planning Proposal.
Provided that the Authority may allow Basement Parking below existing or proposed Play Ground, in the plan at one or two levels below the ground level subject to conditions, as may be prescribed by the Authority.
- v) **Discontinuance of Zoning in pursuance of existing use** - If any land is shown in Public Semi-Public zone or Public Utility Zone because of the activity that existed there or otherwise, such lands shall be deemed to have been shown in the adjacent predominant Zone after such activity ceases to exist, unless otherwise prohibited.

4.2 LAND USE CLASSIFICATION AND EQUIVALENCY OF ZONES

The different land use classifications in Development / Regional Plan / Planning Proposal & different uses permissible in that land use zone and equivalency of zone in various Authorities' areas shall be as given below :-

- I) Residential Zone - Following other zones shall be treated as equivalent to Residential zone.
 - i) Residential Zone - (R1)
 - ii) Residential Zone with Shop line - (R-2)
 - iii) General Residential Zone.
 - iv) Residential Zone - R-2 ⁽¹⁾ (----)
 - v) Residential Zone - ⁽²⁾ R-3 and R-4, with payment of ⁽²⁾ infrastructure cost as decided by the Authority.

⁽¹⁾ The word 'R-3' is deleted vide Corrigendum / Addendum under Regulation No.1.10, CR.121/21, dt.02nd December, 2021

⁽²⁾ Inserted vide Corrigendum / Addendum No.CR.121/21, dt.02nd December, 2021

- vi) Urbanisable Zone.
- vii) Special Residential Zone.
- viii) Pre-dominantly Residential Zone.
- ix) Slum Improvement Zone.
 - x) Low Density Residential Zone in Development Plan of Jalgaon.
 - xi) Mix use Zone.
- II) Low Density Residential Zone.
- III) Future Urbanisable Zone.
- IV) Commercial Zone - Following other zones shall be treated as equivalent to Commercial Zone.
 - i) Local Commercial - (C-1)
 - ii) Commercial Zone - (C-1) / Special Commercial Zone / Business Hub Area / Central Business District Zone
 - iii) Commercial Zone - (C-2)
 - iv) Predominantly Commercial
- V) Industrial Zone - Following other zones shall be treated as equivalent to Industrial Zone.
 - i) Service Industries - (I-1)
 - ii) General Industries - (I-2)
 - iii) Special Industries (I-3)
 - iv) Wholesale Market and Warehousing.
 - v) Transport Hub and Logistic Park.
- VI) Loom Industry cum Residential Zone.
- VII) Public Semi-public Zone - following zone shall be treated ⁽²⁾ as equivalent to Public Semi-public Zone.
 - i) Institutional.
- VIII) Agricultural Zone – Following other zones shall be treated as equivalent to Agricultural Zone.
 - i) Horticultural Zone.
 - ii) Plantation Zone.
 - iii) No Development Zone.
 - iv) Green Zone - 1 / Green Zone.
 - v) Cattle Shed Zone.
 - ^(*) vi) Command Area Zone with following Condition.

Condition – The Development in command Area Shall be permissible subject to prior NOC and Payment of restoration charges, if any, to Irrigation Department.
- IX) Green Belt / Green Belt Zone. (Other than Reservation of Green Belt.) / River Protection Belt. (other than reservation) - Following zone shall be treated as equivalent to Green Belt / Green Belt Zone.
 - i) Recreational land use.
- X) Traffic and Transportation Zone - Following zone shall be treated as equivalent to Traffic and Transportation Zone
 - i) Marshalling yard.

^(*) Inserted vide Order by Director of Town Planning dt.07th April, 2022

XI) Regional Park Zone.

- i) ⁽¹⁾ Recreation Centres
- ii) ⁽¹⁾ Recreational Zone
- iii) ⁽³⁾ Tourism Park
- iv) ⁽³⁾ Tourism Development Strip
- v) ⁽³⁾ Tourism Development Area
- vi) ⁽³⁾ Tourism Development Area & Cultural Kalagram
- vii) ⁽³⁾ Regional Tourism Park

XII) Tourism Development Zone - Following zone shall be treated as equivalent to Tourism Development Zone.

- i) Tourist Centre
- ii) Hill Station Zone.

XIII) Afforestation Zone – ⁽²⁾ Following zone shall be treated as equivalent to Afforestation Zone.

- i) Coastal Garden

XIV) Hill Top-Hill Slope Zone (HTHS) (Slope having gradient more than 1:5 irrespective of whether shown on plan or not.) / Hilly area.

XV) Green Zone -2

XVI) Forest Zone.

XVII) Defence Zone.

XVIII) Mines and Quarry Zone - Following zone shall be treated as equivalent to Mining and Quarry Zone.

- i) Quarry to Park Zone,

XIX) Public Utility Zone.

XX) Woodland Corridor.

XXI) Special Economic Zone.

XXII) Airport and Allied Activities / Service Zone.

Note : In case, any land use zone is not listed above, the equivalency of such zone shall be decided by the Director of Town Planning, Maharashtra State, Pune.

4.3 RESIDENTIAL ZONE - R-1

(Residential Zone R1 includes Residential plots abutting on roads below 9.0 m. in width in congested area shown on the Development Plan and on roads below 12.0 m. in width in outside congested area (i.e. in non-congested area)).

(In case of C Class M.C.s, Nagarpanchayats and R.P. areas, the above road width of 12.0 m. shall be 9.0 m. in non-congested area).

The following uses and accessory uses to the principal use shall be permitted in buildings or premises in purely Residential Zone, subject to other regulations:-

- i) Any residences, Slum Improvement / Rehabilitation.
- ii) Hostels for students / working men/ women, lodging with or without boarding facilities.
- iii) Old age home, sanatorium, orphanage, night shelter dormitories.

⁽¹⁾ Inserted vide Corrigendum / Addendum No.CR.121/21, dt.02nd December, 2021

⁽²⁾ Inserted vide DTP Order No.4274, dt.25th August, 2023

⁽³⁾ Inserted vide DTP Order No.4946, dt.10th September, 2024

-
- iv) Customary Home occupation i.e. occupations customarily carried out by the members of the household without employing hired labourer and shall include stitching, embroidery, beauty parlour, button making etc. with or without motive power. If motive power is used, the total electricity load should not exceed 1 H.P. (0.75 kw).
 - v) Medical and Dental Practitioner's Dispensaries including pathological laboratory, diagnostic clinics, polyclinics, counselling centres, clinics, to be permitted on any floor. Maternity homes, clinics, nursing homes with indoor patients with bed not exceeding 20 on any floor with separate means of access of staircase from within the building or outside may be permitted but not in any case within the prescribed marginal open spaces. Where doctor's residence is located on upper floor, then such separate means of access of staircase may not be necessary.
 - vi) Professional Offices in residential tenement for own purpose not exceeding carpet area of 50 sq.m. each.
 - vii) Community halls, welfare centre, gymnasia (each not exceeding 100 sq.m.).
 - viii) Primary and nursery schools including students' hostels except trade schools.
 - ix) Crèche, Day-care centre upto 100 sq.m. in an independent building or part of building.
 - x) Private coaching classes, student's mess in an independent building or part of building upto 100 sq.m. subject to separate parking facility in the same premises.
 - xi) Religious buildings.
 - xii) Public / City Libraries and Museums in independent building or on ground or first floor of the composite building.
 - xiii) Club Houses or gymkhanas in residential complexes.
 - xiv) Public or Private Park (except an amusement park), garden and play field in independent plot not used for business purpose.
 - xv) Bus shelters, Taxi - Rickshaw stands, trolley bus shelters, Railway Station, Metro station, BRT stand, cycle stand and like uses.
 - xvi) Convenience shops only on ground floor.
 - xvii) Police Station, Police Chowky, Government and Municipal sub-offices, Post and Telegraph Offices, Branch offices of Banks with safe Deposit Vaults, Electric sub-stations, Fire Aid posts, Home Guards and Civil Defence Centres, essential Public utilities, Pumping stations, water installations and ancillary structures thereof required to cater to the local area.
 - xviii) Electronic Industry of the Assembly type (not of the manufacturing type) with the following restrictions :-
 - a) Motive Power shall not exceed 1 H.P.
 - xix) Information technology establishment (ITE) (pertaining to software only) on the plots / premises fronting on roads having width 9.0 m. and above
 - xx) Flour mill and wet / dry masala grinding / subject to following conditions: -
 - a) Power requirement shall not exceed 10 H.P.
 - xxi) Burial grounds, cremation grounds and essential public utilities, on a road having width of 9.0 m. and above.
 - xxii) Agricultural, horticultural and allied uses (except agro-based industries).
 - xxiii) Raisin production, book binding.
 - xxiv) Public conveniences.
 - xxv) Research, experimental and testing laboratories not involving any danger of fire or explosion or of any obnoxious nature
-

4.4 RESIDENTIAL ZONE R-2

(Residential Zone R-2 includes Residential plots abutting on roads having existing or proposed width of 9.0 m. and above in congested area and 12.0 m. and above in non-congested area).

(In case of C Class M.C.s, Nagarpanchayats and R.P. areas, the above road width of 12.0 m. shall be 9.0 m. in non-congested area).

4.4.1 In this zone, the following uses, mixed uses may be permitted

- i) All uses permissible in R-1 shall be permitted in R-2 zone, without any restriction of area;
- ii) All uses or mix uses may be permitted irrespective of restriction on floor or area, except uses mentioned at Regulation No.4.8(ii), 4.11(viii, xviii, xxi, xxii, xxxi, xxxvii), 4.21 and like;
- iii) All Uses permissible in Public Semi-public Zone.

4.4.2 Uses Permitted in Independent Premises / Buildings

- i) Vehicle Fuel filling Station including LPG / CNG / Ethanol with or without service stations subject to provisions of Regulation No.4.11(vi)(c, d and e) and subject to provisions in Regulation No.6.2.2., Sr.No.6 of Table 6-E. (This station may include Electric Vehicle Charging Stations);
- ii) Trade or other similar schools;
- iii) LPG godown, Bulk storage and sale of kerosene subject to NOC of Chief Controller of Explosives, Government of India;
- iv) **Service Industries :-** The Service Industries may be permitted in independent building / Plot as given below :-
 - a) Following Industries may be permitted with power requirement not more than 10 H.P., employment not more than 9 persons and floor area not exceeding 100 sq.m.

(I) FOOD PRODUCT

- i) Manufacture of milk and dairy products such as butter, ghee, etc.;
- ii) (a) Rice huller;
- (b) Groundnut decorticators;
- (c) Grain Mill for production of flour;
- (d) Manufacture of supari and Masala grindings;
- (e) Baby oil expellers;
- iii) Manufacture of bakery products with no Floor above;
- iv) Coffee, curing roasting and grinding;
- v) Manufacture of Ice;
- vi) Sugarcane crushing & Fruit Juice;

(II) BEVERAGES & TOBACCO

- i) Manufacture of bidi (May be permitted in R-1 Zone also);

(III) TEXTILE & TEXTILEPRODUCTS

- i) Handloom / power-loom of yarn for a maximum of 4 looms;
- ii) Embroidery & making of crape laces & fringes;
- iii) Manufacture of all types of textile garments including wearing apparel;
- iv) Manufacture of made up textiles goods such as curtains, mosquito net, mattresses, bedding material pillow cases, textile bags. etc.;

(IV) WOOD PRODUCTS AND FURNITURE

Manufacture of wooden furniture and fixtures;

(V) PAPER PRODUCTS AND PRINTING PUBLISHING

- i) Manufacture of cartons and boxes from papers and paper board, paper pulp;
- ii) Printing & Publishing newspaper;
- iii) Engraving etching block making etc.;
- iv) Book binding (may be permitted in R-1 Zone also);

(VI) LEATHER PRODUCTS

Repair of footwear and other leather;

(VII) RUBBER AND PLASTIC

- i) Re-treading and vulcanizing works;
- ii) Manufacture of rubber balloons, hand gloves and allied products;

(VIII) METAL PRODUCTS

- i) Manufacture of metal building components such as grills, gates, Doors and window frames, water tanks, wire nets, etc.;
- ii) Tool sharpening and razor sharpening works;

(IX) ELECTRICAL GOODS

Repairs of household electrical appliances such as radio set. Television set, tape recorders, heaters, irons, shavers, vacuum cleaners, refrigerators, air-conditioners, washing machines, electric cooking ranges, motor rewinding works etc.;

(X) TRANSPORT EQUIPMENT

- i) Manufacturing of push cart, hand cart, etc.;
- ii) (a) Servicing and repairing of bicycle, rickshaws, motor cycle and motor Vehicles;
- (b) Battery charging and repairs;

(XI) OTHER MANUFACTURING AND REPAIR INDUSTRIES AND SERVICES

- i) Manufacture of jewellery and related articles;
- ii) Repair of watch, clock and jewellery;
- iii) Manufacture of Musical instruments and its repair;
- iv) (a) Repairs of locks, stoves, umbrellas, sewing machines, gas burners, buckets & other sundry household equipment;
- (b) Optical glass grinding and repairs;
- v) Petrol / CNG / Ethanol / All fuel filling / Electric Vehicle Charging Stations) subject to provisions in Regulation No.6.2.2., Sr.No.6 of Table 6-E;
- vi) Laundries, Laundry service and cleaning, dyeing, bleaching and dry cleaning;
- vii) Photo processing laboratories;
- viii) Electronic Industry of assembly type (and not of manufacturing type including heating load);

- ⁽¹⁾ **(XII)** Manufacture of structural stone goods, stone dressing, stone crushing and polishing, Manufacture of earthen & plaster states and images, toys and art wares and Manufacture of cement concrete building components, concrete jallies, septic tank, plaster of paris work lime mortar etc.;

⁽¹⁾ Inserted vide Corrigendum / Addendum No.CR.121/21, dt.02nd December, 2021

- b) Following service industries may be permitted without restrictions mentioned in (a) above.

(I) FOOD PRODUCT

Canning & preservation of Fruits & Vegetables, Meat and Fish including production of Jam, Jelly, Sauce, etc.;

(II) PAPER PRODUCTS AND PRINTING PUBLISHING

Printing & Publishing periodicals, books journals, atlases, maps, envelope, printing picture, post-card, embossing;

4.5 LOW DENSITY RESIDENTIAL ZONE

In this zone, all uses permissible in Residential Zone shall be permitted subject to FSI restrictions mentioned in these regulations. (Chapter 10)

4.6 FUTURE URBANIZABLE ZONE

In this zone all uses permissible in Residential Zone shall be permitted subject to fulfilment of following requirements.

- i) For extending offsite infrastructure like road, water supply, sewage line, electricity, to the land, the expenses shall be borne by the owner and shall be deposited with the Authority as per the expenses communicated by it. However the owner shall have liberty to construct such infrastructure at his own cost, as per the drawing, design and specification approved by the Authority.
- ii) If the land is located on Development Plan road of width more than 18.0 m., then construction of road of width 18.0 m. to his land, shall be the liability of the owner, else 12.0 m. wide road with asphaltting shall be necessary.

4.7 COMMERCIAL ZONE

In commercial zones, buildings or premises shall be used for the uses and purposes given below :-

- i) Any use permitted in residential R - 2 zone.
- ii) Any commercial use, wholesale establishments with or without storage area,
- iii) Uses permissible in Public Semi-public Zone.
- iv) Public utility buildings.
- v) Activities permissible in Service Industries.

4.8 INDUSTRIAL ZONE

Industries shall include any building or part of a building or structure, in which products or materials of all kinds and properties are fabricated, assembled or processed, for example assembly plants, laboratories, dry cleaning plants, power plants, pumping station; smoke houses, laundries, gas plants, refineries, dairies and saw - mills.

The following uses shall be permissible in Industrial Zone.

- i) The service industries as listed in Regulation No.4.4.2(iv) without restrictions on power requirement, employment, floor area and other restrictions.
- ii) Any industry / industries may be permitted. Minimum buffer open space / set back (which may include marginal distance and road width if any) from the boundary of industrial Building / use to residential or habitable zone/ use, shall not be less than 23.0 m. Such buffer open space shall be kept in the land falling in the industrial zone. In cases where construction has already taken place in Industrial Zone, then such Buffer open space may be kept in a Residential Zone.

Provided that, the area under such buffer open space / setback shall not be deducted for computation of FSI.

Provided further that, if the land under industrial zone is utilized entirely for non-polluting industries, IT / ITES or like purposes, then such buffer zone / open space shall not be necessary.

Provided further that, industrial godowns/ godowns shall also be permissible under this regulation.

- iii) Building or premises in industrial zone may be used for any industrial as well as accessory uses like banks, canteens, welfare centre and such other common purposes considered necessary for the industrial workers, quarters of watchmen, caretakers or other essential staff required to be maintained on the premises. Such residential / commercial / other uses may be permitted up to 25% of the total proposed built-up area of such industrial use.
- iv) Following uses may also be permitted
 - a) Parking lots,
 - b) Buildings of public utility concerns,
 - c) Buildings of Banks,
 - d) Residential Hotels, Restaurants,
 - e) Storage Buildings,
 - f) Drive-in-Theatres, cinema or theatres, subject to provisions of the Maharashtra Cinemas (Regulation) Act,
 - g) Highway amenities as permitted in Agriculture zone with FSI at par with Industrial zone,
 - h) Industrial training centre / institute,
 - i) Information Technology Establishments. (IT / ITES),
 - j) Bio-technology units,
 - k) Public Charging Stations for Electric Vehicle, Petrol pumps and Service Stations / Fuel Filling Stations including LPG / CNG / Ethanol etc. subject to provisions in Regulation No.6.2.2., Sr.No.6 of Table 6-E.
 - (l) Hospitals and dispensaries.
- v) Transport Hub and Logistic Park including warehousing, cold storage, multimodal transport, container depot, container freight stations etc.

4.8.1 Allowing Residential / Commercial Uses in Industrial Zone

In consultation with the Divisional Head of concerned division of the Town Planning Directorate in case of areas other than Municipal Corporations and in case of Municipal Corporations without such consultation, and on appropriate conditions,

- a) The existing or newly built-up area of Industrial unit in the Industrial zone (excluding the area of Cotton Textile Mills) may be permitted to be utilized for Residential or Commercial purposes;
- b) The lands in the Industrial Zone in Development Plan, Regional Plan excluding the area of Cotton Textile Mills, but including lands in industrial zone in Town Planning Scheme area, may be utilised for any of the permissible uses in the Residential and Commercial Zone subject to the following provisions :-
 - i) Such use shall be allowed only on payment of Premium at the rate of 5% of the land value arrived at as per the Annual Statement of Rates (without considering the guidelines therein) of the respective year. For calculating land value, industrial holding in the development proposal shall be considered. Out of this, 50% amount shall be paid to the Authority and 50% amount shall be paid to the Government.

- ii) The Residential / Commercial use in respect of industries which are not in operation or which are to be closed, shall not be permitted without an NOC from Labour Commissioner, Maharashtra State, Mumbai stating that all legal dues have been paid to the workers or satisfactory arrangements between management and workers have been made. However, in respect of any open land in the Industrial Zone where industry never existed, NOC from Labour Commissioner shall not be required.
- iii) Recreational open space as may be required under regulations for Residential use shall be provided.
- iv) The land to be provided as amenity space in the provisions mentioned hereunder shall be handed over to the Authority free of encumbrances.
- v) In the layout or sub-division of such land admeasuring up to 2 Ha., 10% of land shall be provided for public utilities and amenities, like electric sub-station, bus-station, sub-post office, police out-post, garden, play ground, school, dispensary and such other amenities / utilities as may be considered necessary. In case of land admeasuring more than 2 ha., such amenity space shall be 10% upto 2 ha. area and 15% for the area over and above 2 ha.
- vi) The land having area up to ⁽²⁾ 1.0 hectare in size which is allocated for industrial use may be permitted to be used for Residential purpose or any other permissible uses in Residential / Commercial Zone. The owner / developer shall provide either 10% amenity space in the form of open land or 5% built up space in the proposed construction at appropriate location, preferably on ground floor. Amenity TDR, as per regulation containing provisions of TDR, shall be permissible.
- vii) The land under public utility / amenity shall be handed over to the Planning Authority in lieu of FSI / TDR with proper access and levelling of the land. These areas will be in addition to the recreational space as required to be provided under these regulations.
- viii) At least 50% of total land provided for public amenity / utility space shall be reserved for unbuildable purposes such as garden, recreational ground, etc. by the Authority.
⁽¹⁾ Provided that if such amenity space is less than 1000 sq.m. then it shall be reserved only for unbuildable purposes such as garden, recreational ground and may be allowed on internal road / Layout road / existing road / accessroad having width less than 12.0 m.
- ix) The required segregating distance between Industrial Zone and the area over which Residential use is permitted under this regulation, shall be provided within such land intended to be used for residential or commercial purpose. In case of adjoining area is developed and obnoxious industry is existing on such part, then necessary segregation distance shall be provided. However, if non-obnoxious user is existing on such part, no such segregation distance shall be provided.
- x) Such residential or commercial development shall be allowed within the permissible FSI of the nearby Residential or Commercial Zone.
- xi) Provision for Amenity Spaces shall be considered to be reservations in the Development Plan and Transferable Development Rights against such amenity as per Regulation No.11.2 may be given or FSI of the same equivalent to the TDR quantum shall be available for utilisation on the remaining land. Moreover, the owner shall be entitled to develop remaining land with permissible TDR potential including the land under amenity space subject to maximum permissible limit of FSI (Maximum Building Potential) as mentioned in Regulation No.6.3.

⁽¹⁾ Inserted vide Corrigendum / Addendum No.CR.121/21, dt.02nd December, 2021

⁽²⁾ Inserted Vide Notification u/s.37(1AA)(C) & 20(4) by Govt. No.CR.236/18 (Part 4), dt.28th December, 2022

- xii) Residential / Commercial use may be allowed on the part area of the land holding subject to the condition that total area of the entire industrial land holding shall be considered for deciding the percentage of the land to be earmarked for public amenity / utility spaces, as per these regulations.
- xiii) If Development Plan Reservations (excluding DP Road / Road widening) falls within or adjacent to the land of the same land owner under I to R provision, then such reservation may be adjusted in amenity space in the following manner :
 - a) If the area under development plan reservation is less than the area required for public amenity space as per this regulation, then only the difference between the areas shall be provided for public amenity space.
 - b) If the area under reservation in development plan is more than the area required for public amenity space as per this regulation, then the area for public amenity space shall be provided equal to area required under this regulation.

The word "adjacent" shall also include the land of the same owner separated by nallah, river, canal, road etc., for the purpose of this regulation.
- xiv) Provisions of Accommodation Reservation mentioned in Regulation No.11.1 shall not be applicable for development of amenity space provided in this regulation.
- xv) Minimum 10% built up area (basic FSI) for area upto 1 ha. and 5% built up area (basic FSI) for area more than 1 ha., shall be used for offices and commercial purpose, in case of development undertaken under this regulation, by closing down the existing industry. However, this provision shall not be applicable, in case of permission being sought under this regulation, where such plot falls in industrial zone, without existing industry.
- ^(#) xvi) The provision of inclusive housing as mentioned in Regulation No.3.8 shall not be applicable. However, 20% of the land or FSI proposed to be used for residential purpose shall be utilised for plots below 100 sq.m.in case of plotted layout development or below 50 sq.mt. built-up area tenement in case of construction of housing scheme.
- xvii) The industrial zone on which Residential / Commercial permission is granted, it shall be deemed to be converted into Residential / Commercial zone to the extent of that area, after issuance of final occupation certificate to the project.
- xviii) If at the request of the Authority, the owner agrees to construct the amenity on the land on such amenity space, then he shall be entitled for construction TDR / FSI as per TDR Regulations.
- c) On the date of draft publication of these UDCPR, if the entire holding of a person at a place in industrial zone admeasures less than 500 sq.m., then regulation mentioned in (b) above shall not be applicable and such plot in industrial zone shall be deemed to be included in adjoining zone, if requested by the owner.
- d) If the land for industrial unit is acquired under the provisions of relevant Land Acquisition Act, then prior permission of the Government is necessary before permitting residential use on such lands and additional items and conditions mentioned in Land and Revenue Department, G.R. No.Sankirna-01/2017/C.R.11/A-2,dated 11/01/2018, as amended from time to time, shall be applicable.

(#) Clarification issued by the Govt. vide Order NO.CR.72/23/UD-12, dt.25th August, 2023

4.9 Loom Industry cum Residential Zone

The following uses shall be permissible :-

- i) Uses permissible in R - 1, R - 2 Zone according to road width;
- ii) Power loom;
- iii) Power looms cum residential to any extent;

User (i) above shall be as per conditions of R - 1 and R - 2 zone. However, (ii) and (iii) shall be permissible with following conditions;

- a) Power loom use shall be restricted up to maximum permissible floor area of 250 sq.m. with maximum 20 H.P. and 20 labourers;
- b) Total FSI permissible shall be as that of residential zone;
- c) Adequate safety measures shall be taken to reduce noise and air pollution etc. by providing vibration absorbing platform and dust settler;
- d) Working hours for looms shall be 8 am to 8 pm.

4.10 PUBLIC / SEMI PUBLIC ZONE

The following uses shall be permissible :-

- (i) Schools, Colleges, Educational Complexes, Training institutions, Hostels for students and essential staff quarters.
- (ii) Home for the aged, Hospitals, Sanatoria, Dispensaries, Maternity Homes, Health Centres and related health facilities with ancillary structures like quarters, Dharmashala, veterinary hospitals etc.
- (iii) Offices and essential staff quarters of the Government / Semi Government and / or their authorities / Local Self-Government, Courts etc., Public Housing by Government / Government Bodies.
- (iv) Public / semi-public sector utility and transport establishments / institutions of research, education and health.
- (v) Libraries, Mangal karyalayas, Gymnasias, Gymkhanas, Stadia, Community halls, Civic and Cultural Centres, Religious Structures, auditoria etc.
- (vi) Commercial use upto 15% shall be permissible subject to following conditions:-
 - a) Shop / permit rooms for liquor / wine / beer, pan, cigarette, tobacco, lottery tickets and such other uses which do not serve public purpose, similarly storage of domestic gas cylinders, kerosene etc., which are dangerous to public health, shall not be permitted.
 - b) The plots in which there is an existing development; such commercial use shall be restricted to a maximum of 15% of the existing and proposed development taken together.

Provided that, in case of lands owned by Zilla Parishad and Panchayat Samiti, which are earmarked as public and semi-public zone, the limit of such commercial use shall be up to 33%.
- (vii) Vehicle Fuel Filling Station including LPG / CNG / Public Charging Stations for Electric Vehicles as per Regulation No.6.2.2, Sr.No.6 of Table 6E.
- (viii) Nursery, crèches, Spastic rehabilitation centres, orphanages, hostel for Autistic persons and Mentally Retarded persons.
- (ix) Fire stations.
- (x) Traffic and Transport related facilities.

4.11 AGRICULTURAL ZONE

- i) All agricultural uses including stables of domestic animals, piggeries, poultry farms accessory building, tents etc.;
- ii) Golf Course and Links, Race tracks, and shooting ranges with necessary safety measures, Trekking Routes / nature trails / nature walks, etc.;
- iii) Garden, forestry, nursery, public parks, private parks; play fields, summer camps for recreation of all types;
- iv) Public / semi-public sector utility establishments such as electric sub-stations, receiving stations, switch yards, over-head line corridors, radio and television stations, receiving stations, main stations for public gas distribution, sewage treatment and disposal works, water works along with residential quarters for essential staff required for such works;
- v) L.P.G. Godown, subject to following conditions :-
 - a) Minimum plot size and area of the plot shall be as decided by concerned Licensing Authority.
 - b) The maximum permissible FSI shall be 20% on this plot.
 - c) Only ground floor structure shall be permissible.
 - d) It is necessary to obtain No Objection Certificate from Controller of Explosives and competent fire authority.
- vi) Vehicle Fuel filling Station including LPG / CNG / Ethanol / Public Charging Stations for Electric Vehicles, subject to following conditions :-
 - a) Plot shall be located on any road with a minimum width of 12.0 m. or more.
 - b) FSI for such facilities in this zone shall be up to 20% on gross area, underground structures along with kiosks shall not be counted towards FSI.
 - c) NOC from Chief Controller of Explosives shall be necessary.
 - d) In case the plot is located on any Classified road, the distance from the junction of roads as may be specified by Indian Road Congress / Ministry of Road, Transport and Highway, shall be followed. (IRC guideline 2009 and MORTH Letter No.RW/NH-33023/19/99-DO III, Dated 25.09.2003 as amended from time to time)
 - e) In a plot of Fuel Station, other building or composite building for sales office, snack bars, restaurant, public conveniences or like activities , may be permitted
- vii) Pottery manufacture.
- viii) Storage and drying of fertilizer.
- ^(#) ix) Farm houses shall be permitted subject to following conditions :-
 - a) Minimum plot area for above use shall be 0.4 Ha. However, one farm house per land holding shall be permitted, irrespective of size of the land holding.
 - ⁽¹⁾ b) The FSI shall not exceed 0.04 subject to a maximum built up area of 400 sq.m. in any case. Only ground + 1 floor structure with height not exceeding 9.0 m. shall be permissible.
- x) Swimming pools / sports and games, canteen, tennis courts, etc.

⁽¹⁾ Substituted vide Corrigendum / Addendum No.CR.121/21, dt.02nd December, 2021

^(#) Clarification issued vide Order No.CR.236/18, dt.23rd December, 2021

-
- xi) Amusement park.
 - a) Amusement park with minimum plot area of 1.0 ha. with recreational and amusement devices like a giant wheel, roller coaster, merry-go-round or similar rides both indoor and outdoor, oceanic-park, swimming pool, magic mountain and lake, ethnic village, shops for souvenirs / citations, toys, goods, as principal uses and ancillary activities such as administrative offices, exhibition hall or auditorium, open air theatre, essential staff quarters, store buildings, fast food shops, museum, small shops, ancillary structures to swimming pool, ancillary constructions along with staff quarters and residential hotels. Maximum permissible FSI shall be 0.70 on gross plot area, out of which 0.20 shall be without payment of premium and remaining with payment of premium at the rate of 20% of the rate mentioned in the annul statement of rates of very said land without considering the guidelines therein.
 - b) The required infrastructure, like proper and adequate access to the park, water supply, sanitation, conservancy services, sewage disposal and adequate off-street parking will have to be provided and maintained by the promoters of the project at their cost.
 - c) The promoters of the project shall provide adequate facilities for collection and disposal of garbage at their cost, and will keep, at all times, the entire environment clean, neat and hygienic.
 - d) Area of Rides, whether covered or uncovered, shall not be computed towards FSI.
 - e) At least 250 trees (of indigenous species) per Hecter shall be planted and grown within the area of the park.
 - f) Sufficient parking facilities and ancillary facilities for cars, buses, transport vehicles etc. shall be provided on site.
 - xii) IT / ITES parks / units with 0.20 FSI, subject to Regulation No.7.8.
 - xiii) Any building / use by the Government / Semi-Government or Government Controlled bodies with basic FSI and village resettlement or resettlement of project affected person with full permissible FSI as that of residential zone.
 - xiv) Biotechnology unit / B.T. Park subject to Regulation No.7.9.
 - xv) Development of buildings of educational, research and medical institutions, community development, human resources development, rural upliftment, yogashram, mediation centres, vipashyana centres, spiritual Centres, goshalas, panjarpol, old Age homes and Rehabilitation Centres along with allied activities, Planetarium / Astronomical / Astrophysical facilities / projects with FSI of 1.00 on gross plot area, out of which 0.20 shall be without payment of premium and remaining with payment of premium at the rate of 20% of the rate mentioned in the annul statement of rates of very said land without considering the guidelines therein subject to following conditions :-

Conditions :-

 - a) The trees at the rate of 250 trees per hectare shall be planted on the plot.
 - b) The provisions of higher FSI mentioned in Chapter - 7 of these Regulations shall apply to the above buildings listed in the said chapter. However, higher FSI in such case shall not exceed 100% of the above.
 - c) In case of educational use, 15% area may be used for commercial purpose subject to provisions of Regulation No.4.10(vi).
 - xvi) Integrated highway / Wayside amenities such as motels, way-side restaurants, fuel pumps, service stations, restroom and canteen for employees working on site and truck drivers, service godowns, factory outlets, highway malls, hypermarket along with public
-

conveniences like toilets, trauma centre, medicine shop, bank ATMs and like activities with FSI of 0.2 on gross area without payment of premium and further FSI upto 0.3 with premium at the rate of 20% land rate in Annual Statement of Rates of the said land without considering the guidelines therein, shall be allowed subject to following conditions :-

Integrated Highway / Wayside Amenities may be permitted to be developed on plots of land having a minimum area of 10,000 Sq.m. abutting to National Highways / State Highways or on any road not less than 18.0 m. width.

Provided that, No subdivision of land shall be allowed and location of fuel pump, if provided, shall be separately earmarked.

- (ⁱ) Notwithstanding anything contained in this regulation, an individual use as mentioned in this regulation may be permissible, on road having minimum width of 12.0 m. The minimum plot size for this regulation shall be entire holding mention in the single 7/12 extract or minimum of 4000 Sq.m. In any case Sub-division / layout shall not be permitted.

xvii) Ancillary Service Industries

Ancillary service industries for agro related products like flowers, fruits, vegetables, poultry products, marine products, related collection centres, auction halls, godowns, grading services and packing units, knowledge parks, cold storages, utility services (like banking, insurance, post office services) etc. on the land owned by individuals / organizations with FSI of 0.20 without payment of premium. Further FSI up to 1.00 may be granted with payment of premium at the rate of 20% of land rate in Annual Statement of Rates of the said land without considering the guidelines therein.

- xviii) Any industry / industries with FSI of 0.20 without payment of premium and further FSI up to 1.00 with payment of premium at the rate of 20% of land rate in Annual Statement of Rates of the said land without considering the guidelines therein. Minimum buffer open space / set back (which may include marginal distance and road width if any) from the boundary of industrial Building / use to residential or habitable zone / use, shall not be less than 23.0 m. Such buffer open space shall be kept in the same land.

Provided that, the area under such buffer open space / setback shall not be deducted for computation of FSI.

Provided further that, if the land under industrial zone is utilized entirely for non-polluting industries, IT / ITES or like purposes, then such buffer zone / open space shall not be necessary.

Provided further that, Industrial layout / sub-division of land shall also be permissible subject to regulations of Industrial Zone. In such case, the plot shall be entitled for 0.20 FSI and further FSI as mentioned above, shall be subject to payment of premium. The condition to this effect shall be stamped on the layout / sub-division plan and also mentioned in the approval letter.

Provided further that, industrial godowns / godowns shall also be permissible under this regulation.

- xix) Solid waste management, land fill sites, bio-gas plants, power generation from waste.
 xx) Power generation from non-conventional sources of energy. Area covered under solar panels shall not be counted in FSI.
 xxi) Brick, tile manufacture.
 xxii) Fish Farming.
 xxiii) Religious buildings subject to conditions as may be prescribed by Authority.

⁽ⁱ⁾ Inserted vide Corrigendum / Addendum No. CR 121/21, dt. 02nd December, 2021.

xxiv) Slaughter house or facilities for processing and disposal of dead animals with the special permission of Authority.

xxv) Cemeteries and crematoria and structures incidental thereto.

xxvi) Scrap Market with FSI of 0.20 without payment premium and further FSI upto 1.00 with the payment of premium at the rate of 20% of land rate in Annual Statement of Rates of the said land without considering the guidelines therein.

xxvii) Mangal karyalayas / lawns.

a) Minimum area for mangal karyalaya shall be 0.4 ha. with FSI of 0.20. It may be permitted along with essential guest rooms not exceeding 30% of the area of mangal karyalaya. Area for parking shall be 40% of gross area which shall be properly earmarked and bounded by bifurcating wall. Further FSI up to 1.00 with payment of premium at the rate of 20% of land rate in Annual Statement of Rates of the said land without considering the guidelines therein.

b) Lawns for ceremony shall be 0.8 ha. with FSI of 0.10. Area for parking shall be 40% of gross area.

c) The plot for mangal karyalaya or lawn shall abut on road width of minimum 9.0 m. in case of Nagar Panchayat, Municipal Council and Regional Plan area and 12.0 m. in case of other areas.

xxviii) Bus Terminus.

xxix) Construction of any communication route, road, railway, airstrips, ropeways, ports, electric lines, etc.

xxx) Town planning scheme under the provisions contained in chapter - V of Maharashtra Regional & Town Planning Act, 1966 shall be allowed for minimum 20 hectare area, with proper road network subject to condition that entire cost of scheme shall be borne by the owners. After sanction of preliminary scheme under section 86 of the Act, all uses as that of residential zone, shall be permitted. FSI and other regulations shall be applicable as per residential zone. Or

If the owners come together for development on aforesaid concept of town planning scheme instead of undertaking town planning scheme under the Act, the Authority may allow and approve such development subject to availability of existing approach road of minimum 12.0 m. width and earmarking 40% of the land for roads, parks, playgrounds, gardens, social infrastructure and sale by the Authority, which shall be handed over to the Authority subject to following -

a) Minimum 10% land shall be earmarked for play grounds and parks, for which no FSI / compensation shall be allowed.

b) Minimum 15% land shall be earmarked for social infrastructure and that for sale by the authority and shall be handed over to the authority for which compensation in the form of FSI shall be allowed in-situ.

c) Road area only to the extent of 15% shall be calculated in this component for which compensation in the form of FSI shall be allowed in-situ. The road area over and above 15% shall be calculated in the owner's / developer's share.

d) The regulation No.3.4 and 3.5 shall not be applicable in this case.

Development permission for uses permissible in residential zone shall be granted phase wise after completion of physical infrastructure works including off-site infrastructure and handing over of land to the Authority. The land under such proposals shall be entitled for basic FSI / Premium FSI / TDR / In-situ FSI as that in Residential Zone.

- xxxi) Manufacturing of Fireworks / Explosives and Storage of Magazine / Explosives beyond 2.0 km. of Gaothan Settlement / Gaothan Boundary subject to No Objection Certificate from the Chief Controller of Explosives.
- xxxii) Development of Cinema and TV film production, shooting, editing and recording studios with its ancillary and supporting users, including construction of staff quarters, rest rooms, canteens etc. subject to the following conditions :-
- The minimum plot area (necessarily under one ownership) shall not be less than 2.0 ha.
 - The permissible FSI shall be 0.2 on gross plot area without payment of premium and up to 1.00 with payment of premium at the rate of 20% of land rate in Annual Statement of Rates of the said land without considering the guidelines therein.
- xxxiii) Tourist homes, Resorts, Hotels, Motels, Health and Wellness spa, Golf courses, Art and Craft villages, Exhibition cum Convention Centre, Camping-Caravanning and tent facilities, Adventure Tourism Project, Eco Tourism Project, Agricultural Tourism Project, Medical Tourism Project, Boutique wineries, Guest houses and Bed and Breakfast scheme approved by MTDC / DoT etc., with Rooms / Suites, support areas for reception, kitchen, utility services etc., along with ancillary structures like covered parking, watchman's quarter, guard cabin, landscape elements, and if required, one observation tower per tourist resort upto the height of 15.0 m. with platform area up to 10 sq.m. in permanent / semi-permanent structural components. The permissible FSI shall be 0.2 on gross plot area without payment of premium and up to 1.00 with payment of premium at the rate of 20% of land rate in Annual Statement of Rates of the said land without considering the guidelines therein.
- xxxiv) Tourist Resort Complexes may be permitted with following conditions :-
- General conditions** - The minimum area of such site shall not be less than 1.00 Ha. and 0.4 Ha. in case of local resident.
 - Condition for Development** -
 - Maximum permissible FSI in this zone shall be 0.25 of gross plot area without payment of premium and remaining up to 1.00 with payment of premium at the rate of 20% of land rate in Annual Statement of Rates of the said land without considering the guidelines therein.
 - The uses like resort, Holiday camp, recreational activities, amusement park, may be permitted in this zone.
 - If the site is located adjacent to forts, archaeological and historical monuments, the development shall be governed by the rules prescribed by the archaeological department.
 - If the site is located near natural lakes, then, development shall be governed by the following :-

Distance from High Flood Line (HFL) / Full Storage Level (FSL)	Development to be allowed
Up to 100 m.	Not permissible.
above 100 m. to 300 m.	Ground floor structure with maximum height of 5.0 m.
above 300 m. to 500 m.	G + 1 storey structure with maximum height of 9.0 m.
above 500 m.	Within permissible FSI and subject to other regulations.

- No subdivision of land shall be allowed.
- The land should have approach of minimum 9.0 m. wide road.
- The land having slope steeper than 1:5, shall not be eligible for development.

C) Infrastructural Facilities - All the infrastructural facilities required in site as specified by the Authority, shall be provided by the owner / developer at his own cost on the site. Proper arrangement for treatment and disposal of sewage and solid waste shall be made. No untreated effluent shall be allowed to pass into any watercourse.

- xxxv) In the areas of Local Bodies and the area of SPA where Development Plan or planning proposal is sanctioned, "Pradhan Mantri Awas Yojana" shall be permitted subject to the provisions of Regulation No.14.4.1.
- xxxvi) Individual house of size upto 150 sq.m. for entire holding mentioned in the single 7/12 extract, as on date of coming in to force of these regulations.
- xxxvii) Mining and quarrying subject to provisions of Regulation No.15.1
- xxxviii) In the area of Regional Plans (excluding the area of Local Bodies and SPA where Development Plan or planning proposal is sanctioned) "Pradhan Mantri Awas Yojana" shall be permitted subject to the provisions of Regulation No.14.4.2.
- xxxix) Development of Tourism and Hospitality Services under Community Nature Conservancy around wild life sanctuaries and national parks shall be permitted as per Regulation No.14.9.
- xxxx) Integrated Township Projects as per Regulation No.14.1.1.
- xxxxi) Buildings for Three star and above category hotels along National / State Highways, MDR and on other roads not less than 18.0 m. in width, may be permitted with FSI 0.2 on gross area without payment of premium and remaining up to 1.00 with payment of premium at the rate of 20% of land rate in Annual Statement of Rates of the said land without considering the guidelines therein.
- xxxii) Bulk storage and sale of Kerosene subject to NOC of Chief Controller of Explosive, Government of India.
- ⁽¹⁾ xxxiii) Development of housing for EWS / LIG as per Regulation No.7.7.
- ⁽¹⁾ xxxiv) Development permissible adjacent to Gaothan as specified in Regulation No.5.1.1.

Notes :-

- 1) The permissible FSI for uses mentioned above shall be 0.20, if not specified.
- 2) Height of building shall be permissible as per regulation No.6.10 subject to FSI permissibility under this regulation.
- 3) For the uses permissible in Agricultural Zone minimum road width shall be 6.0 m. for non-special building, unless otherwise specified, and for special building shall be as per Regulation No.3.3.9.
- 4) The premium for FSI (allowed with payment of premium) shall be levied for FSI actually proposed in the permission.
- 5) The payment to be recovered in above cases shall be apportioned 50% - 50% between the Authority and the State Government, unless otherwise exempted by the Government by separate order.
- 6) The payment to be recovered in above cases may be exempted by the Government by separate order in case of deserving charitable institutions.
- 7) No such premium shall be leviable in case of Government / Semi Government or Government controlled bodies.
- 8) Trees at the rate of 100 / hector shall be planted on the land, unless otherwise specified.

4.12 GREEN BELT ZONE / RIVER PROTECTION BELT

4.12.1 Following uses shall be permissible -

- i) Agriculture,

⁽¹⁾ Inserted vide Corrigendum / Addendum No. CR 121/21, dt. 02nd December, 2021.

- (#) ii) Tree Plantation, Gardens, Public park, Landscaping, Recreational Open Space, Forestry and Nursery etc.
- iii) River front development by Authority or any institution authorised on behalf of Authority.
- iv) Development of pedestrian pathways, Jogging tracks, Cycle tracks, Boat clubs etc.
- v) Swimming pools, club houses, recreational facilities after leaving 15.0 m. belt along river bank and 9.0 m. from Nallahs, subject to other provisions in these regulations.
- vi) Public toilets as per requirement.
- vii) Recreational open space of any layout / sub-division / development proposals, if submitted along with the developable land adjoining such green belt, after leaving marginal distances of minimum 15.0 m. and 9.0 m. from rivers and Nallahs, respectively, or subject to ⁽¹⁾ restrictions mentioned in Regulation No.3.1.3.
 - a) The uses and their extent shall be permissible in such Recreational open space, as prescribed in this regulation.
 - b) If the land under green belt zone, excepting open space therein, if any, is required by Authority for the public purposes mentioned above, the owner shall hand over the possession of such land for the development and maintenance of public purposes. Thereafter, such land shall remain open and accessible to general public for recreational activities.
 - c) The side / rear marginal distances for a proposed building in a land adjoining a river / nallah shall be the maximum of :-
 - (i) Side / rear marginal distance, to be measured from river / nallah, as required according to height of building or
 - (ii) 4.5 m. from the dividing line between green belt zone and the other developable zone; or
 - (iii) Mandatory distance of 15.0 m. or 9.0 m to be observed from a river or nallah respectively.

4.13 TRAFFIC AND TRANSPORTATION ZONE

- i) All uses / activities related to surface, water and air traffic and transportation including Parking, ancillary uses shall be permissible.
- ii) Separable lands of Railways shall be allowed to be developed for uses permissible in Commercial Zone.

4.14 REGIONAL PARK ZONE

The following uses shall be permissible :-

- i) All uses permissible in Green Belt Zone, Hill Top Hill Slope Zone and Afforestation Zone.
- ii) Uses at Regulation No.4.11 (iv, v, vi, viii, ix, x, xiii, xix, xx, xxii, xxv, xxviii, xxix, xxxvi, xxxix, xxxxi) permissible in Agriculture Zone.
- iii) Uses at Regulation No.4.11 (xv, xxxiii, xxxiv) permissible in Agriculture Zone with maximum FSI of 0.20 without premium and additional 0.30 i.e. upto 0.50 with payment of premium @ 20% of land rate in ASR.
- iv) Gaothan expansion as specified in Regulation No.5.1.1 subject to 200 m. from the gaothan limit.

⁽¹⁾ Substituted vide Corrigendum / Addendum No. CR 121/21, dt. 02nd December, 2021

(#) Clarification issued by the Govt. vide letter No.CR.122/23/UD-12, dt.26th October, 2023

4.15 TOURISM DEVELOPMENT ZONE

The following uses shall be permissible :-

- i) All uses permissible in Agricultural Zone (except uses at Sr.No.xviii and xxxi of Regulation No.4.11).
- ii) Gaothan expansion as specified in Regulation No.5.1.1.

4.16 AFFORESTATION ZONE

The following uses shall be permissible :-

- i) All uses permissible in Hill Top and Hill Slope Zone.
- ii) Forest houses, ⁽¹⁾ (--) meant for forest tourist / servants / technicians / owner and for storing of fertilizes etc., may be permitted subject to the following :-

It shall have built-up area not exceeding 150 sq.m., provided that, forest plot area is not less than 0.4 hectare. Structures to be erected for these purposes should be of ground + 1 floor only and should not have height more than 7.0 m. and should be of such material as would blend with the surroundings. The owner shall plant trees at the rate of 250 trees per hectare and shall maintain it properly.

Provided that, layout of the forest houses ⁽¹⁾ (--) may be permitted for areas more than 0.4 hectare.

- iii) Uses mentioned in Regulation No.4.11 (iv, v, vi, xiii, xxviii, xxix) permissible in Agriculture Zone.
- iv) Uses mentioned in Regulation No.4.11 ⁽²⁾ (xv,xvi, xxxiii, xxxiv) permissible in Agriculture Zone with FSI of ⁽¹⁾ 0.2, 0.2, 0.1, 0.15 respectively.
- v) ⁽²⁾ Development permissible adjacent to Gaothan as specified in Regulation No.5.1.1 subject to maximum 200 m. periphery from gaothan limit.
- ⁽²⁾ vi) The above uses shall not be permitted on hill slope steeper than 1:5 and such area shall not be considered for FSI.

4.17 HILL TOP - HILL SLOPE ZONE / HILLY AREA

Kept in abeyance.

4.18 GREEN ZONE - 2

The following users shall be permissible in this zone.

- i) All uses permissible in Hill Top - Hill Slope Zone.
- ii) Gaothan expansion as specified in Regulation 5.1.1.
- iii) Primary and Nursery Schools including student hostels.
- iv) Uses at Regulation No.4.11 (vi, ix, xiii, xx, xxii, xxv, xxviii) with maximum FSI of 0.20.

4.19 FOREST ZONE

The developments as may be required by the Ministry of Forest or its Authorities shall only be permissible on the lands owned and possessed by the Ministry / Department of Forest or its Authorities.

4.20 DEFENCE ZONE

- i) The developments as may be required by the Ministry of Defence or its Authorities shall only be permissible on the lands owned and possessed by the Ministry of Defence or its Authorities.

⁽¹⁾ Word 'Farm house' is deleted vide Corrigendum / Addendum No. CR 121/21, dt. 02nd December, 2021.

⁽²⁾ Inserted vide Corrigendum / Addendum under Regulation No. 1.10 CR 121/21, dt. 02nd December, 2021.

ii) **Restrictive Zone –**

No development in contravention with the notification shall be permissible in the area affected by the notification under Works of Defence Act - 1903, whether earmarked as such on Development Plan / Regional Plan or not or development shall be permissible with the No Objection Certificate from the concerned Defence Authority.

Provided that, it shall be permissible to treat the area under such restrictive zone as marginal distance at the time of construction of any building proposed on contiguous unaffected area.

Provided further that, it shall be permissible to utilise the FSI and also the receiving potential of the land under this zone, on the remaining contiguous unaffected land of the same land owner.

4.21 MINES AND QUARRY ZONE

In this zone quarry, mining, stone crushing or similar operations shall be permissible subject to provisions of Regulation No.15.1. In addition to this following uses shall be permissible.

Stone quarrying, soil excavation, stone crushing or other similar activities, mining activity, bricks kilns, caretaker's quarters or residential quarters for essential staff upto maximum built-up area 20 sq.m. ancillary buildings like site offices, cafeteria with maximum built-up area upto 250 sq.m.

The existing uses within these zones such as bricks kilns, fly ash bricks, cremation ground, etc., shall be continued for the respective purposes. The mining and quarry operation shall not be permitted within the restrictive area as per their prevailing regulations. The development after the closing of existing mining areas / quarries shall be as per the closing policies of the respective department. However, the private lands which are included in Mines and Quarry Zone shall deem to be included in the adjacent zone and Authority shall grant development permission accordingly.

4.22 PUBLIC UTILITY ZONE

The following users shall be permissible in this zone.

Water treatment plant, water reservoirs, pumping station, water storage tank, sewage / influent treatment plant, waste water recycling plant, electric substation, cemeteries, burial ground and cremation grounds, slaughter house, solid waste landfill / management site, fire station, post, telegram and communication office, telephone exchange, cattle pond, dairy farm, public urinals including all public utilities.

4.23 WOODLAND CORRIDOR

Following uses shall be permissible in this zone.

- i) Garden, Nurseries, Horticulture and Arboriculture.

4.24 SPECIAL ECONOMIC ZONE

Following uses shall be permissible in this zone.

- i) Residential, Educational, Institutional, Assembly, Business, Mercantile, Industrial, Storage, information Technology, Recreational.
- ii) Any other land use as may be made permissible by the Government of India within SEZ.

4.25 AIRPORT AND ALLIED ACTIVITIES / SERVICE ZONE

The following uses shall be permissible in this zone.

- i) Airport and allied activities and services incidental thereto.

4.26 ADDITIONAL USES

The lists of uses mentioned under various land use zones herein above may be amended by the Authority from time to time with the consent of Director of Town Planning, Maharashtra State, Pune.

4.27 USES PERMISSIBLE IN DEVELOPMENT PLAN RESERVATIONS

- 1) The uses permissible in a reserved site shall conform to the use for which it is reserved unless specified otherwise. The required parking, public toilets and separate place for garbage bins shall also be permissible in the reserved site itself.
- 2) Where the Authority or the Appropriate Authority proposes to use land / building / premises reserved for one specific public purpose / purposes, partly for different public purpose / purposes, it may do so, provided that such partial use shall not exceed 40% of the reserved area and such combination shall not be of incompatible uses. However, public necessities like Police Stations / Chowkys, water supply establishments, Arogya Kothies (i.e. Waste Segregation Centre at Ward Level with allied uses), etc. and other public utility services can be established in the said area. This provision shall not be applicable for the purposes mentioned below in ⁽¹⁾ 4.27(5) (a), (b) and (c).
- 3) Any site reserved for specific purpose in the development plan may be allowed to be developed for any other public purpose with the permission of the Government. In doing so, buildable reservation may be allowed to be developed for buildable or open / recreational uses and open / recreational reservation may be allowed to be developed for open / recreational uses only.
- 4) Planning Authority, with the prior approval from Government, may acquire and develop any of the reservations proposed in the Development Plan, partly or fully, for multi-storeyed public parking, irrespective of its designation, if amenity of parking is direly needed in the area. However, Authority should be satisfied that there is pressing need for parking in that area and priority for parking is more important than purpose for which the reservation is made. In case of purposes mentioned at Regulation No. ⁽¹⁾ 4.27 (5)(a)(b)(c), parking may be allowed to be developed in basement/s subject to development of main purpose on the ground level with layer of soil of 1.0 m. depth and arrangement of soil water recharge.
- 5) Combination of uses as mentioned below may be permissible with the permission of the Authority even if the reservation is for a specific purpose.
 - a) **Play ground** – In play ground reservation, minimum 90% area shall be kept open for open play activities. In remaining 10% of area, covered swimming pool & allied construction, gymnasium, covered badminton court, pavilion, (with or without shops, offices beneath), watchman's quarter, small restaurant or food stalls to the extent of 20 sq.m. (for every 4000 sq.m. reservation area) may be permitted. The maximum FSI permissible shall be 0.15.
 - b) **Stadium / Sports Complex** - In addition to the uses permissible in play ground mentioned above, shops / offices below the spectators' tiered gallery may be permitted. Permissible FSI shall be as mentioned in Regulation No.6.2.2, Table 6-E, Sr.No.8.
 - c) **Garden / Park** - In addition to the main use of garden, open swimming pool & allied construction, aquarium, water tank, booking counter, toilets, rain water harvesting system, gardener / watchman's quarter, small restaurant or food stalls to the extent of 20 sq.m. (for every 4000 sq.m. reservation area) may be permitted. Total FSI used for such constructions shall not exceed 0.10 of the garden area. If required, the sites of park or garden may be developed for playground; however, such change shall not exceed more than 10% of the like reservations in the said sector of Development plan.
 - d) **Civic Centre / Community and Cultural Centre** - Community Hall, welfare centre, gymnasium, badminton hall, art gallery, museum, club house, public conveniences, cafeteria, gardens, exhibition centre, and like combination of uses. ⁽¹⁾ Convenience Shops may be permitted within 15% of basic FSI.

⁽¹⁾ Substituted / Inserted vide Corrigendum / Addendum No. CR 121/21, dt. 02nd December, 2021.

-
- e) **Vegetable Market** - Open or covered ottas for sale of vegetables and / or mutton and fish, along with petty convenience shops and fruit stalls may be permitted.
 - f) **Shopping Centre / Market** - Shopping, vegetable market, hawkers place etc. and departmental stores, offices, banks / community hall on upper floors.
 - g) **Auditorium / Drama Theatre** - In addition to Auditorium, Drama theatre / Natyagriha, Art Gallery, Exhibition Hall, Library, small restaurant to the extent of 20 sq.m. (forevery 4000 sq.m. reservation area) and allied uses such as guest rooms for the artists may be permitted.
 - h) **Primary School / High School** - Respective uses with their lower / ancillary uses along with canteen and ancillary uses including staff quarters, hostels. Fifteen percent of the built-up area may be permitted for commercial use, on basic FSI related to the educational purpose, on ground floor with a separate entry and exit.
 - i) **Hospital / Maternity Home, etc.** - Respective uses with their lower / ancillary uses and any sort of medical facilities along with ancillary construction such as staff quarters, chemist shop, restaurant, ATM, PCO, cyber café of not more than 20 sq.m., etc. and sleeping accommodation for guests in case of bigger hospitals of built up area not less than 2000 sq.m. may be permitted.
 - j) **Slum Improvement Zone** - It shall be developed for slum rehabilitation as per regulations of Slum Rehabilitation Authority.
 - k) **Truck Terminus** - In addition to minimum 60% area for parking of trucks, ancillary office, restaurant, hotel, motel, lodging facility for drivers, Vehicle fuel Filling station including LPG / CNG / Ethanol /Charging Stations for Electric Vehicles, auto repair centre, auto service centre, shops for auto spare parts, shops for daily needs, ATM, PCO, Primary Health Centre / First Aid Centre and provision for loading-unloading may be permitted. Moreover, these reservations may also be developed for bus stand, bus - MRT interchange with mall.
 - l) **Bus Stand for Local and Regional Services / Metro station / Transport Hub** - In addition to respective purpose, bus-metro reservation may have interchange along with other ancillary uses. Where there is / are any existing building/s accommodating owners / occupants in such reservation, they may be accommodated by the Planning Authority on upper floors of any proposed building/s on the reservation, subject to their willingness.
 - m) **Fire Brigade Station** - Fire brigade station along with allied activities.
 - n) **Sewage Treatment Plant (STP), Solid Waste Facility, Water Works** - respective use with allied activities and interchangeability among one another.
 - o) **Parking / Parking Lot** - Parking along with ancillary uses such as public convenience, drivers room, motor garage etc. on not more than 10% area.

 Provided further that, the Planning Authority may accommodate, on the willingness of the owners / occupants residing in the existing building/s on reserved area, on the same land, on any floor of the proposed parking building.
 - p) **Public Amenity** - Any amenity, along with ancillary use.
 - q) **Municipal Purpose** - Any public purpose related with functioning of Municipal Authority as may be decided by the Authority.
 - r) **Cremation Ground / Burial Ground** - Respective use with allied activities and interchangeability among one another.
 - s) **Weekly Market** - Weekly vegetable market with open ottas, cattle market and ancillary petty convenience shops.
-

t) Multipurpose Ground - Users permissible in sites reserved for Multi-purpose ground :

- i) Playground
- ii) Exhibition ground
- iii) Festival fairs, ceremonies, religious functions etc.
- iv) Circus
- v) Social gathering, public speeches
- vi) Cultural activities like Kalagram etc.
- vii) Music Concerts etc.
- viii) Institutional programs
- ix) Touring Talkies
- x) Govt. or semi-government organisation functions.
- xi) Parking.

In addition to above the Authority may add or alter the above list from time to time. No permanent construction or permanent use, except as a playground, shall be permissible in this reservation.

u) Exhibition Ground / Open Exhibition Ground / Exhibition Centre - All activities related to various exhibitions and ancillary structures like office, restaurant etc. of built-up area not exceeding 10% of the total area.

v) Bio Diversity Park - Uses permissible

- i) Agricultural, including horticultural uses.
- ii) Forestry and Nursery.
- iii) Park.
- iv) Historical museum only on the lands owned by the Govt. / Authority subject to maximum floor space area not exceeding 4% of the total plot with ground floor structure without stilts.
- v) Bio-Diversity information Centre and Research center subject to maximum floor space area not exceeding 4% of the total plot with ground floor structure without stilts.
- vi) Public Streets having width not exceeding 9.0 m. alignment and the cross section of the street shall be finalised by the Authority without cutting the hill area.

w) Composite development of Bus Terminal / Bus Depot / Truck Terminal for cities having population of 5 lacs and above –

In case of cities having population 5 lacs and above, the composite development of the reserved lands for Bus Terminal / Bus Depot / Truck Terminal, may be allowed subject to the following :-

- i) 40% land shall be kept open for basic use with proper maneuvering buses / vehicle and remaining upto 60% land may be allow to be developed for affordable housing.
- ii) Such plot shall be owned by planning authority or development authority.
- iii) Such composite use shall be segregated by separate entry / exit.

x) Other reservations - Other reservations may be developed for the respective purposes along with compatible, ancillary uses.

Note :- The permissible FSI and the maximum permissible loading limit including TDR and FSI with payment of premium for above uses in reservation, shall be as permissible for residential zone, if not specified otherwise.

_*_*_*_*_*_

CHAPTER - 5

ADDITIONAL PROVISIONS FOR REGIONAL PLAN AREAS

5.0 GENERAL

In addition to the provisions mentioned in these Regulations, following additional provisions shall be applicable for the areas of the Regional Plans / Authorities mentioned hereinunder. These provisions shall prevail over the provisions, if any, mentioned in this Development Control and Promotion Regulations to that extent.

5.1 FOR ALL REGIONAL PLAN AREAS

5.1.1 Development Permissible Adjacent to Gaothan

For the villages in the area of Regional Plans (excluding the area of Local Bodies and SPA where Development Plan or planning proposal is sanctioned) where no specific residential zone is shown, for such villages, development permissible in residential zone, may be permitted :-

- i) within a belt of 2.00 km. from the boundaries of Municipal Corporation, 1.00 km. from the boundaries of Municipal Council and 0.50 km. from the boundaries of Nagar Panchayat, where zone plans are ⁽¹⁾ prepared or not prepared in the Regional Plan for such area;
⁽¹⁾ However the proposed development within such belt shall be guided by the road network of published / sanctioned zone plans or elsewhere proper road network plan prepared and approved by the Director of Town Planning within 6 months or within such time limit as extended by Government.
- ii) within a belt of 500 meters from the gaothan limits of settlements having a population of less than or equal to 5000 as per the latest Census and;
- iii) within a belt of 1500 meters from the gaothan limits of settlements having a population of more than 5000 as per the latest Census;
- iv) in the case of settlements of both the categories mentioned ⁽¹⁾ in (ii) and (iii) above, falling in the planning areas / Zone Plans of Regional Plans, such distance from the gaothan limits shall be 500 meters only;
- v) in the case of village settlements in the Western Ghat hilly area (eco sensitive zone) in Regional Plan of Satara, Pune, ⁽¹⁾ Ahmednagar, Dhule, Kolhapur, Nashik, Nandurbar, Sangli, Sindhudurg, Thane, Palghar and Raigad District or as notified by Govt. from time to time such distance shall be 200 m. only
- vi) in the case of villages in Regional Plan of Mumbai Metropolitan Region and Raigad, such distance shall be 500 m. only.

Provided that, such development shall be permitted only on payment of premium of the total area of land. Such premium shall be calculated considering 15% rate of the said land as prescribed in the Annual Statement of Rates of the year granting such developments. This rate of premium shall be subject to orders of the Government from time to time;

Provided further that, for the areas which are converted into Municipal Councils / Nagar Panchayats within the Regional Plan (under the provision of Maharashtra Municipal Councils, Nagarpanchayats and Industrial Townships Act, 1965), such premium shall be calculated considering 5% rate of the said land as prescribed in the Annual Statement of Rate for the year while granting such residential development (without considering the guidelines therein).

Provided further that, no such premium shall be applicable for development of an individual house of an owner or farm house on owner's land.

⁽¹⁾ Inserted vide Corrigendum / Addendum No.CR.121/21, dt.02nd December, 2021

Provided further that no such premium shall be applicable for revised permission on the land where development / Layout permission is granted prior to sanction of the respective Regional Plan, more specifically mentioned in Regulation No.5.1.3.

Provided further that where more than 50 percent of area of the Survey Number / Gut Number is covered within the above peripheral distance, the remaining whole of such Survey Number / Gut Number within same ownership shall be considered for development on payment of premium as above.

Provided further that the criteria of “distance from gaathan” shall also be applicable to the lands from the nearest gaathan of any village.

Provided further that this provision shall not bar development permission for the uses, otherwise permissible, in agricultural zone as per UDCPR within specified distance from gaathan mentioned in this regulation.

Provided also that this regulation shall also be applicable to all declared / Notified Gaathan under M.L.R.C. whether shown on Regional Plan or not.

Provided further that in respect of Ratnagiri-Sindhudurg Regional Plan, this provision shall be subject to provisions mentioned in Regulation No.5.3.

5.1.2 Regulations for Development of Tourist Resorts / Holiday Homes / Township in Hill Stations Type Areas under Hill Station Policy

The developments under the Hill Station Policy shall be governed by the Special Regulations as sanctioned by Government vide notification No.TPS-1893/1231/C.R.123/96/UD-13, dated 26/11/1996 and its amendments by the Government from time to time.

5.1.3 Committed Development

- i) Any development permission granted or any development proposal for which tentative or final approval has been recommended by the concerned Town Planning Office and is pending with the concerned Revenue Authority for demarcation or for final N.A. permission before publication of draft R.P. (date of resolution of the R.P. Board for publication) shall be continued to be valid for that respective purpose / use irrespective of approved Floor Space Index. Provided that, it shall be permissible for the owner either continue with the permission in toto as per such earlier approval or apply for grant of revised permissions under these regulations. However, in such cases of revision, the premium, if any, shall not be applicable, for approved permissions (including tentative). This provision shall not cover the cases mentioned in 5.1.3 (iii) below.
- ii) The layout already approved / development permission already granted for residential purpose and which are valid as per the provisions of UDCPR shall be entitled for development subject to use of earlier permission. This shall also be applicable to cases where sale permission for N.A. use has been granted prior to the date of sanction of these Regulations, for the same use as the one for which sale permission was granted.
- iii) The layout already approved / development permission already granted for the uses permissible in agricultural or such restrictive zone and which are valid as per the provisions of UDCPR shall be entitled for development subject to use and FSI of respective use granted in earlier permission.

5.1.4 Rectification of draftsman's error

- i) Draftsman's errors, which are required to be corrected as per actual situation on site / or as per Survey Records, sanctioned layout etc. shall be corrected by the concerned District Collector, after due verification and prior approval of concerned Divisional joint Director of Town Planning.

- ii) Drafting errors, if any, regarding Private Lands shown by mistake in the restrictive zone such as defence zone, forest zone, command area etc. shall be corrected after due verifications of records and situation on ground by the concerned Authority with prior approval of Divisional Joint Director of Town Planning. In such case Private Lands will be included in the adjacent zone.
- iii) The boundaries of the designated or Notified Eco-Sensitive Zone in respect of Bird Sanctuary, Wildlife Sanctuary and other project shown on Regional Plan shall be as per the final notification issued under Environment (Protection) Act, 1986. All conditions regarding development including Buffer Zone in pursuance of the provisions of the said Act shall be applicable.

5.1.5 Highways notified by State / Central Government

If any highway / ring road / express way and any other classified road is notified by State / Central Government Highway Authority under the provisions of relevant act, then the alignment of such notified road shall be deemed to be the part of Regional Plan and for this, procedure under section 20 of M.R. & T.P. Act, 1966 shall not be necessary.

5.1.6 Station Area Development

The development ⁽¹⁾ in agriculture zone around ⁽¹⁾ any functional railway station upto a distance of 500 m. shall be permitted by charging premium at 30% rate of the said land as mentioned in the ASR on total area of land under development, subject to following -

- i) Within a 100 m. distance from periphery of the station, the users related to railway station and other users (excluding Residential) shall be permitted.
- ii) In remaining distance within 500 m., all users permissible in Residential Zone shall be permitted.
- iii) The rate of premium shall be subject to Government's order from time to time.

5.1.7 Modification proposals already sanctioned

All the modification proposals from Regional Plan already sanctioned by the State Government under section 20(4) of Maharashtra Regional and Town Planning Act, 1966 but not shown in respective zone in Regional Plan shall be treated as included in respective Zone as per the modification sanctioned by the State Government.

5.1.8 Provision of Amenity Space

- i) In any layout or sub-division of land for residential purpose admeasuring more than 0.4 Ha. (excluding the area of R.P. roads, road widening and designations) amenity space shall have to be provided for the areas and specified percentages mentioned in the table below.

Area of Land	Amenity Space to be provided
upto 4000 sq.m.	Nil.
more than 4000 sq.m.	10%

- ii) For calculating the area for Amenity Space, area covered under the development proposal submitted to the Authority shall only be considered.
- iii) The owner shall be entitled to develop the Amenity Spaces as per the uses permissible in the Amenity Space.

⁽¹⁾ Inserted vide Corrigendum / Addendum No. CR 121/21, dt. 02nd December, 2021.

- iii) If owner agrees to handover and the Authority agrees to take over the amenity space, then such Amenity Space shall be deemed to be reservation in the plan and floor space index (FSI) in lieu thereof ⁽¹⁾ subject to maximum receiving potential prescribed in these regulations may be made available in-situ on remaining land. The calculation of this in-situ FSI shall be shown on the layout / building plan. In the areas where TDR regulations are applicable and if the owner desires to have TDR against it, instead of in-situ FSI, then he may be awarded TDR. The in-situ FSI or TDR shall be granted only after transfer of the Amenity Space to the Authority. The generation of TDR or in-situ FSI shall be equivalent to the quantum mentioned in Regulation of TDR.
- iv) ⁽¹⁾ Proviso of Regulation No.3.5.1, ⁽¹⁾ (--) shall be applicable to this regulation.

5.1.9 Residential Zone with payment of Premium

Wherever such zone is proposed in sanctioned Regional Plan, provisions related to such zone will continue to that extent.

5.2 FOR THANE - RAIGAD - PALGHAR REGIONAL PLAN

(***) Development around Tarapur Atomic Power Station in Tarapur - Boisar Area

- 5.2.1 The development within the area of 5 km. to 16 km. radius of Tarapur Atomic Power Station shall be governed by following regulations.

5.2.1.1 Provisions mentioned in Regulation No.6.23 shall be applicable with following changes -

Side and Rear Marginal Distances for building of Height more than mentioned in Table No.6-D / 6-E of Regulation No.6.2.1 and 6.2.2 :- The marginal distances on all sides, except the front side, of building shall be minimum 6.0 m. or $H / 5$, whichever is more.

(Where H = Height of building above ground level) Provisions mentioned in Regulation No.6.2.4 shall be applicable

5.2.1.2 Provisions mentioned in Regulation No.6.10 shall be applicable with following changes :-

Distance between Two Buildings - The distance between two buildings shall be 6.0 m. or $H / 5$ of the taller building between the two adjoining buildings, whichever is more.

(Where H - Height of building above ground level)

5.2.1.3 Provisions mentioned in Regulation No.6.10 shall be applicable with following changes :- Height of Building :-

The maximum permissible height of building, including parking floor shall be 24.0 m.

5.2.1.4 Permissible FSI :-

- a) **Provisions mentioned in Regulation No.6.1 and 6.3 shall be applicable with following changes -**

The permissible Basic Floor Space Index shall be 1.10. In to basic permissible FSI, 0.30 FSI shall be permissible on payment of premium.

If the land is affected by proposed road or road widening and if the owner hand over the land under such proposed road or road widening of very said plot, free of cost and free from all encumbrances, to the Authority, such FSI can be used instead of FSI on payment of the premium to the maximum extent of 0.30 or 0.30 FSI over and above. 1 Basic FSI may be allowed to be utilized partly from road widening FSI of very said plot and partly from premium FSI.

⁽¹⁾ Inserted / Substituted / deleted vide Corrigendum / Addendum No. CR 121/21, dt. 02nd December, 2021.

^(***) Inserted vide Directives u/s 154 & Notice Published u/s 20 (3) No. CR 421/16, dt. 21st December, 2021.

(***) Provided that, above provision of FSI shall also be permissible for earlier sanctioned proposals within the limits of maximum permissible FSI of 0.75 or 1.00, as the case may be, subject to the marginal distances and Distance between Two building as prescribed above.

b) Provisions mentioned in Regulation No.7.7.2 shall be applicable with following changes :- Development of Housing for EWS / LIG - proposed in Agriculture Zone as per Regulation No.7.7.2 - FSI permissible shall be 1.0.

c) Provisions mentioned in Regulation No.4.11 shall be applicable with following changes :- FSI for users permissible in Agriculture Zone shall not exceed the FSI as prescribed in Regulation No.4.11.

However, if FSI on payment of premium is permissible over and above the FSI allowed without payment of premium to certain user in Regulation No.4.11, then the maximum FSI on payment of premium for such user shall be permissible to the extent of such permissible FSI on payment of premium or 0.40, whichever is minimum,

d) Provisions mentioned in Regulation No.6.4 shall be applicable with following changes :- The permissible basic Floor Space Index shall be 1.00. In addition to the basic permissible FSI, 0.40 FSI shall be permissible on payment of premium.

e) Provisions mentioned in Regulation No.6.1 and 6.4 shall be applicable with following changes :- Notwithstanding anything mentioned in various provisions of Unified Development Control and Promotion Regulation, Ancillary FSI shall not be permissible in this area.

5.2.1.5 Excepting the Regulation mentioned above, all other Regulations in Unified Development Control and Promotion Regulation shall be applicable for the area.

5.3 FOR RATNAGIRI - SINDHUDURG REGIONAL PLAN

The Development Control Regulations sanctioned for Ratnagiri - Sindhudurg Regional Plan shall cease to operate and following provisions shall be applicable -

(*) 5.3.1 Area within Ratnagiri District -

The zoning of lands within local authorities' area / special planning authorities' areas shall be governed by zoning / proposals shown in the Development Plan / Planning proposal / Plan. Remaining area of the district where such plan is not sanctioned shall be treated as Agricultural zone. All the provisions of this UDCPR shall be applicable with following additions.

Residential development or development permissible in Residential zone shall be permitted in Agriculture zone within a distance of 200 m. from pada, with payment of premium as mentioned in Regulation No.5.1.1. However, such premium shall not be applicable for individual housing or bungalow, not exceeding two units.

5.3.2 Area within Sindhudurg District -

The Development Control Regulations sanctioned by the Government in respect of Sindhudurg Tourism Plan vide Notification No.TPS-1997/355/C.R.99/UD-12, dt.15/10/2004 shall cease to operate and following provisions shall be applicable.

(***) Inserted vide Directives u/s 154 & Notice Published u/s 20 (3) No. CR 421/16, dt. 21st December, 2021

(*) Directives u/s.154 of the M.R. & T.P. Act, 1966 bearing No.C.R.94/2026/UD-13, dt.01st March, 2024 issued by the Government with certain conditions.

Following land use zones are shown on the Regional Plan of Sindhudurg district area.

i) Exclusive Tourism Zone shall include :

a)	Existing Municipal Council, Nagar Panchayat area and area under New Town Development Authority	T-1
b)	Within Urban Centers, Tourism Growth Centers and area in the Vicinity but outside Municipal Council, Nagar Panchayat area having development potential	T-2
c)	Along National and State highways	T-3
d)	Hill Stations	T-4
e)	Coastal Area (excluding T-1 and T-2)	T-5

ii) Other Zone shall include

- a) Industrial Zone.
- b) Forest Zone.
- c) Agricultural and Horticultural Zone.

iii) For T-1 zone in the Regional Plan, all provisions of UDCPR shall be applicable as per zoning in the respective Development Plan or Planning Proposals.

iv) T-2 and T-3 zone in the Regional Plan shall be treated as Residential Zone and all provisions of UDCPR shall be applicable. However, height of building shall not exceed 16.0 m.

v) For zone plans approved under the M.L.R.C. and included in the Regional Plan, all provisions of UDCPR shall be applicable according to zone in the said zone plans.

vi) For T-4 zone, following uses shall be permissible.

Sr. No.	User	Min. Plot Area (sq.m.)	Max. FSI	Max Height (m.)
1	Residential	500	0.30	12.00
2	Commercial	500	0.50	12.00
3	Hotel, Boarding Houses.			
	a) Below 3 Star	1000	0.25	12.00
	b) Above 3 Star	4000	0.25	16.00
4	Public, Semi-public like Education, Hospital etc. and Assembly building including Cinema Theater.	2000	0.20	12.00

Note -

- a) All other uses permissible in Agricultural zone shall be permitted in T-4 zone subject to maximum FSI of 0.50 and height of building up to 12.0 m.
- b) The FSI limit mentioned above in Sr.No.1, 3 and 4 of the table may be allowed to be exceeded up to 0.50 subject to payment of premium as mentioned in Regulation No.4.11.
- c) Reconstruction / Redevelopment of existing building are permitted without considering minimum area of plot and FSI shall be as per above table or FSI utilized for the existing authorized structure.
- d) Minimum plot size norms shall not be applicable to "Bread and Breakfast Scheme" approved by M.T.D.C.

vii) For T-5 zone, following uses shall be permissible.

Sr. No.	User	Min. Plot Area (sq.m.)	Max. FSI	Max Height (m.)
1	Residential / Commercial	500	0.50	12.00
2	Hotel, Boarding Houses.	1000	0.75	12.00
3	Public, Semi-public like Education, Hospital etc. and Assembly building including Cinema Theater.	2000	0.50	12.00

Note -

- a) The FSI mentioned in the above table shall be allowed to be exceeded up to 1.00, with the payment of premium at the rate of 30% of rates mentioned in ASR, without following guidelines therein.
- b) The development permissible shall be subject to provisions of Coastal Regulation Zone Notification No.G.S.R.37(E), dated 18th January, 2019 as amended or replaced from time to time.
- c) All other uses permissible in Agricultural zone shall be permitted in T-5 zone subject to maximum FSI of 0.50 or mentioned in the said regulations in agricultural zone, whichever is minimum and height of building up to 12.0 m.
- d) Reconstruction / Redevelopment of existing building are permitted without considering minimum area of plot and FSI shall be as per above table or FSI utilized for the existing authorized structure.
- e) Minimum plot size norms shall not be applicable to "Bread and Breakfast Scheme" approved by M.T.D.C.
- viii) Following villages are identified as Tourism growth centers -
Kunkeshwar - Mithbav, Hindale, Achara, Tondavali, Mahapan, Shiroada - Aravali, Amboli and Phonda.
"Tourism Growth Centers" shown on the Regional Plan are for the purpose of showing places of tourist interest.
- ix) The places of "Konkan Tourism Village" and "Day Visit Points" shown on the plan are also places of tourist interest.
- x) Development in Industrial Zone, Forest Zone, Agricultural / Horticultural zone and other zone, if any, shall be governed by the provisions mentioned in this UDCPR. However, in such case FSI and height of building shall not exceed 0.50 and 12.0 m. respectively.
- xi) Natural expansion of gaathan shall be allowed within 200 m. from the gaathan boundary and regulations of Residential Zone shall apply. The villages which are not having notified gaathan the residential and other non-agricultural development shall be permitted only along the existing public roads upto a plot depth of 45 m. from the road boundary and regulations of Residential Zone shall apply. For this development premium shall be applicable as per Regulation No.5.1.1. However, such premium shall not be applicable for individual housing or bungalow, not exceeding two units. The provisions in proviso to Regulation No.5.3.1 shall also be applicable.

5.4 FOR KOLHAPUR REGIONAL PLAN

5.4.1 Committed Development

Instead of Regulation No.5.1.3(i) and (ii), following regulations shall be applicable for committed development -

- i) Regarding Committed Development outside previously Sanctioned Regional Plan of Kolhapur - Ichalkaranji Region :- All development permissions / layout approval granted by the District Collector / Concerned Revenue Authority or any development proposal for which tentative or final approval has been recommended by the concerned Town Planning Office and is pending with the concerned Revenue Authority for demarcation or for final N.A. approval on 12/09/2016 i.e. the date of board resolution for publication of draft R.P. shall continue to be valid for that respective purpose along with approved Floor Space Index.

Provided that it shall be permissible for the owner to either continue with the permission in toto as per such earlier approval and for that limited purpose, erstwhile regulation shall apply or apply for grant of revised permission under the new regulations. However, in such revision of cases, the premium if any shall not be applicable, for the originally approved land use and FSI only.

- ii) Regarding Committed Development within the ambit of previously sanctioned Regional Plan of Kolhapur - Ichalkaranji Region.

The development permission / layout approval granted by the District Collector / concerned Revenue Authority within the ambit of the sanctioned Regional Plan of Kolhapur -

Ichalkaranji prior to the publication of the Draft Regional Plan, Kolhapur and if the said Development permission / layout is as per the provisions of sanctioned Regional Plan of Kolhapur - Ichalkaranji Region then such permission / layouts shall be treated as valid permission for the respective sanctioned use. These permissions / layouts, if submitted for revised approval, then it should be corrected as per the present sanctioned regulations of the Regional Plan of Kolhapur Region.

- a) The development permission / layout approval granted by the District Collector / concerned Revenue Authority within the ambit of the sanctioned Regional Plan of Kolhapur - Ichalkaranji and if the said development permission / layout approval is contradictory or adverse to the provisions of sanctioned Regional Plan of Kolhapur - Ichalkaranji Region or Draft Published Regional Plan of Kolhapur Region then such permission / layout shall be treated as illegal and to be cancelled with immediate effect.

Note :- The layouts which are approved before publication of the Regional Plan but not fulfilling the requirements of the then DCR such as road width, open space etc. but saved as per above special regulation, in such cases the building permission shall be granted with 75% of FSI permissible in such zones.

5.5 FOR SATARA REGIONAL PLAN

- 5.5.1** Regulations for proposed Buffer Zone up to 2.5 km. aerial distance around Mahabaleshwar Panchgani Region.

The following Regulations is applicable for the proposed Buffer Zone :-

Proposed Land-use Zone	Permissible Users	Permissible FSI
Lands falling within 50 m. distance from the boundary of Mahabaleshwar - Panchgani Region.	No development shall be allowed.	
Agriculture / No Development Zone	All users permissible in Agriculture Zone as per Regulation No.4.11.	a) Maximum permissible FSI shall be 0.75 for the lands falling within permissible peripheral distance from the gaathan. b) Maximum permissible FSI shall be as per Regulation No.4.11 from the lands falling beyond such permissible distance.
Forest	The development as may be required by the Ministry of Forest or its Authorities as per the requirements shall only be permissible on the lands owned and possessed by the Ministry of Environment and Forest or its Authorities.	
Eco-Sensitive Area	Users permissible shall be as per MOEF Notification dt.27/02/2017.	a) Maximum permissible FSI shall be 0.75 for the lands falling within permissible peripheral distance from the gaathan. b) Maximum permissible FSI shall be as per Regulation No.4.11 from the lands falling beyond such permissible distance.

Core and Buffer Zone of Sahyadri Tiger Project	Permissible users and FSI shall be as per the Development Control Regulations being prepared for this Zone by the Local Advisory Committee headed by Divisional Commissioner, Pune. Till such Regulations are framed, for the peripheral area of the gaothans falling in Buffer Zone, the users permissible in the Agriculture Zone shall be allowed with the approval of Competent Authority of the Forest Department. In the Core Zone, no development shall be permissible.	For gaothans in Buffer Zone. a) Maximum permissible FSI shall be 0.75 for the lands falling within permissible peripheral distance from the gaothan. b) Maximum permissible FSI shall be as per Regulation No.4.11 from the lands falling beyond such permissible distance.
Area of Growth Centre / Urban Complex falling within the Buffer Zone.	As per the Land use proposed in such Growth Centre / Urban Complex Plan.	0.75 FSI shall be permissible for the proposed Residential Land use Zone and for the proposed Agriculture/ No Development Zone, the FSI for users permissible shall be as per Regulation No.4.11

⁽¹⁾ 5.5.2 ⁽¹⁾ **Regulations Conservation Zone in Satara Region.**

⁽¹⁾ Appendix - L

REGULATIONS FOR CONSERVATION ZONE IN SATARA REGION

PART - I

ADMINISTRATION

1.0 SHORT TITLE, EXTENT AND COMMENCEMENT

- i. Title :- These Regulations shall be called as Regulations for Conservation Zone in Satara Region.
- ii. Extent :- These Regulations shall apply to the area earmarked as Conservation Zone, more specifically shown in green verge on the maps appended herewith as Appendix - "M" and illustratively listed in the Appendix - "N".
- iii. Commencement :- These Regulations will come into force after it is sanctioned by Government.

If there is any conflict between any Regulations sanctioned for Regional Plan Area for Satara Region and these Regulations, these Regulations shall prevail.

2.0 Definition

Conservation Zone

Areas of ecological importance such as, fragile and ecologically sensitive habitats, sites with large number of rare, threatened, endemic flora and fauna, breeding sites, colonies of endemic and threatened species, rare geological formations etc., and environmental importance such as,

⁽¹⁾ Regulations for Conservation Zone - Inserted vide Notification No.C.R.83/19/UD-13, Dt.23rd December, 2021

- (1) sensitive water catchments, hydrological systems, nutrient catchments, those providing water nutrients, pollinator support, fodder and natural resource necessary for rural livelihood activities, other than Forest Department owned or forested lands necessarily required to be protected and conserved .

At present the ecological habitat of the following plateau cluster have been identified and are proposed to be conserved and protected as a Conservation Zone;

- a. Kas Pathar; an UNESCO Natural World Heritage Site;
- b. Chalkewadi Pathar and;
- c. Sadavaghapur Pathar

Each cluster in the Conservation Zone comprises of;

A. Core Zone

The top of Plateau commonly known as tableland, and more specifically shown in Blue colour on the plan appended herewith as Appendix - “M”; and;

B. Buffer Zone

The area consisting mainly the slopes around the Core Zone having ecological importance due to its water shed and more specifically shown in Green colour on the plan appended herewith as Appendix - “M”

The activities in these Zones shall be regulated keeping with the goals of protecting Regional Biodiversity, Supporting & Enhancing the Ecological Conservation values and maintaining the healthy functioning of eco-system services of the area. The regulation for conservation zone shall be as mention in part - II below.

(1) PART-II

1.00 LAND USE CLASSIFICATION AND PERMISSIBLE USES

A. Core Zone of Conservation Zone :

In respect of lands owned by the Forest Department, the Conservation and Restoration activities according to Conservation Management Plan prepared by Forest Department and / or State Biodiversity Authority shall prevail. While following regulations shall apply to allow development permissions and / or activities in the remaining area falling in this zone.

- a. i.** The Unified Development Control and Promotion Regulations as otherwise applicable to the land situated within Gaothans in Sanctioned Regional Plan, Satara along with the modifications made in it from time to time shall be applicable to the Gaothans shown as existing on Village Maps & Gaothans / extension of Gaothans subsequently declared by Revenue Department under the provisions of Maharashtra Land Revenue Code, 1966.
- ii.** Development permissions and / or activities except conservation activities shall not be permitted outside the Gaothan area.
- iii.** Activities of restoration of local biodiversity in the Conservation Zone shall be permissible with the prior permission of the Maharashtra State Biodiversity Board.
- b. i.** Windmills :- New windmills shall not be permissible. However, repowering of existing windmills may be allowed with prior approval of MEDA. Existing foot print of allied buildings for windmills shall be maintained as far as possible and used to its potential.
Provided that, in case of re-powering of existing windmills, appropriate measures to safeguard the biodiversity of the platue be undertaken by the proponent in consultation with the State Biodiversity Authority. No further expansion of existing windmills for land shall be permitted.
- ii.** Solar Farms :- Solar Farms shall not be permissible.

- (1) c. Mining and quarrying activities for rocks, laterite, mud, soil etc. or digging for any purpose shall not be permitted.
- d. Roads :-
- i. All existing tarred roads on the plateau shall be maintained at same width as all-weather roads.
 - ii. Non-tarred roads to be identified and demarcated and shall be maintained as un-tarred with the existing width and length. However, this shall not be applicable to the existing roads connecting to the existing Villages / Wadis / Talukas and District Head Quarters.
 - iii. No new roads shall be permitted.
 - iv. No widening of existing internal road/s shall be permissible.
 - v. a) Roads and Bridges, Railway, Ropeway, Underground Pipelines, Cables and like purpose in any zone. If any Road / Ring road / Express way declared by the State or Central Highway Authority, the alignment of such declared road shall deemed to be the part of the Regional Plan and for this, procedure under section 20 of the M.R. & T.P Act, 1966 shall not be necessary.
b) All projects of public interest undertaken by Central and State Government bodies or Public Authorities controlled by the Government.
- e. Plantations / Afforestation shall not be permitted.
- f. Any activity restricting / obstructing Natural water flows shall not be permitted.
- g. New man made water bodies as well as expansion of existing water bodies shall not be permitted.
- h. Tourism and related infrastructure :-
- i. Riding of animals or manual / automated vehicles or any animal drawn carts for the purposes of entertainment shall be prohibited.
 - ii. Water sports, golf, balloon rides, paragliding, ropeway etc. shall not be allowed.
 - iii. Use of area for entertainment, sports, film shooting shall be prohibited.
 - iv. Forest guest house and Interpretation centre by Forest Dept. blending with nature shall be allowed with ground floor only.
 - v. No parking of any sort by the tourist shall be allowed in the core zone as well as peripheral distance of 1.5 km. from the boundary of core zone. However, there shall be no restriction on the provision of required parking as per prevailing regulations, in the individual premises.
 - vi. Restoration and expansion of existing Temples and sacred groves shall be governed by the Heritage regulations applicable for the Satara Regional Plan.
- B. Buffer Zone of Conservation Zone :-**
The following uses shall be permissible in the Buffer zone of the Conservation Zone :-
- a. All agricultural uses including stables of domestic animals, piggeries, poultry farms accessory building, tents.
 - b. Garden, forestry, nursery, public parks, play fields, summer camps for recreation of all types.
 - c. Storage and drying of only organic manure.
 - d. L.P.G. Godown subject to the following conditions :-

(1)

Minimum plot size and area of the plot shall be as given below

Sr. No.	Qty. of LPG in Kg.s	Total area requirement for storage shed (sq. m.)	Safety Clearance required all around in Meters	Preferable size of land with parking area of 6 m. wide on front side
1	5000	55	6.0	21 m. x 26 m.
2	8000	88	7.0	25 m. x 30 m.
3	10000	110	8.0	28 m. x 33 m.
4	12000	132	9.0	31 m. x 36 m.

Conditions :-

- i) Land should be free from live overhead power transmission or telephone lines.
- ii) The length of the storage shed should not be more than 1.5 times of width of storage shed.
- iii) The land should not be situated in low lying area.
- iv) The land should not be situated in congested area or gaathan.
- e. Public utility establishments such as electric sub-stations, receiving stations, sewage disposal water works along with residential quarters for essential staff for such works.
- f. Farm house :- subject to following conditions :-
 - i. Minimum plot area under above use shall be 0.4 Ha.
 - ii. The land in which it is to be constructed is actually put under agricultural, Plantation, horticulture, floriculture, nursery etc. use.
 - iii. Farm house shall be permitted by the Authority / Collector only after the requisite permission for farm house is obtained by the owner from the Authority / Collector under the provisions of Maharashtra Land Revenue Code, 1966 and attested certified copy of such permission is attached with the application under Section 44 of the Maharashtra Regional and Town Planning Act, 1966.
 - iv. The FSI shall not exceed 0.0375 subject to a maximum built up area of 160 sq.m. in any case. Only ground floor structure with or without stilt shall be permissible with sloping roof.
- g. Swimming pools / sports and games, health clubs, cafeteria, canteen, tennis courts, etc.
- h. Mobile Phone Towers with ancillary equipment.
- i. Raisin / Processing units for Local Agriculture Produce.
- j. No extension for Mining and quarrying operations shall be permitted beyond expiry of valid period.
- k. Ancillary service industries for agriculture produce marketing and management, Ancillary service uses for agro related products like flowers, fruits, vegetables, poultry products, marine products related collection centres, auction hall, godowns, grading services and packing units, knowledge parks, cold storages, utility services (like banking, insurance, post office services) as service industries for agriculture produce marketing on the land owned by individuals / organizations, with construction up to a maximum of 20% (FSI = 0.20) of the net plot area.

(1)

- l.** Petrol Pump / LPG Pump / CNG Pump :- Petrol Pump, LPG Pump, CNG Pump shall be permissible subject to following conditions :-
 - i. The minimum size of plot shall be,
 - (a) 30.50 m. x 16.75 m. in the case of Petrol / LPG / CNG Filling Station with kiosk without service bay;
 - (b) 36.50 m. x 30.50 m. in the case of Petrol / LPG / CNG Filling Station with service bay.
 - ii. Plot shall be located / fronting on National Highway, State Highway, Major District Road, Other District Road or Village Road or other road with minimum width of 12.0 m. or more.
 - iii. Permission from Government of India, Petroleum Ministry and Chief Controller of Explosives shall be necessary.
 - iv. N.O.C. from Public Works Department and other related departments shall be obtained as per the prevailing rules. As regards service road / building line / control line, the Government Resolution, Public Works Department, No.RBD-1081/871/Raste-7, dated 09 March, 2001 and the circulars issued in this regard from time to time shall be observed.
As also instructions contained in Government of India, Ministry of Road Transport and Highways letter dated 25/09/2003 and 17/10/2003 and its enclosures as amended from time to time shall be observed.
 - v. The plot on which a petrol filling station with or without service bays is proposed shall be an independent plot on which no other structure shall be constructed.
 - vi. Petrol / LPG / CNG station shall not be permitted within a distance of 90 m. from junction of roads having minimum width of 12 m. each. Also Petrol station shall not be sited within a distance of 90 m. from the nearest premises of school, hospital and theatre, place of assembly or stadium.
 - vii. In the case of kiosks and other buildings for sales office, snack bars etc. within the plot for Petrol / LPG / CNG filling stations, the setbacks from the boundaries shall be 4.50 m. Further the other clearances for the installations shall be as per the Petroleum Rules of 1937.
- m.** Solid waste management, bio-gas plants, power generation from waste and non-conventional sources of energy.
- n.** Way-side amenities such as motels, way-side restaurants, service stations, service godowns, factory outlets, along with public conveniences like toilets, food stall / stalls upto 15 sq.m. carpet area each, within basic permissible FSI of 0.10. Maximum FSI upto 0.50 on gross plot area shall be permissible for all above way-side amenities. Provided that, FSI above the basic permissible 0.10 FSI upto 0.50 may be granted by the Authority / Collector on payment of premium at the rate of 30% of the land rate of the said land mentioned in the Annual Statement of Rates (ASR) for the year in which such additional FSI is granted. Such premium shall be deposited in the office of the Authority / District Branch of the Town Planning Directorate; having maximum 9.0 m. height and G + 1 or Stilt + 2 structure in independent authorized plot abutting existing classified roads including ODR, MDR or on any road not less than 18.0 mtrs. width shall be Permissible. It shall be mandatory for all Way-side Amenities to provide hygienic toilet facilities and decentralized MSW treatment and disposal facilities.
- o.** Development of buildings of health resort, educational and medical activities, with G + 1 or Stilt + 2 structure, subject to plantation of indigenous trees at the rate of 5 trees per 'are' on the plot within basic permissible FSI of 0.10. Maximum FSI upto 0.20 on gross plot area shall be permissible for all above development.

(1)

Provide that, minimum plot area required for Health Resort shall be 0.40 ha., whereas it shall be 1.0 ha. for Educational and Medical activities.

Provided further that, FSI above the basic permissible 0.10 FSI up to 0.20 may be granted by the Authority / Collector on payment of premium at the rate of 20% of the land rate of the said land mentioned in the Annual Statement of Rates (ASR) for the year in which such additional FSI is granted. Such premium shall be deposited in the office of the Authority / District Branch of the Town Planning Directorate.

- p.** The layout / development permission already granted under erstwhile regulations before 28th March, 2017 (i.e. the date of resolution of the R.P. Board to publish Draft R.P.) shall be valid and continue to be so valid, unless otherwise specified in these regulations.

- q.** Residential and Compatible development within & adjacent to Gaothan in Rural area :

- i. Residential and Compatible development within Gaothan in Rural area :

The development control and Promotion regulations as otherwise applicable to Gaothans in Sanctioned Regional Plan, Satara along with the modifications made in it from time to time shall be applicable to the Gaothans shown as existing on Village Maps & Gaothans / extension of Gaothans subsequently declared by Revenue Department under the provisions of Maharashtra Land Revenue Code, 1966.

- ii. Residential and Compatible development adjacent to Gaothan in Rural area :

Residential and / or Compatible development shall be allowed within 200 m. from Periphery of the Gaothan Boundary with following conditions -

Such development may be permitted as per the prevailing regulations applicable to other such peripheral areas in Sanctioned Regional Plan, Satara along with the modifications made in it from time to time on payment of premium of the total area of land. Such premium shall be calculated considering 15% rate of the said land as prescribed in the Annual Statement of Rate of the year granting such developments. Such premium shall be deposited in the concerned Authority / Branch Office of the Town Planning Department for crediting the same in to the Government Treasury.

Provided that, where more than 50% of area of the Survey Number / Gat Number is covered within the above peripheral distance then the remaining whole of such Survey number / Gat number within one ownership shall be considered for development on payment of premium as above.

Provided further that, such payment of premium shall not be applicable in cases where development permissions already granted or layout is already approved before 28th March, 2017 (i.e. the date of resolution of the R.P. Board to publish Draft R.P.) shall be entitled for development /FSI of respective use / zone by the authority / Collector.

Such premium shall also be not applicable for revision of such already approved permissions.

- r.** Development in Gairan Lands / Government Lands :-

Development / Construction in Gairan Lands / Government Lands is permissible for any public purpose for Central & State Government / Departments Projects including rehabilitation in any zone.

Note 1 :- The premium charges mentioned in the above regulation shall not be applicable, if the work is undertaken by Central or State Govt. or public authorities controlled by it.

Note 2 :- The development in command area shall be permissible subject to payment of restoration charges, if any to Irrigation Department.

(1)

- s. Regulation for development of tourism and hospitality services under Community Nature Conservation around wild life sanctuaries and National parks :-

Applicability :- These regulations shall apply to the privately owned (not applicable to forest land) lands situated within 5 km. or the distance as shown in the STR Conservation Plan, whichever is more, from the boundaries of wild life sanctuaries and national parks. The provisions of existing Regional Plans / Development Plans will prevail over these regulations, wherever lands are marked for urbanisable zones in such plans.

Regulation :- For the lands situated within 5 km. distance from the boundaries of wildlife sanctuaries and national parks, if the land owner applies for development permission, for Development of eco-tourism, nature tourism, adventure tourism, same may be allowed; provided the land under consideration has minimum area of one hector in contiguous manner.

Permissible uses and built up area :-

The uses permissible shall be as follows :-

- i. Agriculture, Farming, development of wild animal shelters, plantation and allied uses.
- ii. Tourist homes, Resorts, Hotels etc. with Rooms / suites, support are as for reception, kitchen, utility services etc. along with ancillary structures like covered parking, Watchman's quarter, guard cabin, landscape element sand only one observation tower per tourist resort up to the height of 15 m. with platform area up to 10 sq.m. in permanent / semi-permanent structural components.

The norms for buildings will be as follows :-

- (a) The maximum permissible total built up area shall not exceed 10% of gross area with only G + 1 or Stilt + 2 structure having height not more than 9.0 m. and it should blend with surroundings.
- (b) The Fencing / fortification may be permissible for only 10% of total land area around built up structures in the form of chain link without masonry walls thereby keeping the remaining area free for movement of wildlife.
- (c) Tourism infrastructure must conform to environment friendly, low height, aesthetic architecture, natural cross ventilation; no use of asbestos, no air pollution, minimum outdoor lighting and merging with the surrounding landscape. The owner shall establish the system for captive energy generation using non-conventional energy sources like solar, wind bio-gas etc. so as to make the development self-sufficient.
- (d) The owner shall establish effective sewage disposal and recycling system during the construction and operational phase of the development. No amount of sewage shall go into the natural stream; failing which the resort shall be closed down within 48 hours.
- (e) The owner shall establish effective systems for collection, segregation composting and / or reuse of different types of solid waste collected during the construction and operational phase of the development.
- (f) The plastic components used within the area shall be recycled; failing which the resort shall be closed down within 48 hours.
- (g) Natural stream / slopes terrain shall be kept as it is, except for the built-up area.
- (h) On the area other than 10% area, only indigenous trees shall be planted and only natural vegetation shall be allowed.
- (i) For the developments existing prior to the publishing of the Regional Plan, condition no.(ii) above shall be applicable retrospectively to the extent of restricting the fencing and keeping the remaining area free for movement of wildlife.
- (j) While allowing such development, principles given in the National Tiger Conservation Authority, New Delhi Notification No.15-31/2012-NTCA, dated 15/10/2012 published in the Gazette of India Ext. pt. III S-4 dated 08/11/2012 and Government of Maharashtra as amended time to time shall be used as guidelines.

- (1) t. Film studios at appropriate location having ground floor structure only with the built up area not exceeding 4% (0.04) of the net plot area with the condition that proper landscaping is done & trees are planted at the rate of 500 indigenous trees per hectare.
- u. Open Parking lots / Open Parking lay outs shall be allowed at a distance beyond 2.5 km. from the boundary of core zone with previous approval of Authority / Collector.
- v. Plantations / Afforestation :- Plantations shall be undertaken as per illustrative List of Plantations attached at Annexure - "A"

Any other compatible use not specified above may be permitted by the Authority / Collector with prior approval of Director of Town Planning, Maharashtra State, Pune.

Notes :

- i. The permissible FSI for uses in Buffer zone of Conservation zone shall be 0.1 of the gross plot area, if not specified.
- ii. Every structure shall be with sloping roof.
- iii. All development proposals shall show the existing contour lines of the land at 3.0 m. intervals, certified by a qualified technical person. NO Development shall be permissible where slope of land is more than 20°.
- iv. The owner / Architect shall mark individual trees, dense tree cover area / forest alike area. However where the tree cluster is too dense for individual trees to be marked then the area covered by the tree cluster is to be clearly demarcated on the plans.
- v. The District Conservator of Forest (DCF), Satara Division shall inspect all sites having dense tree cover and Steep Slopes prior to the sanction for the development permission in order to ascertain and verify the information provided about tree cover shown in the plans. On such inspection, the DCF, Satara shall certify whether the area under proposal has dense forest / tree cover or not and if yes he is required to mention the area covered by such dense forest / tree cover / forest alike area.
- vi. In furtherance of above the D.C.F. shall give his detailed remarks regarding tree/s proposed to be cut and / or transplanted if any. However, the number of trees proposed to be cut or transplant shall not exceed 10 % of the number of trees existing thereupon.
- vii. With prior approval of the Director of Town Planning, Maharashtra State, Pune; the Authority / Collector may include other items of public interest in the list which are not covered in the above list.
- viii. Dumping of construction material outside the property in forest or in natural water course is strictly prohibited. (1)

(1) 5.5.3 (1) Regulations for Development above 1000 m. Mean Sea Level.

(1) Appendix - O

**REGULATIONS FOR AREAS SITUATED ABOVE 1000 m. OF MEAN SEA LEVEL
IN SATARA REGION.**

PART - I

ADMINISTRATION

(1) 1.0 SHORT TITLE, EXTENT AND COMMENCEMENT

- A.** Title :- These Regulations shall be called as Regulations for areas situated above 1000 m. of Mean Sea Level in Satara Region.

(1) Regulations for Conservation Zone - Inserted vide Notification No.C.R.83/19/UD-13, Dt.23rd December, 2021

(1) Regulations for Development above 1000 m. Mean Sea Level - Inserted vide Notification No.C.R.83/19/UD-13, Dt.23rd December, 2021

- ⁽¹⁾ **B.** Extent :- These Regulations shall apply to the area earmarked as areas situated above 1000 m. of Mean Sea Level and, more specifically shown in Red Contours on the maps appended herewith as Appendix - “P” and illustratively listed in the Appendix - “Q”.
- C.** Commencement :- These Regulations will come into force after it is sanctioned by Government.
- If there is any conflict between any Regulations sanctioned for Regional Plan Area for Satara Region and these Regulations, these Regulations shall prevail.

⁽¹⁾ **PART - II**

1.0 LAND USE CLASSIFICATION AND PERMISSIBLE USES

- A.** All Regulation of Buffer Zone of Conservation Zone shall be applicable while allowing Development in such areas and more specifically shown on the plan appended herewith as Appendix - “P”

(Appendix - M (Plan No.TPS-1919/436/C.R.83/19/Sec.20(4)/Ud-13) and Appendix - N and Appendix - P (Plan No.TPS-1919/436/C.R.83/19/Sec.20(4)/Ud-13) and Appendix - Q shall be made available for inspection to the general public during office hours on all working days at the following offices :-

- 1) The Director of Town Planning, Maharashtra State, Pune.
- 2) The Joint Director of Town Planning, Pune Division, Pune.
- 3) The Collector, Satara.
- 4) The Assistant Director of Town Planning, Satara Branch, Satara. ⁽¹⁾

5.6 FOR HINGOLI, BULDHANA, WASHIM, YAVATMAL, NANDED REGIONAL PLAN

Following additional regulations shall be applicable for the development in the areas affected by the LIGO project.

- i) Within the distance of 15 km. from the boundary of the site, no New Railway line shall be proposed.
- ii) Within the distance of 5 km. from the boundary of the site, no classified roads, MDR and above etc. shall be newly proposed. Upgradation of existing roads shall not be treated as new road.
- iii) Within the distance of 5 km. to 30 km., from boundary of the site, no reciprocating activity, requiring the use of sustained heavy equipments including mining, blasting or such other similar activities requiring more than 20 HP power, shall be allowed.
- iv) Within the distance of 15 km. from boundary of the site, no Power Plant Machinery, Rock crushers, Heavy Machinery, Wind Mill shall be allowed. Within the distance of 5 km. from boundary of site, no non-reciprocating (rotating) power plant machinery and industrial machinery shall be allowed.
- v) Within the distance of 60 km. from the boundary of the site, no New Airport shall be proposed.

Note -

- a) If any more clarification or exemption or certain information is required, then permissions shall be referred to the LIGO - India authorities (at local office) before final Grant of permission.
- b) The Development Control Regulations as amended from time to time, by the Department of Atomic Energy, Govt. of India, shall be applicable as it is for this LIGO - India Project.

⁽¹⁾ *Regulations for Development above 1000 m. Mean Sea Level - Inserted vide Notification No.C.R.83/19/UD-13, Dt.23rd December, 2021*

5.7 FOR RAIGAD REGIONAL PLAN

- 5.7.1** The development in Nagothane growth centre shall be governed by following regulations.
The lands which fall within the periphery on the north / south direction of the IPCL project complex have been designated as low density residential zone in which residential user may be permitted subject to following conditions -
- i) Maximum FSI shall be 0.25.
 - ii) Only ground floor structure shall be permissible.
- 5.7.2** The development in wadi lands in the coastal belt, which are marked as such in the Regional Plan, development shall be subject to the following conditions, only along the existing roads.
- i) Plot with frontage on the existing road.
 - ii) Ground + one floor building within 33 m. from the existing road with permissible set back from the road.
 - iii) FSI shall be limited to 0.04 maximum with a maximum built-up area of 150 sq.m.
- Note** - Coastal belt is the area within 1 km. from the sea for the purpose of this Regulation.
- 5.7.3** The development in low density Zone in Rajpuri and Usar growth center shall be subject to 0.5 basic FSI.

5.8 FOR SOLAPUR REGIONAL PLAN

In agricultural zone, residential development for the housing of Economical Weaker Section may be permitted subject to following conditions -

- i) The premium at the rate of 10% of the land rate mentioned in ASR without considering the guidelines therein shall be paid before granting the permission.
- ii) The authority / collector shall decide the beneficiary persons, who are actually under the Economical Weaker Section, as per revenue records.

5.9 FOR PUNE REGIONAL PLAN

- 5.9.1** Regulations for planning areas of growth centres at sector – R - i.e. i) Lonavala – Karla - Malvali And ii) Kune – Pangaloli - Kurwande and surrounded area which is a part of Pune Metropolitan Development Authority area, shall be as per the following Regulations.
- i) **REGULATIONS FOR LONAVALA - KARLA - MALAVALI PLANNING AREA OF SECTOR - R OF REGIONAL PLAN OF PUNE REGION**
- No plots in these zones shall be less than 500 sq.m. provided that smaller plots in these zones admeasuring not less than 300 sq.m. existing before the date of publication of regional plan shall be recognized for the purpose of granting development permissions, provided further that plots directly abutting on Mumbai - Pune road shall not admeasure less than 1000 sq.m. Development in such 1000 sq.m. plot, shall be governed by development control rules in Lonavala Development Plan, applicable to 10 are zone. Built up areas, number of storeys, tenements, marginal open spaces and room sizes, the maximum built up areas, the maximum number of storeys, the maximum number of tenements, the minimum marginal open spaces and the minimum room sizes permissible in these zones shall be as indicated in the statement annexed hereto. As regards rules for layout plots and group housing schemes and buildings of various users other than residential including industrial, other items of building construction, such as balcony, sanitation, height, ventilation and parking etc. and all other such regulations which are not explicitly covered above shall be governed by development control regulations for these items incorporated in Development Plan of Lonavala as amended from time to time and subject to these regulations.

Sr. No.	Plot Size group	Maximum built up area	Max. no. of storeys	Max. no of tenements	Min. marginal open space			Min. Habitable room sizes	Min. sizes for kitchen	Min. sizes for shops & other rooms for commercial use
1	Between 300 sq.m. m and less than 500 sq.m	25%	Ground plus one floor only	2	3.0 m.	2.5 m.	3.0 m.	9.0 Sq.m. m with no side less than 3.0 m.	7.5 sq.m. m with no side less than 2.5 m.	15 sq.m. with no side less than 3.0 m.
2	500 sq.m. and above	25%	Ground plus one upper	4	4.5 m.	3.0 m.	4.5 m.			

- 1) A ground floor on stilts or columns without enclosing walls (except retaining walls, where such floor is constructed by cutting the sloping ground) intended to be used as parking space shall not be counted as ground floor.
- 2) In case of classified roads, the minimum marginal open spaces to be observed from roads, shall be as prescribed above or as prescribed by Government from time to time under the ribbon development rules, whichever is more.
- 3) Sr.No.1 is applicable to the plots existing on or before the date of publication of the notification of sectioning of regional plan in the official gazette.

ii) **REGULATIONS FOR KUNE - PANGALOLI - KURWANDE PLANNING AREA OF SECTOR - R OF REGIONAL PLAN OF PUNE REGION** - Development in this area shall be governed by the regulations applicable to 10 Are zone in the Lonavala Regional / Development Plan. The maximum built up areas, the maximum number of storeys, the maximum number of tenements, the minimum marginal open spaces and the minimum room sizes permissible in these zones shall be as indicated in the statement annexed hereto. As regards rules for layout plots and group housing schemes and buildings of various users other than residential including industrial, other items of building construction, such as balcony, sanitation, height, ventilation and parking etc. and all other such regulations which are not explicitly covered above shall be governed by development control regulations for these items incorporated in Development Plan of Lonavala as amended from time to time and subject to these regulations.

Sr. No.	Plot Size group	Maximum built up area	Max. No. of storeys	Max. No. of tenements	Min. marginal open space			Min. habitable room sizes	Min. sizes for kitchen
					Road side	Side	Rear		
1	Between 500 sq.m. and less than 1000 Sq.m.	25%	Ground plus one floor only	2	4.5 m.	3.0 m.	4.5 m.	9.0 sq.m. with no side less than 3.0 m.	7.5 sq.m. with no side less than 2.5 m.
2	1000 sq.m. and above	25%	Ground plus one upper	4	4.5 m.	3.0 m.	4.5 m.	11 sq.m. with no side less than 3.0 m.	

- 1) A ground floor on stilts or columns without enclosing walls (except retaining walls, where such a floor is constructed by cutting the sloping ground) intended to be used as parking space shall not be counted as ground floor.
- 2) In case of classified roads, the minimum marginal open spaces to be observed from roads, shall be as prescribed above or as prescribed by Government from time to time under the ribbon development rules, whichever is more.
- 3) Sr.No.1 is applicable to the plots existing on or before the date of publication of the notification of sanctioning of regional plan in the official gazette.

5.10 CERTAIN REGULATIONS CEASE TO OPERATE IN FUTURE.

The Regulation No.5.8 shall cease to operate on 1st Jan, 2022 or as decided by the Government from time to time and thereafter provisions of these regulations shall apply.

⁽¹⁾ 5.11 BOARD OF APPEALS.

Any person aggrieved by an order / communication made by an authority / Collector under these Regulations may prefer an appeal before the Board of Appeals. The board shall be constituted at division level consisting of the Divisional Head of Town Planning Department of the concerned division as President and concerned A.D.T.P. / T.P. of the district as a member.

⁽²⁾ 5.12 AURANGABAD REGIONAL PLAN

Tourism Development Strip shown in Tourist Complex of Mhaismal Giristhan, Tourist Complex Sulibhanjan, Tourist Complex Verul, Tourist Complex Doulatabad.

Notwithstanding anything contained in these rules, the following Building users will be permissible in this Zone -

Conventional Hotels, Including cottages for tourist.

- i) Canteens / Restaurants & Tea stalls including pan shops.
- ii) Baths & Toilets for camping sites providing for tents / caravans.
- iii) Public utilities and services like information centre, tourist reception centre, telephone booths, first aid centre, health farm, gymnasium, indoor game hall and lawn tennis court, structures for recreation purposes such as Amusement Park, water sports facilities, marine jitties & pontoons for docking of boats, swimming pools, boat house, and like, with following restrictions -
 - a) Minimum plot size should be 100 m. x 50 m. irrespective of holdings.
 - b) 12.0 m. service road should be provided
 - c) Minimum 6.0 m. side margin from all side should be provided. Similarly ribbon development Control Rules should be observed.
 - d) The permissible FSI shall be 0.2 on gross plot area without payment of premium and upto 1.00 with payment of premium at the rate of 20% of land rate in ASR of said land, without considering the guidelines therein.
 - e) Sculpture tree plantation along service road to be carried out with the help of social forest Department. Plantation at the rate of 300 plants per Hectors to be carried out before commencement of work.
 - f) In this strip user of tourist interest is only be permitted.

On the plots, for which regular N.A. and / or layouts are sanctioned and which area affected by this strip, the above said users shall only be permitted, keeping the area & the shape of the plot intact as per sanction. ⁽²⁾

_*_*_*_*_*_*_

⁽¹⁾ Inserted Vide Addendum No.C.R.236/18, dt.14th January, 2021

⁽²⁾ Inserted vide Corrigendum / Addendum No.C.R.121/21, dt.02nd December, 2021

CHAPTER - 6

GENERAL BUILDING REQUIREMENTS - SETBACK, MARGINAL DISTANCE, HEIGHT AND PERMISSIBLE FSI

6.0 GENERAL

Following regulations shall be applicable for the lands included in congested area (or core area) as shown on the Development Plan. These regulations shall also be applicable for the gaathan areas in Regional Plans (including the areas of Local Bodies and Special Planning Authorities where Development Plan or Planning Proposal is not sanctioned).

However, in congested area, if the original land holding is more than 0.40 Hectare, then regulations of non-congested area, except FSI, shall apply. FSI in such cases shall be as per the Regulation No.6.1.1

6.1 REGULATIONS FOR CONGESTED AREA IN DEVELOPMENT PLANS / GAOTHANS OF VILLAGE SETTLEMENTS IN METROPOLITAN REGION DEVELOPMENT AUTHORITIES AND REGIONAL PLANS

(Note - In Nashik Municipal Corporation, the term 'Core Area' is synonymous to 'Congested Area'.)

6.1.1 Residential Buildings / Residential Buildings with mixed-use

i) Floor Space Index :-

The maximum permissible basic floor space index, FSI on payment of premium, permissible TDR loading shall be as per the following Table No.6-A.

Note for Table No.6-A :

- 1) In addition to what is mentioned in Table No.6-A, ancillary area FSI upto the extent of 60% of the proposed FSI in the development permission (including Basic FSI, Premium FSI, TDR but excluding the area covered in Regulation No.6.8) shall be allowed with the payment of premium at the rate as specified below on the land rate in Annual Statement of Rates of the said land without considering the guidelines therein. This shall be applicable to all buildings in all zones.

Sr. No.	Authority / Area	Rate of Premium
1	Pune and Thane Municipal Corporation	15%
2	Nagpur, Nashik Municipal Corporation and Municipal Corporations in M.M.R. (except Thane) and Metropolitan Development Authority area ⁽¹⁾ and CIDCO as Planning Authority by virtue of NTDA.	10%
3	All other Municipal Corporations.	10%
4	Municipal Councils, Nagar Panchayats and R.P. area.	10%

Provided that in case of non-residential use, the extent of ancillary area FSI shall be upto 80%. No separate calculation shall be required to be done for this ancillary area FSI. Entire FSI in the development permission shall be calculated and shall be measured with reference to permissible FSI, premium FSI, TDR, additional FSI including ancillary area FSI added therein.

⁽¹⁾ Inserted vide Notification u/s.37(1AA)(c) No.C.R.236/18 (Part 6), dt.12th October, 2022

Provided further that, the above mentioned rates shall not exceed the rate of premium mentioned in column 4 of Table 7-A under Chapter - 7 where the development permission is sought for the uses mentioned in the said table.

Provided further that, this ancillary area FSI shall be applicable to all other schemes like TOD, PMAY, ITP, IT, MHADA, etc. except ⁽¹⁾ Rehabilitation component in SRA. In the result, free of FSI items in the said schemes, if any, other than mentioned in UDCPR, shall stand deleted.

- 2) All notes mentioned below Table 6-G of Regulation No.6.3 shall be applicable, mutatis-mutandis.
- 3) Utilisation of ancillary area FSI is optional. It can be used fully / partly.
- 4) In case of composite building of mixed users premium and ancillary area FSI shall be on prorate basis.

Table No.6-A								
Sr. No.	Road width in meter	Basic FSI	For all Municipal Corporations and ⁽²⁾ CIDCO as Planning Authority by Virtue of NTDA			For remaining authorities / areas		
			FSI on payment of premium	Maximum permissible TDR loading	Maximum building potential on plot	FSI on payment of premium	Maximum permissible TDR loading	Maximum building potential on plot
1	2	3	4	5	6	7	8	9
1	Below 9.0 m.	1.50	--	--	1.50	--	--	1.50
2	9.0 m. and below 18.0 m.	2.00	0.30	0.30	2.60	0.30	0.10	2.40
3	18.0 m. and below 30.0 m.	2.00	0.30	0.50	2.80	0.30	0.20	2.50
4	30.0 m. and above	2.00	0.30	0.70	3.00	0.30	0.20	2.50

ii) Front Marginal Distances / Setback / Roadside Margin/s in Congested Area

The minimum front setback from the existing or proposed road / roads shall be as per the following Table No.6-B.

Table No.6-B			
Sr. No.	Road width	For Residential building	For Residential Buildings with mixed use
(i)	For streets / lane less than 4.5 m. width	2.25 m. from the centre of the street / lane	2.25 m. + 1.50 m. from the centre of the street / lane
(ii)	For streets 4.5 m. to less than 6.0 m. in width	NIL	1.50 m.
(iii)	For streets 6.0 m. to less than 12.0 m. in width	1.00 m.	2.00 m.
(iv)	For streets 12.0 m. in width and above	2.00 m.	2.50 m.

⁽¹⁾ Inserted Vide Addendum No.CR.236/18, dt.14th January, 2021

⁽²⁾ Inserted vide Notification u/s.37(1AA)(c) No.CR.236/18 (Part 6), dt.12th October, 2022

iii) Side and Rear Marginal Distances in Congested Area

The minimum side and rear marginal distances shall be as per the following Table No.6-C.

Table No.6-C		
Plot Area	Side	Rear
Up to 1000 Sq.m.	0.00	0.00
Above 1000 & upto 4000 Sq.m.	1.00 m.	1.00 m.
Above 4000 Sq.m.	As per Regulation for non-congested area	

Note :-

- 1) For light and ventilation, provisions about interior & exterior chowks shall apply.
- 2) Irrespective of the area of a plot, if the width thereof is 7.0 m. or less, then the side margin shall be nil.
- iv) For the lanes having width less than 4.5 m. abutting to any side of plot, a setback of 2.25 m. from the centre of lane shall be provided to make such lane 4.5 m. wide. No projections shall be permissible on such widened lane.
- v) Excepting the FSI and its maximum loading limit & marginal distances as prescribed above, all other regulations shall be applicable for development permission in congested area.
- vi) **Height :** Above setback and marginal distances shall be applicable for buildings less than 15.0 m. in height. Marginal distances shall be increased by 1.0 m. for buildings having height 15.0 m. and more but less than 24.0 m. For buildings having height 24.0 m. and more, marginal distances shall be as per regulations of non-congested area.

6.1.2 Other buildings like Public / Semi-Public, Educational, Medical, Institutional, Commercial, Mercantile, etc.

(a) **Floor Space Index** - The FSI permissible for these buildings shall be as per Regulation No.6.1.1.

(b) **Marginal Distances** - For these buildings marginal distances shall be 3.0 m. on all sides including front up to 24.0 m. height.

Provided that for building more than 24.0 m. height, regulations of non-congested area shall apply.

Provided further that, for buildings like cinema theatres, multiplex, assembly buildings, shopping malls etc., regulations for outside congested area, except FSI, shall apply.

6.1.3 Pathway for access to internal building or interior part of the building shall not be less than 3.6 m. in width.

6.1.4 Front setback (marginal distance) as prescribed under highway or any other rules shall be applicable if they are over and above as prescribed in these regulations.

6.2 REGULATIONS FOR OUTSIDE CONGESTED AREA (NON-CONGESTED AREA)**6.2.1 Marginal Distances and set-back for Residential Buildings and mixed use with Height up to 15.0 m. or as mentioned in the Table No.6-D.**

The provisions for minimum marginal distances as given in **Table No.6-D** below shall apply for the Residential buildings, Residential with mixed uses permissible in Residential Zone and Residential buildings permissible in other zones.

Table No.6-D							
Sr. No	Description of the road	Min. Plot Size in sq.m.	Min. width of plot in meters	Min. setback from road side in meters	Min. side margins in meters	Min. rear margins in meters	Remarks
1	2	3	4	5	6	7	8
1	Roads of width 30.0 m. and above in local authority area.	450	15	6.0 in case of A, B, C class Municipal Corporations and 4.50 in case of other areas.	3.0	3.0	Side and Rear Margins for building upto 15.0 m. height (excluding parking floor upto 6 m. height)
2	In case of Regional Plan area. NH / SH	450	15	4.5 or as specified by Highway rules whichever is more.	3.0	3.0	Side and Rear Margins for building upto 15.0 m. height (excluding parking floor upto 6.0 m. height)
3	Roads of width 18.0 m. and above but below 30.0 m.	250	10	4.5	2.0	2.0	Side and Rear Margins for building upto 10.0 m. height (excluding parking floor upto 6.0 m. height)
4	Roads of width 15.0 m. and above but below 18.0 m.	200	10	3.0	1.5	1.5	Margins for buildings G + 2 or stilt + 3 structure

5	Roads of width less than 15.0 m.	80	6	3.0	1.5 (in case of semi-detached building, only one side marginal distance shall be permissible)	1.5	Margins for buildings G + 2 or stilt + 3 structure
6	Row Housing on roads of 12.0 m. and below	30	3.5	2.25	0.0 (In case of corner plot, 1.50 or building line of adjoining road whichever is more)	1.5	-- do --
7	Row Housing for EWS / LIG / by public authority / private individual / Slum Upgradation etc. by public authority	20	3.0	0.9 from pathway or 2.25 from road boundary	0.0 (In case of corner plot, 1.5 or building line of adjoining road whichever is more)	0.9	G + 1 or stilt + 2 structure only

Notes :-

- (1) The width of the road in above table shall govern the requirements in column 3 to 8.
- (2) In case of Sr.No.1 to 6 structures having higher height may be permitted subject to marginal distance mentioned in Regulation No.6.2.3.
- (3) The minimum area of plots fronting on service roads along highways shall be with reference to the actual width of the service road.
- (4) For semi-detached buildings, side margin shall be on one side only. Plots for semi-detached buildings shall be in pairs.
- (5) Row-housing plots at the junction of two roads shall be larger to maintain the setback from both roads. Not more than 12 and not less than 3 plots shall be allowed in each block of row housing. Each block shall be separated from the other by a 4.5 m. wide road / pathway or 4.5 m. side marginal distance within the plot or space including side marginal distance of the plot.

- (6) No garage shall be permitted in a building having stilt or basement provided for parking.
- (7) Construction of ottas, railings, barricades or supporting columns for canopy or porch shall not be allowed in minimum front marginal distances. However, steps may be permitted within 1.2 m. from the building line. Also supporting columns for canopy or porch may be allowed within building line.
- (8) In case of Regional Plan areas, ribbon development rules shall not be relaxed without consent of the Highway Authority.
- (9) In case of special building, marginal distances shall be as per regulations for such buildings.
- (10) The plot width to depth ratio shall be 1 : 1.5 to 1 : 2.5, as far as possible in plotted layout.
- (11) In Public Housing Schemes for E.W.S. undertaken by government or semi-government organizations, marginal distances shall be as per the respective schemes and rules.
- (12) The front setback set-out in already approved and partially developed layouts/ schemes, may be retained as per original approval, so as to maintain the building line.
- (13) The pattern of development like semi-detached, row housing etc. in already approved layout shall be as per said approved layout.
- (14) Where commencement certificate is granted prior to publication of draft development plan or sanction of Development Plan and the plot gets affected by new road / road widening, proposed in the development plan, the front margin shall stand relaxed to that extent.
- (15) In case of redevelopment proposal affected by line of street up to 9.0 m. width under Municipal Council or Municipal Corporation Act or development plan road of up to 9.0 m. width, the front margin shall stand relaxed to the extent of land affected by such proposal⁽¹⁾ subject to minimum setback of 1.0 m. for roads having width 12.0 m. or less and 2.0 m. for roads having width more than 12.0 m., from the final line of the street.
- (16) Subsidiary structure such as garage (limited to one), outhouse and independent sanitary block may be permitted only in plots having area 250 sq.m. or more.
- (17) Rear or side marginal distances for development along nallah or watercourses shall be subject to Regulation regarding “Sites Not Eligible for Construction of Building” and “Construction Within Flood Line”. (Chapter 3)
- (18) The plots which are substandard in area shall be developed as per marginal distances mentioned in the above table with reference to road width.
- (19) In case of plots having approach by dead-end road, (point access) front margin shall be limited to width of point access.
- ⁽²⁾ (20) Building Line along classified roads as mentioned in Regulation No.3.1.6 shall be applicable for residential buildings defined in Regulation No.1.3.93(i) and Control Line along classified roads shall be applicable for other uses or for commercial uses as mentioned in Regulation No.3.1.6 or for mixed use buildings where non-residential uses are proposed at least 50% or more of total proposed built-up area.

6.2.2 Other Buildings

The Provision in respect of minimum road width, minimum marginal distances etc., as given in **Table No.6-E** below shall apply for different categories of other buildings.

⁽¹⁾ Inserted Vide Corrigendum / Addendum No.CR.79/2021, dt.02nd December, 2021

⁽²⁾ Inserted vide Corrigendum / Addendum No.CR.121/21, dt.02nd December, 2021

Table No.6-E				
Sr. No	Type of building	Minimum road width required	Minimum marginal distances	Other stipulations
1	2	3	4	5
1	Medical buildings			
	a) Hospital, Maternity Homes, Health Club, Clinics etc. buildings not being special buildings	9.0 m. in case of A, B, C class Municipal Corporation, Metropolitan Authority Area and 7.5 m. in case of other areas.	Margins as per Table No.6-D subject to side marginal distance of minimum 3.0 m.	NIL
	b) Hospital, Maternity Homes, Health Club etc. buildings under category of special building.	Road width as required for Special Buildings. (Regulation No.3.3.9)	6.0 m. on all sides	Height of building subject to provisions of Maharashtra Fire Prevention and Life Safety Measures Act 2006.
2.	Educational buildings			
	a) Pre-primary School	On any road.	Margins as per Table No.6-D	Other requirements shall be as mentioned in the Table No.7-A of Regulation No.7.1. Height of building subject to provisions of Maharashtra Fire Prevention and Life Safety Measures Act 2006.
	b) Primary School not being special building.	6.0 m.	-- do --	
	c) Other Educational Buildings not being special building.	9.0 m.	3.0 m. on all sides	
	d) Any building of category a, b, c above being special building.	Road width as required for Special Buildings	6.0 m. on all sides	
3.	Public-Semi Public Building			
	a) Public-Semi Public Building not being special building.	9.0 m.	Margins as per Table No.6-D subject to side marginal distance of minimum 3.0 m.	.--
	b) Public-Semi Public Building being special building.	Road width as required for Special Buildings	6.0 m. on all sides	--

4.	Cinema Theatre			
	Cinema Theatre / Drama Theatre / Assembly Hall / Multiplex / Shopping Malls	12.0 m.	Front - 12.0 m. (only on one major road). 6.0 m. on all remaining sides	i) In case of cities having population more than 2.5 lakhs as per latest census, redevelopment of existing cinema theatre on plots shall be allowed subject to the condition that at least 1/3rd of the existing seats shall be retained, which shall not be below 150 seats and may be developed in combination with user permissible in R-2 zone. ii) For redevelopment of existing theatre, marginal distances including front margin as per these regulations shall not be insisted. Redevelopment shall be allowed as per existing set back distances. Parking area required as per these regulations shall not be insisted; however existing parking area shall be maintained. iii) In cases where redevelopment of existing Cinema Theatre is carried out on the same place with the capacity more than existing capacity in the form of single or multiscreen cinemas, then owner / developer shall be allowed FSI potential mentioned in column 6 or 9, as the case may be, of Table No.6-G at the rate of 20% land rate mentioned in Annual Rates of Statement without considering guidelines therein, for the additional capacity. iv) The existing Cinema Theatre shall be allowed to be relocated and constructed at some other place within a distance of 5 km. In such case, original site shall be allowed to be developed as per uses permissible in adjoining zone. Construction of Cinema Theatre / Multiplex shall conform to the provisions of Maharashtra Cinema (Regulations) Rules, 1966 and as amended from time to time, except the provisions mentioned above. v) For redevelopment of Cinema plot having area less than 1000 Sq.m., and if redevelopment of existing cinema theatre on such plot is not possible considering the other requirements in these regulations, the condition of providing atleast 1/3rd of the existing seats or minimum 150 seats for cinema theatre shall not be insisted. In such case users permissible in adjoining predominant zone shall be permissible with special permission of sanctioning authority.

5.	Mangal Karyalaya			
	a) Mangal karyalaya and like buildings not under the category of special building.	Road width as required for R-2 zone.	3.0 m. on all sides.	-
	b) Mangal karyalaya and like buildings under the category of special building.	12.0 m.	6.0 m. on all sides.	-
6.	(#) Fuel Stations			
	Fuel Filling Stations / including Petrol / Ethanol / LPG / CNG etc., Public Charging Stations for Electric Vehicles with or without service bays	9.0 m.	4.5 m. on all sides	i) In case the plot is located on any Classified road in Regional Plan area, the distance from the junction of roads as may be specified by Indian Road Congress/ Ministry of Road, Transport and Highway, shall be followed. (IRC guideline 2009 and MORTH Letter No.RW/NH-33023/19/99-DOIII, Dated 25.09.2003 as amended from time to time) ii) NOC from Chief Controller of Explosives shall be necessary. iii) In a plot of Fuel Filling Station, other building or composite building for sales office, snack bars, restaurant, public conveniences or like activities may be permitted. The FSI shall not exceed 0.25 and underground structures along with kiosks shall not be counted towards FSI.
7.	Mercantile Buildings.			
	a) Mercantile / Business / Hotel / Commercial building under the category of special buildings.	Road width as required for Special Building.	Front 6.0 m. Side & rear 6.0 m.	i) Shops may also face on side and rear of a plot. ii) Minimum width and area of Shop shall be as per convenience of the owner / developer. iii) In case of construction of shops / offices only on ground floor (not being special building) side and rear marginal distance shall be as per Table No.6-D.
	b) Mercantile / Business / Hotel / Commercial building not under category of special buildings	Road width as required for R-2 zone.	Margins as per Table No.6-D subject to side marginal distance of minimum 3.0 m.	
	c) Convenience shopping in R-1 zone.	On any road.	Margins as per Table No.6-D.	--

^(#) Clarification issued vide letter No.CR.68/2021 dt., 10th May, 2021

8.	Stadium			
	Stadium with Pavilion	12.0 m.	6.0 m. on all sides	The covered portion of spectator's gallery shall not exceed 25% of plot area, which shall not be counted towards FSI. Shops below spectator's gallery may be permitted which shall not be counted towards FSI. In addition to this, ancillary office, sports persons accommodation, public convenience like structures may also be permitted which shall not consume more than 0.10 FSI on gross plot area.

Note :

- i) In case of plots fronting on National Highways, State Highways and Major District Roads in Regional Plan area, the building line shall be as per Ribbon Development Rules or as given in Table above, whichever is more.
- ii) Side and rear marginal distances mentioned in above Table shall be subject to Regulation No.6.2.3, whichever is more.
- iii) In case of special buildings, marginal distances shall be as per regulations for special buildings.
- iv) A stadium should desirably accommodate 400 m. running track.
- v) For above buildings, permissible FSI shall be as per Regulation No.6.3, unless otherwise specified above.
- vi) Point access (approach by dead end road) to a plot shall be considered for the minimum road width requirement mentioned in above table. In such case, front margin shall be applicable for the width of point access road.
- vi) The provisions about Cinema Theatre in column 5 of Table No.6-E shall be applicable to Cinema Theatres in congested area also.

6.2.3 Marginal distances for buildings of heights more than mentioned in Table No.6-D of Regulation No.6.2.1

- ^(#) **(a) Front Margin** - Front margin shall be as given in **Table No.6-D** shall be applicable to a building irrespective of its height.

Provided that, in the case of group housing schemes where building abuts on internal road, the minimum 3.0 m. set back from internal road or distance between two buildings, whichever is more, shall be provided. For Development / Regional Plan roads or classified roads or through roads, passing through Group Housing Schemes, the setback as prescribed in these regulations shall be provided.

- ^(#) **(b) Side or rear marginal distance** - Side or rear marginal distance in relation to the height of the building for light and ventilation shall be as below :-

The marginal distance on all sides shall be as per Table No.6-D / Table No.6-E for building height or floors mentioned therein. For height more than stipulated in Table No.6-D / Table No.6-E, the marginal distance on all sides, except the front side of a building, shall be minimum $H / 5$ (Where H = Height of the building above ground level).

Provided that, such marginal distance shall be subject to a maximum of 12.0 m. from the plot boundary and distance between two buildings shall be ⁽¹⁾ as per Regulation No.6.2.4.

⁽¹⁾ Substituted Vide Corrigendum / Addendum No.CR.79/2021, dt. 02nd December, 2021

^(#) Clarification issued vide Order No.CR.236/18 (Part 2), dt., 23rd December, 2021

Provided further that, in case of redevelopment of building which has ceased to exist in consequence of accidental fire / natural collapse / demolition for the reason of the same having been declared dangerous or dilapidated or unsafe by or under a lawful order of the authority or building having an age of more than 30 years, such marginal distance may be allowed upto 6.0 m. for height of building upto 45 m. For redevelopment of smaller plots having area less than 1000 sq.m., one of the side margin / rear margin of 6.0 m may be relaxed subject to Fire NOC in case of bonafide hardship.

Provided further that, such marginal distance from recreational open space shall be 3.0 m. in case of non-special buildings and 6.0 m. in case of special buildings, irrespective of its height.

Provided further that, the building height for the purposes of this regulation and for calculating the marginal distances shall be exclusive of height of parking floors upto 6.0 m.

Provided further that, where rooms do not derive light and ventilation from the exterior open space, i.e. dead walls, such marginal distance may be reduced ⁽¹⁾ to 6.0 m. in case of special building and 3.0 m. in case of other buildings.

Provided further that the plot / land of the owner falls within the jurisdiction of more than one authority, then continuous building (without leaving margin on the boundary of the authorities) may be allowed with the consent of the other Authorities.

- (c) **Provision for Step Margin :-** Step margins may be allowed to be provided on upper floors to achieve required side or rear marginal distances as mentioned in these regulations subject to minimum marginal distance of 6.0 m. on ground level in case of special building.

This provision shall also be applicable to congested area.

6.2.4 In the cases of layouts of two or more buildings in a plot for any uses :-

Distance between two buildings :- The distance between two buildings shall be the side / rear marginal distance required for the taller building between the two adjoining buildings.

Provided that, the pathway / internal road may be allowed to be proposed in such marginal distance.

6.2.5 In case of group housing scheme where building abuts on internal road, the minimum 3.0 m. set back from internal road or distance between two buildings whichever is more shall be provided. For Development plan road / Regional plan road or classified road or through road, passing through Group Housing Scheme, normal setback as prescribed in the regulations shall be provided.

6.2.6 Buildings Abutting Two or More Streets

When a Building abuts two or more streets, the setbacks from the streets shall be such as if the building is fronting on each of such streets.

6.3 PERMISSIBLE FSI

Permissible basic FSI, additional FSI on payment of premium, Permissible TDR Loading on a plot in **non-congested** area for **Residential and Residential with mixed uses** and other buildings in developable zones like residential, commercial, public-semi-public etc. shall be as given in **Table 6-G below :-**

⁽¹⁾ Substituted Vide Corrigendum / Addendum No.CR.79/2021, dt. 02nd December, 2021

Table 6-G								
Sr. No.	Road width in meters	Basic FSI	For all Municipal Corporations ⁽²⁾ CIDCO as Planning Authority by Virtue of NTDA			For remaining Authorities / Areas		
			FSI on payment of premium	Maximum permissible TDR loading	Maximum building potential on plot including in-situ FSI	FSI on payment of premium	Maximum permissible TDR loading	Maximum building potential on plot including in-situ FSI
1	2	3	4	5	6	7	8	9
1	Below 9.0 m.	1.10	--	--	1.10	--	--	1.10
2	9.0 m. and above but below 12.0 m.	1.10	0.50	0.40	2.00	0.30	0.30	1.70
3	12.0 m. and above but below 15.0 m.	1.10	0.50	0.65	2.25	0.30	0.60	2.00
4	15.0 m. and above but below 24.0 m.	1.10	0.50	0.90	2.50	0.30	0.70	2.10
5	24.0 m. and above but below 30.0 m.	1.10	0.50	1.15	2.75	0.30	0.90	2.30
6	30.0 m. and above	1.10	0.50	1.40	3.00	0.30	1.10	2.50

Note –

- i) In addition to above, ancillary area FSI up to the extent of 60% of the proposed FSI in the development permission (including Basic FSI, Premium FSI, TDR but excluding the area covered in Regulation No.6.8) shall be allowed with the payment of premium as specified in Regulation No.6.1.1. This shall be applicable to all buildings in all zones.

Provided that in case of non-residential use, the extent of ancillary area FSI shall be upto 80%. No separate calculation shall be required to be done for this ancillary area FSI. Entire FSI in the development permission shall be calculated and shall be measured with reference to permissible FSI, premium FSI, TDR, additional FSI including ancillary area FSI added therein.

Provided further that, this ancillary area FSI shall be applicable to all other schemes like TOD, PMAY, ITP, IT, MHADA, etc. except ⁽¹⁾ Rehabilitation component in SRA. In the result, free of FSI items in the said schemes, if any, other than mentioned in UDCPR, shall stand deleted.

- ii) The column of TDR shall not be applicable for the area, where there is no Planning Authority and accordingly, values in subsequent column shall stand modified.
- iii) The maximum permissible limits of FSI specified in the Table above, may be allowed to be exceeded in cases mentioned in Chapter-7, where higher FSI is permissible over and above the limit specified in above table.

⁽¹⁾ Substituted Vide Addendum No.CR.236/18, dt. 14th January, 2021

⁽²⁾ Inserted vide Notification u/s.37(1AA)(c) No.CR.236/18 (Part 6), dt.12th October, 2022

- iv) Maximum permissible building potential on plot mentioned under column No.6 or 9 shall be exclusive of FSI allowed for Inclusive Housing as per Regulation No.3.8. There is no priority fixed to utilise premium FSI or TDR as mentioned in Column No.4, 5 and 7, 8. ⁽¹⁾ However the Authority, considering the local situation, may allow utilisation of premium FSI and TDR, in equal proportion of permissible premium FSI and TDR mentioned in column No.4, 5 and 7, 8. (e.g. if out of premium FSI mentioned in column No.4 & 7, 40% is proposed to be utilised then out of TDR mentioned in column No.5 & 8, 40% TDR shall also be utilised.) In such cases the Authority shall issue written, well-reasoned speaking orders to that effect. Other conditions of TDR utilisation shall be applicable as per the TDR Regulations No.11.2. In respect of service road, shown on development plan or in approved layout, or plots facing on major road, however deriving access from other roads, the width of highway or major road shall be considered for entitlement of building potential as per column 6 or 9 of above table, as the case may be.
- v) Out of quantum of TDR mentioned in Column No.5 or 8 minimum 30% and subject to maximum 50% of TDR shall be utilised out of the TDR generated from Slum Rehabilitation Scheme (Slum TDR) / Urban Renewal TDR / ⁽²⁾ TDR generated from the area of notified URP as per Regulation No.14.8.8(iv)(c)(i) / Amenity construction TDR (till generation of URT). If such TDR is not available then other TDR may be used.
- vi) The restrictions of road width mentioned above shall not be applicable in cases where, the permissible FSI is more than the basic FSI in various schemes such as slum rehabilitation scheme, redevelopment of dangerous buildings, cluster development for congested (core) area, redevelopment of MHADA buildings, TOD etc. in such scheme, regulations of respective scheme shall be applicable. ⁽³⁾ However, for special buildings as mentioned in Regulation No.1.3(93)(xiv), provisions mentioned in Regulation No.3.3.9 shall be applicable.
- vii) The maximum limits of FSI prescribed above shall be applicable to (a) fresh permission (viz. green-field development (i.e. building on a vacant plot of land) and brown-field development (i.e. cases of addition to existing building where a permissible FSI has not been exhausted.) and also to (b) an existing building which has not been granted full occupation certificate. The cases of existing buildings shall be subject to production of stability certificate from structural engineer.
- viii) **Premium** - Rate of premium for the premium F.S.I., as mentioned in Column No.4 and 7 above shall be 35% of the rate of the said land mentioned in Annual Statement of Rates without considering the guidelines therein. Apportionment of such amount between Authority and Government shall be as decided by Government from time to time. The premium of the Government, if to be paid, shall be deposited by the Authority in the specified head of account of the Government. In the area of Regional Plans, entire premium shall be paid to the Government through the District offices of Town Planning and Valuation Department.
- ix) Basic FSI ⁽¹⁾ and premium FSI for unauthorisedly subdivided plots having area up to 0.4 ha. Shall be ⁽²⁾ 75% of the quantum mentioned in column No.3, 4 & 7 and the TDR shall be to the extent of 50% of the quantum mentioned in column No.5 & 8. This provision shall be subject to provisions in Regulation No.3.4.1(i)(a) and (c) wherein plot shall be entitled for full potential.
- x) The utilisation of TDR mentioned in above table would be available to an existing road width of 9.0 m. and above so marked under relevant Act.

⁽¹⁾ Inserted Vide Addendum No.CR.236/18 (Part 1), dt. 8th October, 2021

⁽²⁾ Inserted / Substituted vide Corrigendum / Addendum No.CR.121/21, dt.02nd December, 2021

⁽³⁾ Inserted Vide Notification No.CR.236/18 (Part-3), dt. 02nd December, 2021

- xi) For plots regularised under Maharashtra Gunthewari Development (Regularisation, Upgradation and Control) Act 2001, these regulations shall apply and allowance of TDR in column No.5 and 8 shall be to the extent of 50%. This shall also be applicable for cases mentioned in Regulation No.3.4.1(i)(b).
- xii) ^(##) In case plots having approach by dead end road, (point access) the potential of plot mentioned in above table shall be permissible if length of such access road does not exceed 100 m.
- xiii) If the strip of land / plot adjacent to road is surrendered by the owner to the authority for road widening, then benefit of widened road in terms of building potential, permissible height shall be granted subject to condition that such road widening shall result in widening of road from junction of roads (or origin of road) to junction of roads (or T junction).
- xiv) ^(#) Entire area of plot may be considered for calculating the potential of plot in respect of premium FSI + TDR, but not the basic FSI. Basic FSI shall be calculated on area of the plot remaining with the owner after deducting area under D.P. road / ⁽¹⁾ road widening / reservations and amenity space. This shall be applicable in cases where reservation area or amenity space is handed over to the authority.
- xv) If ⁽²⁾ any road of width less than 9.0 m. is proposed to be widened to 9.0 m. by the Authority under the provisions of the Municipal Corporation or Municipal Council Act, by prescribing line of street ⁽²⁾ considering 4.5 m. from centre line of the existing road and owner of the plot hands over such affected strip along such road to the authority, then he may be entitled for FSI and potential applicable to 9.0 m. road. ⁽²⁾ This shall be applicable to roads in congested area also.

^(#) Clarification issued vide Letter No.CR.236/18 (Part -2) dt.17th September, 2021

⁽¹⁾ Inserted / Substituted Vide Corrigendum / Addendum No.CR.121/21, dt. 02nd December 2021

⁽²⁾ Inserted / Substituted Vide Corrigendum / Addendum No.CR.79/2021, dt. 02nd December 2021

^(##) Clarification issued vide Order No.CR.236/18 (Part -2) dt.23rd December, 2021

6.4 INDUSTRIAL BUILDINGS

Minimum plot area, front, side and rear margins, Permissible FSI, Additional FSI with payment of premium for industrial buildings in industrial zone shall be as per **Table No.6-H** given below :-

Table No.6-H						
Sr. No.	Min. road width (m.)	Plot Size in sq.m.	Basic Permissible FSI	FSI on Payment of premium	Min. Front Margin in m.	Min. Side & Rear Margins in m.
1	2	3	4	5	6	7
1	9	Up to 300	1.00	0.40	3.00	2.25
2	9	Above 300 and upto 500	1.00	0.40	3.00	3.00
3	9	Above 500 and upto 1000 not being Special Building.	1.00	0.40	4.5	3.00
4	12	Above 1000 and not being special building.	1.00	0.40	4.5	4.50
5	12	Above 500 and being special building.	1.00	0.40	6.0	6.00

Notes :-

- (i) In addition to above, ancillary area FSI up to the extent of 80% of the proposed FSI in the development permission (including Basic FSI, Premium FSI but excluding the area covered in Regulation No.6.8) shall be allowed with the payment of premium as specified in Regulation No.6.1.1. The notes mentioned below Table No.6-G of Regulation No.6.3, which are relevant in respect of industrial use, shall be applicable.
- (ii) In case of Regional Plan areas, the plots fronting on National Highway, State Highway and Major District Roads, the building line / control line shall be as per Ribbon Development Rules or as given in Table above, whichever is more.
- (iii) Maximum floor height shall be 4.5 m. for industrial buildings. However, greater heights maybe permitted as per the requirement.
- (iv) **Buffer zone** - For construction of industrial building, a 23.0 m. wide buffer zone shall be kept from residential or incompatible zone, wherever necessary. Such buffer zone may form part of sizable required recreational open space. Roads and marginal distance may also be treated as a part of Buffer Zone. However, area of such buffer zone, falling within the plot, shall be counted in gross area for computation of FSI. Where green belt is shown in Development Plan between residential and industrial zone, area of such green belt may be counted in gross area for calculation of FSI, if land under such green belt is owned by the applicant.

Provided that, if the land under industrial zone is utilized entirely for non-polluting industries, IT / ITES or like purposes, then such buffer zone / open space shall not be necessary.

6.5 FSI OF GREEN BELT

⁽¹⁾ Basic FSI along with full potential of premium FSI and TDR of the green belt zone shown on the Development Plan / Regional Plan may be allowed on remaining land of the owner by counting area of green belt in gross area of plot subject to condition that the area shall always be under tree cover. The owner shall plant trees in this area with proper planning at the rate of minimum 100 trees per hectare that should have survived for at least one year prior to issuance of occupation certificate.

⁽¹⁾ Inserted vide Corrigendum / Addendum CR.121/21, dt.02nd December, 2021

6.6 CALCULATION OF BUILT UP AREA FOR THE PURPOSES OF FSI

Outer periphery of the construction floor wise (P-line) including everything but excluding ducts, voids, and items in Regulation No. 6.8, shall be calculated for the purpose of computation of FSI. The open balcony, double height terraces and cupboard shall also be included in P-line of respective floor, irrespective of its use / function. If part of the stilt, podium or basement is proposed for habitation purpose or for the construction which is counted in FSI, then such construction shall also be measured in P-line in that respective floor.

6.7 PERMISSIBLE PROJECTIONS IN MARGINAL OPEN SPACES / DISTANCES

The following projections shall be permissible in marginal open spaces :-

- (a) **Projections into Marginal Open Spaces** :- Every open space provided either interior or exterior shall be kept free from any erection thereon and shall be open to the sky and no cornice, chajja, roof or weather shade more than 0.75 m. wide shall overhang or project over the said marginal open spaces so as to reduce the width to less than the minimum required. However, sloping / horizontal chajja provided over balcony / gallery etc. may be permitted up to balcony projections at horizontal level.
- (b) **Balconies** - as specified in Regulation No.9.14
- (c) Ledge for Air conditioning unit as specified in Regulation No.9.5.
- (d) **A canopy or porch** not exceeding 5m.in length and 2.5 m. in width in the form of cantilever and unenclosed over the main and subsidiary entrances providing a minimum clear height of 2.4 m. below the beam bottom of canopy. The canopy shall not have access from upper floors (above floors), for using as sitting out place. There shall be a minimum clearance of 1.5 m. between the plot boundaries and canopy.
Provided that more than one canopy may be permitted in the case of special buildings as per requirement.
- (e) **A projection** of maximum 30 cm. on roof top terrace level may be allowed through out the periphery of the building. In case of pitched roof projection of maximum 45 cm. at rooftop level throughout periphery of the building shall be allowed.
- (f) **Accessory buildings** :- The following accessory buildings may be permitted in the marginal open spaces :-
 - i) In an existing building where toilet is not provided, a single storeyed toilet subject to a maximum area of 4.0 sq.m. in the rear or side open space and at a distance of 7.5 m. from the road line or the front boundary and 1.5 m. from other boundaries may be permissible. The Authority may reduce 1.5 m. margin in exceptional cases to avoid hardship.
 - ii) Parking lock-up garage not exceeding 2.4 m. in height shall be permissible in the rear corner of an independent bungalow plot. Parking lock up garage when attached to main building shall be 7.5 m. away from the road line and shall be of such construction capable of giving fire resistance of 2 hours. The area of sanitary block and parking lock up garage shall be taken into account for the calculation of FSI.
 - iii) Underground Suction tanks, soak pits, wet and dry garbage separately with collection chambers, space required for fire hydrants, electrical and water-fittings, underground water tanks, dustbins etc.
 - iv) One watchman's cabin / booth not more than 6 sq.m. in built up area having minimum width or diameter of 1.80 m. Cabin / booth may be allowed at every entrance and / or exit.

Note :- When a building abuts three or more roads, the above mentioned uses, except (iv), shall be permissible in front setback facing a smaller road of less importance from traffic point of view.

- (g) **Ramp for basement** in side and rear marginal distances subject to provisions under Regulation No.9.12.
- (h) **Fire escape staircase** of single flight not less than 1.2 m. width excluding the marginal distance required for special building.
- (i) **Staircase mid-landing** of 1.2 m. width with clear minimum head room of 2.1 m. below the mid-landing. However, clear distance from edge of landing to the plot boundary shall not be less than 1.8 m. in case of non-special building and 6.0 m. in case of special building.
- (j) **Architectural projections** - Architectural projections as specified in Regulations No.9.30.
- (k) Construction of ottas, railings, barricades or supporting columns for canopy or porch shall not be permitted within the minimum required front marginal distances. However, steps or steps along with otta may be permitted to project upto 1.2 m. from the building line.
- (l) **Cupboard** as specified in regulation No.9.6.

6.8 EXCLUSION OF STRUCTURES / PROJECTIONS FOR FSI CALCULATION

- i) Exclusion of Structures / Projections for FSI Calculation Structures / Projections / features / ornamental projection of glass façade permitted in marginal open spaces as mentioned in Regulation No.6.7 (a), (c), (d), (e), (f)(iii), (g), ⁽¹⁾(--), (j), (k).
- ii) Stilt / Multi-storeyed floors / podium / basement, if used ⁽²⁾ exclusively for parking including passages ⁽²⁾ and staircase, Lift Duct / Lobby therein and basement used for users mentioned in Regulation No.9.11.1(i) to (iii).
- iii) Areas covered by Porches, Canopies, lofts, ledge or tand, shelves, Air Conditioning Plant Rooms, Lift Well, Lift-Machine Room and Service Floor of height not exceeding 1.8 m. height ⁽²⁾ or as permissible as per Regulation No.9.33 below the beam, for hospitals, shopping malls, plazas and Star category hotels (rating with three stars and above) and like buildings, other buildings above 15.0 m. in height.
- iv) Area of structures for water, grey water, wet-waste or an effluent treatment plant, rain water harvesting Pump rooms, ⁽¹⁾ (--) electric cabin of sub-stations / of generator set area, electric meter rooms as per requirements, Refuge chutes / garbage chutes /garbage shafts for wet and dry garbage separately with collection chambers.
- v) Rockery, Well and well structures, Plant Nursery, Water Pool, platform around a tree, Fountain, bench, Chabutara with open top and unenclosed sides, Ramps, Compound wall, Gate, slide / swing, Steps outside the buildings, Domestic working place (open to sky), Overhead water tank on top of the building, Refuge area for high rise buildings as specified in Regulation No.9.29.6
- vi) Telecommunication tower, antenna and allied activities.
- vii) Atrium may be allowed in any type of building. Such atrium may be allowed to be enclosed on top by transparent or opaque sheet.
- viii) Open to sky terraces, top of podium, open to sky swimming pool on the top terrace and top of podium with plant room.
- ix) Structures permissible in recreational open space as per Regulation No.3.4.7.

⁽¹⁾ The words (i) & 'maximum 10 Sq.m.' deleted vide Corrigendum / Addendum CR.121/21, dt.02nd December, 2021

⁽²⁾ Inserted vide Corrigendum / Addendum CR.121/21, dt.02nd December, 2021

6.9 INTERIOR & EXTERIOR CHOWK

- (a) **Interior chowk** : Wherever habitable rooms or kitchen derive ventilation from inner chowk or interior open space, the minimum size of such interior open space shall not be less than 3.0 m. x 3.0 m. ⁽¹⁾ Further such interior chowk shall have an area of not less than the square of one sixth of the height of the highest wall abutting the chowk considered from the lowest point of the chowk, at all levels.
- (b) **Exterior chowk** : The minimum width of the exterior chowk for the purpose of light and ventilation shall not be less than 2.4 m. and the depth shall not exceed 2 times the width, for buildings up to 17.0 m. height and for height more than 17.0 m., the exterior open space shall not be less than $H / 7$ m. x $H / 7$ m. where H = Height of highest wall of the Chowk from ground level. If the width of the exterior chowk is less than 2.4 m., it shall be treated as a notch and shall not be considered for deriving ventilation.
- (c) Where only water closet, bathroom, combined bathroom and water closet are abutting on the interior open space, the size of the interior open space shall be in line with the provision for ventilation shaft as given in Regulation No.9.20.2.

Provided that, for (a) and (b) above maximum distance shall be subject to 16.0 m. If the owner wishes to provide chowk size more than what is prescribed above, it shall be allowed.

6.10 HEIGHT OF BUILDING

This regulation shall be applicable for buildings to be constructed in all land use zones, unless and otherwise specified in the respective regulation.

- (*) (i) Height of building shall be allowed to the extent mentioned below subject to approval of Chief Fire Officer of the Authority or Director of Fire services, if required, under these regulations.

6.10.1

Sr. No.	Authority / Area	Permissible height (m.) excluding parking floor upto 6.0 m. height
1.	For Pune, Pimpri-Chinchwad, Nagpur, Nashik, Municipal Corporations in MMR and Metropolitan Authorities area ⁽²⁾ and Area Development Authorities, Special Planning Authorities ⁽³⁾ CIDCO as Planning Authority by Virtue of NTDA within these areas.	Permissible height as per approval from Fire Department.
2.	For remaining Municipal Corporations area ⁽²⁾ and Area Development Authorities, Special Planning Authorities within these areas.	70
3.	For All Municipal Councils, Nagar Panchayats, Non Municipal Council D.P. and Regional Plan areas.	50

Provided that higher height may be allowed in case of Integrated Township Project where fire station and fire-fighting facilities are to be constructed / provided. Also, if such facilities are available in nearby area of the project, then buildings of higher heights may be allowed in such project. However, necessary certificate to that effect and NOC shall be produced from Director of Fire Services.

⁽¹⁾ Inserted Vide Corrigendum / Addendum No.CR.79/2021, dt.02nd December, 2021

⁽²⁾ Inserted vide Corrigendum / Addendum CR.121/21, dt.02nd December, 2021

⁽³⁾ Inserted vide Notification u/s.37(1AA)(c) No.CR.236/18 (Part 3), dt.12th October, 2022

(*) Directives u/s 154 issued by Govt. Vide Order No. UOR 31/2024/CR 100/2024/UD13 dt. 25th September, 2024.

- (ii) The building height upto 24.0 m. shall be allowed on roads less than 12.0 m. For a building having height more than 24.0 m., the minimum road width shall be 12.0 m.
- (iii) For building in the vicinity of aerodromes, the maximum height of buildings shall be subject to parameters framed by the Civil Aviation Authorities or the development permission shall be considered only after applicant produces NOC from Airport Authority.
- (iv) (a) In addition to (iii), for Industrial Chimneys in the vicinity of aerodromes, it shall be of such height and character as prescribed by Civil Aviation Authorities and all Industrial Chimneys shall be of such character as prescribed by the Chief Inspector of Steam Boilers and Smoke Nuisance, and
 (b) Buildings intended for hazardous godowns for storage of inflammable materials and storage of explosives shall be single storied structures only.
- (v) The buildings of height more than 70.0 m. shall be allowed subject to fulfilment of the requirements mentioned in Regulation No.6.12.

6.11 HEIGHT EXEMPTIONS

The appurtenant structures such as roof tanks and their supports, two toilets on terrace not exceeding 8 sq.m. built-up area and height upto 3.0 m. in case of residential building, ventilating, air-conditioning structures, lift rooms and similar service equipment, stair cover, chimneys and parapet walls and architectural features not exceeding height allowed in these regulations, and Solar panels not exceeding 1.8 m. in height shall not be included in computation of height of building.

6.12 REQUIREMENTS IN CASE OF BUILDING MORE THAN 70.0 M. HEIGHT

It is mandatory for all the high rise buildings to comply with the requirements of Structural Design and Stability, Geo-technical and other aspects and Fire Safety norms as per provisions of UDCPR, Maharashtra Fire (Prevention and life Safety Measures) Act, 2006 and National Building Code of India, amended from time to time, for the aspects not covered in UDCPR. The certificates from structural and geo-technical engineers about the fulfilment of necessary requirements shall be attached with the application. The responsibility of structural and other stability and safety of such high-rise buildings shall lie with owner / developer and concerned expert, consultant, executants appointed by owner / developer.

6.13 FSI OF LANDS AFFECTED BY HEMRL OR OTHER RESTRICTIONS

The lands which are affected by the restrictions of High Energy Material Research Laboratory or provisions of other Central or State Government Acts, forms the part of the entire land, then FSI of such affected land may be allowed to be utilised on the remaining contiguous land. However, sub-division of such land shall not be allowed.

6.14 PROVISION OF RECREATIONAL FLOOR

In case of residential building having height more than 30.0 m., recreational floor may be allowed subject to following -

- i) the height of such floor shall be upto 4.5 m. and shall be open on all sides,
- ii) such floor shall be used for recreational purpose / activities including construction of swimming pool and shall be in addition to the recreational open space required as per UDCPR,

- iii) one such floor may be allowed at every 50.0 m. height, however, first floor may be allowed after 30.0 m. height,
- iv) such floor shall not be counted in FSI, however, ancillary constructions like changing room, wash room, etc. shall be computed in FSI.

⁽¹⁾ 6.15 PROVISION OF HIRKANI KAKSHA (LADIES ROOM)

⁽¹⁾ In any Public / Semi Public, Institutional, Educational, Commercial, Assembly, Mercantile, Business and Office building area upto 25 sq.m. may be allowed for the use of ladies with their children under the age of 6 years, Pregnant women and new born child mother.

Notes :-

- 1) Hirkani Kaksha (Ladies Room) is a facility at a work place / public place where pregnant women, lactating mothers can rest and brestfeed the baby in this room.
- 2) It shall be accessable from common passage / staircase / lift etc. and shall be located preperabaly on ground or firest floor or incase if the ground / upper floor are used as stillt / podium / parking floors, then the floor next above the said parking floor / floors.
- 3) Ladise toilet shall be provided with appropriate ventilation, lighting and drainage facilities.
- 4) For this purpose, all ncessary infrastructures should be provided in the room.
- 5) It shall not be counted in FSI.
- 6) The ownership shall vest with the society / association of owners if any.

_*_*_*_*_*_*_

⁽⁴⁾ Inserted vide Notification u/s.37(1AA)(a) & 20(3) bearing No.CR 35/2023/UD-13, dt.27th November, 2024

CHAPTER - 7

HIGHER FSI FOR CERTAIN USES

7.0 GENERAL

Higher Floor Space Index may be allowed for certain uses in congested and non-congested area, except as otherwise specified and subject to following conditions :

- i) Permissible higher FSI for the buildings as mentioned in Table No.7-A shall be the maximum permissible building potential according to road width as mentioned in column 6, 9 of Table No.6-A or column 6, 9 of Table No.6-G under Regulation No.6.1 or 6.3 (whichever is applicable) minus Basic FSI. Instead of availing this higher FSI, the owner shall be entitled to avail premium FSI / TDR or both to that extent.
- ii) Such higher FSI shall only be available for use for which higher FSI is granted along with ancillary uses.
- iii) **Premium** - Premium for higher F.S.I. shall be as per column 4 of the Table No.7-A below :-
Rate of the premium is based on the land rate mentioned in ASR for respective S.No. / CTS. No. The premium collected shall be shared 50:50 between State Government & the Authority respectively. Premium to be paid to the Government shall be deposited in the concerned Account Head of Urban Development Department at Government Treasury by the Authority. In case of areas of Regional Plans, such entire premium shall be paid to the Government through the District office of the Town Planning and Valuation Department. The quantum / rates of premium shall be subject to the orders of the Government from time to time.
- iv) In addition to above, other ancillary area FSI as mentioned in notes below Table No.6-A and 6-G (whichever is applicable) shall also be applicable for these uses.
- vi) The higher FSI shall also be permissible to existing authorised uses subject to structural stability.
- f) If the owner / developer desires to avail such higher F.S.I. in future for new buildings, then while seeking building permission at first instance, the building plan shall be submitted considering the marginal distances as required for the height of buildings for such higher F.S.I. No condonation in the required open spaces, parking and other requirements in these regulations shall be allowed. However, for the proposals in respect of existing building, such condition need not be insisted upon and the proposal shall be cleared only after strictly conforming to structural and fire safety norms.
- h) No Amenity Spaces as per Regulation No.3.5 shall be required to be provided for the uses mentioned in Table No.7-A.
- j) In agricultural zone, uses mentioned at Sr.No.A & B of table 7-A, shall be entitled for 100% additional FSI over and above, permissible in said zone.

Table No.7.1 – Higher F.S.I.**Table No.7-A**

Categories of the other buildings	Basic FSI	Additional FSI	Rate of the Premium	Conditions if any,
1	2	3	4	5
A) Educational i) Pre-primary School, nursery Kinder-garten and Special Educational Institute for Physically challenged / Mentally ill.	As per Regulation No.6.1 or 6.3, whichever is relevant.	Maximum Building Potential limit as per road width as mentioned in Table No.6-A or 6-G (whichever is relevant) minus basic FSI.	5 %	a) Provision of playground shall be complied with as specified in these regulations. Provided that, it shall not be necessary to increase area of existing play ground, if any, when utilisation of higher F.S.I. as otherwise permissible in these regulations, is proposed on upper floor of existing building. Provided further that, in case of existing building wherein utilisation of higher F.S.I. is proposed on the vacant land, area of play ground shall not be less than 40% or the existing area of play ground whichever is minimum.
ii) Primary School	-- do --	-- do --	5%	Provided further that, in case of existing building wherein utilisation of higher F.S.I. on upper floors is not possible and it is necessary to expand the existing building to accommodate number of students, then in such exceptional circumstances, required area of playground (and not existing) may be permitted to be reduced.
iii) Other Educational Buildings including boys / girls / youth hostels within 500 m. periphery from the recognised educational institutions.	-- do --	-- do --	For Charitable Institutions 10% and for private buildings 15%.	b) Maximum height of Educational building shall be as per the Maharashtra Fire protection and Life Safety Measures Act, 2006.
B) Medical Institutions - Hospital, Maternity	-- do --	As per Sr. No.A(i) above. However,	For Charitable Institutions 10%	Maximum height of building for hospitals, sanatorium and nursing homes, shall be as per the Maharashtra Fire protection

Homes, buildings.		maximum building potential shall be considered as 3.00 subject to Road width 18.0 m. and above.	and for private buildings 15%.	and Life Safety Measure, Act, 2006.
C) Institutional buildings / Banks.	-- do --	As per Sr. No.A(i) above.	As per Sr.No.B above.	
D) Starred category hotels (two star and above) Mega-Ultra Mega and Large Tourism Project / Unit as per Maharashtra Tourism Policy - 2016 or as amended from time to time.	-- do --	-- do --	20%	i) Certificate from the Tourism Department, GOI shall be necessary for type of category of hotels. ii) The maximum building potential limit mentioned in Table No.6-A or 6-G shall be allowed considering the road width one step below. e.g. for the roads as mentioned at Sr.No.3 in Table No.6-G, the maximum building potential shall be considered as given at Sr.No.4. iii) Mega / Ultra Mega / Large Tourism Project / Unit may also include Tourism support activities to the extent of 20% of the additional FSI consumed.
E) Buildings of Government and Semi-Government Offices, Local Authorities and Public Sector Undertakings / the Land in possession of Maharashtra State Road Transport Corporation /	-- do --	As per Sr. No.A(i) above. However, maximum building potential shall be considered as 3.00 for Roads having width 18.0 m. and more.	Government and Semi-Government Originations, Local Authorities – Nil. For Public Sector Institutions – 15%.	i) The Authority may allow exceeding the limit of higher FSI mentioned in column 3. ii) ⁽¹⁾ For the land in possession of MSRTC, maximum 2/3 FSI out of maximum building potential shall be permitted to be utilized for commercial use. Provided that, Minimum 50% contiguous land shall be used for principal purpose of MSRTC.

⁽¹⁾ Inserted vide Corrigendum / Addendum No.CR.121/21, dt.02nd December, 2021

City Transport / Metro Stations and Depot including Govt. Guest Houses.				
F) Religious Building.	-- do --	As per Sr. No.A(i) above.	15%	i) It shall be necessary to obtain the No-Objection Certificate from concerned Police Authority and Collector (District Magistrate), before grant of permission. ii) Other ancillary user like, administration office, Dharmashala or Accommodation for devotees, eateries, convenience shops, etc. may be permitted.
G) Yatri Niwas.	-- do --	-- do --	15%	
I) Basic shelter for urban poor and Housing schemes developed for EWS / LIG.	-- do --	As per Sr. No.A(i) above or FSI upto 2.5, whichever is maximum.	No premium	Any housing scheme for EWS / LIG undertaken by the authority, government / semi government organisation, under the basic shelter for urban poor or similar programme / scheme of the Central / State Government, shall be eligible for higher FSI.
J) Students' Hostel / Working Women - Men Hostel / Dormitories / Hostel for Labourers. (for whom Labour Laws are applicable.)	-- do --	As per Sr. No.A(i) above	10%	i) Built-up area of the unit shall not exceed 17 Sq. m. with or without toilet, excluding common area. ii) Unit shall not be sold and shall be on rental basis. The condition to that effect shall be stamped on plans and be incorporated in permission letter. iii) Ancillary facilities such as kitchen, dining hall, common hall, common toilets may be permitted.
Note : i) The owner shall be at liberty to avail TDR instead of paying premium mentioned in above table to the extent specified above. ii) The above premium shall not be applicable for development under taken by Government, Semi-Government Departments, Local Authorities and Public Sector Undertakings.				

7.2 Entitlement of FSI for Road Widening or Construction of New Roads / Surrender of Reserved Land

The Authority may permit on the same plot, additional FSI of the area required for road widening or for construction of a new road proposed under the Development Plan / Regional Plan / Planning Proposal, and also service road proposed to NH / SH / MDR / ODR whether shown on plan or not, if the owner (including the lessee) of such land surrenders such land without claiming any monetary compensation in lieu thereof and hands over the same free from encumbrances to the satisfaction of the Authority. FSI generated against the surrender of land, shall be in proportion to the provisions mentioned in Regulation of TDR and may be utilised on the remaining land within the building potential mentioned in Table 6-A, 6-G and 6-H of Regulation No.6.1, 6.3 and 6.4 respectively, whichever is applicable. If desired by the owner, TDR, wherever applicable, may be granted against such surrendered land instead of utilizing FSI on remaining land. Such TDR shall be allowed to be utilised as a Development Right in accordance with the provisions regulating Transfer of Development Rights (TDR). Thereafter, the road shall be transferred in the city survey records / revenue records in the name of the Authority and shall vest in it becoming part of a public street.

Provided further that, this concession shall not be granted in respect of :-

- a) Roads in the areas of Town Planning Scheme which are the proposals of the scheme.
- b) Cases mentioned in provision of TDR as mentioned in Regulation No.11.2.3.

7.3 DEVELOPMENT / REDEVELOPMENT OF STAFF QUARTERS OF THE STATE GOVERNMENT OR ITS STATUTORY BODIES OR PLANNING AUTHORITY

7.3.1 Construction / reconstruction of staff quarters of the State Government or its statutory bodies or Authority shall be permitted on land belonging to such Authorities which are situated in developable zones such as Residential / Public Semi-public / Commercial Zones etc. on the following conditions

7.3.2 The basic FSI specified in these regulations may be allowed to be exceeded as per following table on the gross plot area solely for the project of construction of staff quarters (hereinafter referred to as - staff quarter project) for the employees of the Government, or its statutory bodies or the Planning Authority (hereinafter collectively referred to as - User Authority), on land belonging to such User Authority, by the PWD of the Government of Maharashtra or MHADA or Maharashtra Police Housing Corporation or Planning Authority or any other Public Agency nominated by the Government for this purpose, which may also include any Special Purpose Vehicle, wherein the Government or a fully owned Company of the Government holds at least 51% equity share (hereinafter collectively referred to as - “implementing Public Authority”)

7.3.3	Road width and plot area	Maximum permissible FSI including basic FSI
	18.0 m. or above, minimum plot area 4000 sq.m. and above	3.00
	12.0 m. or above but below 18.0 m.	2.50

7.3.4 For the purpose of calculating the FSI, the entire area of the plot excluding area under Development Plan roads / Regional Plan Roads and Development Plan reservations, if any, shall be considered.

Provided that, the Development Plan reservations like Government Staff Quarters, Police Housing, Municipal Housing, Municipal Staff Quarters etc. on lands belonging to Government / Public Authorities / Local Authorities, shall not be excluded, if the scheme is undertaken on the said reservation.

Provided further that, amalgamation of such Development Plan reservation/s with adjoining lands for the execution of project under this regulation shall be permissible.

7.3.5 The total permissible FSI under this regulation shall be utilised for construction of staff quarters and ancillary activities for the User Authority, subject to the following :-

- i) The area of staff quarters for various categories of employees shall be as per the norms prescribed by the concerned User Authority and in no case shall the area of staff quarters exceed the maximum limit of carpet area as prescribed therein.
- ii a) The Authority may also permit up to 1/3rd of the total permissible FSI under this regulation for construction of free sale area (hereinafter referred to as “free sale component”) to be disposed of by the Implementing Public Authority as provided herein. The free sale component shall preferably be constructed in a separate block. Sub-division of plots shall be permissible on the basis of equitable distribution of FSI, in case construction of free sale component is permitted by the Authority.

The free sale component may be utilised for commercial use as per potential of plot as decided by the following committee. The extent of commercial use, if required, shall be decided by the said committee strictly within the limits as specified in these regulations.

Sr. No.	Municipal Corporations / Metropolitan Authorities	Status	Authorities other than those in column 2 including Regional Plan Area
1	2	3	4
1	Municipal / Metropolitan Commissioner (of the Municipal Corporation / Metropolitan Authority)	Chairman	Collector of Concerned District
2	Police Commissioner / District Superintendent of Police of Concerned District	Member	District Superintendent of Police of Concerned District
3	Collector of Concerned District	Member	Chief Officer / Chief Executive Officer of the Authority or Assistant Director of Town Planning of concerned District in the Regional Plan area.
4	Superintendent Engineer (PWD)	Member Secretary	Superintendent Engineer (PWD)

ii-b) If the User Authority requires construction of staff quarters to the extent of full permissible FSI, then the User Authority shall pay full cost of construction + 5% of construction cost as establishment charges to the Implementing Public Authority.

ii-c) The flats constructed under the free sale component shall be first offered to the Central Government, its statutory bodies, Central / State PSUs for purchase as staff quarters and if the Central Government or its statutory Bodies or Central / State PSUs do not indicate willingness to purchase the same within the prescribed time limit, such flats shall be sold in open market.

- 7.3.6** i) Notwithstanding anything contained in these regulations, no amount shall be charged towards Premium, Scrutiny Fee etc., for the projects proposed under this regulation.
- ii) The provisions of Inclusive Housing, mentioned in these regulations, shall not be applicable for development under this regulation.

7.3.7 For any staff quarters project under this regulation, a development agreement shall be executed between the User Authority and the Implementing Public Authority, which, inter alia, shall authorise the Implementing Authority to dispose of the flats constructed under the free sale component of the project, wherever applicable. Such development agreement shall contain the details regarding the modalities and conditions of transferring such quarters (whether free of cost or on payment / receipt of certain amount by the User Authority) to the user authority and also conditions, modalities of disposing of the flats under the free sale component by the Implementing Public Authority.

7.4 DEVELOPMENT / REDEVELOPMENT OF HOUSING SCHEMES OF MAHARASHTRA HOUSING AND AREA DEVELOPMENT AUTHORITY

7.4.1 Development / re-development of housing schemes of Maharashtra Housing and Area Development Authority shall be subject to the following provisions :-

- i) The FSI for a new scheme of Low Cost Housing, implemented by MHADA departmentally on vacant lands for Economically Weaker Sections (EWS), Low Income Group (LIG) and Middle Income Group (MIG) categories shall be ⁽¹⁾ 3.00 or maximum building potential as per road width (Regulation No.6.1 or 6.2) whichever is maximum, on the ⁽¹⁾ Gross Plot Area and at least 60% built-up area in such scheme shall be in the form of tenements under the EWS, LIG and MIG categories, as defined by the Government in Housing Department from time to time.
- ii) For redevelopment of existing housing schemes of MHADA, containing (i) EWS / LIG and / or (ii) MIG and / or (iii) HIG houses with carpet area less than the maximum carpet area prescribed for MIG, the total permissible FSI shall be ⁽¹⁾ 3.00 on the gross plot area.

7.4.2 Where redevelopment of buildings in existing housing schemes of MHADA is undertaken by the housing co-operative societies or the occupiers of such buildings or by the lessees of MHADA, the Rehabilitation Area Entitlement, Incentive FSI and sharing of balance FSI shall be as follows :-

- i) Rehabilitation Area Entitlement :- Under redevelopment of building in existing Housing scheme of MHADA, the entitlement of rehabilitation area for an existing residential tenements shall be equal to sum total of -
- a) a basic entitlement equivalent to the carpet area of the existing tenement plus 35% thereof, subject to a minimum carpet area of 35 sq.m.
- b) an additional entitlement governed by the size of the plot under redevelopment, in accordance with the Table 7-B below :-

Table 7-B	
Area of the Plot under Redevelopment	Additional Entitlement (As % of the Carpet Area of the Existing Tenement)
Upto 4000 sq.m.	Nil
Above 4000 sq.m. to 2.0 hect.	15%
Above 2.0 hect. to 5.0 hect.	25%
Above 5 hect to 10 hect.	35%
Above 10 hect.	45%

⁽¹⁾ Substituted Vide Notification No.CR.236/18 (Part-3), dt.16th June, 2021

Provided that the entitlement of rehabilitation area as admissible under this regulation shall be exclusive of the area of balcony.

- ii) **Incentive FSI** - Incentive FSI admissible against the FSI required for rehabilitation, as calculated in (A) above, shall be based on the ratio (hereinafter referred to as Basic Ratio) of Land Rate (LR) in Rs. / sq.m. of the plot under redevelopment as per the Annual Statements of Rates (ASR) and Rate of Construction (RC)* in Rs. / sq.m. applicable to the area as per the ASR and shall be as given in the Table 7-C below :-

Table No.7-C	
Basic Ratio (LR / RC)	Incentive (As % of Admissible Rehabilitation Area)
Above 6.00	40%
Above 4.00 and up to 6.00	50%
Above 2.00 and up to 4.00	60%
Up to 2.00	70%

Explanation :-

* RC is the rate of construction in respect of R.C.C. Construction, as published by the Chief Controlling Revenue Authority & Inspector General of Registration, Maharashtra State in the Annual Statements of Rates.

Provided that the above incentive shall be subject to the availability of the FSI on the Plot under redevelopment and its distribution by MHADA.

Provided further that in case there are more than one land rate applicable to different parts of the plot under redevelopment, a weighted average of all applicable rates shall be taken for calculating the Average Land Rate and the Basic Ratio.

Provided further that the Land Rate (LR) and the Rate of Construction (RC) for calculation of the Basic Ratio shall be taken for the year in which the redevelopment project is approved by the authority competent to approve it.

- iii) **Sharing of the Balance FSI :-** The FSI remaining in balance after providing for the rehabilitation and the incentive components, calculated as per (i) and (ii) above respectively, shall be shared between the Co-operative Housing Society and MHADA in the form of built-up area, as given in Table No.7-D below and the share of MHADA shall be handed over to MHADA free of cost.

Table No.7-D		
Basic Ratio (LR/CR)	Sharing of balance FSI	
	Share of Co-operative Society	Share of MHADA
Above 6.00	30%	70%
Above 4.00 and up to 6.00	35%	65%
Above 2.00 and up to 4.00	40%	60%
Up to 2.00	45%	55%

Provided that in case of plots up to 4000 sq.m., MHADA without insisting MHADA's Share in the form of BUA, may allow additional BUA over and above existing BUA up to ⁽¹⁾ 3.00 FSI by charging premium at the percentage rate of ASR defined in Table No.7-E below :-

Table No.7-E			
LR/RC Ratio	EWS / LIG	MIG	HIG
0 to 2	20%	45%	60%
2 to 4	23%	49%	64%
4 to 6	25%	53%	68%
Above 6	28%	56%	71%

7.4.3 Where redevelopment of buildings in the existing Housing Schemes of MHADA is undertaken by MHADA or jointly by the MHADA along with the housing societies or along with the occupiers of such building or along with the lessees of MHADA, the Rehabilitation Area Entitlement shall be as follows:-

i) Rehabilitation Area Entitlement :- The Rehabilitation Area Entitlement shall be increased by 15% of the existing carpet area, over and above the Rehabilitation Area Entitlement calculated as per Regulation No.7.4.2(i) above.

7.4.4 For the purpose of calculating the FSI, the entire area of the layout including Development Plan roads / Regional Plan Roads and internal roads but excluding the land under the reservation of public amenities shall be considered. Sub-division of plots shall be permissible on the basis of the compulsory open spaces as in these Regulations. For low cost housing schemes of MHADA for EWS / LIG categories, the Regulations of the UDCPR shall apply.

The reservations in the MHADA layout may be developed as per the provisions of these Regulations.

Provided that there shall be no restriction on the utilization of the FSI permissible under this Regulation except for the restrictions under any law, rule or regulation.

7.4.5 For the purpose of this Regulation the carpet areas for EWS, LIG or MIG tenements shall be as determined by the Government from time to time.

7.4.6 i) For providing the requisite infrastructure for the increased population, an infrastructure charge at the rate of 7% of the Land Rate as per the ASR of the year of approval of the redevelopment project shall be chargeable for the extra FSI granted over and above the basic FSI admissible for the redevelopment schemes. 50% of the Infrastructure Charge levied and collected by MHADA shall be transferred to the Authority for developing necessary off site infrastructure.

ii) No premium shall be charged for the FSI admissible as per the prevailing regulations.

a) Construction of EWS / LIG and MIG tenements by MHADA on a vacant plot, **or**

b) In a redevelopment project for the construction of EWS / LIG and MIG tenements towards the share of MHADA.

7.4.7 Notwithstanding anything contained in these Regulations, the relaxation incorporated for slum rehabilitation scheme shall apply to the Housing Schemes under this Regulation for tenements under EWS / LIG and MIG categories. However, the front open space shall not be less than 3.6 m.

⁽¹⁾ Substituted Vide Notification No.CR.236/18 (Part-3), dt.16th June, 2021

- 7.4.8** i) In any Redevelopment Scheme where the Co-operative Housing Society / Developer appointed by the Co-operative Housing Society has obtained No Objection Certificate from the MHADA, thereby sanctioning additional balance FSI with the consent of 51% of its members and where such NOC holder has made provision for alternative permanent accommodation in the proposed building (including transit accommodation), then it shall be obligatory for all the occupiers / members to participate in the Redevelopment Scheme and vacate the existing tenements for the purpose of redevelopment. In case of failure to vacate the existing tenements, the provisions of relevant sections of the MHADA Act mutatis mutandis shall apply for the purpose of getting the tenements vacated from the non-co-operative members.
- ii) For redevelopment of buildings in any existing Housing Scheme of MHADA under clause 7.4.8(i) hereinabove, by MHADA, the consent of the Co-operative Housing Society in the form of a valid Resolution as per the Co-operative Societies Act, 1960 will be sufficient. In respect of members not co-operating as per approval of the redevelopment project, action under relevant sections of the Maharashtra Housing and Area Development Act, 1976 may be taken by MHADA.
- 7.4.9** A corpus fund, as may be decided by MHADA, shall be created by the Developer which shall remain with the Co-operative Housing Societies for the maintenance of the new buildings under the Rehabilitation Component.
- 7.4.10** i) In case of layout of MHADA where development is proposed under this Regulation and where such land is observed to be partially occupied by slum, under section 4 of Slum Act existing prior to 1.1.2000 or such other reference date notified by the Govt., then for integrated development of the entire layout area and in order to promote flexibility, MHADA may propose development, including area occupied by the slum, under this regulation.
- ii) a) Each eligible residential or residential cum commercial slum dweller shall be entitled to a tenement of carpet area of 27.88 sq.m. (300 sq.ft.) and
b) Existing or 20.90 sq.m. whichever is less in case of non-residential.
- iii) If such land occupied by slum is observed to be affected by reservation then the development of reservation on land occupied by slum shall be regulated by the Slum Regulation.
- iv) Corpus fund : An amount as may be decided by SRA as per Regulation shall be deposited with MHADA Authority for each eligible slum dwellers.

7.5 PROTECTION OF FSI IN REDEVELOPMENT OF EXISTING BUILDINGS

For redevelopment or reconstruction of existing buildings, the FSI to be allowed shall be FSI permissible under Regulation No.6.1 or 6.3, or the FSI consumed by the existing authorized building including TDR, premium FSI etc., whichever is more. (Such TDR, Premium FSI etc. utilised in existing building shall be treated as authorisedly consumed FSI entitled for redevelopment.)

7.6 REDEVELOPMENT OF OLD DILAPIDATED / DANGEROUS BUILDINGS

Reconstruction / Redevelopment in whole or in part of any building which has ceased to exist in consequence of accidental fire / natural collapse or demolition for the reasons of the same having been declared dangerous or dilapidated or unsafe by or under a lawful order of the Authority or building having age of more than 30 years, shall be allowed subject to following conditions.

⁽³⁾ 7.6.1 ⁽³⁾ Redevelopment of Multi-Dwelling Buildings of Co-Operative Housing Societies / Apartments

- i) FSI allowed for redevelopment shall be FSI of existing authorized building and incentive FSI to the extent of 30% of existing built up area or 15 Sq.m. per tenement, whichever is more. Provided further that if the existing authorized built up area and incentive thereon as stated above is less than maximum building potential mentioned in Regulation No.6.1 or 6.3, as the case may be, then society may avail premium FSI / TDR upto maximum building potential. Such incentive FSI shall not be applicable for redevelopment of existing bungalow.
- ii) In cases where carpet area occupied by residential tenement in the existing building is less than the carpet area of 27.87 sq.m. then such tenement shall be entitled for minimum carpet area of 27.87 sq.m. and difference of these areas shall be allowed as additional FSI without any premium.
In case of non-residential occupier the area to be given in the reconstructed building shall be equivalent to the area occupied in the old building.
- iii) This regulation shall be applicable only when existing members of the societies are proposed to be re-accommodated.
- iv) If tenanted building/s and building/s of co-operative housing society / non-tenanted building/s coexist on the plot under development, then proportionate land component as per existing authorized built up area of existing tenanted building on the plot shall be developed as per Regulation No.7.6.2 and remainder notional plot shall be developed as per this regulation.

7.6.2 Redevelopment of tenanted buildings

- i) The FSI allowed for redevelopment of building having protected tenants under the relevant provisions of law, shall be FSI permissible under Regulation No.6.1 or 6.3, or the FSI consumed by the existing authorized building including TDR, premium FSI etc., whichever is more. (Such TDR, Premium FSI etc. utilised in existing building shall be treated as a basic FSI for redevelopment.) In addition to this, 50% incentive FSI of the rehab. area required for rehabilitation of tenants shall be allowed. Provided that rehab. area shall be the authorisedly utilised area or 27.87 sq.m. carpet area per tenement, whichever is more. In case of non-residential occupier the area to be given in the reconstructed building shall be equivalent to the area occupied in the old building.
Provided that, where such building is partly self-occupied by the owners, then entitlement of such partly area shall be governed by the provisions mentioned in Regulation No.7.6.1 above.
Provided further that, if the existing authorised built up area and incentive thereon as stated above is less than maximum building potential mentioned in Regulation No.6.1 or 6.3, as the case may be, then society may avail premium FSI / TDR upto maximum building potential.
- ii) All the eligible tenants of the old building shall be re-accommodated in the redeveloped building.
- iii) In case of fire gutted buildings, the conditions of more than 30 years age of buildings shall not be applicable.

Note :- (applicable for Regulation No.7.6.1 & 7.6.2)

- 1) For the purpose of deciding authenticity of the structure if the approved plans of existing structure are not available, the Authority shall consider other evidences such as Assessment Record or City Survey Record or Sanad.

⁽³⁾ Inserted Vide Notification No.CR.236/18 (Part-3), dt.02nd December, 2021

- 2) The new building may be permitted to be reconstructed in pursuance of an agreement to be executed on stamp paper by at least 51% of the landlord / occupants in the original building, within the meaning of the Bombay Rents, Hotel and Lodging House Rents Control Act, 1947 or Apartment Act and its related provision and in such agreement provision for accommodation for all occupants in the new building on agreed terms shall be made and a copy of such agreement shall be deposited with the Planning Authority before commencement or undertaking reconstruction of the new buildings.
- 3) An amount as may be decided by the Government shall be paid by the Owner / Developer / Society as additional Development Cess for the built up area over and above the Base FSI. A corpus fund as decided by the Authority is to be created by the Developer which will take care of the maintenance of the building for a period of 10 years.
- ^(a) 4) Provided further that, for the purpose of Regulation 7.6.1 and 7.6.2, incentive FSI shall be allowed for redevelopment of building which were existing in Gram Panchayat areas before their enclosure in ULB for any Regional Development Authority subject to following conditions :-
 - i. Building shall be atleast 30 years old;
 - ii. Gram Panchayat must have levied property tax on the building and authorised area shall be taken from the said property tax bill.

7.7 DEVELOPMENT OF HOUSING FOR EWS / LIG

(#) 7.7.1 In Residential Zone -

If the owner constructs the housing for EWS / LIG in the form of tenements of size up to 50 sq.m. ⁽¹⁾ carpet area on his plot, then he shall be allowed FSI of maximum building potential mentioned in the column 6 or 9 of Table No.6-A or column 6 or 9 of Table No.6-G of Regulation No.6.1 or 6.3, subject to following conditions -

- i) For the FSI availed over and above the basic FSI, the premium shall be charged at the rate of 15% of land rate in ASR, without considering guidelines therein.
- ii) Out of the total tenements, at least 40% tenements shall be of ⁽¹⁾ carpet area not more than 30 sq.m.
- iii) Only one tenement should be sold to a family. Adjoining tenement should not be sold to a close relative of such tenement owner. Affidavit to that effect shall be obtained from the land owner / developer and purchaser.
- iv) For these proposals, marginal distances (except front margin) parking and other requirement shall be as per Slum Redevelopment Regulations, wherever such regulations exist.
- v) The owner shall have option to avail TDR over and above basic FSI instead of availing FSI with the payment of premium as mentioned in (i) above.

⁽¹⁾ Note - Out of the permissible FSI, 10% of the basic FSI mentioned in Regulation No.6.1 or 6.3 shall be allowed for commercial use.

7.7.2 In Agricultural Zone -

The housing scheme mentioned in Regulation No. ⁽¹⁾ 7.7.1 shall be permissible in Agricultural Zone with FSI of 1.00 with approach road of minimum 9.0 m. The responsibility of development of infrastructure shall lie with the owner / developer.

⁽¹⁾ **Note** - Out of the permissible FSI, 10% of the FSI shall be allowed for commercial use.

7.7.3 For Regional Plan Area -

The housing scheme mentioned in Regulation No.7.7.1 and 7.7.2 shall be applicable for Regional Plan area mutatis mutandis.

(1) Substituted / Inserted vide Corrigendum / Addendum No.CR.121/21, dt.02nd December, 2021

(#) Clarification issued vide Letter No.CR.100/2/UD-12, dt.18th October, 2023

(2) Directives u/s 154 along with Notice u/s 37(1AA)(A) and 20(3) bearing No. UOR 38CR 118/2024/UD-13, dt. 7th October, 2024.

⁽¹⁾ 7.8 REGULATIONS FOR DEVELOPMENT OF INFORMATION TECHNOLOGY ESTABLISHMENT / DATA CENTERS

⁽¹⁾ 7.8.1 For Municipal Corporations in Mumbai Metropolitan Region and Pune Metropolitan Region.

Development of Information Technology Establishments / Data Center shall be regulated as per the Information Technology & Information Technology Enabled Services (IT / ITES) Policy - 2023 as declared by Industries Department vide Government Resolution No.ITP-2021/CR-170/IND-2, dated 27/06/2023 and amended from time to time which are mentioned below :-

- i) a) The Authority may permit additional FSI as mentioned below over and above the basic permissible F.S.I. to all registered Public and Private IT / ITES Parks / AVGC Parks / IT SEZs or IT Parks in SEZs / Stand-alone IT / ITES units in public IT Park / Data Centers (including IT / ITES units / Data Centers located in Residential / Industrial or any other land use zone in which such users are permissible), which have been approved by the Directorate of Industries, proposed to be set up or already set up under present / previous IT / ITES policies, (hereinafter referred to as the "said unit") by charging premium of 10% of the land rate for the said land OR if such land is included in Central Business District (CBD) by charging premium of 25% of the land rate for the said land, as prescribed in Annual Statement of Rates for the relevant year of granting such additional F.S.I., without applying guidelines.

Sr. No.	Min. Road width (m.)	Max. Permissible FSI
1	12	Up to 3
2	18	Up to 3.5
3	27	Up to 4

Maximum additional FSI permissible shall be as mentioned above or as per Regulation No.6.1 or 6.3, as the case may be, whichever is more.

- b) The Authority may permit additional FSI up to 200% over and above the basic permissible F.S.I. to all registered Public and Private IT / ITES Parks / AVGC Parks / IT SEZs or IT Parks in SEZs / Stand-alone IT / ITES units in public IT Park / Data Centers located in No Development / Green / Agriculture zone in which such users are permissible, which have been approved by the Directorate of Industries, proposed to be set up or already set up under present / previous IT / ITES policies, (hereinafter referred to as the "said unit") by charging premium of 10% of the land rate for the said land as prescribed in Annual Statement of Rates for the relevant year of granting such additional F.S.I., without applying guidelines.

Provided that additional FSI above 100% and up to 200% shall be permissible only on plots having an access road of minimum 18.0 m. width.

In the case of lessor authorities such as New Town Development Authorities as land owner, such Authorities may recover lease premium for additional F.S.I., if applicable, under their land disposal policy.

In addition to what is mentioned above, ancillary FSI as mentioned in Regulation No.6.1.1 shall be applicable.

Premium for additional FSI, ancillary FSI, Development Charges, other charges as may be required to be recovered under this regulations shall be allowed to be paid to the Authority in installments with interest @ 8.5% p.a. as per options and conditions mentioned in Regulation No.2.2.14.

⁽¹⁾ Inserted / Substituted vide Notification u/s.37(1AA)(c) & 20(4) No.CR.97/2023/UD-13, dt.12th January, 2024 (Reg.No.7.8)

- (1) Provided further that, the premium so collected shall be shared between the Planning Authority and the Government in the proportion of 50 : 50. The share of the Government shall be paid to the concerned Branch office of the Town Planning Department.

(Explanation :- Premium charges shall be calculated on the value of lands under such zones, determined by considering the land rates of the said land as prescribed in Annual Statement of Rates (ASR). These charges shall be paid at the time of permitting additional F.S.I. by considering the ASR for the relevant year without applying the guidelines.)

- ii) Maximum 40% of total proposed Built-up area (excluding parking area) inclusive of such additional F.S.I. may be permitted for allied services / support services including commercial and residential activities except polluting activities in IT Parks. Remaining built-up area shall be utilized for IT / ITES / Data center.

Stand alone building / Group of buildings in IT Parks with a minimum built-up area of 20,000 sq.ft. will also be eligible for above benefits.

- iii) Such new unit shall allocate at least 2% of the total proposed built-up area for providing incubation facilities for new units. This area would be treated as a part of the Park to be used for IT activities and eligible for additional FSI benefits accordingly.
- iv) Premium to be received by the Planning Authority against availing additional FSI for IT & ITES industries / Data Center as per provisions in this regulation shall be deposited in a separate account head as provided by State Government as a separate fund viz. "Critical Infrastructure Fund for IT / ITES Industries" and this fund shall be utilized only for creation of Critical Infrastructure for IT / ITES Industries / Data center. The matching contribution from the State Government / MIDC (as a special Planning Authority) will be deposited in the same infrastructure fund.

Provided that in the event, the developer come forward for providing such off site infrastructure at his own cost, instead of paying premium as prescribed above, then the Planning Authority may determine the estimated cost of the work by using rates prescribed in District Schedule of Rates (DSR) of the relevant year, in which order for commencement of such work is issued. The Planning Authority shall also prescribe the standards for the work. After completion of the works, the Planning Authority shall verify and satisfy itself that the same is developed as per prescribed standards and thereafter, by deducting the cost of works, the balance amount of premium shall be recovered from such developer before issuing Occupancy Certificate.

Provided that, in case the cost of work is more than the premium to be recovered, such additional cost to be borne by such developer.

- v) Permission for erecting towers and antenna up to height permitted by the Civil Aviation Department shall be granted by the Authority as per the procedure followed for development permission or otherwise as may be decided by the Government.
- vi) While developing site for IT / ITES / Data Center with additional FSI, support services as defined in the IT Policy - 2023 or amended from time to time, shall be allowed.
- vii) Notwithstanding anything contained in the Development Control Regulations of Planning Authorities, no amenity space is required to be left for development of IT / ITES / Data Center buildings.
- viii) The Directorate of industries will develop a web portal on which the developer of every IT park / Data Center will be bound to provide / update detailed information about names of the units in the park, utilization of built-up area and activities being carried out, manpower employed in the IT Park for IT / ITES / Data Center and support services on yearly basis.

⁽¹⁾ Inserted / Substituted vide Notification u/s.37(1AA)(c) & 20(4) No.CR.97/2023/UD-13, dt.12th January, 2024 (Reg.No.7.8)

⁽¹⁾ If a private IT park / Data Center has availed additional FSI as per the provisions of IT / ITES policy and subsequently it is found that the built-up space in the park is being used for non IT / ITES / Data Center / commercial activities / any other activity not permitted as per the IT / ITES policy under which the said park was approved, a penal action as below will be taken, the payment shall be shared between the concerned Planning Authority and the Government in the ratio of 3 : 1.

- a) The misuse shall be ascertained by physical site verification of the said private IT park / Data Center by a team of officers from the Directorate of Industries and the Planning Authority which has approved the building plans of the said private IT park.
- b) A per day penalty equal to 0.3% of the prevailing ASR value of the built-up area that has been found to be used for non-IT / ITES activities / Data Center.
- c) The penalty will be recovered from the date of commencement of unauthorized use till the day non-IT use continues.

After payment of the penalty to the concerned Planning Authority which has sanctioned the building plans of the concerned private IT park, the said private IT Park will restore the use of premises to the original purpose for which LOI / Registration was granted. If the private IT Park / Data Center fails to pay penalty and / or restore the use to its original intended use, the concerned Planning Authority will take suitable action under the Maharashtra Regional and Town Planning Act, 1966, against the erring private IT Park under intimation to the Directorate of Industries. This provision will also be applicable to existing IT Parks. ⁽¹⁾

⁽¹⁾ **7.8.2 For areas except areas mentioned in Regulation No.7.8.1 above and except Regional Plan areas**

The regulations mentioned in Regulation No.7.8.1 above shall be applicable to the areas except areas mentioned in Regulation No.7.8.1 above and except Regional Plan areas with following modifications. The Authority shall grant additional FSI accordingly.

- i) Premium to be paid for additional FSI shall be 15% of the land rates for the said land as prescribed in Annual Statement of Rates, without applying guidelines.
- ii) Sharing of premium between the Planning Authority and the Government shall be 75 : 25.
- iii) Maximum 50% of total proposed Built-up area may be permitted for allied services / support services including commercial and residential activities except polluting activities.

Stand alone building / Group of buildings in IT Parks with a minimum built-up area of 20,000 sq.ft. will also be eligible for above benefits. ⁽¹⁾

⁽¹⁾ **7.8.3 For Regional Plan area**

The provisions mentioned in Regulation No.7.8.1 above shall be applicable to Regional Plan area with following modifications. The Authority shall grant additional FSI accordingly.

- i) In case of Regional Plan area, premium to be paid for additional FSI shall be 5% of the land rates for the said land as prescribed in Annual Statement of Rates without applying guidelines and shall be paid to the Government through District office of the Town Planning and Valuation Department.
- ii) Maximum 50% of total proposed Built-up area may be permitted for allied services / support services including commercial and residential activities except polluting activities. ⁽¹⁾

⁽¹⁾ Inserted / Substituted vide Notification u/s.37(1AA)(c) & 20(4) No.CR.97/2023/UD-13, dt.12th January, 2024 (Reg.No.7.8)

- ⁽¹⁾ Note :- 1) In case of Regulation No.7.8.2 and 7.8.3, no premium shall be chargeable in areas of Planning Authorities, if they are covered under Vidarbha, Marathwada, Dhule, Nandurbar, Ratnagiri and Sindhudurg Districts and no Industry Districts and Naxalism affected areas of the State (as defined in the "Package Scheme of Incentives-2013" of the Industries, Energy & Labour Department of the State.)
- 2) If additional development potential over and above maximum permissible development potential mentioned in this provision is permissible under any other provisions of the prevailing Development Control and Promotion Regulations, such additional development potential shall be permissible as per the provisions of the relevant regulations of the prevailing Development Control and Promotion Regulations. ⁽¹⁾

7.9 REGULATION FOR DEVELOPMENT OF BIOTECHNOLOGY PARKS

7.9.1 Definition

The Biotechnology Units / Parks shall mean Biotechnology units / parks which are certified by the Development Commissioner (Industries) or any officer authorised by him in his behalf. The Biotechnology Park and unit / units outside park shall have minimum land area of 0.80 ha. or 1,858 sq.m. (20,000 sq.ft.) built up area.

7.9.2 Biotechnology Units / Parks to be Allowed in Industrial Zone

Biotechnology Units / Parks shall be permitted in Industrial Zone on all plots fronting on roads having width more than 12.0 meter and all regulation of Industrial Zone shall apply.

7.9.3 Biotechnology Units / Park to be allowed in No Development Zone earmarked in the Development / Regional Plan.

Biotechnology Units / Parks shall be permitted in No Development Zone subject to following conditions :-

- i) Maximum FSI limit shall be 0.20 on gross area and as far as possible the development shall be at one place of the total land.
- ii) The ground coverage shall not exceed 10% of the area of the plot.
- iii) Tree plantation shall be done at the rate of 500 Trees / Ha. on the remaining land excluding the built up area and the surrounding open space / utility space.
- iv) The maximum height of buildings shall not exceed 24.0 m.
- v) Essential residential development for the staff / officers' accommodation shall be permitted up to the extent of 33% of the permissible built up area.

7.9.4 Additional FSI to Biotechnology Units / Park

The Authority may permit the floor space indices specified in these regulations to be exceeded to the extent of 100% over and above the permissible basic FSI for biotechnology units / parks subject to following conditions :-

- i) Out of total built up area minimum 90% shall be used for Biotechnology purpose and maximum 10% (by deducting parking space) shall be used for ancillary users such as specified in the Govt. Resolution of Industry, Energy and Labour Department No. BTP-2008/CR-1608/Ind-2, dated 10/2/2009 or as amended from time to time.
- ii) Additional FSI to Biotechnology units would be available to Biotechnology Parks duly approved by the Directorate of Industries and after observance of all the regulation of environment.

⁽¹⁾ Inserted / Substituted vide Notification u/s.37(1AA)(c) & 20(4) No.CR.97/2023/UD-13, dt.12th January, 2024 (Reg.No.7.8)

- iii) Parking spaces, as per the provision of Development Control and Promotion Regulation shall be provided subject to minimum requirement of one parking space per 100 sq.m. built up area.
- iv) The additional FSI shall be granted upon payment of premium which shall be paid in the manner as may be determined by the Government. Such premium shall be recovered at the rate of 20% of the present day market value of the land under reference as indicated in the ASR.
- v) 25% of the total premium shall be paid to the Government and remaining 75% amount shall be paid to the said Authority. In Regional Plan area, such amount shall be entirely paid to the Government through the concerned branch office of the Town Planning and Valuation Department.
- vi) The premium so collected by the Authority shall be primarily used for development of offsite infrastructure required for the Biotechnology Parks.
- vii) In the event, the developer comes forward for provision of such off site infrastructure at his own cost, then the said Authority shall determine the estimated cost of the works and shall also prescribe the standards for the work. After completion of the works the said Authority shall verify as to whether the same is as per prescribed standards and thereafter, by deducting the cost of works, the balance amount of premium shall be recovered by the said Authority
- viii) No condonation in the required open spaces, parking and other requirement prescribed in the regulations shall be allowed in case of additional FSI.
- ix) Development of biotechnology park shall be done as per the guidelines issued by Industries Department vide the Government resolution dated 10th February, 2009 as amended from time to time.

7.10 INCENTIVE FOR GREEN BUILDINGS

The Authority shall strive to promote green building concepts within the municipal area, ⁽²⁾ CIDCO as Planning Authority by Virtue of NTDA. In order to do so it may empanel agencies of repute as listed / recognised by the State / Central Government. The following incentives shall be provided for green rated buildings.

- i) Green buildings shall be entitled for incentive FSI as below.
 - GRIHA Three star / IGBC Silver / LEED silver / ⁽¹⁾ The ASSOCHAM GEM or equivalent rating - 3% incentive FSI on basic FSI.
 - GRIHA Four star / IGBC Gold / LEED Gold / ⁽¹⁾ The ASSOCHAM GEM or equivalent rating - 5% incentive FSI on basic FSI.
 - GRIHA Five star / IGBC Platinum / LEED Platinum / ⁽¹⁾ The ASSOCHAM GEM or equivalent rating - 7% incentive FSI on basic FSI.

Provided, achieving minimum GRIHA Three star / IGBC Silver / LEED silver / ⁽¹⁾ The ASSOCHAM GEM or equivalent rating for construction projects shall be mandatory for all buildings belonging to Government, Semi- Government, local bodies and public sector undertakings.
- ii) Incentive FSI will be awarded after pre-certification from the empanelled agency. This FSI shall be exclusive of the limits specified in this UDCPR.
- iii) In case that the developer fails to achieve committed rating as per pre-certification at the time of final occupancy, a penalty shall be imposed at the rate 2 times of the land cost as per ASR for the incentive FSI for the rating not achieved.

⁽¹⁾ Inserted vide Corrigendum / Addendum No.CR.121/21, dt.02nd December, 2021

⁽²⁾ Inserted vide Notification u/s.37(1AA)(c) No.CR.236/18 (Part 6), dt.12th October, 2022

7.11 DEVELOPMENT OF PUBLIC TOILET

If any person constructs public toilet prescribed by the Authority on its land, preferably on ground floor, he may be granted Amenity TDR against the constructed area as per regulation of Transferable Development Rights. If owner constructs such amenity on his own land, he shall also be entitled for aforesaid benefit alongwith additional 50% TDR thereon as incentive, in addition to TDR of land occupied by such structure along with appurtenant land. In such case, the said structure along with land shall be transferred, to the Authority with proper approach.

7.12 BUILDINGS OF SMART FIN-TECH CENTRE

- i) The Authority may permit additional FSI up to 200% over and above the basic permissible FSI to Smart Fin-Tech Centre located in Residential / Industrial / Commercial Zone, which have been approved by the Directorate of Information Technology, proposed to be set up (hereinafter referred to as the "said unit") by charging premium of 20% of the land rate for the said land as prescribed in Annual Statement of Rates for the relevant year of granting such additional FSI.

Provided that additional FSI shall be permissible only on plots having an access road of minimum 18.0 m. width and subject to approval by committee chaired by the Principal Secretary, Information Technology and comprising representatives of Industries, Finance and Urban Development Department (UD-1).

Provided further that, the premium so collected shall be shared between the Planning Authority and the Government in the proportion of 50 : 50. The share of the Government shall be deposited in the Fin-Tech Corpus fund which is being set up by Director of Information Technology.

(Explanation :- Premium charges shall be calculated on the value of lands under such zones, determined by considering the land rates of the said land as prescribed in Annual Statement of Rates (ASR). These charges shall be paid at the time of permitting additional FSI by considering the ASR for the relevant year without applying the guidelines).

- ii) The total maximum permissible FSI shall not exceed limit of 3.00. In case of plot fronting on roads having width of 24.0 m. or more, the FSI may be permitted to be exceeded upto 4.00.
- iii) No amenity space is required to be left for development of plot / land up to 2.00 Hectare for Smart Fin-Tech Centre.
- iv) At least 85% of total proposed Built-up area (excluding parking area) shall be permitted for business of Fin-Tech (start-ups, incubators, and accelerators), banking and financial service including NBFC and insurance, and IT / ITES with focus on Fin-Tech.
- v) The Directorate of Information Technology will develop a web portal on which the developer of every Smart Fin-Tech Centre will be bound to provide / update detailed information about names of the units in the park, utilization of built-up area and activities being carried out, manpower employed in the Smart Fin-Tech Centre on yearly basis.
- vi) If a Smart Fin-Tech Centre has availed additional FSI as per the provisions of this regulation and subsequently it is found that the built-up space in the Smart Fin-Tech Centre is being used for non-Fin-Tech / commercial activities / any other activity, not permitted as per the Smart Fin-Tech Centre policy under which the said Centre was approved, a penal action as below will be taken, the payment shall be shared between the Authority and the Government in the ratio of 3:1.
 - a) The misuse shall be ascertained by physical site verification of the said Smart Fin-Tech Centre policy by a team of officers from the Directorate of Information Technology and the Authority, which has approved the building plans of the said Smart Fin-Tech Centre.

- b) A per day penalty equal to 0.3% of the prevailing readyreckoner value of the built-up area that has been found to be used for non-Fin-Tech activities, shall be imposed.
- c) The penalty will be recovered from the date of commencement of unauthorized use till the day non-Fin-Tech activities.

After payment of the penalty to the Authority, which has sanctioned the building plans of the concerned Smart Fin-Tech Centre, the said Smart Fin-Tech Centre will restore the use of premises to the original purpose for which LOI / Registration was granted. If the Smart Fin-Tech Centre fails to pay penalty and / or restore the use to its original intended use, the Authority will take suitable action under the Maharashtra Regional and Town Planning Act, 1966, against the erring Smart Fin-Tech Centre under intimation to the Directorate of Information Technology. These provisions will be over and above the penal provisions of the M.R. & T.P. Act, 1966.

- vii) In this regulation the terms and expression shall have the meaning specified in Fin-Tech Policy declared by Directorate of Information Technology vide Govt. Resolution No.DIT-2018/CR-17/D-1/39, dated 16th February, 2018. Notwithstanding anything contained in the existing regulation, the above provisions shall be applicable for Smart FinTech Centre.

Other provisions of existing regulations, which are not specifically mentioned in this regulation, shall be applicable.

(1) 7.13 (1) COMMERCIAL BUILDINGS IN CBD, COMMERCIAL, RESIDENTIAL ZONE IN PLANNING AUTHORITIES AREAS

Additional FSI for Commercial user development in Central Business District (CBD) or plot situated in Residential or Commercial Zone or Independent plot wherein Residential or Commercial uses allowed in Industrial zone :

The Authority may allow FSI up to 5.0 including permissible FSI as per provision of Regulation No.6.3, Table No.6-G in Chapter - 6 for commercial user / development on plots marked as CBD or plots situated in Residential or Commercial zone or independent plot wherein Residential or Commercial uses allowed in Industrial zone after compliance of Regulation No.4.8.1 of these Regulations subject to the condition that permissible FSI as per Table No.6-G will be utilized first and the additional FSI under this Regulation on payment of premium subject to following conditions :

- 1) Additional FSI shall be allowed for plots which are not reserved / designated in the D.P. except affected by proposed D.P. roads / sanctioned regular line of street under M.M.C. Act and parking reservation.
- 2) The development of reserved / designated plots in CBD shall be governed by provisions of these Regulations.
- 3) Development for residential purpose to the extent of maximum 30% of the permissible FSI as per provisions of Regulation No.6.3, Table No.6-G may be allowed. Additional FSI as per this regulation shall not be permissible for residential user / development.
- 4) Premium for granting such additional BUA beyond permissible FSI as per Table No.6-G shall be charged at the rate of 50% of ASR for land and shall be equally shared between the GoM and the Authority.
- 5) Provision of Inclusive Housing shall not be applicable for development in CBD.

⁽¹⁾ Inserted vide Notification No.CR.236/18 (Part-3), dt.16th June, 2021 (Reg.No.7.13)

Provided further that in case the entire commercial development is on a plot situated in Commercial zone / independent plot in Residential zone, and satisfies other related provisions of these regulations, the Authority may allow FSI as detailed below including permissible FSI as per provision of Regulation No.6.3, Table No.6-G for commercial uses / development on area of plots excluding area covered under reservation / designation in the D.P. except affected by proposed D.P. roads / sanctioned RL under M.M.C. Act on payment of premium for built up area @ 50% of ASR for open developed land for FSI 1.00 and shall be equally shared between the GoM and Authority. In this case, no residential development will be allowed on such plot.⁽¹⁾

Sr. No.	Minimum	Maximum Permissible FSI
1	12.0 m.	3
2	18.0 m.	4
3	27.0 m.	5

_*_*_*_*_*_*_

⁽¹⁾ Inserted vide Notification No.CR.236/18 (Part-3), dt.16th June, 2021 (Reg.No.7.13)

CHAPTER - 8

PARKING, LOADING AND UNLOADING SPACES

8.1 PARKING SPACES

Wherever a property is to be developed or redeveloped, parking spaces at the scale laid down in these Regulations shall be provided. A parking plan showing the parking spaces along with manoeuvring spaces / aisles shall be submitted as a part of building plan. When additions are made to an existing building, the new parking requirements will be reckoned with reference to the additional space only and not to the whole of building but this concession shall not apply where the use is changed. The provisions for parking of vehicles for different occupancies shall be as given in Table No.8-A

8.1.1 General Space Requirements

i) Location of Parking Spaces

The parking spaces include parking spaces in basements or on a floor supported by stilts, podium or on upper floors, covered or uncovered spaces or in separate building in the plot and / or lock up garages. The height of the stilt shall not be less than 2.4 m. from the bottom of beam. In case of stack parking, height up to 4.5 m. may be allowed.

ii) Size of Parking Space

The minimum sizes of parking spaces to be provided shall be as shown below in Table No.8-A

Table No.8-A - Parking Space Requirement		
Sr. No.	Type of Vehicle	Minimum size / area of parking space
1	Motor vehicle	2.5 m. x 5.0 m.
2	Scooter, Motor Cycle	1.0 m. x 2.0 m.
3	Transport vehicle / Ambulance / Mini Bus	3.75 m. x 7.5 m.

Note :

- ⁽¹⁾ (a) In the case of parking spaces for motor vehicle, upto 50 percent of the prescribed space may be of the size of 2.3 m. x 4.5 m.
- ⁽¹⁾ (b) Minimum size of parking space in mechanized / puzzle parking system shall be 2.3 m. x 5.8 m. for big cars and 2.1 m. x 5.0 m. for small cars.

iii) Marking of Parking Spaces

Parking space shall be paved and clearly marked for different types of vehicles.

iv) Manoeuvring and Other Ancillary Spaces

Off street parking space must have adequate vehicular access to a street and the area shall be exclusive of drives, aisles and such other provisions required for adequate manoeuvring of vehicles. The width of drive for motor vehicles and scooter, motor cycle shall be minimum 3.00 m. and 2.00 m. respectively.

v) Composite parking

The composite parking of vehicles like one car with two scooters may be allowed. Also, six scooters' parking may be allowed to be converted in one car parking. In such cases, drives or aisles shall be required taking into consideration entire composite parking.

vi) Bus bay for schools / multiplex / malls / assembly buildings / group housing

For these occupancies, being a special building, a bus bay of required size shall be provided within premise or along main road on which plot abuts. This shall be applicable for housing scheme having more than 500 flats.

⁽¹⁾ Inserted Vide Corrigendum / Addendum No.CR.79/2021, dt.02nd December, 2021

vii) Ramps for Basement Parking

Ramps for parking in basement should conform to the requirement of Regulation No.9.12

viii) Other Parking Requirements

- a) To meet the parking requirements as per these regulations, common parking area for group of buildings, open or multi-storeyed, may be allowed in the same premises.
- b) In addition to the parking spaces provided for building of Mercantile (Commercial) like office, market, departmental store, shopping mall and building of industrial and storage, loading and unloading spaces shall be provided at the rate of one space for each 1000 sq.m. of floor carpet area or fraction thereof exceeding the first 200 sq.m. of floor area, shall be provided. The space shall not be less than 3.75 m. x 7.5 m. ⁽¹⁾ subject to maximum requirement of 4 such parking spaces for office buildings and 6 parking spaces for other buildings. However, in case of office building, such parking spaces shall not exceed more than 4.
- c) Parking lock up garages shall be included in the calculation for F.S.I. calculations.
- d) The space to be left out for parking as given in this regulation shall be in addition to the marginal open spaces left out for lighting and ventilation purposes as given in these regulations. These spaces may be used for parking provided minimum distance of 3.0 m. (6.0 m. in case of special building mentioned in Regulation No.2.2.8) around the buildings is kept free of any parking or loading and unloading spaces, excepting the building as mentioned in Clause (c) above. Such parking area adjoining the plot boundary may be allowed to be covered on top by sheet roofing, so as not to in fringe the marginal distance to be kept open as specified above. Further such sheet roofing shall not include the area adjoining the plot boundary to be used for tree plantation as mentioned in Regulation No.3.4.1(iii), if any.
- e) In case of parking spaces provided in basements, at least two separate ramps of adequate width and slope for entry and exit shall be provided preferably at opposite ends. One ramp may be provided as specified in Regulation No.9.12.
- ⁽¹⁾ f) Mechanical / Hydraulic / Stack parking / Parking tower may be permitted at 1.5 m. in side and rear margin under following circumstances -
 1. Minimum 6.0 m. drive way shall be kept clear from all kind of obstruction for easy manoeuvrability of fire and rescue appliances like ambulance. For building defined as High Rise building and special building in these regulations, 9.0 m. turning circle around the building shall be maintained.
 2. For Non Special building as defined in these regulations, such distance shall not be less than 3.0 m.
 3. Such mechanical / hydraulic / parking tower may be permitted touching the building on dead wall side. Provided that the dead wall must be 2 hours fire rated wall.
 4. The fire protection arrangement as per storage building will be made applicable to such parking towers as per Table - 7 of Part - 4 of NBC - 2016.

8.2 OFF STREET PARKING REQUIREMENT**8.2.1 Off-street parking requirement**

Off street parking requirement shall be based on Table No.8-B below and factors mentioned in Table No.8-C of Regulation No.8.2.2 for various cities / areas. Total parking requirement for a building shall be worked out as per Table No.8-B, and then factor mentioned in Table No.8-C shall be applied to arrive at required parking for a building.

⁽¹⁾ Inserted Vide Corrigendum / Addendum No.CR.79/2021, dt.02nd December, 2021

Table No.8-B - Parking Requirements							
Sr. No.	Occupancy	Size of tenement	Parking Spaces Required				Remarks
			Congested Area		Non Congested Area		
			Car	Scooter	Car	Scooter	
1	Residential i) Multi-Family residential.	For every tenement having carpet area of 150 sq.m. and above.	2	⁽¹⁾ 1	2	⁽¹⁾ 1	In addition 5% visitor parking
		For every tenement having carpet area equal to or above 80 sq.m. but less than 150 sq.m.	1	⁽¹⁾ 1	1	⁽¹⁾ 1	In addition 5% visitor parking
		For every two tenements with each tenement having carpet area equal to or above 40 sq.m. but less than 80 sq.m.	1	⁽¹⁾ 2	1	⁽¹⁾ 2	In addition 5% visitor parking
		For every two tenements with each tenement having carpet area less than 40 sq.m. but more than 30 sq.m.	1	1	1	2	In addition 5% visitor parking
		For every two tenements with each tenement having carpet area less than 30 sq.m.	0	⁽¹⁾ 2	0	⁽¹⁾ 2	In addition 5% visitor parking
	ii) Lodging establishment's tourist homes, hotels with lodging accommodation, Star Category Hotels.	For every five guest rooms	1	4	1	6	--
	iii) Restaurants	For every 50 sq.m. of carpet area of restaurant including kitchen, pantry hall, dining room etc.	0	8	1	8	--

⁽¹⁾ Inserted vide Notification u/s.37(1AA)(c) & 20(4) No.CR.236/18 (Part 4), dt.28th December, 2022

2	Institutional (Hospitals, Medical Institutions)	For every 10 beds.	2	12	3	10	For hospital (special building), space for 1 ambulance per hospital, shall be provided.
3	Assembly (theatres, cinema houses, concert halls, auditoria, assembly halls including those of college and hostels)	For every 40 seats.	4	16	4	16	--
	Multiplexes	For every 40 seats.	5	14	5	14	--
	Mangal karyalaya / Marriage Halls, Cultural Halls and Banquet Hall	For every 100 sq.m. carpet area / lawn area of fraction thereof.	1	5	1	5	--
	Community hall and club house in layout open space(applicable only for open spaces having area 4000 Sq.m. and more)	For every 200 sq.m. carpet area.	1	5	1	5	--
4	Educational Schools and the administrative as well as public service areas therein	For every 100 sq.m. carpet area of the administrative as well as public service area of the school.	1	4	2	4	--

		For every 3 class rooms	⁽¹⁾ 1) 5 two wheelers for every three class rooms. 2) The number of mini bus parking shall be at the rate of bus for every 40 numbers of students for 50% strength of students may be provided at the option of owner / developer. 3) Mini bus parking shall be permitted on playground except during school timing.				
	College & administrative as well as public service area therein.	For every 100 sq.m. carpet area of the administrative as well as public service area of the school.	1	12	2	17	--
		For every 3 class rooms.	1	24	2	24	--
	Coaching Classes / Tuition Classes / Hobby Classes.	For every 20 students.	1	9	1	9	--
5	Government or semi public or private business buildings.	For every 100 sq.m. carpet area or fraction thereof.	1	12	2	12	In addition 20% visitor parking
6	Mercantile (markets, departmental stores, shops and other Commercials users)	For every 100 sq.m. carpet area or fraction thereof.	1	6	2	6	--
	Whole sale shops not being used for retail trading.	For every 100 sq.m. carpet area or fraction thereof.	1	4	1	5	--

⁽¹⁾ Inserted vide Notification u/s.37(1AA)(c) & 20(4) No.CR.236/18 (Part 4), dt.28th December, 2022

	Hazardous building	For every 100 sq.m. carpet area.	0	4	1	3	--
	Office and I.T. building	For every 200 sq.m. carpet area or fraction thereof.	3	11	3	11	--
7	Industrial	For every 300 sq.m. carpet area or fraction thereof.	2	9	3	9	--
8	Storage (any type)	For every 300 sq.m. carpet area or fraction thereof.	0	4	1	3	--
⁽¹⁾ 9	Data centre	Per 400 sq.m.	1	0	1	0	--

Note -

- i) After calculating the parking for entire building, multiplying factor given in Table 8-C shall be applied. Fraction of parking spaces more than 0.5 shall be rounded to next digit.
- ii) In case of independent single family residential bungalows having plot area upto 300 sq. m., parking space need not be insisted separately. Further a garage shall be allowed in rear or side marginal distance at one corner having minimum dimensions of 2.5 m. x 5.0 m. and maximum dimensions 3.0 m. x 6.0 m. i.e. minimum 12.5 sq.m. and maximum 18.0 sq.m. built up area.
- iii) In the case of shops, row houses on plots upto 100 sq.m., parking space need not be insisted.
- iv) Mechanical / Hydraulic / Stack parking / multi-storeyed parking with or without car lift may be allowed to meet the requirement.
- v) Parking more than 50% over and above stipulated in table 8-B and 8-C, shall be liable for payment of charges at the rate of 10% of land rate mentioned in the ASR without taking into account guidelines therein. Such charges shall be recovered on the area covered under car / scooter parking over and above the requirement. However, for public semi-public, hotel, hospital, educational buildings, such charges shall not be leviable.
- ⁽¹⁾ Parking requirement as stipulated in Table 8-B and Table 8-C, may be permitted for full permissible potential of the plot even though Building permission is sought for and sanctioned for only part of the full potential. In such cases the difference between number of parking required for such part potential and full permissible potential shall be liable for payment of charges as above, at the time of final occupancy certificate for such sanctioned permission,

Or

If the building permission proposal for the balance potential is not submitted before such final occupancy certificate, then such excess parking shall deemed to be treated as public parking and shall be handed over for the same purpose to the Authority free of cost.

⁽¹⁾ Inserted / Substituted vide Notification u/s.37(1AA)(c) & 20(4) No.CR.97/2023/UD-13, dt.12th January, 2024

- vi) In case of plan for additional built-up area on existing building and where existing built-up is to be retained as per earlier sanction - off-street parking requirement (number of units) shall be calculated only for the newly proposed additional built-up area as per this regulation and existing parking area shall be retained as per approved plan. If the additional built-up area along with existing built-up area is proposed to be revised as per these regulations (UDCPR) then total parking requirement shall be calculated as per this regulation and existing parking units are to be deducted to arrive the new number of parking units required.
- ⁽¹⁾ vii) Multiplying factor as per regulation No.8.2.2, Table No.8-C shall not be applicable for Two Wheeler parking ⁽²⁾ for Sr.No.(i) - Multi Family residential of Sr.No.1 - Residential in Table No.8-B of Regulation No.8.2.1.

⁽¹⁾ Inserted vide Notification u/s.37(1AA)(c) & 20(4) No.CR.236/18 (Part 4), dt.28th December, 2022

⁽²⁾ Inserted vide Corrigendum No.CR.236/18 (Part 4), dt.12th January, 2023

8.2.2 Off street parking requirement for various Planning Authorities / Areas

Off street parking requirement for various Planning Authorities / Areas shall be worked out by applying multiplying factor given in Table No.8-C below. This multiplying factor shall be applied to the total quantum of parking spaces worked out as per Table No.8-B above.

Table No.8-C		
Sr. No.	Authority / Area	Multiplying Factor
1	Pune, Pimpri-Chinchwad and Thane Municipal Corporation area and PCNTDA area.	1.00
2	Nagpur, Nashik Municipal Corporation area.	0.9
3	Other Municipal Corporations in MMR area except Thane M.C., ⁽¹⁾ CIDCO as Planning Authority by Virtue of NTDA	0.8
4	Remaining Municipal Corporations not covered at Sr.No.1 to 3 and 5, Metropolitan Area Development Authority / Area Development Authority / SPA area.	0.7
5	'D' Class Municipal Corporation area except at Sr.No.3	0.6
6	'A' Class Municipal Council area.	0.6
7	'B' and 'C' Class Municipal Council area.	0.5
8	Nagar Panchayat, Non Municipal Town Development Plan area and areas in Regional Plan.	0.4

_*_*_*_*_*_

⁽¹⁾ Inserted vide Notification u/s.37(1AA)(c) No.CR.236/18 (Part 6), dt.12th October, 2022

CHAPTER - 9

REQUIREMENTS OF PART OF BUILDING

9.0 STANDARD REQUIREMENTS OF VARIOUS PARTS OF BUILDINGS

This part sets out the standard space requirements of various parts of building, light and ventilation, the building services, fire safety, etc. The following parts of a building, wherever present, shall conform to the requirements given herein:

9.1 PLINTH

- i) The plinth of building shall be so located with respect to the surrounding ground level that adequate drainage of the site is assured. The height of the plinth shall not be less than 30 cm. above the surrounding ground level. In areas subjected to flooding, the height of the plinth shall be at least 45 cm. above the high flood level.
- ii) Covered parking spaces and garages shall be raised at least 15 cm. above the surrounding ground level and shall be satisfactory drained.

9.2 HABITABLE ROOMS

9.2.1 Size and Dimension of Habitable Rooms

Size and dimension of habitable rooms, shall be as per requirement and convenience of the owner.

9.2.2 Height of Habitable Rooms

The minimum and maximum height of a habitable room shall be given in Table No.9-A hereunder :

Table No.9-A			
Sr. No.	Occupancy	Minimum Height (m.)	Maximum Height (m.)
(1)	(2)	(3)	(4)
1	Flat Roof -		
	a) Any habitable room	2.75	4.5
	a1) Habitable room in EWS / LIG Housing.	2.75	4.2
	b) Air-conditioned habitable room	2.4	4.5
	c) Assembly Halls, Residential Hotels of 3 star category and above, Institutional, Educational, Industrial, Hazardous or storage occupancies, Departmental Stores, Malls, IT Buildings, Office Buildings, Exhibition Centre, Convention Hall, Theatre, Film Studio, Entrance Halls and Lobbies to these buildings.	3.0 (2.40 m. in case of Air conditioned room)	6.00 or higher according to the requirement of occupancy.
	d) Shops	3.00	4.5
2	Pitched roof-		
	a) Any habitable room	2.75 (average with 2.0 m. at the lowest point)	4.5 (average with 3.2 m. at the lowest point)

	b) Habitable room in EWS / LIG Housing.	2.6 (average with 2.0 m. at the lowest point)	4.2 (average with 3.2 m. at the lowest point)

Provided that the minimum head-way under any beam shall be 2.4 m.

Provided further that height more than that specified above, if required for particular occupancy, shall not be counted towards calculation of FSI.

9.3 KITCHEN

9.3.1 Size of Kitchen

The size of kitchen or a cooking alcove serving as cooking space shall be as per requirement and convenience of the owner.

9.3.2 Height of Kitchen

The height of a kitchen measured from the surface of the floor, to the lowest point in the ceiling (bottom of slab) shall not be less than 2.75 m. except for the portion to accommodate floor trap of the upper floor.

9.4 BATH ROOMS, WATER CLOSETS, COMBINED BATH ROOM AND WATER CLOSET

9.4.1 Size of bath room and water closet

Minimum size shall be as under -

- i) Independent Bath room 1.00 m. x 1.20 m.
- ii) Independent Water closet 0.9 m. x 0.9 m.
- iii) Combined bath room and water closet 1.50 sq.m. with minimum width or 1.00 m.

9.4.2 Height of bath room and water closet

The height of a bathroom or water closet measured from the surface of the floor to the lowest point in the ceiling (bottom of slab) shall be not less than 2.1 m.

9.4.3 Other requirements of bath room and water closet

Every bathroom or water-closet shall –

- i) be so situated that it derives ventilation from ventilation shaft or external air;
- ii) have a window or ventilator, opening to a shaft or open space, of area not less than 0.3 sq.m. with side not less than 0.3 m.;
- iii) all the sewerage outlets shall be connected to the sewerage system. Where no such systems exist, a septic tank shall be provided within the plot conforming to the requirements of Regulation No.9.25.

9.5 LEDGE OR TAND / LOFT

9.5.1 Location and extent

Ledge or Tand may be provided at suitable places as per requirement. Lofts may be provided over kitchen, habitable rooms, bathrooms, water closets, and corridor within a tenement in residential buildings, over shops and in industrial building, as mentioned in below Table No.9-B subject to the following restrictions –

- i) The clear head room under the Loft shall not be less than 2.1 m.
- ii) Loft in commercial areas and industrial building shall be located 2.0 m. away from the entrance.
- iii) Loft shall not interfere with the ventilation of the room under any circumstances.
- iv) The maximum height of loft shall be 1.5 m.

Table No.9-B - Provision of Loft		
Sr. No.	Rooms over which Permitted	Maximum Coverage (Percentage to area or room below)
(1)	(2)	(3)
1	Kitchen / Habitable room	25
2	Bathroom, water closet, corridor	100
3	Shops with width up to 3.0 m.	33
4	Shops with width exceeding 3.0 m.	50
5	Industrial	33

9.5.2 Location and extent of Ledge for Air Conditioning unit

Ledge for Air Conditioning unit may be provided on the exterior of wall of the rooms of size not exceeding 0.5 m. x 1.0 m. at suitable location.

9.6 CUPBOARD

- 9.6.1** In residential buildings, cantilever projections of cupboards, floor to floor level, may be permitted except on ground floor. Such projections excluding window area, may project upto 0.60 m. in the setbacks for buildings. However, the window frame shall be placed on the inner side of the wall and such cupboard shall be allowed only on one wall of each room. Moreover, such projection shall be at least 6.0 m. from plot boundary in case of special buildings.
- 9.6.2** For height 24.0 m. and more no cupboard shall reduce the marginal open space to less than 6.0 m. on first floor and 4.5 m. on upper floor. In congested area cupboard may be permitted on upper floors projecting in front setbacks except over lanes having width 4.50 m. or less and in marginal distances subject to 1.0 m. clear marginal distance from the plot boundary to the external face of the cupboard.

9.7 MEZZANINE FLOOR

9.7.1 Size of Mezzanine Floor

The minimum size of the mezzanine floor shall be as per requirement and convenience of owner. The aggregate area of such mezzanine floor shall in no case exceed 50% of ⁽¹⁾ carpet area of that room, shops, etc. Where loft is provided in the room, the mezzanine floor shall not be allowed.

Note - Mezzanine floor area shall be counted towards FSI.

9.7.2 Height of Mezzanine Floor

The head room under mezzanine floor shall not be less than 2.1 m.

9.7.3 Other requirements of mezzanine floor

A mezzanine floor may be permitted in a room or within a space, provided -

- i) it conforms to the standards of living rooms as regards lighting and ventilation in case the mezzanine floor is used as habitable room.

(1) Substituted vide Corrigendum / Addendum No.C.R.121/21, dt.02nd December, 2021

- ii) it is so constructed as not to interfere, under any circumstances, with the ventilation of the space over & under it.
- iii) such mezzanine floor or any part thereof will not be used as a kitchen.
- iv) it is atleast 1.8 m. away from front wall of such rooms.
- v) access to the mezzanine floor is from within the respective room only.
- vi) in no case shall a mezzanine floor be closed so as to make it liable to be converted into unventilated compartments.

9.8 STORE ROOM

9.8.1 Size of Store Room

The area of a store room / rooms, if provided in a residential building, where light, ventilation and height are provided at standards lower than as required for living room, shall be as per requirements and convenience of the owner.

9.9 GARAGE

9.9.1 Size of private Garage

The size of a garage in individual residential building shall not be less than 2.5 m. x 5.0 m. and not more than 3.0 m. x 6.0 m. The garage, if located in the side open space, shall not be constructed within 3.0 m. from the main building, but at least 7.5 m. away from the any access road. The area of garage shall be including in FSI.

9.9.2 Height of private Garage

The minimum and maximum height of garage shall be 2.4 m. and 2.75 m. respectively.

9.9.3 Plinth of private Garage

The plinth of garage located at ground level shall not be less than 15 cm. above the surrounding ground level.

9.9.4 Set Back of private Garage

The garage shall be set-back behind the building line for a street or road on which the plot abuts and shall not be located affecting the access ways to the building.

When the site fronts on two streets, the location of a garage (in a corner plot) (if provided within the marginal distances) shall be on diagonally opposite the point of intersections.

9.10 ROOFS

9.10.1 The roof of a building shall be so constructed or framed as to permit effectual drainage of the rain water there from by means of sufficient rain water pipes of adequate size, wherever required, so arranged, jointed and fixed as to ensure that the rain water is carried away from the building without causing dampness in any part of the walls or foundations of the building or those of an adjacent buildings.

9.10.2 Top Terrace of a building shall not be sub-divided and it shall have only common access. However, intermediate terraces may be allowed to be attached with flat and shall not be counted in balcony area.

9.10.3 The Authority may require rain water pipes to be connected to a drain or sewer through a covered channel formed beneath the public foot path to connect the rain water pipe to the road gutter or in any other approved manner, if not used for rain water harvesting.

Rain water pipes shall be affixed to the outside of the walls of the buildings or in recesses or chases cut or formed in such walls or in such other manner as may be necessary.

9.11 BASEMENTS

- 9.11.1** Basement shall generally be constructed within the prescribed setbacks / margins with one or more level.

Following uses shall be permissible at free of FSI.

- i) Air-conditioning equipment's and other machines used for services and utilities of the building;
- ii) Parking spaces;
- iii) D.G. set room, meter room and electric substation (which will conform to required safety requirements), Effluent Treatment Plant, suction tank, pump room;
- ⁽¹⁾ iv) Storage (only for use of Data Centre)

Following uses shall be permissible and counted in FSI.

- a) Storage of household or other goods or ordinarily non-combustible material incidental to principle use;
- b) Strong rooms, bank lockers, safe deposit vaults, laundry room, Radio / laser therapy, post mortem room, mortuary, medical shop and cold storage for hospital building etc.
- c) Commercial use in first basement in case of shopping centre / shopping malls.
- d) Uses strictly ancillary to the Principal use.
- e) Nursing quarters as ancillary use to hospital in first basement, if it is 0.9 m. to 1.2 m. above ground level with proper ventilation.

Provided that,

- i) If the basement is proposed flushing to average surrounding ground level, then such basement can be extended in side and rear margins upto 1.5 m. from the plot boundary.
- ii) Multilevel basements may be permitted if the basement is used for parking.

- 9.11.2** The basement shall have the following requirements -

- a) Every basement shall be in every part at least 2.4 m. in height from the floor to the soffit of beam.
- b) Adequate ventilation shall be provided for the basement with a ventilation area not less than 2.5% of the area of the basement. Any deficiency may be met by providing adequate mechanical ventilation in the form of blowers, exhaust fans or air-conditioning systems, etc.;
- c) The minimum height of the ceiling of any basement shall be 0.9 m. and the maximum shall be 1.2 m. above the average surrounding ground level. However, it does not apply to the mechanically ventilated basements. In such cases, basement may also be allowed flushing to the average ground level;
- d) Adequate arrangements shall be made so as to ensure that surface drainage does not enter the basement;
- e) The walls and floors of the basements shall be water-tight and be so designed that the effect of the surrounding solid and moisture, if any, is taken into account in design and adequate damp proofing treatment is given. In case of special building, where, movement of fire fighting vehicle is proposed on the basement flushing to the ground level, the slab of the basement shall be designed to withstand the pressure of fire fighting vehicle.
- f) The access to the basement shall be separate from the main and alternate staircase providing access and exit from higher floors. Where the staircase is continuous, the same shall be enclosed type serving as a fire separation from the basement floor and higher floors. Open ramps shall be permitted subject to the provision of Regulation No.9.12.

⁽¹⁾ Inserted / Substituted vide Notification u/s.37(1AA)(c) & 20(4) No.CR.97/2023/UD-13, dt.12th January, 2024

9.12 RAMP

9.12.1 Non Vehicular Ramp

All the requirements of stairways in Regulation No.9.28.8 shall apply mutatis mutandis to non-vehicular ramp. In addition, the following requirement shall be complied with.

- a) Ramps with a slope of not steeper than 1 in 10 may be substituted for and shall comply with all the applicable requirements of required stairways as to enclosure, capacity and dimensions. In certain cases, steeper slopes may be permitted but in no case greater than 1 in 8 shall be permitted. Ramps shall be surfaced with approved non-slipping material. Provided that in the case of public offices, hospitals, assembly halls, etc. the slope of the ramp shall not be more than 1 : 12.
- b) The minimum width of the ramps in hospitals shall be 2.25 m.
- c) Handrails shall be provided on both sides of the ramp.
- d) Ramps shall lead directly to outside open space at ground level or courtyards or safe place.
- e) For building above 24.0 m. in height, access to ramps from any floor of the building shall be through smoke stop door.
- f) When there is a difference in level between connected areas for horizontal exits, ramps not more than 1 : 10 slope shall be provided; steps shall not be used.
- g) In case of non-special building, ramp may be permitted in side marginal distances. In case of special building, ramps may be permitted in side marginal distances, after leaving 6.0 m. marginal distance for movement of fire fighting vehicle.

9.12.2 Ramp to basements and upper storeys for vehicles

For parking spaces in a basement and upper floors, at least two ramps of minimum 3.0 m. width with slope not more than 1 : 8 shall be provided, preferably at the opposite ends. Instead of two ramps, one ramp of 6.0 m. width may be allowed. In addition to these, the owner may provide car lifts, if he so desires.

If the ramp is proposed to be used only for two wheeler, then at least two ramps of 2.0 m. width with slope not more than 1 : 8 shall be provided, preferably at the opposite ends. Instead of two ramps one ramp of 4.0 m. width may be allowed.

In case of plot admeasuring 1000 sq.m. or less, only one ramp of 3.0 m. may be provided for ⁽¹⁾ car / two wheeler parking or one ramp of 2.0 m. may be provided for two wheeler parking ⁽¹⁾ or the owner may provide minimum 2 Car lifts instead of Ramp.

In case of plot admeasuring up to 2000 sq.m., one ramp of minimum 6.0 m. width may be provided for car / two wheeler parking or the owner may provide minimum 2 Car lifts instead of Ramp.

⁽²⁾ Note - Sub Regulation No. 9.12.1(g) shall also be applicable in this regulation.

9.13 ^(#) PODIUM

Podium for parking of the vehicles and other uses mentioned herein, may be permitted with following requirements / conditions :

- i) Height of the podium shall be at least 2.4 m. from the floor to the soffit of beam.
- ii) Podium maybe allowed at a distance of 6.0 m. from front, side and rear of the plot boundary in case of special building, subject to provisions of Regulation No.6.2.3(c).

⁽¹⁾ Inserted / Substituted Vide Corrigendum / Addendum No.CR.79/2021, dt.02nd December, 2021

⁽²⁾ Inserted vide Corrigendum / Addendum No.CR.121/21, dt.02nd December, 2021

^(#) Clarification issued vide Order No.CR.236/18 (Part 2), dt.23rd December, 2021

- iii) Podium shall be designed to take load of fire engine, if required.
- iv) Recreational open space may be permitted on Podium subject to regulation No.3.4.1(iii). The structure mentioned in Regulation No.3.4.7 may be permitted over the podium on which recreational open space is provided, subject to 15% area of such recreational open space.
- v) Podium shall be permissible joining two or more buildings or wings of buildings, subject to availability of manoeuvring space for fire engine. In such case, the distance between two buildings / wings of the building shall be provided as otherwise required under these Regulations.
- vi) Part of the podium may be used for recreation or play area for schools.
- vii) Part of the podium may be used for club houses subject to regulation No.3.4.7(i).

9.14 BALCONY

Balcony or balconies of a minimum width of 1.0 m. and maximum of 2.0 m. may be permitted in residential and other buildings at any floor except ground floor, and such balcony projection shall be subject to the following conditions :-

- i) In non-congested area, no balcony shall reduce the marginal open space (including front) to less than 2.0 m. upto 24.0 m. building height. For height 24.0 m. and more no balcony shall reduce the marginal open space to less than 6.0 m. on first floor and 4.5 m. on upper floor. In congested area balcony may be permitted on upper floors projecting in front setbacks except over lanes having width 4.50 m. or less and in marginal distances subject to 1.0 m. clear marginal distance from the plot boundary to the external face of the balcony.
- ii) Balcony, though not cantilever, shall be allowed on ground floor, after leaving required setback / marginal distances.
- iii) The width of the balcony shall be measured perpendicular to the building up to the outermost edge of balcony.
- iv) The balcony may be allowed to be enclosed in the room, at the time of development permission, if desired by the owner / developer. In such case depth of the enclosed balcony shall not exceed $\frac{1}{3}$ rd of the depth of the room. (including the depth of balcony)
- v) Nothing shall be allowed beyond the outer edge of balcony.

9.15 SUPPORTED DOUBLE HEIGHT TERRACES

Supported double height terraces shall be permitted (open terraces with railing and minimum height equal to two floors) within the building line.

9.16 STILT

A stilt with one or more levels may be permitted underneath a building. The height of the stilt floor below the soffit of the beam shall not be less than 2.4 m. At least two sides of the stilt shall be open. In case of stack parking, clear height of 4.50 m. shall be maintained. The open stilt portion shall not be used for any purpose other than for vehicles parking or play area for children. However, habitable use may be allowed in part of the stilt which shall be counted in F.S.I. In case of stilt at ground floor plinth of stilt shall not be more than 15 cm. from surrounding ground level.

9.17 CHIMNEYS

Chimney, where provided, shall conform to the requirements of Indian Standard Code of Practice for Fire Safety of Building. Provided that the Chimney shall be built at least 0.9 m. above flat roof. In the case of sloping roofs, the chimney top shall not be less than, 0.6 m. above the ridge of the roof in which the chimney penetrates.

9.18 LETTER BOX

A letter box of appropriate dimensions shall be provided on the ground floor of residential and commercial buildings.

9.19 METER ROOM

Meter room shall be provided as per the requirement of M.S.E.D.C.L. or power supply company as per the number of tenements / units.

9.20 LIGHTING AND VENTILATION OF ROOM**9.20.1 Adequacy and manner of provision**

- i) The minimum aggregate area of opening of habitable rooms and kitchens excluding doors shall be not less than $1/10^{\text{th}}$ of the floor area of the room.
- ii) No portion of a room shall be assumed to be lighted, if it is more than 7.5 m. away from the opening assumed for light and ventilation, provided additional depth of any room beyond 7.5 m. may be permitted subject to provision of proportionate increase in the area of opening.
- iii) A staircase shall be deemed to be adequately lighted and ventilated, if it has one or more openings and area taken together admeasures not less than 1.0 sq.m. per landing on the external wall.
- iv) An opening with a minimum area of 1.0 Sq.m. in a kitchen, and 0.30 sq.m. with one dimension of 0.30 m. for any bathroom, water closet or store shall be treated as adequate.

9.20.2 Ventilation Shaft

For ventilating the spaces for water closets & bathrooms, if not opening on front, side, rear & interior open spaces, these shall open on the ventilation shaft, the size of which shall not be less than the values given in table below :-

Table No.9-C - Ventilation Shaft			
Sr. No.	Height of Buildings in m.	Cross-section of Ventilation shaft in Sq.m.	Minimum one dimension of the shaft in m.
(1)	(2)	(3)	(4)
1	Upto10	1.2	0.9
2	Upto12	2.4	1.2
3	Upto 18	4.0	1.5
4	Upto 24	5.4	1.8
5	Upto30	8.0	2.4
6	Above 30	9.0	3.0

Note :-

- a) For buildings above 30.0 m., mechanical ventilation system shall be installed besides the provisions of minimum ventilation shaft.
- b) For fully air-conditioned residential / other buildings, the ventilation shaft need not be insisted upon, provided the air-conditioning system works in an uninterrupted manner, also provided; there is an alternative source of power supply.

9.20.3 Artificial Lightning and Mechanical ventilation

Where lighting and ventilation requirements are not met through day-lighting and natural ventilation, they shall be ensured through artificial lighting and ventilation in accordance with the provisions of Part-8, Building Services - Section-1, Lighting and Ventilation, National Building Code of India.

9.21 OVERHEAD TANKS

Every overhead water storage tank shall be maintained in a perfectly mosquito-proof condition by providing a properly fitting hinged cover and every tank more than 1.5 m. in height shall be provided with a permanently fixed iron ladder.

9.22 PARAPET

Parapet walls and handrails provided on the edges of roof terraces, podium, balcony, verandah and recreational floor shall not be less than 1.0 m. and not more than 1.2 m. in height from the finished floor level. In case of occupancies like educational, health etc. such parapet may be permitted upto 2.00 m. height.

9.23 CABIN

Where cabins are provided, the size of cabins shall be 3.0 sq.m. with a minimum width of 1.0 m. The clear passages within the divided space of any floor shall not be less than 0.9 m. and the distance from the farthest space in a cabin to any exit shall not be more than 18.5 m.

9.24 WELLS

Wells intended for supply of water for human consumption or domestic purposes may be permitted at suitable place in a plot.

9.25 SEPTIC TANKS

Every building or group of buildings together shall be either connected to a Drainage system or be provided with sub-soil dispersion system in the form of septic tank of suitable size and technical specifications. Modern methods of disposals, as may be specified by Government / Government bodies such as NEERI etc. may also be permissible.

9.26 BOUNDARY / COMPOUND WALL

- i) The maximum height of the front compound wall shall be 1.5 m. above the central line of the front street. Compound wall up to 2.4 m. height may be permitted, if the top 0.9 m. is of open type construction. The maximum height of side and rear compound wall shall be 1.5 m. above the average ground level of the particular plot.
- ii) In case of a corner plot, the height of the boundary wall shall be restricted to 0.75 m. for a length equal to fanning of the road on the front and side of the intersection and the remaining height of 0.75 m., if required, in accordance with sub-regulation (i) above, may be of open type construction (railings).
- iii) The provision of sub-regulations (i) and (ii) above shall not be applicable to boundary walls of jails.
- iv) In the case of industrial buildings, electric sub-stations, transformer stations, institutional buildings like sanatoria, hospital, industrial building like workshops, factories and educational buildings like schools, colleges including the hostels and other user of public utility undertakings the height up to 2.4 m. may be permitted by the Authority.
- v) The gates in a compound wall shall not open on any public access / pathway / road / street and shall open entirely inside the property.

9.27 PROVISION OF LIFT

9.27.1 ^(#) Planning and Design

Atleast one lift shall be provided in every building more than 15 m. in height. In case of buildings more than 24 m. height, atleast two lifts shall be provided. However, in case of a proposal to add one additional floor to an existing building having a lift, it will not be necessary to raise the existing lift to the additional floor.

For building or floors of the building to be constructed for Retirement Home or Senior Citizen Housing, lift shall be provided irrespective of height of building.

The planning and design of lifts including their number, type and capacity depending on the occupancy of the building, the population of each floor based on the occupant load and the building height shall be in accordance with Section-5 - Installation of Lift & Escalators of Part VIII - Building Services of National Building Code of India.

All the floors shall be accessible for 24 hours by the lifts. The lifts provided in the buildings shall not be considered as a means of escape in case of emergency. Grounding switch at ground floor level to enable the fire service to ground the lift cars in an emergency shall also be provided.

The lift machine rooms shall be separate and no other machinery shall be installed therein.

9.27.2 Fire Lift

Fire lift shall be provided as mentioned in Regulation No.9.29.8.

9.28 EXIT REQUIREMENTS

9.28.1 The following General requirements shall apply to exits

- a) In every building or structure, exits shall comply with the minimum requirements of this part, except those not accessible for general public use.
- b) Every exit, exit access or exit discharge shall be continuously maintained free of all obstructions or impediments to full use in the case of fire or other emergency.
- c) Every building meant for human occupancy shall be provided with exits sufficient to permit safe escape of occupants, in case of fire or other emergency.
- d) No building shall be so altered as to reduce the number, width or protection of exits to less than that required.
- e) Exits shall be clearly visible and the route to reach the exits shall be clearly marked and signs posted to guide the occupants of the floor concerned.
- f) All exits shall provide continuous means of egress to the exterior of a building or to an exterior open space leading to a street and,
- g) Exits shall be so arranged that they may be reached without passing through another occupied unit.

9.28.2 Type of Exits

An exit may be a doorway, a corridor, a passage or a way to an internal staircase or external staircase, ramp or to a varandah and / or terraces which have eaves to the street or to roof of a building. An exit may also include a horizontal exit leading to an adjoining building at the same level. Lifts and escalators shall not be considered as exits.

^(#) Clarification issued vide Order No.CR.236/18 (Part 2), dt.23rd December, 2021

9.28.3 Number and Size of Exits

The requisite number and size of various exits shall be provided, based on number of occupants in each room and floor based on the occupant load, capacity of exits; travel distance and height of building as per provisions of Regulation No.9.28.4 to Regulation No.9.28.8.

9.28.4 Arrangement of Exits

Exits shall be so located that the travel distance on the floor shall not exceed as given below :-

Table No.9-D	
Type of Building	Travel Distance
Residential, Educational, institutional and Hazardous occupancies	22.5 m.
Assembly, business, mercantile, Industrial and Storage Occupancies.	30.0 m.

Whenever more than one exit is required for a floor of a building, exits shall be placed at remote from each other as possible. All the exits shall be accessible from the entire floor area at all floor levels.

⁽¹⁾ **Note** – For the buildings where sprinkler system has been provided in entire building for fire fighting, the travel distance may be increased by 50% of the value specified in above table.

9.28.5 Occupant Load

For determining the exits required, the number of persons within any floor area or the occupant load shall be based on the actual number of occupants, but in no case less than that specified in Table No.9-E below :-

Table No.9-E		
Sr. No.	Group of Occupancy	Occupant Load Floor Area in sq.m. per person
(1)	(2)	(3)
1	Residential	12.5
2	Educational	4.0
3	Institutional	15 (See Note i)
4	Assembly	
	a) With fixed or loose seat and dance floors	0.6 (See Note ii)
	b) Without seating facilities including dining rooms	1.5 (See Note ii)
5)	Mercantile	
	a) Street floor & Sales basement	3
	b) Upper sale floors	6
6)	Business and industrial	10
7)	Storage	30
8)	Hazardous	10

⁽¹⁾ Inserted Vide Corrigendum / Addendum No.CR.79/2021, dt.02nd December, 2021

Note :

- i) Occupant load in dormitory portions of homes for the aged, orphanages, insane, asylums etc. where sleeping accommodation provided, shall be calculated at not less than 7.5 Sq.m. gross floor area per person.
- ii) The gross floor area shall include, in addition to the main assembly rooms or space, any occupied connecting room or space in the same storey or in the storeys above or below where entrance is common to such rooms and spaces and they are available for use by the occupants of the assembly place. No deductions shall be made in the area for corridors, closets or other subdivisions, that area shall include all space serving the particular assembly occupancy.

9.28.6 Capacity of Exits

- 1) The unit of exit width use to measure the capacity of any exit should be 50 cm. A clear width of 25 cm. should be counted as additional half unit. Clear width less than 25 cm. should not be computed for exit width.
- 2) Occupants per unit exit width shall be in accordance with Table No.9-F


Table No.9-F				
Sr. No.	Group of Occupancy	Number of Occupants		
		Stairways	Ramps	Doors
(1)	(2)	(3)	(4)	(5)
1	Residential	25	50	75
2	Educational	25	50	75
3	Institutional	25	50	75
4	Assembly	40	50	60
5	Business	50	60	75
6	Mercantile	50	60	75
7	Industrial	50	60	75
8	Storage	50	60	75
9	Hazardous	25	30	40

9.28.7 Provision for Staircase

All buildings having height more than ground floor shall have provision of one staircase. The special buildings specified in Regulations No.1.3(93)(xiv) shall have two staircases out of which one shall be fire escape staircase.

They shall be of enclosed type. At least one of them shall be on external walls of buildings and shall open directly to the exterior, interior open space or to an open place of safety. Further, the provision or otherwise of alternative staircases shall be subject to the requirements of travel distance being complied with.

A staircase shall not be provided around the lift shaft unless provided with fire stop door of 1 hour rating at every floor level and no other openings in the inside wall as illustrated below.



9.28.8 Width of staircase

The minimum width of staircases / corridors for various buildings shall be as below.

Table No.9-G - Minimum width of staircase		
S. No	Use of Building	Minimum width of Stair Case (in m.)
1	Residential Buildings	
	a) Individual Housing upto G + 2 storeys	0.75
	b) Multi-storied Residential Building upto 15 m. height	1.00
	c) Multi-storied Residential Building above 15 m. & upto 24 m. height	1.20
(#)	d) Multi-storied Residential Building above 24 m.height	1.50
2	Residential hotel buildings	1.50
3	Assembly Building likes auditorium, theatres, cinemas, multiplex, mangal karyalaya, marriage halls, etc.	2.00
4	Institutional & Educational Buildings.	2.00
5	All other buildings excluding Sr.No. (1) to (4) above	1.50

⁽¹⁾ Note - Internal staircase for duplex tenements shall be of minimum width 0.75 m. and for mezzanine floor shall be of minimum width 0.90 m.

9.29 OTHER REQUIREMENTS OF INDIVIDUAL EXIT AT EACH FLOOR

The detailed requirements in respect of exits shall be as provided in Regulations No.9.29.1 to 9.29.8 given below.

9.29.1 Doorways

- i) Every exit doorway shall open into an enclosed stairway or a horizontal exit, or a corridor or passageway providing continuous and protected means of egress:
- ii) No exit doorway shall be less than 90 cm. in width except assembly buildings where door width shall be not less than 200 cm. Doorway shall be not less than 200 cm. in height. Doorways for the bathrooms, water-closets or stores shall be not less than 75 cm. wide.
- iii) Exit doorways shall open outwards, that is away from the room but shall not obstruct the travel along any exit. No door, when opened shall reduce the required width of stairways or landing to less than 90 cm. Overheads or sliding doors shall not be installed.
- iv) Exit door shall not open immediately upon a flight of stair. A landing equal to at least the width of the door shall be provided in the stairway at each doorway. Level of landing shall be the same as that of the floor which it serves.
- v) Exit doorway shall be openable from the side which they serve without the use of a key.
- vi) Mirrors shall not be placed in exit ways or exit doors to avoid confusion regarding the direction of exit.

9.29.2 Revolving doors

Revolving doors shall not be used as required exits except in residential business and mercantile occupancies but they shall not constitute more than half the total required door width.

^(#) Clarification issued vide Order No.CR.236/18 (Part 2), dt.23rd December, 2021

⁽¹⁾ Inserted vide Corrigendum / Addendum No.CR.121/21, dt.02nd December, 2021

9.29.3 Stairways

- i) Interior staircase shall be constructed of non-combustible materials throughout.
- ii) Interior staircase shall be constructed as a self-contained unit with at least one side to the extent of required opening adjacent to an external wall and shall be completely enclosed.
- iii) Hollow combustible construction shall not be permitted.
- iv) The minimum width of tread without nosing shall be 25 cm. for an internal staircase for residential buildings. In the case of other buildings, the minimum tread shall be 30 cm. The treads shall be constructed and maintained in a manner to prevent slipping.
- v) The maximum height of riser shall be 19 cm. in the case of residential buildings and 15 cm. in the case of other buildings. They shall be limited to 15 per flight.
- vi) Handrails shall be provided with a minimum height of 100 cm. from the centre of the tread to the top of the handrails. Balusters / railing shall be provided such that the width of staircase does not reduce.
- vii) Floor indicator - The number of each floor shall be conspicuously painted in figures at least 15 cm. large on the wall facing the flights of a stairway or at such suitable place as is distinctly visible from the flights.
- viii) The minimum headroom in a passage under the landing of a staircase shall be 2.2 m.
- ix) ⁽¹⁾ For special building, access to main staircase shall be gained through at least half an hour fire resisting automatic closing doors placed in the enclosing wall of the staircase. It shall be a swing type door opening in the direction of the escape.
- x) No living space, store or other space including fire risk shall open directly into the staircase.
- xi) External exit door of staircase enclosure at ground level shall open directly to the open spaces or should be reached without passing through any door other than a door provided to form a draught lobby.
- xii) In the case of assembly, institutional or residential occupancies or hotels or industrial and hazardous occupancies, the exit sign with arrow indicating the way to the escapes route shall be provided at a height of 0.5 m. from the floor level on the wall and shall be illuminated by electric light connected to corridor circuits. All exit way marking signs should be flushed with the wall and so designed that no mechanical damage shall occur to them due to moving of furniture or other heavy equipment. Further all landings of floor shall have floor indicating boards prominently indicating the number of floor. The floor indication board shall be placed on the wall immediately facing the flight of stairs and nearest to the landing. It shall be of the size not less than 0.5 m. x 0.5 m.
- xiii) In case of a single staircase, it shall terminate at the ground floor level and the access to the basement shall be by a separate staircase. Whenever the building is served by more than one staircase one of the staircases may lead to basement level provided the same is separated at ground level by either a ventilated lobby or a cut-off screen wall without opening, having a fire resistance of not less than 2 hours with discharge point at two different ends or through enclosures. It shall also be cut-off from the basement areas at various basement levels by a protected and ventilated lobby or lobbies.

⁽¹⁾ Substituted vide Corrigendum / Addendum No.CR.79/2021, dt.02nd December, 2021

9.29.4 Fire escape or external stairs

A fire escape or external stair shall be provided as provided in Regulation No.9.28.7. External stairs, when provided, shall comply the following :

- i) External stairs shall always be kept in sound operable conditions.
- ii) All external stairs shall be directly connected to the ground.
- iii) Entrance to the external stairs shall be separate and remote from the internal staircase.
- iv) Care shall be taken to ensure that no wall opening or window opens on to or close to an external stairs.
- v) The route to the external stairs shall be free of obstructions at all times.
- vi) The external stairs shall be constructed of non-combustible materials, and any doorway leading to it shall have the required fire resistance.
- vii) No external staircase, used as a fire escape, shall be inclined at an angle greater than 45 degree from the horizontal.
- viii) External stairs shall have straight flight not less than 1250 mm. wide with 250 mm. treads and risers not more than 190 mm. The number of risers shall be limited to 15 per flight.
- ix) Handrails shall be of a height not less than 1000 mm. and not exceeding 1200 mm. There shall be provisions of balusters with maximum gap of 150 mm.
- x) The use of spiral staircase shall be limited to low occupant load and to a building not exceeding 9 m. in height. A spiral stair case shall be not less than 1500 mm. in diameter and shall be designed to give adequate headroom.
- xi) Unprotected steel frame staircase will not be accepted as means of escape. However, steel staircase in an enclosed fire rated compartment of 2 h will be accepted as means of escape.
- xii) Fire escape staircase shall be connected to other staircases through common passage at every floor.
- ⁽¹⁾ xiii) It shall not be permitted to provide fire escape chutes in alternate to fire escape or external stairs. However the applicant may provide fire escape chute in addition to fire escape / external stairs as mandatory under this Regulation.

9.29.5 Corridors and passageways

- i) The minimum width of a corridor shall not be less than 75 cm. in the case of 2 storeys row housing residential buildings and 100 cm. in the case of other buildings and actual width shall be calculated based on the provision of Regulations No.9.28.3 to 9.28.8 (both inclusive)
- ii) Where there is more than one staircase serving a building, there shall be at least one smoke-stop door in the space between the staircases.
- iii) Exit corridors & passageways shall be of width not less than the aggregate required width of exit doorways leading from them in the direction of travel of the exterior / stairways.
- iv) Where stairways discharge through corridors & passage ways the height of the corridors & passage ways shall not be less than 2.4 m.
- v) All means of exit including staircases, lifts, lobbies & corridors shall be adequately ventilated.

⁽¹⁾ Inserted vide Notification u/s.37(1AA)(c) No.CR.236/18 (Part 6), dt.12th October, 2022

9.29.6 Refuge Area

For buildings more than 24 m. in height, refuge area of 15 sq.m. or an area equivalent to 0.3 sq.m. per person to accommodate the occupants of two consecutive floors, whichever is higher, shall be provided as under :

The refuge area shall be provided on the periphery of the floor or preferably on a cantilever projection and open to air at least on one side protected with suitable railings.

- a) **For floors above 24.0 m. and upto 39.0 m. height** - One refuge area on the floor immediately above 24.0 m.
- b) **For floors above 39.0 m height** - One refuge area on the floor immediately above 39.0 m. and so on after every 15.0 m.

Refuge area provided in excess of the requirements shall be counted towards FSI. However, area remained in excess because of planning constraints, shall not be counted in FSI, provided, such excess area does not exceed 100% of the required refuge area.

9.29.7 Lifts and Escalators

- i) Lifts :- Provision of lift shall be made as mentioned in Regulation No.9.27.
- ii) Escalators :- Escalators may be permitted in addition to required lifts. Such escalators may also be permitted in atrium area of the buildings.

9.29.8 Fire lift

Where applicable, fire lifts shall be provided with a minimum capacity for 8 passengers and fully automated with emergency switch on ground level. In general, buildings 15.0 m. in height or above shall be provided with fire lifts. In case of fire, only fireman shall operate the fire lift. In normal course, it may be used by other persons. Each fire lift shall be equipped with suitable inter-communication equipment for communicating with the control room on the ground floor of the building. The number and location of fire lifts in a building shall be decided after taking into consideration various factors like building population, floor area, compartmentation, etc.

9.29.9 Fire Escape Chutes / controlled Lowering Device for evacuation

- i) a) High rise building having height more than 70 m. shall necessarily be provided with fire escape chute shaft/s for every wing adjacent to staircase.
- b) Walls of the shaft shall have 4 hours' fire resistance.
- c) One side of the shaft shall be at external face of the building with proper ventilation.
- d) The dimension of the shaft shall not be less than 2.5 m. x 1.5 m.
- e) The access to the fire escape chute's shaft shall be made at every floor level from lobby area or from staircase mid-landing with self-closing door having fire resistance of at least one hour.
- f) The fire chute shall be of staggered type with landing of each section at the vertical height of not more than 21.0 m.

Alternatively,

- ii) High rise building having height more than 70.0 m., shall be provided with fire tower at landing / mid-landing level with smoke check lobby with fireman lift being integral part of the fire escape staircase or fire evacuation lift (Hydro pneumatic / electrically operated) on the external face of the building having opening within the fire escape staircase at landing / mid-landing level with smoke check lobby as approved by Chief Fire Officer shall be provided.

Note - Both the smoke check lobby with evacuation lift shall have positive level difference of minimum 75 mm. with respect to staircase landing or mid-landing level to avoid ingress of water in fireman lift shaft.

9.29.10 Refuge chute / Garbage Chute -

In residential buildings, Refuge chute / garbage chute may be provided with opening on each floor or on mid-landing. Design and specifications of Refuge chute shall be in accordance with provisions of IS 6924.

9.30 ARCHITECTURAL PROJECTIONS

Architectural Projections may be allowed to the following extent.

Horizontal	Vertical (above building)
H/20, subject to min 0.3 m. and max 3.0 m. exclusive of side and rear marginal distance of 6.0 m. required for movement for fire fighting vehicle in case of special buildings.	H / 20, subject to max. 6.0 m.

Where H = Height of building from ground level.

The owner shall submit the undertaking to the authority that, such architectural projection shall not be converted to any habitable or other purpose.

9.31 ADDITIONAL REQUIREMENTS IN CASE OF HOUSING SCHEMES

Following amenities shall be provided in any housing scheme and shall be counted in FSI.

- i) Fitness Centre, Crèche, society office cum letter box room, admeasuring area of about 20 sq.m. in scheme having minimum 100 flats and thereafter additional 20 sq.m. area for every 300 flats.
- ii) Sanitary block for servants having maximum area of 3.0 sq.m. in schemes having minimum 100 flats and thereafter additional 3.0 sq.m. area for every 200 flats.
- iii) Drivers room of size 12.0 sq.m. with attached toilet in schemes having minimum 100 flats and thereafter additional 10.0 sq.m. area for every 300 flats.

In case of scheme having more than 1000 flats, the above amenities shall be reasonably provided keeping in view the above requirements.

- iv) Every Residential building having more than 6 flats / tenements shall have entrance lobby of minimum 9.0 sq.m. at ground floor. Minimum dimension of such lobby shall not be less than 2.50 m.
- v) The requirements at (i) to (iii) above shall firstly be provided for the building having 30 ⁽¹⁾ to 100 tenements and thereafter the quantum mentioned in the said provisions shall be provided.

9.32 FIRE PROTECTION REQUIREMENT

All special buildings shall be planned, designed and constructed to ensure fire safety and this shall be done in accordance with the regulations of Maharashtra Fire Prevention and Life Safety Measures Act, 2006. For the provisions not included in these regulations and the said Act, provisions mentioned in Part IV of Fire Protection of National Building Code India, amended from time to time shall be referred and prevail.

⁽¹⁾ Inserted vide Corrigendum / Addendum No.CR.121/21, dt.02nd December, 2021

9.33 SERVICE FLOOR

A service floor of height not exceeding 1.8 m. may be provided in a building exclusively for provision / diversion of services. Provided further that a service floor with height exceeding 1.8 m. may be allowed in a building of medical use or in building having height more than 70.0 m. with the special permission of Authority with reasons recorded in writing.

_*_*_*_*_*_

CHAPTER - 10

CITY SPECIFIC REGULATIONS

10.0 GENERAL

Notwithstanding anything contained in these regulations, following city / authority specific regulations shall be applicable to respective Planning Authorities / Areas.

10.1 PUNE CITY MUNICIPAL CORPORATION

10.1.1 Height of Building

For the building having height more than 36 m., the minimum road width shall be 12 m. and for building having height equal to or more than 50 m., the minimum road width shall be 15 m.

10.1.2 The height restriction in Koregaon Park Area shall be as per special regulations applicable in Koregaon Park Area as below -

a) Koregaon Park Area is bounded as below :-

- i) The Koregaon Park North Road on the north;
- ii) The Ghorpadi village boundary on the east;
- iii) The Southern Railway line on the south; and
- iv) The Circuit House - Fitzgerald Bridge Road on the west.

b) Special Building Rules framed by the Collector of Pune for this area shall be applicable which are as given below -

- i) The minimum area of a building plot shall be as mentioned in the layout. No building plot as shown in the layout shall be sub-divided.

No building shall be allowed to be erected in any plot unless the said plot has suitable access by an existing metalled road or by projected road which shall be previously constructed. (i.e. metalled in conformity with the layout sanctioned by the Collector.)

- ii) Only one main building together with such outhouses as are reasonably required for the bonafide use and enjoyment by its occupants and their domestic servants shall be permitted to be erected in any building plot. Provided that this restriction shall not prevent the erection of two or more building on the same plot, if the plot admeasures at least twice or thrice as the case may be (according to the number of buildings) the minimum size required. Provided also that the same open space shall be required around each main building as if each of these were in a separate building plot.
- iii) Every building to be built shall face the road and where the plot has frontage on more than one road the building shall face the more important road.
- iv) Every building shall be set back at least 20 feet from the boundary of any road, 40 feet or more in width and 15 feet from the other roads as shown in the layout.
- v) No building shall be constructed within 10 feet of the side boundaries of the plot.
- vi) The distance between the main building and the rear boundary of the plot shall be; not less than 20 feet. Provided that, subsidiary buildings such as outhouse, a garage, stable, privy and the like may be permitted at the rear of the main building subject to the condition that such building shall be at a distance of not less than 10 feet from either any building in the compound or boundary of the plot.

- vii) The open space to be kept around every building shall be open to sky and free from any erection except projection of roof, chajja or weather sheds, steps or hounds or fountains with parapet walls not more than 4 feet high. Provided that balcony or gallery may be allowed to project over such open space if the distance between the outer edge of such a projection and the boundary of the plot is not less than 10 feet.
- viii) Not more than one-third of the total area of any building plot shall be built upon. In calculating the area covered by buildings the plinth area of the; buildings and other structures excepting compound walls, steps, open ottas and open hounds or wells with parapet walls not more than 4 feet high or Chajja and weather sheds shall be taken into account. Area covered by a staircase and projections of any kind shall be considered as built over. Provided a balcony or gallery which -
 - a. is open on three sides;
 - b. has no structure underneath on ground floor;
 - c. projects not more than 4 feet from the walls; and
 - d. length of which measured in a straight line does not exceed $\frac{2}{3}$ rd the length of the wall to which it is attached; shall not be counted in calculating the built over area.
- ix) No building shall contain more than two storeys including the ground floor.
- x) If flats are constructed there shall be not more than two self-contained flats on each floor, each flat being occupied by one family only.
- xi) The minimum standard of accommodation to be provided exclusively for one family shall consist of one living room and one bed room together admeasuring not less than 250 sq.ft. one kitchen, one verandah not less than 6 feet in width in front and rear, a bathroom and a water-closet or latrine.
- xii) In no circumstances shall one roomed tenements be allowed to be constructed or used as residence. No chawls or temporary sheds shall be allowed to be constructed.
- xiii) Every building shall have a plinth of at least 2 feet above the general level of the ground.
- xiv) No building shall exceed 100 feet in length in any direction.
- xv) All subsidiary buildings such as an outhouse providing auxiliary accommodation such as a garage, servant's quarter, stable, storeroom, privy etc. appurtenant to the main building but detached thereon shall be ground floor structures only and shall be constructed at the rear of the plot at a distance of not less than 10 feet from one another or from the main building or from the boundary of the plot.
- xvi) Owner of the adjoining plots may be permitted with their mutual consent to group the subsidiary ground floor buildings, such as outhouses, stables, privies etc. along the common boundary in the rear of their plots provided that such building shall be at a distance of not less than 10 feet from any other building in the compound.
- xvii) The minimum floor area of any room intended for human habitation shall be not less than 120 sq.ft.
- xviii) No sides of a room for residential purposes shall be less than 10 feet long at least one side of every such room shall be an external wall abutting on the surrounding open space through its length or on an interior open yard (chowk) not less than 300 sq.ft. in area and 15 feet in any direction or on an open verandah.
- xix) The height of every room inside the building shall be not less than 10 feet from the floor to ceiling and in the case of a sloping roof the height of the lowest point thereof shall be not less than 7 feet and 6 inches from the floor.

- xx) Every room shall be provided with windows or other apertures other than doors opening out into the internal air for the admission of light and air and the aggregate area of such openings shall not be less than $1/7^{\text{th}}$ of the floor area of the room in which they are provided.
- xxi) Privies shall be at the rear of the main building and not less than 10 feet from it. They shall be innocuous to the neighbors. They shall not be within 30 feet of a well and shall be screened from public view.
- xxii) No cesspools shall be allowed to be constructed unless there exists an agency for clearing them regularly and properly.
- xxiii) No cesspool shall be used or made within 100 feet of any well.
- xxiv) No Khalkuwa Khalketi shall be used for reception of night soil.
- xxv) No cattle shall be kept in any part of the residential buildings. No stable or cattle shed shall be constructed within 10 feet of a residential building.
- xxvi) Shops may be allowed on the ground floor of the building in the plots reserved for shops only. The upper floor of the building may be used for residence. Provided all regulations applicable to residential building are adopted.
- xxvii) The Collector may within his discretion sanction or license the erection of any building other than a dwelling house if he is satisfied after necessary inquiry in the locality that the erection and user of such building will not adversely affect the amenities of the adjoining lands or buildings.
- xxviii) All buildings shall be of pucca construction and no easily combustible materials shall be used in their construction.
- xxix) No boundary or compound wall or fence shall be erected on the boundary not to any street of a greater height than 4 feet measured from the center of the road in front.
- xxx) No addition to or alterations in a building shall be carried out without the previous written permission of the Collector.
- xxxi) In the case of land or building situate within the limits of a Municipal Corporation or any other Local Authority, the rules and bylaws of the Municipal Corporation or Local Authority in that behalf shall apply in addition to regulations prescribed above.
- xxxii) The permission shall be liable to be revoked on breach of any of the conditions.
- xxxiii) All the roads within lay-out will be constructed and got ready within six months from the date of sanctioning the layout.
- xxxiv) Central arrangements for the delivery of water to the individual plot holder will be made and got ready within six months from the date of sanctioning the layout.
- xxxv) No building shall be used for other than the residential purposes.

Note - This regulation stand modify if modified by the Government / Collector.

10.1.3 Notwithstanding anything contained in these regulations, height of building shall not be more than 21.0 m. in following area. This height may be relaxed by Government in special cases.

- a) **Parvati** - Area bounded by Singhagad Road on the north, Singhagad Road on the west, Southern boundary of P.L. Deshpande Udyan on the south, and Road from over bridge upto Laxminagar and western boundary of Tulsibagwale Colony in S.No.89, 90 etc. of Parvati on the east.

b) Chatushrungi - S.No.105, 106 pt., 107 pt. etc. of village Bhamburda.

Area bounded by Ganeshkhind Road on the North, Senapati Bapat Road on the east, S.No.106 - South boundary on the south, Western boundary of S.No.107,105,106 - on the west.

10.1.4 No piece of land shall be used as site for the construction of building,

- (a) If the land is within a prohibited distance (currently of seventy five meters) from the crest of the outer parapet of the Armament Research and Development Establishment (ARDE), Range Pashan, Pune;
- (b) If the land is within a prohibited distance of approximately 457.2 m. (500 yards) from the crest of the outer parapet of the High Energy Materials Research Laboratory (HEMRL), Sutarwadi, Pune as shown on Development Plan;

10.2 THANE MUNICIPAL CORPORATION AREA**^(S) 10.2.1 Development along Ram Maruti Road and Gokhale Road**

Front set-backs for development on above roads shall be as below :-

- i) In the case of plots fronting on Ram Maruti Road, only ground floor of the structure shall be set back by 3.05 m. from the road line and rest of the floors shall be set back at a distance of 4.5 m. ⁽¹⁾ The front terrace so formed shall be allowed to be accessible.
- ii) In case of any plot fronting on Gokhale Road, from the portion between Ashok Talkies and its junction with M.G. Road, the ground floor of the building shall be set back by 2.3 m. from the road line and the upper floors shall be set back at a distance of 4.5 m. subject to condition that the owner of the plot shall pave the front open space. ⁽¹⁾ The front terrace so formed shall be allowed to be accessible.

10.2.2 Setbacks from Eastern Express Highway and Roads more than 52.5 m. in width

No construction of building shall be undertaken within 7.5 m. from the boundary of the Eastern Express Highway and other roads having prescribed width more than 52.5 m.

10.2.3 a) Development of Multi Storey Public Parking Lot (PPL) near Metro Stations

For development of Multi-storied PPL on any plot abutting a road of minimum width of 18.0 m., additional FSI (hereinafter referred to as "Incentive FSI") as specified below on built up parking area, created and handed over to the Thane Municipal Corporation (TMC) free of cost with amenities required for parking area as prescribed by the Commissioner such PPL shall be allowed, on the land belonging to a private owner / Lease hold plots of Govt. and TMC with prior consent, which is not reserved for any public purpose, subject to the conditions contained herein below :

- I. The minimum area of plot shall be 1000 sq.m. in sector - 1, 2, 3 and 2000 sq.m. in remaining sectors. The minimum number of Motor Vehicle public parking spaces provided shall not be less than 50. The location of parking spaces can be in 2 level basement, ground floor or upper 2 floors maximum, with access through ramp / lift or combination of both subject to clearance from CFO with special emphasis on fire hazard.
- II. A Committee under the Chairmanship of Municipal Commissioner, TMC shall earmark / select the plots for public parking, on the basis of their suitability. The Committee shall comprise the following or their representatives (i) Metropolitan Commissioner, MMRDA, (ii) Dy.Commissioner of Police (Traffic), (iii) Joint Director of Town Planning, Konkan Division, (iv) Assistant Director of Town Planning, TMC (Member Secretary).

⁽¹⁾ Inserted vide Notification u/s.37(2) No.CR.236/18 (Part 5), dt.16th December, 2022 & (S) Directives u/s.154, dt.16th December, 2022

- III. The incentive FSI given on this account will be over and above the base FSI permissible under any other provisions of UDCPR. This incentive FSI shall be allowed to be used on the same plot in conformity with UDCPR / D.P., within the overall cap / limit of total maximum permissible FSI as given at (vii) below.
- IV. The proposed development shall be subject to any other conditions prescribed by the Municipal Commissioner.
- V. Concerned land owner / developer / society / company shall not be allowed to operate the public parking lot.
- VI. Area covered under parking shall not be counted towards FSI consumption.
- VII. The incentive FSI permissible under this Regulation against BUA of the PPL shall be 50% of the BUA of the PPL, such that the total permissible FSI including the incentive FSI under this Regulation does not exceed the limit as per Regulation 6.3.
- VIII. The maximum cap on BUA per parking shall be 50 sq.m. for LMVs, 65 sq.m. for LCVs and 120 sq.m. for HMTVs / Buses. Incentive FSI shall be calculated as per BUA of the PPL, based on these norms or the actual BUA of the PPL, whichever is less.
- IX. The developer of the PPL shall pay 'premium', worked out as per the following formula :-

$$\text{Premium} = 60\% \text{ of } [\text{Value of the additional BUA corresponding to the incentive FSI admissible under this Regulation, as per A.S.R.} - (\text{Cost of construction of PPL} + \text{cost of any extra amenities / facilities provided} + \text{cost of construction of BUA corresponding to the incentive F.S.I. admissible under this Regulation})]$$

For the purpose of calculating premium as above, the cost of construction of PPL including amenities / facilities and the cost of construction of BUA corresponding to the Incentive FSI admissible under this Regulation shall be 75% and 125% respectively of the rate of RCC construction as per ASR.
- X. The Premium shall be paid before the issuance of building permission for the incentive FSI admissible under this Regulation.

Upon Payment of 100% premium as aforesaid, building permission shall be issued in respect of 50% of incentive FSI. In no case, Incentive FSI be released without handing over of the PPL, complete in all respects, to TMC.

The year in which premium is paid before the issuance of building permission for the PPL shall be taken as the year for determination of construction cost as well as ASR for calculation of the premium. Out of the total premium payable, 50% shall be paid to the GoM and the remaining 50% to TMC.

Provision of this Regulation may also be applicable to lease hold plots of Govt. and TMC with prior approval from Government / Municipal Corporation.
- XI. The land owner / developer / Society / company shall hand over PPL with separate entrance and exit for the dedicated use of TMC by way of registered conveyance deed. Such PPL will not be part of proposed society / apartment / owners association.
- XII. The PPL shall not be permissible in combination with other regulations.
- XIII. Public Parking shall be developed in independent building as far as possible, but it may be permissible in composite buildings subject to compliance of these regulations.
- XIV. The Commissioner may hand over such PPL to any agency to transparent bidding procedures for its operations and maintenance upon such terms and conditions as deem

fit and proper. However in any condition such PPL shall not be allotted to concerned land owners / housing society / association of apartment owners of occupiers in the plot of PPL.

- XV. No public parking lots shall generally be more than 500 vehicles. However in exceptional cases Commissioner may permit PPL for 1000 vehicles for the reasons to be recorded in writing.
- XVI. PPL connectivity to nearest station of Local / Mono / Metro / BRTS etc. may also be insisted if propose PPL is within 250 m. by skywalk and underground connectivity within 100 m. These areas shall also be counted for giving incentive FSI and shall not be included for calculating limits of vehicles.
- XVII. For every sectors Commissioner shall endeavour to evaluate total need of PPL and shall cause it to be declared in local newspaper within three months of promulgation of these regulation for every 5 years. Total PPL sanctioned in any sector shall not increase beyond that for next 5 years. PPL shall be allowed only after studying traffic impact analysis of area with the periphery of 250 m. of PPL.

10.2.4 Development around Hazardous Industries (Chemical Zone Areas)

a) Green Belt -

- i) There shall be green belt of 100 m. around the boundary of the Hazardous Chemical Industries as shown on plan attached with the report of authority.
- ii) The creation of the green belt, its development and maintenance as per report of authority will be the responsibility of Municipal Corporation.
- iii) The cost of acquisition of land for the green belt, around the Hazardous Chemical Industries will be borne by the Industry / Industry Association. The private land owner will be given Transfer of Development Rights based on FSI for the present land usage. The cost of acquisition to be borne by industry will be exclusive of the value of TDR.
- iv) The existing authorised structures should be tolerated. However, only repairs to such existing structures should be allowed in future and no reconstruction or new construction should be allowed in the Green Belt.
- v) Unauthorised structures should be removed or relocated by the Thane Municipal Corporation as per the existing Public Policy.

b) Creation of Low Density Zone -

- i) Beyond the Green Belt, another belt of 150 m. should be created as "Low Density Zone" as shown on plan, attached with the report of the Authority.
- ii) The FSI in the Low Density Zone shall be 0.5 and only Ground plus two storey structures should be allowed.
- iii) The existing buildings if already authorised with the higher FSI and plan of the proposed building already approved by the Thane Municipal Corporation and Commencement Certificate have been given to such structure should be allowed to continue, be completed and occupied by the issuing Occupation Certificate. Where the plans have been approved by the Thane Municipal Corporation but commencement certificates have not been issued, they should be reviewed and the permission should be revised in accordance with the Low Density Zone Regulation, now be prescribed.
- iv) The development proposals in Low Density Zone shall be scrutinised and permission shall be granted as per these UDCPR.

c) Development between 250 and 1000 Meters -

The Development proposals beyond the area of 250 m. shall be scrutinised and permissions shall be granted as per these UDCPR.

d) Other Stipulations -

- i) The original land under Chemical Industry, which has been certified by the Director of Industries / Director of Industrial Safety and Health / Competent Authority as permanently closed or having shifted elsewhere shall be allowed to be developed as per the relevant provisions in the prevailing Development Control Regulations.
- ii) Upon certification by the Director of Industries / Director of Industrial Safety and Health / Competent Authority that the Chemical Industry has been permanently closed or has shifted elsewhere, the 100 m. Green Belt and the further 150 m. low density belt around the plot boundary of such Chemical Industry shall suo-moto cease to exist.

10.2.5 Development around Air Force Stations

- i) As per Government of India, MoD, SRO.No.4, dated 13th January, 2010 which was published in Part - II, Section - 4 of Gazette Notification dated 23rd January, 2010. Air Force Station Thane falls within the 100 m. restriction zone. As per notification, no construction should be permitted within the restricted zone of 100 m. from the outer parapet of the Air Force boundary. Similarly, live hedges, tree/rows or clumps of trees or orchards shall not be maintained, planted, added to or altered within the 100 m. restricted zone. The restriction is equally applicable for construction of underground structure, wherein no digging and / or change in the level of ground is permitted within the notified zone.
- ii) Beyond the notified zone of 100 m., no restriction is required to be imposed as per the Works of Defence Act 1903 and no N.O.C. from Air Force Station, Thane is necessary.

⁽¹⁾ (--)

10.2.6 Development around Defence Establishment

- ⁽²⁾ Following restrictions are imposed in and around the land in the vicinity of the said unit as per the plan enclosed with Notification No.TPS-1203/1254/C.R.193/05/UD-12, Dt.30/12/2006.

Village : Kolshet / Kavesar / Waghbil (within the limit of Thane Corporation)

Circle / Taluka : Thane, District : Thane, State: Maharashtra

Height Restrictions :-

- (a) The height restrictions to any of the future constructions on North, North-West, West and South-West sides will be as follows :-

Sr. No.	Height Limiting zones from unit boundary (Zones indicated by colours)	Permissible height in meters	Remarks.
A	Red	Nil	Unit Area
B	Brown	Nil	Buffer Zone (No Dev. Zone)
C	Orange	18	--
D	Pink	27	--
E	Navy Blue	32	--
F	Yellow	46	--
G	Violet	64	--
H	Green	84	--

⁽¹⁾ Sr.No.(iii) & (iv) deleted vide Govt. Corrigendum No.CR.236/18, dt.09th December, 2020

⁽²⁾ Substituted vide Corrigendum / Addendum No.CR.121/21, dt.02nd December, 2021

- ⁽²⁾ (b) The height restrictions to any of the future constructions on North East, East and South-East sides will be as follows :-

Sr. No.	Height Limiting zones from unit boundary (Zones indicated by colours)	Permissible height in meters	Remarks.
A	Red	Nil	Unit Area
B	Brown	Nil	Buffer Zone (No Dev. Zone)
C	Orange	15	--
D	Pink	20	--
E	Yellow	35	--
F	Violet	40	--
G	Sky Blue	45	--

Other Restrictions :- In addition to the above restrictions, following general restrictions are also enforced :-

- No high tension power line up to 22 KV is to be setup within 1500 meters from unit boundary.
- Open wires, overhead lines, including telephone cables are to be outside 500 meters from unit boundary. However, UG cables. (below 5 meters) are permissible.
- No rail line with electric traction is permitted within two kilometers from the unit.
- Area within one kilometer radius from unit boundary is to be clear of all metallic structures including bridges.
- Ground water level is to remain constant. No efforts are to be made to change the electrical conductivity of the designated zone.
- No industry / equipment, which generate any kind of RG noise, are permitted to operate within 1 km. Radius from unit boundary.

10.2.7 Regulations for G-1 Zone (Yeur village Section - VII only)

Following uses shall be permitted in G - 1 Zone.

The residential Building on the lands which are actually under cultivation and the holiday homes for weekend stay and the Rest Houses subject to following conditions :-

- The plot to be permitted for such development shall be not less than 4000 sq.m. with the maximum FSI of 0.025.
- Each building to be not more than ground plus one storey with height not exceeding 9.75 m. including the height of stilt portion if any, subject to maximum built up area 100 sq.m. excluding stilt.
- To permit Club House, open play Grounds and other recreational purposes as normally permissible under green zone with permissible FSI as per these Regulations.
- To insist plantation at the rate of two fast growing trees per 100 sq.m. of land under development.

⁽²⁾ Substituted vide Corrigendum / Addendum No.CR.121/21, dt.02nd December, 2021

10.2.8 Regulations for G - 3 Zone for Forest Area

No development of any sort shall be allowed in this zone except the project of the Forest Department. In case of pockets of private lands in G - 3 zone, development shall be permitted as per the provisions of Green Zone / as per the provisions of G - 1 / G - 2 Zone subject to concurrence of Forest Department.

10.2.9 ⁽¹⁾ For the sake of Regulations No.1.3.74, No.1.3.93 (xiv)(i) and No.6.2.3(b) High Rise Building / Special Building means any multi-storied Residential Building, which is under redevelopment, and which is more than 25.0 m. in height above average surrounding ground level.

10.2.10 ⁽²⁾ Redevelopment of Old Dilapidated / Dangerous Buildings

Reconstruction / Redevelopment in whole or in part of any building which has ceased to exist in consequence of accidental fire / natural collapse or demolition for the reasons of the same having been declared dangerous or dilapidated or unsafe by or under a lawful order of the Authority or building having age of more than 30 years, shall be allowed subject to following conditions.

Redevelopment of multi-dwelling buildings of society / Co-Operative Housing Societies / Apartments -

- i) The FSI allowed for redevelopment of such building shall be FSI permissible under Regulation No.6.1 or 6.3 including FSI on payment of premium and maximum permissible TDR loading as per Table 6-A or 6-G, or the FSI consumed by the existing authorized building including TDR, premium FSI etc., whichever is more. (Such TDR, Premium FSI etc. utilised in existing building shall be treated as a basic FSI for redevelopment.) In addition to this, incentive FSI to the extent of 50% of the existing authorised built up area or 15 sq.m. per tenement, whichever is more, shall be allowed.

Provided that in cases where carpet area occupied by residential tenement in the existing building is less than the carpet area of 27.87 sq.m. then such tenement shall be entitled for minimum carpet area of 27.87 sq.m. and difference of these areas shall be allowed as additional FSI without any premium.

In case of non-residential occupier the area to be given in the reconstructed building shall be equivalent to the area occupied in the old building.

Such incentive FSI shall not be applicable for redevelopment of existing bungalow.

- ii) This regulation shall be applicable only when existing members of the societies are proposed to be re-accommodated.
- iii) If tenanted building/s and building/s of co-operative housing society / non-tenanted building/s coexist on the plot under development, then proportionate land component as per existing authorized built up area of existing tenanted building on the plot shall be developed as per Regulation No.7.6.2. and remainder notional plot shall be developed as per this regulation.
- iv) Notes below Regulation No.7.6 shall be applicable to this regulation.

10.2.11 ⁽¹⁾ Height of Building Permissible for Re-development Proposals / SRA Proposals

For all re-development proposals and slum-rehabilitation schemes in Municipal Corporation area, the building height upto 70.0 m. shall be permissible on roads having width between 9.0 to 12.0 m. subject to minimum front margin as per these regulations or minimum 6.0 m., whichever is less and subject to condition that such road shall be widened to 12.0 m. under the provisions of the Municipal Corporation Act, by prescribing line of street before granting occupation certificate to such buildings of re-development or slum-rehabilitation schemes. This shall be subject to Fire prevention, protection and life safety requirements and Fire N.O.C. from Chief Fire Officer.

⁽¹⁾ Inserted Vide Corrigendum / Addendum No.CR.79/2021, dt.02nd December, 2021

⁽²⁾ Substituted vide Corrigendum / Addendum No.CR.121/21, dt.02nd December, 2021

10.2.12 ⁽¹⁾ Podium

Podium for parking alongwith ramp may be permitted with side and rear marginal distance of 1.5 m. from plot boundary, subject to following conditions :-

- a) Top of the Podium shall be accessible for Fire Engine by 7.5 m. Ramp with gradient 1 : 10.
- b) Structural Stability Certificate regarding such Podium and Ramp shall be submitted with respect to stand Fire Engine over it & sustain load of Fire Engine.
- c) Minimum 6.0 m. marginal distances with required turning circle over the Podium shall be provided for manoeuvring of Fire Engine.

Provided that, if the podium is not accessible for Fire Engine then 6.0 m. marginal open space shall be provided all around the building excluding front margin. Turning circle shall not be less than 9.0 m. The refuge area in such cases shall be facing front road and shall be connected to Fire Tower as per Clause 2.24 of Part - 4 of NBC 2016.

- d) Provisions mentioned in Regulation No.9.13 shall be applicable except (ii).

10.2.13 ⁽¹⁾ Front Marginal Distances / Set-back / Road side margin/s in congested area - minimum front marginal distance for buildings under re-development proposal shall be 1.5 m. for roads having width 6.0 m. or more.

10.2.14 ⁽¹⁾ Off street parking requirement - For Redevelopment Projects in Thane Municipal Corporation area, multiplying factor for off street parking requirement as per Regulation No.8.2.2 shall be 0.8.

10.2.15 ⁽¹⁾ (a) For Redevelopment of smaller plots having area upto 1500 sq.m. with multistoried building upto 24.0 m. height plus height of parking upto 6.0 m., side / rear margin of 6.0 m. shall be relaxed upto 3.0 m. subject to Fire N.O.C., in case of bonafide hardship and such building shall not be considered as special building.

(b) Other provisions mentioned in Regulation No.6.2.3 shall be applicable.

10.3 NAGPUR MUNICIPAL CORPORATION

The following regulations shall be applicable.

10.3.1 Buildings in Commercial Zone :

(a) In non-congested area :

FSI for buildings outside congested area in commercial zone - the basic FSI permissible shall be 2.00 for commercial cum residential use or purely residential use and 2.50 for purely commercial use.

(b) In congested area :

The permissible FSI for commercial use shall be 1.50 for the plots fronting on the road having width less than 9.0 m. and 2.00 for the plots fronting on the road having width 9.0 m. or more.

10.3.2 Buildings in Industrial Zone

- a) In congested area, the permissible FSI for industrial use shall be 1.00.
- b) In non-congested area, the permissible FSI for industrial use shall be 2.5.

10.3.3 I to R provisions - Allowing Residential / Commercial uses in Industrial Zone.

The Regulation No.4.8.1 in these regulations shall be applicable to Nagpur Municipal Corporation area with following modifications.

⁽¹⁾ Inserted Vide Corrigendum / Addendum No.CR.79/2021, dt.02nd December, 2021

- i) Any open land or lands of closed Industrial unit/ units in the Industrial Zone (Excluding the leased out plots by NIT / NMC) may be permitted to be utilized for all the users permissible in the Residential zone with permissible FSI in Residential Zone, subject to payment of premium to be paid equal to 15% of the rate of developed land as given in the Annual Statement of Rates published by IGR every year.

However, for the Industrial Plots leased out by Planning Authority, (NIT / NMC) while granting I to R permission on these plots, FSI of 2.5 for purely commercial use and 2.00 for Mix use shall be permissible subject to payment of premium at the rate of 15% for Residential and 20% for Commercial use. Premium charges shall be as per rate of developed lands as given in the Annual Statement of Rates published by IGR every year.

- ii) Provisions of Regulation No.4.8.1(b)(iv) shall not be applicable where the Industrial layout has already been approved, and where in amenity space has already been provided in the approved layout.

10.3.4 For Plots admeasuring 1000 sq.m. and above (including amalgamated plots) in Residential Zone, basic FSI shall be 1.25, in congested and non-congested area, irrespective of road width. In cases covered in Regulation No.10.3.1 and 10.3.4 maximum building potential on plot including in-situ FSI shall remain the same, as mentioned in Table No.6-A and 6-G. However, the owner shall be at liberty to avail, the difference of potential if any, out of column 4 or / and 5.

⁽ⁱ⁾ 10.3.6 ⁽ⁱ⁾ Generation of TDR :-

For encumbered plots which are required for implementation of public purpose on urgent basis, following shall be applicable :-

(i) In case of land which were /are fully encumbered and where encumbrances had / have to be removed and / or rehabilitated by the project implementing authority, TDR / DRC shall be issued equivalent to the area of land taken over for free public project.

(ii) In case of land which were / are partly encumbered and where encumbrance are / were removed and / or rehabilitated elsewhere by the project implementing authority, the entitlement for TDR / DR for the portion of land which is / was vacant shall be as per Sr.No.(a) of Regulation 11.2.4 and the entitlement of TDR / DRC for the portion of land which is / was encumbered shall be equivalent to the area of encumbered land taken over for public project.

However, before permitting / granting TDR / DRC for encumbered land, project implementing authority shall separately certify the area of land which are vacant and the area of land under encumbrance alongwith detail as per the joint measurement survey carried out in this respect with the city survey officer. The area of vacant land and land under part encumbrance shall be clearly distinguished and demarcated, otherwise the land under part encumbrance shall be treated as fully encumbered land.

10.4 NAGPUR METROPOLITAN REGION DEVELOPMENT AUTHORITY

10.4.1 ^(#) Development along Ring Road :

250 m. Residential Zone / Residential Belt proposed along the 60 m. wide Outer Ring Road as a corridor development is sanctioned, subject to payment of premium. The development in this 250 m. corridor is permitted on payment of premium as decided by the Government on the total area of land under development or building permission. Such premium shall be deposited with the concerned Authority.

10.4.2 Special Regulations for the Improvement Schemes :

The improvement schemes by Public participation which are sanctioned by the Government under the provisions of the Nagpur Improvement Act, 1936 and which comes under the

^(#) Clarification issued vide Order No.CR.236/18 (Part 2), dt.23rd December, 2021

⁽¹⁾ Inserted Vide Notification u/s.37(1AA)(c) bearing No.CR.53/24/UD-12, dt.04th October, 2024

jurisdiction of the NMA area shall be valid and continue to be valid for the said purpose under the said Act. The Special Development Control Regulations for these schemes shall be as mentioned below :-

Any changes / Modifications / Amendments in the details layout or in the master plan shall be carried out by the Metropolitan Commissioner at his own level. However the Public Amenity / Public Utility Areas and their percentage as per original sanction shall not be changed while making Modifications / Amendments in the Schemes.

- i) **Improvement Scheme** - The scheme is prepared under the NIT Act, 1936 for the notified area and is duly approved by the State Government and which is now included in NMRDA area.
- ii) **Original Plot** - A plot consisting of nearby khasras calculated as a single record in a village which is under same ownership and has the same tenure status as defined in the respective 7/12 documents of the khasras.
- iii) **Final Plot** - The plot which is reconstituted or reshaped from the Original Plot within a draft / sanctioned Improvement Scheme in a manner appropriate for development and given access from the public right of way. The Final Plots is reconstituted as per the relevant regulations / Act as Final plots for Authorities share and owners share.
- iv) **Owner** - An owner is a person who has legal title for land or building. The definition also includes :-
 - a) An agent or trustee who receives the rent on behalf of the owner;
 - b) An agent or trustee who receives the rent of a or is entrusted with or is concerned with any building devoted to religious or charitable purposes;
 - c) A receiver, executor or administrator or a manager appointed by any court of competent jurisdiction to have the charge of, or to exercise the rights of the owner; and
 - d) A mortgage in possession.
- v) **Permissible FSI For Final Plot** -
 - i) The Metropolitan Commissioner may allow the owner to develop the final plot in possession of the owner subject to handing over to the Planning Authorities share as independent plot free of cost as per norms prescribed by Metropolitan Commissioner.
 - ii) The owner shall thereafter be entitled to develop his final plot for the uses permissible in adjoining zone as per the this DCPR with full permissible FSI of the entire Plot alongwith Additional FSI / TDR potential permissible for his Final plot share as per Chapter No.6 of this DCPR .
 - iii) The Metropolitan Commissioner shall develop the Final Plot in his possession (Authorities Share) for the purpose for which the scheme is sanctioned. This plot shall be entitled to be developed as per potential permissible for Authorities Final plot share as per Chapter No.6 of this UDCPR.
 - iv) **Net Plot area for Computation of FSI** - For the purpose of computing FSI / Built-up area, the net area of the plot shall be as defined in these regulations.
 - v) **Special Regulations For Inclusive Housing** - The provision regarding inclusive housing in development proposal shall be not made applicable in Improvement scheme if the Final Plot in the possession of Authority is to be designed and develop for the purpose of any affordable housing scheme.

- vi) Height of Building** - The maximum height of building for all users shall be as per Chapter No.6 of this UDCPR.
- vii) Amenities Space** - If the Amenity space has already provided in the scheme at the time of approval of scheme / layout, in such cases the amenity space as required under this UDCPR shall not be insisted.
- viii) Land Use Permissible** - All land uses mentioned in this UDCPR shall be permissible in the Improvement Schemes.
- ix) Development Charges** - The Development charges shall be recovered as mentioned in these regulations.
- x) Power to Authority** - For the smooth implementation of the schemes, the Metropolitan Commissioner with the Approval of the Authority, makes / amends the rule in consistent to the relevant Act and Regulations assigned to it with prior approval of by the Government.
- xi) UDCPR** - All regulations of UDCPR shall apply except above special regulations.

(#) 10.4.3 The following regulation shall be applicable only for the reference of Regulation No.25.6(xxxx) mentioned in the notification of sanctioning the Development Plan of Nagpur Metropolitan Region Development Authority.

In Agriculture zone, Residential use shall be allowed subject to following conditions -

- a) Minimum area of land shall be 15.0 hect.
- b) Land shall front on minimum 12.0 m. wide existing road.
- c) Permissible FSI / TDR shall be as that of Residential zone.
- d) The offsite infrastructure like road, water supply, sewerage treatment plant having zero discharge shall be developed by land owner at his own cost, unless this infrastructure is provided by Authority.
- e) 10% of the entire holding area shall be handed over to the Authority free of cost, without any FSI / TDR and free of all encumbrances for sale by Authority for residential, commercial or industrial use depending upon the nature of development. This 10% area shall be over and above recreational open space and amenity space to be provided as per regulation. This 10% area shall front on minimum 12.0 m. wide road.
- f) Premium on gross area at the rate of 5% of land rate in Annual Statement of Rates of the said land without considering the guidelines therein shall be paid to the Authority.

10.4.4 ⁽¹⁾ The following regulation shall be applicable only for the reference of Regulation No.25.6 (xxxiii) mentioned in the notification of sanctioning the Development Plan of Nagpur Metropolitan Region Development Authority.

Development permission around the periphery of Gaothan boundary -

Development permission around the periphery of Gaothan boundary shall be allowed as per the Regulation mentioned as below. This regulation shall be applicable only for the Rural centre and rural area. (excluding nine urban centre area) Regulation for residential zone and other regulation shall be applicable.

The peripheral residential area shown along the Gaothan village is deleted and land thereunder included in Agriculture Zone. The development along the periphery of the Gaothan shall be allowed subject to following :

⁽¹⁾ Inserted Vide Addendum No.CR.236/18 (Part-1), dt.23th June, 2021

^(#) Clarification issued vide letter No.CR.67/2022, dt.6th September, 2022

- ⁽¹⁾ a) In the villages in Rural area / Rural Centre excluding the area under nine urban centres, Residential Development or development allowed in Residential Zone, may be permitted within the periphery of Gaothan boundary as per the criteria given below. The regulations in respect of residential zone specified in these UDCPR shall be applicable.

Sr. No.	Category of Village (Populations as per latest census)	Development allowed from Gaothan boundary
1	Up to 5000	750 m.
2	Above 5000	1000 m.

Such development may be permitted on payment of premium of the total area of land. Such premium shall be calculated considering 15% rate of the said land as prescribed in the Annual Statement of Rates of the year granting such developments. Such premium shall be deposited in the concerned Authority.

Provided that, where more than 50% of area of the Survey Number/ Gat Number is covered within the above peripheral distance then the remaining whole of such Survey Number / Gat Number within one ownership shall be considered for development on payment of premium as above.

Provided further that, the premium charges shall be recovered at the time of tentative approval of the Development permission. Where tentative development permission is already granted before publication of this Development Plan and final approval is yet to be granted, then in such cases premium charges shall not be recovered at the time of final approval.

Provided further that, such payment of premium shall not be applicable in cases where development permission is already granted or layout is already approved by the authority before publication of Development Plan. Such premium shall also be not applicable for revision of such already approved permissions.

However, such development should not be permitted on lands which deserve preservation or protection from Environmental considerations viz. Hills and Hill tops and within the required Buffer Zone / Prohibited Zone from river, lakes and reservoirs of minor and major project of water resource department. ⁽¹⁾

⁽²⁾ **10.4.5** ⁽²⁾ Generation of TDR :-

For encumbered plots which are required for implementation of public purpose on urgent basis, following shall be applicable :-

(i) In case of land which were /are fully encumbered and where encumbrances had / have to be removed and / or rehabilitated by the project implementing authority, TDR / DRC shall be issued equivalent to the area of land taken over for free public project.

(ii) In case of land which were / are partly encumbered and where encumbrance are / were removed and / or rehabilitated elsewhere by the project implementing authority, the entitlement for TDR / DR for the portion of land which is / was vacant shall be as per Sr.No.(a) of Regulation 11.2.4 and the entitlement of TDR / DRC for the portion of land which is / was encumbered shall be equivalent to the area of encumbered land taken over for public project.

However, before permitting / granting TDR / DRC for encumbered land, project implementing authority shall separately certify the area of land which are vacant and the area of land under encumbrance alongwith detail as per the joint measurement survey carried out in this respect with the city survey officer. The area of vacant land and land under part encumbrance shall be clearly distinguished and demarcated, otherwise the land under part encumbrance shall be treated as fully encumbered land.

⁽¹⁾ Inserted Vide Addendum No.CR.236/18 (Part-1), dt.23rd June, 2021

⁽²⁾ Inserted Vide Notification u/s.37(1AA)(c) bearing No.CR.53/24/UD-12, dt.04th October, 2024

10.5 NASHIK MUNICIPAL CORPORATION

10.5.1 Applicability of Regulations for some areas

- i) The special Regulations framed by the Arbitrator for some final plots in T.P. Scheme No.1 (First Varied) shall remain in force.

⁽²⁾ (--)

10.5.2 Development of Cycle Track Along River and Nallah

A cycle track shall be developed in green belt areas earmarked on Development Plan along the rivers. Also, cycle track proposal is shown on canal land in the Development Plan.

A distance of 6.0 m. from the edge of minor water course (nallah) is to be left as marginal distance for construction of any building. A 3.0 m. strip of land from the edge of such water course out of this 6.0 m. distance to be left shall be available for use as cycle track for general public. The compound wall shall be constructed excluding this distance of 3.0 m. strip for cycle track. The owner shall be entitled for FSI of this strip of land for cycle track, in-situ. This 3.0 m. wide strip shall be handed over to Municipal Corporation for which, owner shall be entitled for TDR or in-situ FSI equivalent to 35% of the area of 3.0 m. wide strip. This regulation shall be applicable for development of land along Nallahs specified in Plan - A annexed with this UDCPR. Where development is already taken place and it is not possible to make provision for such 3.0 m. wide cycle track, then Municipal Commissioner shall be empowered to decide not to apply this regulation for particular stretch of nallah. In such cases, normal marginal distances under these regulations shall apply.

10.5.3 Set back and marginal distances for 36 m. wide D.P. road passing through village Gangapur and Ambad

Notwithstanding anything contained in Regulation No.6.2.1, following set back and marginal distance shall be applicable for road mentioned below.

Description of the road	Min. Plot Size in sq.m.	Min. width of plot in m.	Min. set back from road side in meters	Min. side margins in m.	Min. rear margins in m.	Remarks
36 m. wide D.P. road from Gangapur S.No.12 to Ambad S.No.199	300	12	3.00 (for commercial use also)	2.00	2.00	Margins for buildings G + 2 or stilt + 3 structure. Higher height permissible subject to marginal distances in Regulation No.6.2.3.

10.6 VASAI VIRAR CITY MUNICIPAL CORPORATION

Following regulations shall be applicable for the low intensity development areas in the Vasai Virar City Municipal Corporation.

The basic and total permissible FSI with DR / TDR on the plot shall be as under :-

Table No.10-A					
Sr. No.	Land use Zone	Base FSI	Additional FSI on payment of premium	Admissible TDR including Road widening FSI if any	Maximum permissible FSI
1	Low Density Residential Zone	0.3	0.2	--	0.5
⁽¹⁾ (--)	⁽¹⁾ (--)		—	—	—

⁽¹⁾ Deleted vide Notification No.C.R.121/21, dt.27th October, 2021

⁽²⁾ Sr.No.(ii) deleted vide Corrigendum / Addendum No.CR.121/21, dt.02nd December, 2021

10.7 MIRA BHAYANDAR MUNICIPAL CORPORATION

10.7.1 Uses permissible in Agriculture Zone

The lands along 45.0 m., 30.0 m. wide roads upto a depth of 30.0 m. may be developed for residential purpose on condition that the owner should provide infrastructural facilities such as septic tank, drainage, water supply etc. at his own cost.

10.7.2 Manori - Gorai - Uttan Notified Area

Special Development Control Regulations sanctioned for the Manori -Gorai-Uttan Notified Area as amended from time to time shall be applicable for the development / redevelopment in the said notified area being a special Tourism Development Plan sanctioned for this notified area.

10.8 ULHASNAGAR CITY MUNICIPAL CORPORATION

10.8.1 Regulation for unauthorised development in Ulhasnagar City Municipal Corporation shall be governed by the Regularisation of unauthorised Development in the City of Ulhasnagar Act, 2006.

10.8.2 For the purpose of Clause 10.8.1, the FSI permissible shall not be more than 4.00 plus the Ancillary FSI permissible in these regulations.

Provided that, for the structure/s which has consumed FSI, more 4.00 plus the Ancillary FSI, then such additional construction shall be demolished before regularisation of such structure.

10.8.3 The unauthorised structure/s, those cannot be regularised due to lack of structural stability or those are declared Dangerous / Dilapidated by the lawful order of the Municipal Commissioner, the FSI for redevelopment of such structure/s shall be permissible to the extent of, the consumed FSI of the existing structure (to be measured by considering the method a measurement prescribed in these Regulations i.e. P- Line) or as mentioned in clause 10.8.2 above, whichever is minimum (it may be called as protected FSI).

Provided that, the incentive FSI permissible for the redevelopment under these regulations shall be allowed over and above the protected FSI as mentioned hereinabove

10.8.4 The structures, those can not be permissible under clause 10.8.2 and 10.8.3 shall necessarily be developed under the provisions of Regulation No. 14.8 (Urban Renewal Scheme).

However, the structures under clause 10.8.2 and 10.8.3 shall also have option of development under Regulation No. 14.8.1 (Urban Renewal Scheme).

10.8.5 The minimum area for cluster in Urban Renewal Scheme (URS), under regulation no.14.8.1(i), shall be 4000 sq.m. both for congest and non-congested areas. All other regulations of URS shall be applicable as per regulation no.14.8.

10.9 KOLHAPUR MUNICIPAL CORPORATION

10.9.1 Open spaces, area, FSI and height limitations for characteristic specified areas in Kolhapur.

For characteristic specified areas in Kolhapur, listed herein below, shall have the open spaces and regulations for FSI and height limitations as given in table No.10-B below :-

TABLE NO.10-B.						
Sr. No.	Particulars of Areas	Minimum size of plot	Marginal distance to be observed			Permissible Max. built-up area
			Front	Rear	Side	
1	2	3	4	5	6	7
1	Rajarampuri almost all	40 x 78 = 3120 sq.ft. (12.16 m. x 23.77 m.)	10.0 (3.05 m.)	2.0 (0.60 m.)	2.6 (0.76 m.)	-

	plots are of 40 x 78 except corner plots of 80 x 78	294 sq.m.				
2	Shahupuri Commercial lane 30 x 75 (9.12 m. x 22.86 m.) or 40 x 75 (12.16 m. x 22.86 m.) Part of old cantonment (new Shahupuri) Shown as ABCDE on Development Plan.	30 x 75 = 2250 sq.ft. (9.12 m. x 22.86 m.)	1.0 (0.305 m.)	1.0 (0.305 m.)	1.06	-
	Shahu Road	40 x 75 = 3000 sq.ft. (12.216 m. x 22.86 m.)	1.0 (0.305 m.)	1.0 (0.305 m.)	2.6	-
	Other lanes (12.16 m. x 24.30 m.)	40 x 80 = 3200 sq.ft. (0.305 m.)	1.0 (0.305 m.)	1.0 (0.305 m.)	2.6	-
3	Laxmipuri	80 x 160 = 12800 sq.ft. (24.3 m. x 48.64 m.)	20.0 (6.00 m.)	5.0 (1.52 m.)	5.0 (1.52 m.)	-
		50 x 100 = 5000 sq.ft. (15.2 m. x 30.48 m.)	10.0 (3.05 m.)	2.6 (0.76 m.)	2.6 (0.76 m.)	-
		40 x 80 = 3200 sq.ft. (12.16 m. x 24.3m.)	5.0 (1.52 m.)	2.6 (0.76 m.)	2.6 (0.76 m.)	
4	Subhash road (South side Uma Talkies	40 x 100 = 4000 sq.ft. (12.16 m. x 30.4 m.)	10.0 (3.05 m.)	3.0 (0.91 m.)	5.0 (1.52 m.)	-

TABLE NO.10-B.

Sr. No.	Particulars of Areas	Minimum size of plot	Marginal distance to be observed			Permissible Max. built-up area
			Front	Rear	Side	
1	2	3	4	5	6	7
	Gokhale College	Upto 3000 sq.ft.	10.0 (3.05 m.)	3.0 (0.91 m.)	5.0 (1.52 m.)	-
5	Balbag Vashant	80 x 120 = 9600 sq.ft. (24.32 m. x 36.48 m.)	15.0 (4.56 m.)	10.8 (3.04 m.)	5.0 (1.52 m.)	-
6	Muskuti Talao	40 x 80 = 3200 sq.ft. (12.16 m. x 24.32 m.)	5.0 (1.52 m.)	2.6 (0.76 m.)	2.6 (0.76 m.)	-

7	Old cantonment (New Shahupuri) Remaining part area excluding in Sr. No.2	80 x 120 = 9600 sq.ft. (24.32 m. x 36.48 m.)	2.6 (0.76 m.)	2.6 (0.76 m.)	2.6 (0.76 m.)	-
		40 x 80 = 3200 sq.ft. (12.16 m. x 24.32 m.)	2.6 (0.76 m.)	2.6 (0.76 m.)	2.6 (0.76 m.)	
8	Patankar Colony	80 x 120 = 9600 sq.ft. (24.32 m. x 36.48 m.)	-	-	-	-
		Main Road	10.0 (3.05 m.)	3.0 (0.91 m.)	5.0 (1.52 m.)	-
		Other Roads	5.0 (1.52 m.)	2.6 (0.76 m.)	2.6 (0.76 m.)	-
9	Rajarampur New vasahat East side of Tararani vidyapeeth	40 x 80 = 3200 sq.ft. (12.16 m. x 24.32 m.)	10.0 (3.05 m.)	3.0 (0.91 m.)	5.0 (1.52 m.)	-
10	Petala New Mahadwar Road	40 x 100 = 4000 sq.ft. (12.16 m. x 30.4 m.) Other plots interior roads.	5.0 (1.52 m.)	3.0 (0.91 m.)	5.0 (1.52 m.)	-
11	Tarabai Park	5000 sq.ft. and above (460 Sq.m.)	15.0 (4.56 m.)	10.0 (3.05 m.)	10.0 (3.05 m.)	-
		3000 sq.ft. to 5000 sq.ft. (278.5 sq.m. to 460 sq.m.)	15.0 (4.56 m.)	10.0 (3.05 m.)	7.6 (2.25 m.)	-
12	Shahaji Nagar	5000 sq.ft. (460 sq.m.)	15.0 (4.56 m.)	10.0 (3.05 m.)	10.0 (3.05 m.)	-
13	Sykes Extension	80 x 120 = 9600 sq.ft. (24.32 m. x 36.40 m.)	15.0 (4.56 m.)	10.0 (3.05 m.)	10.0 (3.05 m.)	-
	CTS No. 1143, E	60 x 70 = 3200 sq.ft. (18.29 m. x 21.33 m.)	10.0 (3.05 m.)	5.0 (1.52 m.)	5.0 (1.52 m.)	-
	CTS No. 1141, E	40 x 80 = 3200 sq.ft. (12.16 m. x 24.32 m.)	5.0 (1.52 m.)	2.6 (0.76 m.)	2.6 (0.76 m.)	-
14	Old Gavati Mandai opposite Jijamata Girls High School	40 x 80 = 3200 sq.ft. (12.16 m. x 24.32 m.) and other Plots.	10.0 (3.04 m.)	2.6 (0.76 m.)	2.6 (0.76 m.)	-
15	Subhash Nagar	40 x 60 = 2400 sq.ft. (12.16 m. x 10.24 m.)	5.0 (1.52 m.)	2.6 (0.76 m.)	2.6 (0.76 m.)	-
16	Jawahar Nagar	40 x 60 = 2400 sq.ft. (12.16 m. x 10.24 m.)	10.0 (3.05 m.)	5.0 (1.52 m.)	5.0 (1.52 m.)	-

17	Line Bazar near Masjid	40 x 90 = 3600 sq.ft. (12.16 m. x 27.42 m.)	10.0 (3.05 m.)	2.6 (0.60 m.)	2.6 (0.76 m.)	-
18	Shivaji Udyam Nagar (Industrial use only permitted except to residential use already in use)	80 x 120 = 9600 sq.ft. (24.32 m. x 36.48 m.)	20.0 (6.10 m.)	3.6 (1.064 m.)	2.6 (0.76 m.)	-
		40 x 80 = 3200 sq.ft. (12.16 m. x 24.32 m.)	5.0 (1.52 m.)	2.6 (0.76 m.)	2.6 (0.76 m.)	-
		On Rajaram Road 80 x 80 = 6400 sq.ft. (24.32 m. x 24.32 m.)	5.0 (1.52 m.)	3.6 (1.064 m.)	5.0 (1.52 m.)	-
		40 x 80 = 3200 sq.ft. (12.16 m. x 24.32 m.)	5.0 (1.52 m.)	3.6 (1.064 m.)	5.0 (1.52 m.)	-
	CTS No.1325	40 x 80 = 3200 sq.ft. (12.16 m. x 24.32 m.)	5.0 (1.52 m.)	2.6 (0.76 m.)	2.6 (0.76 m.)	-
	CTS No. 1243/2 to 1243/4 for foundry use. Power Nagar, Udyam nagar extension		20.0 (6.10 m.)	5.0 (1.52 m.)	5.0 (1.52 m.)	-
19	Dhor Vasahant	80 x 160 = 12800 sq.ft. (24.32 m. x 48.64 m.)	15.0 (4.56 m.)	10.0 (3.05 m.)	5.0 (1.52 m.)	-
20	Town Planning Scheme	Kolhapur No.1 Special	-	-	-	-
	For final Plots	Upto 2 Gunthas (less than 2 area)	5.0 (1.52 m.)	5.0 (1.52 m.)	2.06 (0.76 m.)	50%
	For final Plot	2 Gunthas to 5 gunthas (2 Ares to 5 areas)	10.0 (3.05 m.)	5.0 (1.52 m.)	5.0 (1.52 m.)	50%
	For final Plots	5 gunthas (5 Ares)	15.0 (4.5 m.)	15.0 (4.56 m.)	10.0 (3.05 m.)	33%
21	Town Planning Scheme Kolhapur No.II Special Regulations.					
B)	Excepting above further final plots		15.0 (4.56 m.)	15.0 (4.56 m.)	5.0 (1.52 m.)	33%
22	Two planning Scheme Kolhapur No.III Special Regulations.					
	A. Final plot about 5000 sq.ft. (460 sq.m.)		15.0 (4.56 m.)	15.0 (4.56 m.)	10.0 (1.56 m.)	33%

	B. Final plot No.15 and 19		10.0 (3.04 m.)	10.0 (3.04 m.)	10.0 (3.04 m.)	33%
23	Mahatma Phulewadi Housing society	40 x 110 = 4400 sq.ft. (12.016 m. x 33.53 m.)	10.0 (3.05 m.)	2.6 (0.76 m.)	2.06 (0.76 m.)	-
		40 x 60 = 2400 sq.ft. (12.16 m. x 18.29 m.)	10.0 (3.05 m.)	2.6 (0.76 m.)	2.6 (0.76 m.)	-
24	Sambhaji Nagar	40 x 80 = 3200 sq.ft. (12.16 m. x 24.32 m.)	5.0 (1.52 m.)	2.0 (0.60 m.)	2.6 (0.76 m.)	-
		40 x 60 = 2400 sq.ft. (12.16 m. x 18.29 m.)	5.0 (1.52 m.)	2.0 (0.60 m.)	2.6 (0.76 m.)	-
25	Sagar Mal. Behind Maharashtra Housing Board colony. (Shastri Nagar)	50 x 85 = 4250 sq.ft. (15.20 m. x 25.90 m.)	10.0 (3.05 m.)	2.6 (0.76 m.)	2.6 (0.76 m.)	-
26	Khasbag Road from CTS No. 2557 to 2533		As per gaathan regulation	1.0 (0.305 m.)	2.6 (0.76 m.)	-
27	Sakoli Vasahat to the South West of Rankala S.T. Stand		As per gaathan regulation	1.0 (0.305 m.)	1.6 (0.45 m.)	-
28	Timber Market	100 x 150 = 15000 sq.ft. (30.48 m. x 45.72 m.)	15.0 (4.56 m.)	15.0 (4.56 m.)	15.0 (4.56 m.)	-
29	Golibar Vasahat K Bavada	40 x 40 = 1600 sq.ft. (12.16 m. x 12.16 m.)	2.6 (0.76 m.)	2.6 (0.76 m.)	2.6 (0.76 m.)	-
30	Patharvat Vasahat Near Daulat Nagar	30 x 50 = 1500 sq.ft. (9.14 m. x 15.24 m.)	5.0 (1.52 m.)	2.6 (0.76 m.)	2.6 (0.76 m.)	-
31	Old Vasahats Dombur Wada Takala portion on Koti-tirth	Gaathan Regulation would be applicable	-	-	-	-
32	Sotewala Vasahat		5.0 (1.52 m.)	2.0 (0.60 m.)	2.6 (0.76 m.)	-
33	Nagala Area of Tarbai Park	5000 sq.ft. and above (460 sq.m. & above)	15.0 (4.56 m.)	10.0 (3.05 m.)	10.0 (3.05 m.)	33%
		3000 sq.ft. to 5000 sq.ft. (278.5 sq.m. to 460 sq.m.)	15.0 (4.56 m.)	10.0 (3.05 m.)	7.6 (2.25 m.)	33%

34	Hind co-Operative Housing Society (Ruikar Colony)	65 x 80 = 52000 sq.ft. (19.81 m. x 24.36 m.)	10.0 (3.05 m.)	-	7.0 (2.13 m.)	-
		60 x 90 = 5400 sq.ft. (18.91 m. x 27.42 m.)	15.0 (4.56 m.)	5.0 (1.52 m.)	7.0 (2.13 m.)	-
35	Dinanath Mangeshkar Nagar - site No.272 & 273	i) 1500 to below 2000 sq.ft. (139.35 sq.m. to 185.80 sq.m.)	10.0 (3.05 m.)	5.0 (1.52 m.)	5.0 (1.52 m.)	1/2
		ii) 2000 to below 3000 sq.ft. (185.0 sq.m. to 278.7 sq.ft.)	10.0 (3.05 m.)	10.0 (1.52 m.)	5.0 (1.52 m.)	1/2
		iii) 3000 to below 5000 sq.ft. (278.7 sq.m. to 464.5 sq.m.)	15.0 (4.56 m.)	10.0 (3.05 m.)	7.6 (2.25 m.)	1/2
36	Sagarmal (S.No.1330) E Ward, site No. 338)	do	do	do	do	do
37	R.S. No.690 site No. 365	400 sq.ft. (37016 sq.m.) 400 to 784 sq.ft. (37016 to 67.03 sq.m.)	Gaothan Regulation shall be applied 5.0 (1.52 m.)	- 2.0 (0.60 m.)	- 2.6 (0.76 m.)	-
38	Site No.87 (Housing the Dishoused)	AS mentioned in Sr.No.135	AS mentioned in Sr.No.135	-	-	-
39	R.S.No.711 K, Karveer	500 to 1000 sq.ft. (46.45 to 92.90 sq.mt.)	5.0 (1.52 m.)	-	3.0 (0.9 m.) on one side 2.6 (Common distance (0.76 m.)	-
40	Remanmala Zopadpatti	1800 to 2000 sq.ft. (1167.22 to 185.8 sq.m.)	5.0 (1.52 m.)	2.6 (0.76 m.)	2.6 (0.76 m.)	1/2
41	Site No.60	50 x 30 = 1500 sq.ft. (15.24 m. x 9.14 m.)	5.0 (1.52 m.)	2.6 (0.76 m.)	2.6 (0.76 m.)	1/2
42	Daulat Nagar	1500 sq.ft. (139.35 m.)	5.0 (1.52 m.)	2.6 (0.76 m.)	2.6 (0.76 m.)	1/2

Note 1 - Maximum permissible Basic FSI for Sr.No.1 to 3 and 26, 27 and 31 shall be 1.5 for residential use and 2.0 for residential cum-Commercial use and for remaining areas, it shall be 1.1 and mix non-residential use to be allowed without any restriction of percentage.

Note 2 -The properties fronting on “Mahadwar to Mahadwar Chowk Road” shall be given building permission with a front set back of only 0.5 m.

Note 3 - The Maximum permissible Basic FSI, permissible TDR loading and additional FSI on payment of premium shall be as allowed as per these regulations.

Note 4 - Height of building

i) Height of building to be constructed on Kiranotsav Marg of Mahalaxmi Temple shall be determined by the Municipal Commissioner.

ii) For Sr.No.1, 2 & 3 - upto 21.0 m. height with marginal distances as per column No.4, 5 & 6 of table above.

Above 21.0 m. height - it shall be as per Regulation No.⁽¹⁾ 6.1.1(iii), (vi) or Regulation No.6.2.3, as the case may be.

iii) For Sr.No.4 to 42 upto 15.0 m. as per column No 4, 5 & 6 of table above.

For height above 15.0 m., 1.0 m. set-back for every 3.0 m. height on all sides except front for open plot. For the existing structures and ongoing projects only front and rear set-back to be kept in addition to the marginal open spaces as per column No.4, 5 & 6 of table above. This may be allowed in form of step margin. Side margin as mentioned in column No.6 of table above may be continued upto 21.0 m. height.

Above 21.0 m. height - it shall be as per Regulation No.⁽¹⁾ 6.1.1(iii), (vi) or Regulation No.6.2.3, as the case may be.

Note 5 - Other provisions excluding above, shall be as per UDCPR.

Note 6 - For parking spaces in basement and upper floor at least one vehicular ramp of 3.00 m. width in side and rear margin for 4 wheeler ⁽²⁾ and for 2 wheeler or one vehicular ramp of 2.0 m. width for 2 wheeler shall be provided for plot area upto 1000 sq.m. ⁽²⁾ or the owner may provide minimum 2 Car lifts instead of Ramp.

10.9.2 Height of building on Kiranotsav Marg other than specified area

The height of building to be constructed along Kiranotsav Marg of Mahalaxmi Temple shall be determined by the Municipal Commissioner.

10.10 NAVI MUMBAI MUNICIPAL CORPORATION

^(#) 10.10.1 Basic FSI Permissible for Certain Categories of Plots.

Business or Mercantile use wholly or in combination with the residential use in any other zone mentioned in Regulation, other than Regional Park Zone and No Development Zone, shall be as below.

Provided that, in case of combination, Business or mercantile use shall not be less than 10% of the admissible FSI. Provided further that the area of all such plots taken together in the zone from Node shall not exceed 15% of the area of the relevant zone from the Node.

a. For plots of area below 1000 sq.m.	Basic FSI = 1.00
b. For plots of area 1000 sq.m. and above	
& fronting on minimum 15.0 m. wide road	Basic FSI = 1.50

Note :

- 1) The benefit of the regulation mentioned at (a) above may be extended to plots of land leased out or agreed to be leased out by CIDCO earlier with different (lower) FSI, in Zones other than predominantly Commercial Zone, provided further that all other UDCPR provisions including parking are fully complied with.

⁽¹⁾ Substituted vide Corrigendum / Addendum No.CR.121/21, dt.02nd December, 2021

⁽²⁾ Substituted / Inserted Vide Corrigendum / Addendum No.CR.79/2021, dt.02nd December, 2021

^(#) Clarification issued vide letter No.CR.31/2023/UD-13, dt.24th July, 2023

- 2) All plots leased by CIDCO with FSI 1.50 and fronting on roads less than 15.0 m. if any, prior to the sanction of this UDCPR shall be exempted from the 15.0 m. road with criteria.

If the intended development is within the scheme for allotment of land to the project affected land holders in the defined area contiguous to the villages or within the scheme of allotment of 12.5% / 22.5% land to the project affected land holders, 15% of such FSI may be utilized for commercial area and FSI permissible shall be 1.50. ⁽¹⁾ In such case, the clear marginal open spaces within the plot required to be provided for the purposes of deriving light and ventilation, shall be as follows :-

Category	Area of plot fronting road (in m.)		Max permissible height of buildings	Min. Marginal Open Spaces (in m.)			
				Front	Side	Side - 2	Rear
Row houses with or without common walls	a	40 m ² to less than 150 m ²	13 m	1.5	0.0	0.0	2.25
	b	150 m ² to less than 150 m ²	13 m	3.0	0.0	0.0	3.0
Semi-detached building	a	150 m ² to less than 150 m ²	13 m	1.5	2.25	0.0	2.25
	b	150 m ² to less than 300 m ²	13 m	3.0	1.5	0.0	3.0
	c	More than 300 m ² to less than 450 m ²	13 m	3.0	3.0	0.0	3.0
Detached building	a	450 m ² to less than 1000 m ²	13 m	3.0	3.0	3.0	3.0
	b	1000 m ² and above	As per regulation No. 6.2 and 6.3 of these regulation.				

- ^(#) 3) In case of plot where basic FSI is 1.5 the maximum building potential of plot including in-situ FSI as mentioned in table 6-G may be allowed to be exceeded by further 0.5.

10.10.2 Reconstruction / Redevelopment of Building in CIDCO / NMMC Areas

Regulation for reconstruction / redevelopment schemes undertaken by CIDCO / Owner's Association / Co-operative Housing Society (CHS) in respect of the authorized buildings previously constructed by CIDCO but subsequently destroyed by natural calamities or accidental fires or which have collapsed by aging or are demolished or being demolished under a lawful order of the Municipal Commissioner etc. :-

Reconstruction / Redevelopment, in whole or in part of a building, previously constructed by CIDCO (not being a building wholly occupied by warehousing / Industrial user and also not being an individually owned structures, which has ceased to exist for the reasons mentioned above) or a building constructed by CIDCO which has been declared dilapidated by the Commissioner NMMC or a buildings constructed by CIDCO which is above 30 years of age, irrespective of its status of dilapidation, (hereinafter collectively referred to as "dangerous / dilapidated building") shall be permissible in accordance with the following Regulations.

Regulation for Reconstruction / Redevelopment :-

- For redevelopment of building or buildings in the housing schemes of CIDCO, containing houses or tenements for (i) EWS / LIG and / or (ii) MIG and / or (iii) HIG, the total permissible FSI shall as specified in Table below Rehab + Incentive FSI as per clause 2(A) & (B), whichever is more and shall be based on gross plot area :-

⁽¹⁾ Inserted vide Notification u/s 37 (1AA)(c) No.CR.236/18 (Part 6), dt.12th October, 2022

^(#) Clarifications issued vide Letter No.CR.42/21, dt.14th June, 2021 & Order No.CR.236/18 (Part 2), dt.12th October, 2022

Table No.10-C		
Sr. No.	Category	Permissible FSI
i)	Plot area of 1000 sq.mt. or more and having access road of minimum 15.0 m width.	3.00
ii)	Plots area of 1000 sq.mt. or more and having access road of minimum 9.0 m. width	2.00
iii)	All other plots having access road below 9.0 m. width.	1.80 or Authorisedly consumed FSI + 50% Incentive whichever is less

If the entitlement of FSI as above is less than maximum building potential mentioned in column 6 or 9 of Table 6-G of Regulation No.6.3, then difference of FSI entitlement shall be availed by payment of premium. Moreover, the maximum building potential mentioned in Table No.6-G shall be allowed considering the road width one step below subject to road width of minimum 12.0 m.

e.g. for the roads as mentioned at Sr.No.3 in Table No.6-G, the maximum building potential shall be considered as given at Sr.No.4.

Identification of dangerous / dilapidated buildings shall be done by a Committee under the Chairmanship of the Municipal Commissioner, N.M.M.C., comprising Superintendent Engineer, Public Works Department, Thane; Joint Director, Town Planning, Konkan Division; City Engineer, N.M.M.C.; Chief Engineer, CIDCO; Chief Planner, CIDCO and such other members as may be appointed by the Municipal Commissioner, N.M.M.C., having regard to their academic qualifications, technical competence and previous experience in the field of Structural Engineering.

2. Where redevelopment of any dangerous / dilapidated buildings(s) in a Housing Scheme of CIDCO constructed building is undertaken by the Co-op Housing Society or the occupiers of such building(s) or by the lessees of CIDCO, the Rehabilitation area Entitlement, Incentive FSI and sharing of balance FSI shall be as follows:-

A) Rehabilitation Area Entitlement :

- i) Under redevelopment of any dangerous / dilapidated building(s) in a Housing Scheme of CIDCO, the entitlement of rehabilitation are for an existing residential tenement shall be equal to sum total of -
 - (a) a basic entitlement equivalent to the carpet area of the existing tenement plus 35% thereof, subject to a minimum carpet area of 300 sq.ft. and
 - (b) an additional entitlement, governed by the size of the plot under redevelopment, in accordance with the Table below :-

Table No - 10 D	
Area of the Plot under Redevelopment	Additional Entitlement (As % of the Carpet Area of the Existing Tenement)
Upto 4000 sq.m.	Nil
Above 4000 sq.m. to 2 hect	10%
Above 2 hect. to 5 hect.	15%
Above 5 hect. to 10 hect.	20%

Explanation : The plot under redevelopment means the total area of the land on which redevelopment of dangerous / dilapidated building(s) is to be undertaken.

Provided that the maximum entitlement of rehabilitation area shall in no case exceed the maximum limit of carpet area prescribed for MIG category by the Govt., as applicable on the date of approval of the redevelopment project.

Provided further that the entitlement of rehabilitation area, as admissible under this regulation, shall be exclusive of the area of balcony.

- ii) Under redevelopment of any dangerous / dilapidated building(s) in a Housing Scheme of CIDCO, the entitlement of rehabilitation area of any existing authorized commercial unit / amenity unit in the Residential Housing Scheme shall be equal to the carpet area of the existing unit plus 20% thereof.

- B) Incentive FSI :** Incentive FSI admissible against the FSI required for rehabilitation, as calculated above, shall be based on the ratio (hereinafter referred to as Basic Ratio) of Land Rate (LR) in Rs. / sq.m. of the plot under redevelopment as per the Annual Schedule of Rates (ASR) and Rate of Construction (RC)* in Rs. / sq.m. applicable to the area as per the ASR and shall be as given in the Table below :-

Table No.10-E	
Basic Ration (LR / RC)	Incentive (As % of Admissible Rehabilitation Area)
Above 3.00	70%
Above 2.00 and upto 3.00	80%
Above 1.00 and upto 2.00	90%
Upto 1.00	100%

Explanation :- * RC is the rate of construction in respect of R.C.C. Construction, as published by the Chief Controlling Revenue Authority & Inspector General of Registration, Maharashtra State in the Annual Schedule of Rates.

Provided that the above incentive will be subject to the availability of the FSI on the Plot under redevelopment and its distribution by N.M.M.C., with prior approval of CIDCO.

Provided further that in case there are more than one land rate applicable to different parts of the plot under redevelopment, a weighted average of all the applicable rates shall be taken for calculating the Average Land Rates and the Basic Ratio.

Provided further that the Land Rate (LR) and the Rate of Construction (RC) for calculation of the Basic Ration shall be taken for the year in which the redevelopment project is approved by the authority.

- C) Sharing of the Balance FSI :**

The FSI remaining in balance after providing for the rehabilitation and the incentive components, calculated as per (A) and (B) above respectively, shall be shared between the existing or proposed Co-operative Housing Society / Apartment Ownership Association and CIDCO, in the form of built-up area, as given in Table below and the share of CIDCO shall be handed over to CIDCO free of cost.

Table No.10-F		
Basic Ratio (LR/RC)	Sharing of Balance FSI	
	Society / Association Share	CIDCO Share
Above 3.00	30%	70%
Above 2.00 and upto 3.00	40%	60%
Above 1.00 and upto 2.00	50%	50%
Upto 1.00	60%	40%

Provided that building or buildings under redevelopment in the N.M.M.C. area, upto 20% of the CIDCO's share in the form of tenement shall be handed over free of cost to the N.M.M.C. N.M.M.C. require the same for rehabilitation of the project affected persons.

- 2.1 Where redevelopment of dangerous / dilapidated building(s) in a Housing Scheme of CIDCO is undertaken by CIDCO directly or jointly by CIDCO along with the Co-operative Housing Society / Association or the occupiers of such building(s) or by the lessees of CIDCO, the Rehabilitation Area Entitlement, incentive FSI and sharing of balance FSI shall be as follows :

A) Rehabilitation Area Entitlement :

The Rehabilitation Area Entitlement shall be increased by 15% of the existing carpet area, over and above the Rehabilitation Area Entitlement calculated in (A) of Clause 2 above, subject to the maximum of the size of MIG, prescribed by the Government in the Housing Department.

B) Incentive FSI : Incentive FSI shall be the same as in (B) of Clause 2.

C) Sharing of the balance FSI : There shall be no sharing of the balance FSI, which shall be entirely available to CIDCO for implementing Affordable Housing Project.

3. Other requirement / Criteria :

- i. For the purpose of calculating the FSI, the entire area of the layout including widening of existing roads and internal roads but excluding the land earmarked for public amenities shall be considered. Sub-division as well as amalgamation of plots shall be permissible. Amalgamation of more than one Apartment Owners' Association / Co.op. Hsg. Society (CHS) / Residents' Association shall be permissible and after such amalgamation, the amalgamated plot should be in the name of the applicant CHS with legal ownership title, without considering the provision made in the Regulation of the DCR. However consent of at least 70% leaseholders / occupants who intend to amalgamate such condominium shall be necessary.
- ii. In a condominium / plot area, widening of existing roads as per the regular line of street prescribed by the Commissioner, N.M.M.C. or widening of road providing vehicular access to the condominium plot to bring it to the minimum right of way as prescribed in Table No.10-C, shall be permissible for reconstruction / redevelopment, after handing over required stretch of land under road to N.M.M.C., free of cost, duly developed with storm water drains and footpath, if any, to the satisfaction of the Municipal Commissioner.
- iii. In case where there are a number of dangerous / dilapidated buildings on a plot, in such cases, equivalent land component of such buildings shall be worked out and incentive F.S.I. shall be based on such land component.
- iv. The normal permissible tenement density per net hectare may be allowed to be exceeded in multiple of F.S.I. permissible.
- v. The existing residential premises (other than R + C premises) shall be permitted to be redeveloped for residential user only. No change of use from Residential to Residential cum Commercial shall be permitted. However, in such premises, if area of such plot is more than 1000 sq.m. and the same is fronting on a road having width of 20 mt. and above then it shall be permissible to construct convenience shopping to the extent of 5% of the plot area and if the plot area is more than 1000 sq.m. and the plot is fronting on a road having width of 30 mtrs and above then this limit for convenience shopping will be upto 10%.
- vi. In a condominium / plot area, It shall be mandatory to keep minimum 10% or 15%, as the case may be, compulsory recreational open space on ground clearly open to sky over and above podium garden, in the proposed redevelopment project in respect of land area between 2500 sq.mt. to 4000 sq.mt. or more than 4000 sq.mt., respectively.

-
- vii. 5% of the Plot area under reconstruction / redevelopment project shall be surrendered to the Municipal Corporation, free of cost, towards essential amenity area, in case the plot area is more than 2500 sq.mt. The FSI of such amenity area shall be permissible on the balance plot area and the entire area of such amenity space will be considered for computation of FSI, without deducting this area from the gross plot area. However, 1.0 FSI out of amenity space FSI will be deducted from the total permissible FSI. Alternatively carpet area equivalent to 5% of the area of the plot Under redevelopment can be constructed within the Scheme, providing Separate access, and handed over to N.M.M.C. free of cost as Social amenity.
 - viii. The Layout of entire condominium / residential / Residential cum commercial premises, duly signed by the Apartment owners' Association / CHS shall be submitted at the time of Commencement Certificate to ascertain the feasibility of the entire condominium for redevelopment, so that in future, proper redevelopment of other buildings in the condominium / residential premises is smoothly feasible. However, such redevelopment can be undertaken in a phased manner in respect of one or two buildings likewise as per the approved layout of the entire condominium / residential premises. In case of such partial redevelopment, the infrastructure charges shall also be deposited in proportion to the area under such partial redevelopment.
 - ix. For the purpose of deciding the authenticity of the age of the structure, if the approval plans of such existing structure are not available, the Municipal Commissioner shall consider other evidence such as Assessment Record, or city survey record or sanad.
 - x. In any Redevelopment project where the existing or proposed Co-operative Housing Society / Apartment Owners' Association / Developer appointed by the concerned Society / Association has obtained No Objection Certificate from the CIDCO, thereby securing additional balance FSI with the consent of 70% of its members and where such N.O.C. holder has made provision for alternative accommodation in the proposed building (including transit accommodation), then it shall be obligatory for all the occupiers / members to participate in the Redevelopment Scheme and vacate the existing tenements for the purpose of redevelopment. However, in case of Apartment owners' Association, the Consent as per the concerned Act will be required.
 - xi. For redevelopment of any dangerous / dilapidated buildings in any Housing Scheme of CIDCO under clause 2.1 hereinabove, by CIDCO, the consent of the Cooperative Housing Society in the form of a valid Resolution as per the Co-operative Societies Act, 1960 will be sufficient. Similarly in case of Apartment Owners' Association, the consent as per the concerned Act will be required.
 - xii. For providing the requisite infrastructure for the increased population, an infrastructure charge at the rate of 10% of the Land Rate as per the ASR of the year of approval of the redevelopment project shall be levied and charged by the N.M.M.C. for the extra FSI granted for the redevelopment project, over and above the Basic Zonal FSI.
 - xiii. A corpus fund, as may be decided by Municipal Commissioner, shall be created by the Developer which shall remain with the concerned Co-operative Housing Society / Apartment Owners' Association for the maintenance of the new buildings under the Rehabilitation Component.
 - xiv. For the purpose of this Regulation, the carpet areas for EWS, LIG or MIG tenements shall be as determined by the Government in the Housing Department from time to time.
 - xv. Any redevelopment proposal where N.M.M.C. has already issued Commencement Certificate (C.C.) prior to the date of coming into force of this Modification (hereinafter
-

referred to as “the appointed date”) and which is valid as on the appointed date, shall be allowed to convert to redevelopment projects under this Regulation, provided it satisfies all the requirements specified in this Regulation.

10.10.3 Road width of 11.0 m.

The road width of 11.0 m. in Navi Mumbai Municipal Corporation area shall be treated at par width of 12.0 m. for all purposes including permissible uses mentioned in this UDCPR.

10.10.4 Allowance of premium FSI in lieu of TDR

In addition to the quantum of premium FSI mentioned in Table 6-A of Regulation No.6.1.1 and Table 6-G of Regulation No.6.3, the additional premium FSI to the extent of TDR mentioned in the said table shall be allowed till the generation of TDR in Navi Mumbai Municipal Corporation area ⁽¹⁾ and CIDCO as a Planning Authority by virtue of NTDA.

10.10.5 Provision of Amenity Space

The Regulation No.3.5 shall not be applicable to CIDCO area.

10.10.6 Provision of Recreational Open Space

The recreational open space required to be provided in the lands allotted outside the Action area shall be as per the relevant clause of the Agreement to lease or as per these regulations (UDCPR), whichever is more.

The Action area means area for which the CIDCO intends to prepare a detailed layout plan with special development control regulations.

10.11 NATIONAL PARK AND TUNGARESHWAR ECO-SENSITIVE ZONE

10.11.1 Development around National Park and Tungareshwar Eco-sensitive Zone

The restrictions imposed by Ministry of Environment, Forests and Climate Change for the Eco-sensitive Zone declared around Sanjay Gandhi National Park and Tungareshwar Eco-sensitive Zone shall be applicable as amended from time to time in addition to these Regulations.

10.12 MAHARASHTRA AIRPORT DEVELOPMENT COMPANY NOTIFIED AREA

10.12.1 In the areas notified for Maharashtra Airport Development Company as Planning Authority / Special Planning Authority, the following additional regulation shall be applicable.

The basic FSI permissible for development in Airport and allied activities / services, Special Economic Zone, Mix Use Zone, Public-Semi-Public Zone shall be 1.50.

10.13 BHIWANDI SURROUNDING NOTIFIED AREA

10.13.1 REGULATIONS FOR AFFORDABLE HOUSING SCHEME :

1. In order to promote construction of affordable housing stock on private lands, the Planning Authority may permit implementation of Affordable Housing Scheme in accordance with the provisions of these Regulations. Affordable Housing Scheme (hereinafter referred to as 'the Scheme') shall be permissible only on the lands situated within the limits of the Bhiwandi Surrounding Notified Area in the Mumbai Metropolitan Region (MMR).
- 2.(i) Affordable Housing Scheme shall be permissible in Residential Zone / Affordable Housing Zone shown on the Development Plan only and on plots having access from an existing or proposed Development Plan Road having width equal to or in excess of 18.0 m., or an existing road in respect of which Regular Line of Street has been declared under the relevant provisions of Maharashtra Municipal Corporation Act, Maharashtra Municipal Councils, Nagar Panchayats and Industrial Townships Act, 1965 for a width of 18.0 m. or more,

⁽¹⁾ Inserted vide Notification u/s.37(1AA)(c) No.CR.236/18 (Part 6), dt.12th October, 2022

provided permissible FSI on such plots is 0.95 or more and TDR / additional FSI on payment of premium more than 0.6 is allowable. However in case of a proposed road, the land under the said proposed road shall be acquired before the approval of building plans for the Affordable Housing Scheme. Affordable Housing Scheme shall not be allowed in areas where FSI is less than 0.95 or where use of TDR is not permissible.

- (ii) Minimum plot area for the Affordable Housing Scheme shall be 4000 sq.mt. excluding area under D.P. Roads and D.P. Reservations, if any.
 - (iii) The plot under the Scheme shall be independent, unencumbered and contiguous.
 - (iv) The Scheme shall not be permissible in congested areas, demarcated as such on the Development Plan.
3. The Special Planning Authority for Bhiwandi Surrounding Notified Area shall be competent to grant both location clearance and layout approval/building permission for an Affordable Housing Scheme.
4. (i) Maximum permissible FSI (including the base FSI of 1.00) under the Scheme shall be 3.00 on the gross plot area, including mandatory layout recreational open space and Amenity Space. The FSI to be utilized shall be in the proportion of 1:3 for the Affordable Housing Component and the Free Sale Housing Component on 1/4th and 3/4th part of the land respectively. Thus Affordable Housing and Free Sale Housing shall be proposed on the same plot of land but on two separate independently buildable pockets. For lands in Affordable Housing Zones, the owner / developer may be allowed to develop the land as per the Rules of the Affordable Housing Policy with the proviso that free sale to Affordable Housing FSI ratio will be 1.8:1 instead of 1.66:1 and the maximum FSI will be 2.5. **Or**
- the owner / developer may be allowed to develop the land as permissible in Residential Zone as per prevailing Development Control Regulation subject to the condition that the area of tenements to be constructed with entire potential of the land, shall be of Affordable Housing Scheme. However if the provisions of inclusive housing stipulated in UDCPR are applicable to this area then, it shall also be made applicable to such land.
- (ii) Under Affordable Housing Scheme, upto 15% of the total built-up area of the Affordable Housing Component may be used for construction of shops / commercial use as per the direction of Special Planning Authority for Bhiwandi Surrounding Notified Area and such commercial built-up area shall be handed over to the Special Planning Authority for Bhiwandi Surrounding Notified Area free of cost.
5. (i) An Affordable Housing Unit shall be a self-contained dwelling unit of 25 sq.mt, carpet area, However the carpet area of a Housing Unit shall be 160 sq.ft., where the construction under the Rental Housing Scheme has already commenced.

- (ii) The amenity space for Affordable Housing shall be 10% of the gross plot area under the Scheme and it shall be proportionately provided in the area earmarked for the Affordable Housing Component and the Area kept for Free Sale Housing Component.

Provided that where the Scheme is to be implemented on a plot in Industrial Zone where the Planning Authority has duly permitted Residential user under the relevant provisions of the Development Control Regulations :-

no further area shall be required to be kept as amenity space under Regulation 5(ii) for the Scheme if the area prescribed to be kept as amenity space while permitting residential user in Industrial zone is equal to or more than 10% of the gross plot area.

only the balance area shall be required to be kept as amenity space under Regulation 5(ii) for the Scheme if the area of amenity space prescribed by the Planning Authority, while permitting residential user in Industrial zone, falls short of 10%.

- (iii) Notwithstanding anything contained in the relevant provisions of the Development Control Regulations of Amenity Space in general, and also regarding permitting Residential User in Industrial Zone, it shall be obligatory on the Developer / Owner to develop the amenity space for users (hereinafter referred to as prescribed amenity users) such as School, Play Ground, Garden, Health Care Facilities, Multipurpose Hall, Auditorium, etc. with the approval of Chief Executive Officer of Special Planning Authority, as per the specifications prescribed by the said Authority, subject to the condition that at least 50% of such amenity space shall be kept for open users, before seeking Occupancy Certificate for the Free Sale Housing Component of the Scheme, failing which the land under such amenity space shall be handed over free of cost to the Planning Authority and such land shall be developed by the Chief Executive Officer of Special Planning Authority for the aforesaid prescribed amenity users only.

No compensation in the form of TDR shall be admissible to the Owner / Developer for development of such prescribed amenities under this Regulation.

- (iv) Irrespective of whether the Owner / Developer develops the prescribed amenity users as per the provision of Clause (iii) above or fails to do so, the process of handing over the land under such amenity space, along with the developed prescribed amenities, where such prescribed amenities have been developed, shall be completed within one month from the date of application by the Developer / Owner for seeking Occupancy Certificate for the free sale Housing Component of the Scheme and if such handing over process is not completed within the said period, the occupancy Certificate for the free sale Housing Component of the Scheme shall be withheld by the Chief Executive Officer of Special Planning Authority, till such amenity space, along with developed prescribed amenities, where such prescribed amenities have been developed, is handed over to the Planning Authority.
- (v) Under the Affordable Housing Scheme, there shall be a welfare hall and a Balwadi at the rate of 30 sq.m. for every multiple or part of 200 residential units and an office for Managers / Co-operative Housing Society at the rate of 30 sq.m. per every multiple or part of 500 residential units which shall be treated as a part of Affordable Housing Component and shall not be counted towards the FSI while computing 3.00 FSI on the site and shall be given along with layout / DP roads and shops, free of cost to the Special Planning Authority for Bhiwandi Surrounding Notified Area. These facilities shall be constructed at locations as suggested by the Special Planning Authority for Bhiwandi Surrounding Notified Area and shall be transferred free of cost to it.
6. Under the Affordable Housing Scheme, Off-Site Infrastructure Charges at the rate of 5% of the land rate as given in the Annual Statement of Rates (ASR) prepared by the Inspector General of Registration, Maharashtra State, for the year in which Commencement Certificate is issued, subject to a minimum of Rs.2000 per sq.m., shall be paid by the Developer for the built up area, over and above the normal permissible FSI. This amount shall be paid to the Special Planning Authority for Bhiwandi Surrounding Notified Area.
7. Release of FSI under the Scheme shall be as follows :-

FSI for Affordable Housing Component and the Free Sale Housing Component under the Scheme shall be released in accordance with the following Table :-

Sr. No.	Stages of Release FSI	Affordable Housing Component*	Free Sale Component*
1	On Grant of Building Permission / Commencement Certificate up to plinth by 1.1-L-B Special Planning Authority for Bhiwandi	3.00	1.00

	Surrounding Notified Area / Planning Authority to the Affordable Housing Project.		
2	On Completion of 50% BUA of Affordable Component	-	0.75
3	On Completion of 100% BUA of Affordable Component	-	0.75
4	On handing over of 25% land and completed Affordable Housing Component buildings with Occupancy Certificate	-	0.50
	Total	3.00*	3.00*

* **Explanation** - The FSI of 3.00 is to be calculated on the one-fourth of plot area for Affordable Housing Component as well as three-fourth of plot area for Free-Sale Housing Component.

8. The Affordable Housing Component under the Scheme shall be handed over alongwith the 1/4th part of the total plot of land, free of cost to the Special Planning Authority for Bhiwandi Surrounding Notified Area.
9. (i) The affordable Housing stock created under the Scheme shall be allotted by the Special Planning Authority for Bhiwandi Surrounding Notified Area as follows :-

Percent-age	Allotment to	Category of Stock	Rate of Allotment
25	Special Planning Authority for Bhiwandi Surrounding Notified Area for use as PAP tenements or Staff Quarters or Transit Accommodation,	Ownership	Free of Cost
25	Outright sale to Govt. of Maharashtra and its statutory bodies / Govt. undertakings for use as PAP tenements or staff quarters or Transit Accommodation.	Ownership	As per Construction rate of ASR
50	Outright sale as affordable housing by MHADA subject to the general or specific directions of the Government.	Ownership	Free of Cost to MHADA which shall dispose of the same as per its pricing policy and by draw of lots.

- (ii) The Affordable Housing stock shall be disposed of as per the prevailing policy of MHADA regarding pricing and disposal of its housing Stock meant for affordable housing. Each Project approved under the Scheme Shall be brought to the notice of the Government of Maharashtra and its statutory bodies / Government undertakings by means of Press Advertisement and if the Government of Maharashtra or any of its statutory bodies / Government Undertakings doesn't place firm requirement for the housing stock earmarked for them in the Scheme before the Completion Certificate / Occupation Certificate for the said Scheme is issued, the same shall come to the share of MHADA for outright sale as per the Prevailing Policy of the MHADA.
- 10.(i) The other aspects of the Development of Affordable Housing Scheme, not specifically dealt with hereinabove, shall be as per the relevant provisions of the Development Control Regulations of the respective Planning Authority.
- (ii) It shall also be permissible for the Developer / Owner to utilize the FSI available for Free Sale Housing Component, fully / partly for any other user otherwise permissible as per Development Plan and Development Control Regulations.

(iii) In case owing to genuine hardship and site conditions, relaxation in marginal open spaces is sought by the Developer / Owner, the Chief Executive Officer of Special Planning Authority may consider such request, using his discretionary powers under the Development Control Regulations, subject to the condition that in no case shall the clear marginal open space reduced below 6.0 m. No premium shall be charged for granting such relaxation in marginal open space in respect of Affordable Housing Component of the Scheme.

^(#) 11. No project under the Rental Housing Scheme envisaged under the said directives issued by the Government vide orders dated 6th August, 2008, 25th August, 2009, 4th November, 2008 and August 2008 shall be permitted after the date on which the Notice No.TPS-1212/79/CR-60/12/ UD-12, Dated 30th November, 2013 regarding this Regulation Under section 37(1AA) of the Maharashtra Regional and Town Planning Act, 1966 was published in the official (herein after referred to as 'the cut date')

Provided that the Rental Housing Projects in respect of which Location Clearance had been granted by MMRDA, but Commencement Certificate has not been issued by the concerned planning Authority, shall be allowed to continue, as such, in case such project proposals are resubmitted to MMRDA within a period of 31 days from the date of this Notification in the Official Gazette. All such project proposals received by MMRDA within the prescribed time limit shall be scrutinized by MMRDA on merit and to be submitted for the prior approval of the State Government for their continuance under the Rental Housing Scheme.

Provided further that the Rental Housing Projects already approved may be allowed to be converted into Affordable Housing Projects under the provisions of this Regulation, with prior approval of the State Government.

10.14 CIDCO AREA EXCLUDING NAINA AREA

10.14.1 The Regulations No.10.10.1, 10.10.2, 10.10.3, ⁽¹⁾10.10.4, 10.10.5 and 10.10.6 shall be applicable to CIDCO area.

10.14.2 Regulations for Land Compensation Scheme and Rehabilitation Pocket in Navi Mumbai

(i) Land Compensation Scheme and Rehabilitation Pocket: Land Compensation Scheme means the Scheme devised by City and Industrial Development Corporation of Maharashtra Ltd. (CIDCO) with the approval of State Government vide Government Resolution CID-1812/C.R.274/UD-10, dated 1/3/2014 and as amended from time to time for compensating the land holders whose lands are being acquired on or after 1st March, 2014, The Rehabilitation Pocket means the land identified by CIDCO for allotment under land compensation scheme. The compensation under Scheme shall have three components.

- a) Component - I : involving allotment of 10% developed land in lieu of monetary compensation after deduction of 30% of the eligible area for the development of infrastructure and amenities. Maximum 15% FSI may be used for commercial use provided that such commercial use shall be permissible as per provisions of UDCPR.
- b) Component - II : involving allotment of 12.5% developed land in lieu of monetary compensation after deduction of 30% of the eligible area for the development of infrastructure and amenities. Maximum 15% FSI may be used for commercial use provided that such commercial use shall be permissible as per provisions of UDCPR.
- c) Component - III : involving allotment of developed plot to the eligible owner of the house whose house and land under house are being acquired and resettled at another location Maximum 15% FSI may be used for commercial use provided that such commercial use shall be permissible as per provisions of UDCPR.

⁽¹⁾ Inserted vide Notification u/s.37(1AA)(c) No.CR.236/18 (Part 6), dt.12th October, 2022

^(#) Clarification issued by the Govt. vide letter dt.13th January, 2023

(ii) Floor Space Index admissible on lands allotted under the scheme shall be as follows :

- a) Component - I : Floor Space Index for the development of lands allotted under Component - I shall be 2.5.
- b) Component - II : Floor Space Index for the development of land allotted under Component - II shall be 1.5.
- c) Floor Space Index for the development of total land allotted under Component - I and Component - II that is 22.5% shall be 2.0.
- d) Component - III : Floor Space Index for the development of land allotted under Component - III shall be 1.5.
- e) The base FSI of the lands within Pushpak Node as described by CIDCO shall be 2.0 irrespective of the land use and the maximum permissible FSI shall be 2.5. Provided that with the previous approval of V.C. & M.D., CIDCO, this additional 0.5 FSI may be granted for utilization on these plots subject to payment of additional premium as may be decided by the Corporation.

Alternatively, with the previous approval of V.C. & M.D., CIDCO, additional FSI 0.5 in the form of DRC shall be allowed on lands within the Pushpak Node only over and above the base FSI of 2.0. However, while granting such additional 0.5 FSI V.C. & M.D., CIDCO shall give priority to grant of such additional FSI in the form of DRC.

- ⁽²⁾ (f) The basic FSI for the lands allotted to project affected person by the JNPT in any area, defined and made available by the JNPT under 12.5 % scheme, shall be 2.0. All the aspects of development shall be governed by these regulations.

Provided that -

- A Maximum FSI 2.0 shall be admissible for plots having an area equal to or in excess of 1000 sq.m., however in case, the available FSI cannot be used at site due to hardship of height restriction and for any other reasons recorded in writing in Pushpak Node, floating of TDR shall be allowed and such TDR shall be used within Pushpak Node only with the approval of V.C. & M.D.
- B FSI 1.5 shall be admissible for plot having area less than 1000 sq.m. and the balance 0.5 or 1.0 FSI, as may be applicable, shall be admissible for utilization in the form of Development Right Certificate (DRC) as a Transferable Development Right (TDR), the utilization of which shall be within Pushpak Node only.

(iii) Locations for utilization of DRC –

DRC in the form of TDR shall be eligible for utilization in the following locations.

- a) Pushpak Node as shown on the plan with CIDCO.

(iv) Extent of Utilization of DRC :

The utilization of DRC within Pushpak node only shall be permitted is as follows :

Road width	Maximum Permissible Utilization of TDR in addition to basic FSI under these regulations.
Equal to or above 20.0 mtr and along the service road in Pushpak node	Upto 0.5 FSI on receiving plot.

⁽²⁾ 10.14.3 Development of land Notified for Acquisition

- i) In case of land notified for acquisition under the Land Acquisition Act, 1894 or The Right to Fair Compensation and Transparency in Land Acquisition, Rehabilitation and Resettlement Act, 2013 and where the land has not been acquired, the CIDCO may in its absolute discretion to grant permission for temporary development.

⁽²⁾ Inserted vide Notification u/s.37(1AA)(c) No.CR.236/18 (Part 6), dt.12th October, 2022

- (2) Provided that the period of such temporary development shall not exceed 1 year and provided further that the applicant shall undertake to remove the so executed on or before the date specified by the CIDCO.
- ii) Temporary Development shall be permissible as per uses permissible in respective zones as per UDCPR.
- iii) The permission may be renewed from time to time at the discretion of the CIDCO.
- iv) Security Deposit :-
- The applicant shall deposit and keep deposited an amount as Security Deposit at the rate of Rs.10/- per Sq.m. of the floor area of the proposed development for the due performance of the conditions of the permission granted under the Commencement Certificate.
 - The amount shall be refunded, without interest; after the removal of the development with due compliance with the conditions of the Commencement Certificate.
 - The Security Deposit shall be forfeited either in whole or in part at the discretion of the CIDCO, for breach of any of the provisions of these regulations and conditions attached to the permission covered under the Commencement Certificate.
- v) The development permission may be granted at the discretion of the CIDCO with following conditions of the Commencement Certificate.
- The applicant shall remove all the development on land when directed by the CIDCO.
 - The applicant shall neither be entitled for any compensation for the removal of the development nor for any alternative land.
 - The applicant if he desires may apply in writing for renewal of the permission.

10.14 A CIDCO AREA WITHIN PANVEL MUNICIPAL CORPORATION

10.14 A.1 The Regulations No.10.10.1, 10.10.2, 10.10.3, 10.10.5 and 10.10.6 shall be applicable to CIDCO area within Panvel Municipal Corporation.

10.15 CERTAIN REGULATIONS CEASE TO OPERATE IN FUTURE

The Regulation No. *10.1.1, 10.3.1, 10.3.2, 10.3.4, ⁽¹⁾ (--), ⁽²⁾ (--) shall cease to operate on 1st Jan, 2022 or as decided by the Government from time to time and thereafter provisions of these regulations shall apply.

(3) 10.16 (3) AREA WITHIN PANVEL MUNICIPAL CORPORATION

⁽⁴⁾ In area of Panvel Municipal Corporation, 75% of the total permissible TDR component as mentioned in Coloum 5 of the Table 6-G in the Regulation No.6.3, may be utilised on payment of premium at the rate of 60% land rate mentioned in the Annual Statement of Rates subject to following condition. Balance 25% to be utilised in the form of TDR only.

Condition :- This provision shall only be applicable till the sanction of the Development Plan of Panvel Municipal Corporation under section 31(1) of the Maharashtra Regional and Town Planning Act, 1966.

_*_*_*_*_*_

⁽¹⁾ The "10.4.1" is deleted vide Corrigendum / Addendum No.CR.121/21, dt.02nd December, 2021

⁽²⁾ Inserted & ⁽²⁾ Deleted vide Notification u/s.37(1AA)(c) No.CR.236/18 (Part 6), dt.12th October, 2022

⁽³⁾ Inserted vide Notification u/s.37(1AA)(c) bearing No.CR.15/24/UD-12, dt.07th October, 2024

* Modification proposed u/s 37(1AA) vide Notice No. CR 42/2023/UD-13, dt. 04/01/2024 brought into force u/s 154, stayed by UDD vide letter dt. 03/04/2024.

CHAPTER - 11

ACQUISITION AND DEVELOPMENT OF RESERVED SITES IN DEVELOPMENT PLANS

11.0 GENERAL

These regulations shall be applicable for the areas within the jurisdiction of planning authorities, unless otherwise specified.

11.1 Manner of Development of Reserved Site in Development Plan (Accommodation Reservation Principle)

The use of lands situated within the limits of Planning Authority which have been reserved for certain purpose in the Development Plan, shall be regulated in regard to type and manner of development / redevelopment according to the provisions mentioned in following Table No.11-A.

When owner is allowed to develop a reservation, he should have exclusive ownership/ title of the land without any restriction under any other Act or Regulations in force.

Table No.11-A - Manner of Development		
Reservation	Person / Authority who may acquire/ develop	Principle For Development through Accommodation Reservation subject to which development is permissible
1	2	3
1) Recreational -		
1.1) Open reservations like Garden, Play Ground, Children PG, Open Space, Recreation Ground, Recreational Centre, Park etc.	Planning Authority / Appropriate Authority / Owner	Planning Authority may acquire the land and develop the same for the purpose. If the Land under reservation is owned by any Government agency / Authority, in such cases the Planning Authority may allow such Government agency/ Authority to Develop full reservation for the said purpose subject to condition as may be decided by the Authority and such Developed Amenity shall be open to the general Public. OR The Authority, after handing over of 70% of the land of the reservation to the planning authority by the owner ⁽¹⁾ free of cost and free from all encumbrances, may allow him to develop remaining 30% of land as per adjoining use, subject to following terms / conditions :-

⁽¹⁾ Substituted vide Corrigendum / Addendum No.CR.121/21, dt.02nd December, 2021

		i) The owner shall be entitled to develop remaining 30% land for the uses permissible in adjoining zone with full permissible FSI of the entire Plot and permissible TDR potential of the entire Plot. ii) The Authority, if required, shall allow the TDR for the unutilized FSI, if any (after deducting in-situ FSI as mentioned in Sr.No.(i) above), to be utilised as per TDR Regulations. iii) The reservation shall be allowed to be developed in parts. However, it shall be ensured that Garden and Play Ground area to be handed over to Authority shall be minimum 1000 sq.m.
1.2) Stadium, Sport Complex, etc.	Planning Authority / Appropriate Authority	Planning Authority / Appropriate Authority shall acquire the land and develop the same for the purpose.
1.3) Swimming Tank / Swimming Pool	Planning Authority / Appropriate Authority / Owner	The Planning Authority / Appropriate Authority may acquire and develop the site for the same purpose. OR The Planning Authority / Appropriate Authority after acquiring the land or after acquiring and developing the same, as the case may be, lease out as per the provisions of the Municipal Councils / Municipal Corporations / Authority Act, to the Registered Public Institution for developing and running or only for running the same. OR The Owner may be allowed to develop according to the designs; specifications and conditions prescribed by the Authority and run the same.
2) Public Utilities		
a) Cremation Ground, b) Burial Ground, c) Slaughter House, d) Sewerage Treatment Plant, e) Water Treatment Plant, f) Water Tank	Planning Authority / Appropriate Authority	The Planning Authority / Appropriate Authority shall acquire the land and develop the reservation for the same purpose.

3) Commercial		
3.1) Market and Mandies - a) Weekly Market b) Vegetable Market c) Open Market. d) Hawkers Market 3.2) Shopping centres a) Shopping Centre, b) Commercial Complex, c) District Commercial Centre, d) Municipal Market e) Fish Market f) District Commercial (C-2) etc.	Planning Authority / Appropriate Authority / Owner	The Planning Authority / Appropriate Authority shall acquire the land and develop the reservation for the same purpose. OR i) The Authority may allow the owner to develop the reservation, subject to handing over to the Planning Authority an independent plot along with constructed amenity of total area, mentioned in Note - 1 below this table & as per norms prescribed by the Authority. ii) The owner shall be entitled to develop remaining land for the uses permissible in adjoining zone with full permissible FSI of the entire Plot and permissible TDR potential of the entire Plot. iii) The Authority, if required, shall allow the TDR for the unutilized FSI, if any (after deducting in-situ FSI), to be utilised as per TDR Regulations. iv) Reservation may be allowed to be developed in parts.
4) Health Facility		
a) Health Centre b) Hospital c) Dispensary d) Maternity Home e) Veterinary Hospital / Clinic f) Urban Health Centre g) Rural Hospital and like	Planning Authority / Appropriate Authority / Owner	The Planning Authority / Appropriate Authority may acquire and develop the reservation site for the same purpose. OR The owner may be allowed to develop entire reservation for the intended purpose only. OR i) The Authority may allow the owner to develop the reservation, subject to handing over to the Planning Authority an independent plot along with constructed amenity of total area, mentioned in Note -1 below this table & as per norms prescribed by the Authority. ii) The owner shall be entitled to develop remaining land for the uses permissible in adjoining zone with full permissible FSI of the entire Plot and permissible TDR potential of the entire Plot.

		iii) The Authority, if required, shall allow the TDR for the unutilized FSI, if any (after deducting in-situ FSI), to be utilised as per TDR Regulations. iv) Reservation may be allowed to be developed in parts.
5) Transportation		
5.1) Depots and Stands a) Bus Stand b) Bus Depot etc. c) Metro Car Shed d) MRTS Station	Planning Authority / Appropriate Authority / Owner	The Planning Authority / Appropriate Authority may acquire and develop the reservation site for the same purpose. OR The owner may be allowed to develop entire reservation for the intended purpose. OR i) The Authority may allow the owner to develop the reservation, subject to handing over to the Planning Authority an independent plot along with constructed amenity of total area, mentioned in Note-1 below this table & as per norms prescribed by the Authority. The Authority shall ensure that constructed amenity to be handed over is of proper size and utilisable for the said use. ii) The owner shall be entitled to develop remaining land for the uses permissible in adjoining zone with full permissible FSI of the entire Plot and permissible TDR potential of the entire Plot. iii) The Authority if required, shall allow the TDR for the unutilized FSI, if any (after deducting in-situ FSI), to be utilised as per TDR Regulations. iv) In case of Bus Stand/ Bus Depot, atleast 40% of the area shall be kept for parking/ movement of buses. v) Reservation may be allowed to be developed in parts.
5.2) Roads Proposed	Planning Authority / Appropriate Authority / Owner	The Planning Authority / Appropriate Authority shall acquire the land and develop the reservation for the same purpose. OR The Authority may allow the owner to develop the new Development Plan road,

		along with the construction of road as per the specifications given by the Authority. After handing over the said constructed road along with the land under proposed road to the Authority, the owner shall be entitled for TDR and Amenity TDR. The cost incurred for construction of road shall be calculated on the basis of District Schedule of Rates of Public Works Department.
5.3) Parking	Planning Authority / Appropriate Authority / Owner	The Planning Authority / Appropriate Authority may acquire and develop the site for the same purpose. OR The Planning Authority / Appropriate Authority after acquiring the land or after acquiring and developing the same, as the case may be, lease out as per the provisions of the Municipal Corporations Act, to the Registered Public Institution for developing and running or only for running the same. OR The owner may be allowed to develop entire reservation for public parking and he shall maintain it for public parking forever. Agreement to that effect shall be executed with the Authority by the owner. OR The Owner may be allowed to develop area of the reservation, subject to following :- - The owner shall develop parking space according to the designs, specifications and conditions prescribed by the Authority and handover the constructed parking area equal to the reservation area, to Authority. - The operation and the maintenance of the facility will be decided by the Authority. - Parking spaces may be in basement or on stilts or on first / second floor with separate entry & exit. - After handing over the above said parking area to the Planning Authority, the owner shall be entitled to construct with full permissible FSI of the entire Plot and permissible TDR potential of

		the entire Plot for other permissible user in that zone. v) The Authority, if required, shall allow the TDR for the unutilized FSI, if any (after deducting in-situ FSI), to be utilised as TDR Regulations. ⁽¹⁾ vi) Reservation may be allowed to be developed in parts, if the area under such part reservation is 50% or more, out of total area of reservation.
5.4) Truck Terminus or similar	Planning Authority / Appropriate Authority / Owner	The Planning Authority / Appropriate Authority may acquire and develop the reservation site for the same purpose. OR The owner may be allowed to develop entire reservation for the intended purpose. OR i) The Authority may allow the owner to develop the reservation, subject to handing over to the Planning Authority an independent plot along with constructed amenity of total area, mentioned in note-1 below this table & as per norms prescribed by the Authority. ii) The owner shall be entitled to develop remaining land for the uses permissible in adjoining zone with full permissible FSI of the entire Plot and permissible TDR potential of the entire Plot. iii) The Authority, if required, shall allow the TDR for the unutilized FSI, if any (after deducting in-situ FSI), to be utilised as per TDR Regulations. iv) Reservation may be allowed to be developed in parts.
6) Educational		
(a) Primary School (b) High School (c) College	Planning Authority / Appropriate Authority / Registered Educational Institution Trust / Owner	The Planning Authority / Appropriate Authority may acquire and develop the site for the same purpose. OR The Planning Authority / Appropriate Authority after acquiring land or after acquiring and constructing the building on it, as the case may be, lease out the same as

⁽¹⁾ Inserted vide Corrigendum / Addendum No.CR.121/21, dt.02nd December, 2021

		per the provisions of the Municipal Councils / Municipal Corporations / Authority Act, to the Registered Public Educational Institution trust for developing and running or only for running the same. OR The owner may be allowed to develop the reservation for the same purpose. The Registered Public Educational Institution trust on behalf of owner may also be allowed to develop subject to terms / conditions as prescribed by the Authority. OR i) The Authority may allow the owner to develop the reservation, subject to handing over to the Authority an independent plot along with constructed amenity of total area, mentioned in Note-1 below this table & as per norms prescribed by the Authority. ii) The owner shall be entitled to develop remaining land for the uses permissible in adjoining zone with full permissible FSI of the entire Plot and permissible TDR potential of the entire Plot. iii) The Authority, if required, shall allow the TDR for the unutilized FSI, if any (after deducting in-situ FSI) to be utilised as per TDR Regulations. iv) Reservation may be allowed to be developed in parts. However, it shall be ensured that school or college of proper size is constructed. It shall be ensured that Primary School and High School area to be handed over to Authority shall be minimum 2000 sq.m.
(c) Educational Complex	Planning Authority / Appropriate Authority / Land Owner	The Planning Authority / Appropriate Authority may acquire and develop the site for the same purpose. OR The Planning Authority / Appropriate Authority after acquiring land or after acquiring and constructing the building on it, as the case may be, lease out the same as per the provisions of the Municipal Corporations Act, to the Registered Public Educational Institution Trust for developing

		and running or only for running the same. OR The owner may be allowed to develop the reservation for the same purpose. The Registered Public Educational Institution trust on behalf of owner may also be allowed to develop subject to terms / conditions as prescribed by the Authority. OR If the area of the Educational Complex reservation is more than 1.00 Ha. then, i) The Authority may allow the owner to develop the reservation, subject to handing over to the Planning Authority an independent plot along with constructed amenity of total area, mentioned in Note-1 below this table & as per norms prescribed by the Authority. ii) The owner shall be entitled to develop remaining land for the uses permissible in adjoining zone with full permissible FSI of the entire Plot and permissible TDR potential of the entire Plot. iii) The Authority, if required, shall allow the TDR for the unutilized FSI, if any (after deducting in-situ FSI), to be utilised as per TDR Regulations. iv) Reservation may be allowed to be developed in parts.
7) Residential		
a) Public Housing / EWS / LIG Housing. b) High Density Housing. c) Housing for Dis-housed. d) Reservation similar as above.	Planning Authority / Appropriate Authority / Owner	Planning Authority / Appropriate Authority may acquire the reserved land and develop for the same purpose. OR i) The Authority may allow the owner to develop the reservation, subject to handing over to the Planning Authority an independent plot along with constructed tenements of not more than 30 sq.m. carpet area each to the Authority, mentioned in Note-1 below this table & as per norms prescribed by the Authority. ii) The owner shall be entitled to develop remaining land for the uses permissible in adjoining zone with full permissible FSI of the entire Plot and permissible TDR potential of the entire Plot.

		iii) The Authority, if required, shall allow the TDR for the unutilized FSI, if any (after deducting in-situ FSI), to be utilised as per TDR Regulations. iv) The Planning Authority / Appropriate Authority shall allot such tenement on priority to the persons dispossessed by implementation of Development Plan. v) Reservation may be allowed to be developed in parts. OR The Authority may allow the owner to develop the reservation, subject to - a) Handing over of 40% land to Authority in lieu of FSI / TDR, for laying out plots for EWS / LIG. The owner shall thereafter be entitled to develop remaining plot as per the uses permissible in residential zone with permissible FSI / TDR potential of entire plot on remaining plot without taking into account the area handed over to the Planning Authority. b) The Planning Authority / Appropriate Authority shall prepare layout for EWS / LIG plots and allot such plots on priority to the persons dispossessed by implementation of Development Plan. The Planning Authority may construct EWS / LIG tenements on such land.
8) Assembly and Institutional		
a) Town Hall, b) Drama Theatre, c) Auditorium, d) Samaj Mandir, e) Community Hall, f) Multipurpose Hall, g) Library h) Town Centre, i) Town Sub-Centre etc.	Planning Authority / Appropriate Authority / Owner	The Planning Authority / Appropriate Authority may acquire and develop the site for the same purpose. OR The Planning Authority / Appropriate Authority after acquiring the land or after acquiring and developing the same, as the case may be, lease out as per the provisions of the Authorities' Act to a Registered Public Institution to develop and running or only for running the same. OR The owner may be allowed to develop entire reservation for the intended purpose only. OR

		i) The Authority may allow the owner to develop the reservation, subject to handing over to the Planning Authority an independent plot along with constructed amenity of total area, mentioned in Note-1 below this table & as per norms prescribed by the Authority. ii) The owner shall be entitled to develop remaining land for the uses permissible in adjoining zone with full permissible FSI of the entire Plot and permissible TDR potential of the entire Plot. iii) The Authority, if required, shall allow the TDR for the unutilized FSI, if any (after deducting in-situ FSI), to be utilised as per TDR Regulations. iv) Reservation may be allowed to be developed in parts.
9) Public-Semi public		
a) Govt. Offices b) Fire Brigade Station c) Reservations similar to above.	Planning Authority / Appropriate Authority / Owner	The Planning Authority / Appropriate Authority may acquire and develop the reservation site for the same purpose. OR i) The Authority may allow the owner to develop the reservation, subject to handing over to the Planning Authority independent plot along with constructed amenity of total area, mentioned in Note - 1 below Table & as per norms prescribed by the Authority. ii) The owner shall be entitled to develop remaining land for the uses permissible in adjoining zone with full permissible FSI of the entire Plot and permissible TDR potential of the entire Plot. iii) The Authority, if required, shall allow the TDR for the unutilized FSI, if any (after deducting in-situ FSI), to be utilised as per TDR Regulations. iv) Reservation may be allowed to be developed in parts.
10) Reservations of composite nature like Vegetable Market & Shopping Centre, Town Hall & Library, etc.	Planning Authority / Appropriate Authority / Owner	The Planning Authority / Appropriate Authority may acquire and develop the site for the same purpose. Explanation - For the reservation of composite nature, proposed in Development Plan except Town Hall & Library, area of

		each user shall be considered equal i.e. 50 - 50% and for Town Hall & Library, area of Library shall be 10% of area of Town Hall and such area shall be allowed to be developed as per the norms applicable for such reservation as mentioned in these regulations.
11) Reservations which are not included in these regulations but are compatible to other similar type of reservation.	Planning Authority / Appropriate Authority / Owner	Planning Authority / Appropriate Authority may acquire the reserved land and develop for the same purpose. OR The development permissions for such type of user under this Regulation may be granted by the Authority in consultation with the Divisional Joint Director of Town Planning, subject to verification of compatibility of both the users and as per the norms applicable for such reservation as mentioned in these regulations.
12) For other buildable reservations shown in Development Plan which are not covered above	Planning Authority / Appropriate Authority / Owner.	The Planning Authority / Appropriate Authority may acquire and develop the reservation site for the same purpose. OR i) The Authority may allow the owner to develop the reservation, subject to handing over to the Planning Authority an independent plot along with constructed amenity of total area, mentioned in Note - 1 below this table & as per norms prescribed by the Authority. ii) The owner shall be entitled to develop remaining land for the uses permissible in adjoining zone with full permissible FSI of the entire Plot and permissible TDR potential of the entire Plot. iii) The Authority, if required, shall allow the TDR for the unutilized FSI, if any (after deducting in-situ FSI), to be utilised as per TDR Regulations. iv) Reservation may be allowed to be developed in parts.
13) Reservations for the Appropriate Authority other than Planning Authority	Planning Authority / Appropriate Authority / Owner	Planning Authority / Appropriate Authority may acquire the reserved land and develop for the same purpose. OR

		The Authority may allow the owner to Develop the reservation subject to condition that; i) Wherever the reservation is to be developed by the Appropriate Authority other than Municipal Corporation, No Objection Certificate from the Appropriate Authority shall be obtained before granting development permission. ii) The concerned Appropriate Authority (other than the State Government Department) shall deposit cost of construction for the built- up area to be handed over to it, as per Annual Statement of Rates with the Planning Authority. However, the Authority shall handover such constructed area to the State Government / concerned State Government Department free of cost.

General conditions / notes to allow development under above regulations :-

- i) The percentage of land and construction of amenity to be surrendered to the Authority as per above mentioned regulations for various authorities, shall be as below :-

Sr. No. of above Table	Reservation	Type of Authority	Percentage of total land to be surrendered free of cost & free from encumbrances	Percentage of constructed amenity of the total land area to be surrendered free of cost & free from encumbrances
1	2	3	4	5
3	Commercial	A, B, C Class Municipal Corporations and Development Authorities	40	50
4	Health Facility			
5	Transportation			
7	Residential	D Class Municipal Corporations & A Class Municipal Councils.	40	25
8	Assembly & Institutional			
9	Public-Semi public	B & C Class Municipal Councils and Nagar Panchayats.	30	20
12	Other Buildable Reservations			
5.4	Truck Terminus or Similar	A, B, C Class Municipal Corporations and Development Authorities.	40	10
		D Class Municipal Corporations & A Class Municipal Councils.	30	7

		B & C Class Municipal Councils and Nagar Panchayats	20	5
5.1	Bus Stand	A, B, C Class Municipal Corporations and Development Authorities	50	20
		D Class Municipal Corporations & A Class Municipal Councils	40	15
		B & C Class Municipal Councils and Nagar Panchayats	40	10
6	Education	A, B, C Class Municipal Corporations and Development Authorities	40	50
		D Class Municipal Corporations & A Class Municipal Councils	40	40
		B & C Class Municipal Councils and Nagar Panchayats	40	30

- ii) The owner shall be entitled for Amenity TDR against the construction of amenity, if any, as per TDR Regulation.
- iii) The word 'Authority' means Municipal Commissioner of Municipal Corporation, Chief Officer of Municipal Council, Metropolitan Commissioner of Metropolitan Development Authority or Chief Executive Officer of the concerned Authority.
- iv) If the area of reservation is not adequate to construct independent building as mentioned above OR When it is not possible to handover individual plot along with public amenity, then in such cases Authority may allow composite building on said land subject to condition that the built up area mentioned as above may be allowed to be handed over to the Planning Authority or Appropriate Authority, as the case may be, preferably on ground floor and subject to payment of premium ⁽¹⁾ for the land required to be handed over to Authority at the rate of 40% of land rate in ASR, without considering the guidelines therein. If ground floor is utilised for parking, then such built up area shall be given on stilt / first floor with separate entry & exit from Public Street. In such cases, built-up area (along with proportionate undivided share in land) shall be handed over to the Planning Authority or Appropriate Authority, as the case may be.
- v) In case of development of reservation of Bus Stand at Sr.No.5.1, the construction area for allied activities and uses permissible in Residential Zone may be allowed to be constructed up to FSI of 2.00 of the surrendered plot with the consent of owner. In such cases, the owner shall be entitled for amenity TDR to that extent. If the plot along with construction is handed over to MSRTC, the regulations applicable to the plot owned by MSRTC shall be applicable to the said plot.

⁽¹⁾ Inserted vide Corrigendum / Addendum No.CR.121/21, dt.02nd December, 2021

- vi) If owner desires to construct area of amenity more than what is mentioned above table ⁽ⁱ⁾ upto maximum building potential as per Regulation No.6.1, Table 6-A or Regulation No.6.3, Table 6-G, as the case may be, with the consent of the authority, then he shall be entitled for amenity TDR to that extent.
- vii) It shall be obligatory on the Authority to make registered agreement with the developer / owner at the time of granting the development permission subject to terms and conditions as it deem fit. Occupancy Certificate shall be issued only after compliance of all terms & conditions and getting possession of the constructed amenity.
- viii) The area / built-up area to be handed over to the Planning Authority under these Regulations shall be earmarked on the sanctioned building plan clearly mentioning the same. After completion of construction, the said amenity shall be handed over by executing the deed of transfer in this respect and expenses thereon shall be borne by the owner. The occupation certificate to the construction belonging to owner shall be granted only after handing over said amenity to the Planning Authority. The constructed amenity shall be made available to the general public by the Authority within 3 month from possession.
- ix) In cases, where permission for development under accommodation reservation principle is already granted as per earlier regulations, the same shall continue to be valid till completion of construction.
- x) Provisions of Regulations of Inclusive Housing, Amenity Space, if any, shall not be applicable for development under this Regulation. Moreover Regulation of required recreational open space shall not be applicable for development of reservation other than Residential purpose as mentioned at Sr.No.7.
- xi) Notwithstanding anything contained in these regulations, there shall be no cap for utilization of available in-situ FSI / and ⁽ⁱ⁾ Premium FSI and TDR potential of the entire plot on the remaining plot.
- xii) Once sanction is granted under this regulation, the owner / developer shall have to complete the development and hand over the developed reservation to the Authority within the period as specified by Authority. Thereafter Authority may levy penalty for any delay.
- xiii) The development permissions granted under the provisions of Accommodation Reservation provisions and full & final occupation certificate is issued, in such cases the portion / location designated for respective reservation is continued to be in said reservation and rest of land on which residential / commercial development permission is granted is deemed to be converted into residential / commercial zone to the extent of that area.
- xiv) Where appropriate authority for development of reservation is other than the planning authority, then such appropriate authority may be consulted for usefulness of the constructed amenity to be handed over, before granting the development permission.
- xv) In case of Nagpur Municipal Corporation, for development of commercial reservation at Sr.No.3 of Table No.11-A, FSI permissible for development of reservation shall be as per Regulation No.10.3.1. In such case the construction area to be handed over to the authority shall be 1.5 times of the plot area to be handed over and the owner shall be entitled to utilise entire potential of reserved plot as per Regulation No.10.3.1.
- xvi) This regulation shall not be applicable for development of amenity space to be provided as per Regulation No.3.5 and Regulation No.4.8.1.
- xvii) The norms mentioned above in note ⁽ⁱ⁾ (i) for B and C class Municipal Councils, shall be applicable to non-Municipal Town Development Plan also.

⁽ⁱ⁾ Inserted vide Corrigendum / Addendum No.CR.121/21, dt.02nd December, 2021

11.2 REGULATIONS FOR GRANT OF TRANSFERABLE DEVELOPMENT RIGHTS

11.2.1 Transferable Development Rights

Transferable Development Rights (TDR) is compensation in the form of Floor Space Index (FSI) or Development Rights which shall entitle the owner for construction of built-up area subject to provisions in this regulation. This FSI credit shall be issued in a certificate which shall be called as Development Right Certificate (DRC).

Development Rights Certificate (DRC) shall be issued by Authority under his signature and endorse thereon in writing in figures and in words, the FSI credit in square meters of the built-up area to which the owner or lessee is entitled, the place from where it is generated and the rate of that plot as prescribed in the Annual Statement of Rates issued by the Registration Department for the concerned year. TDR generated within the jurisdiction of a particular Authority, shall be utilised within the jurisdiction of the same Authority as per this regulation.

11.2.2 Cases eligible for Transferable Development Rights (TDR)

Compensation in terms of Transferable Development Rights (TDR) shall be permissible for -

- i) lands under various reservations for public purposes, new roads, road widening etc. which are subjected to acquisition, proposed in Draft or Final Development Plan, prepared under the provisions of the Maharashtra Regional and Town Planning Act, 1966;
- ii) lands under any deemed reservations according to any regulations prepared as per the provisions of Maharashtra Regional & Town Planning Act, 1966;
- iii) lands under any new road or road widening proposed under the provisions of Maharashtra Municipal Corporation Act, Maharashtra Municipal Council, Nagar Panchayat and Industrial Township Act;
- iv) In case where layout is submitted along with proposed Development Plan Road, in such cases TDR shall be permissible for entire road width as per these regulations.
- v) development or construction of the amenity on the reserved or deemed reserved land;
- vi) unutilized FSI of any structure or precinct which is declared as Heritage structure or precinct under the provisions of Unified Development Control and Promotion Regulations, due to restrictions imposed in that regulation;
- vii) in lieu of constructing housing for slum-dwellers according to regulations prepared under the Maharashtra Regional & Town Planning Act, 1966;
- viii) for handing over land to the Authority for development of housing under PMAY by the Authority.

The purposes as may be notified by the Government from time to time.

11.2.3 Cases not eligible for Transferable Development Rights (TDR)

It shall not be permissible to grant Transferable Development Rights (TDR) in the following circumstances :-

- i) For earlier land acquisition or development for which compensation has been already paid partly or fully by any means;
- ii) Where award of land has already been declared and which is valid under the Acquisition Act or the Right to Fair Compensation & Transparency in Land Acquisition, Rehabilitation and Resettlement Act, 2013 unless lands are withdrawn from the award by the Appropriate Authority according to the provisions of the relevant Acts.
- iii) In cases where layout has already been sanctioned and layout roads are incorporated as Development Plan roads prior to these regulations.
- iv) If the compensation in the form of FSI / or by any means has already been granted to the owner.

- v) Where lawful possession including by mutual agreement / or contract has been taken and such agreement does not provide for TDR.
- vi) For an existing user or retention user or any required compulsory open space or recreational open space or recreational ground, in any layout.
- vii) For any designation, allocation of the use or zone which is not subjected to acquisition.
- viii) Existing nallah, river, natural stream, natural pond, tank, water bodies etc.
- ix) Reservations which are not developable under the provisions of UDCPR.
- x) For the lands owned by the State Government, ⁽²⁾ except Government land leased on long term for a nominal lease rent wherein remaining tenure of lease is more than 30 years.

11.2.4 Generation of the Transferable Development Rights (TDR)

Transferable Development Rights (TDR) against surrender of land :-

- a. For surrender of the gross area of the land which is subjected to acquisition, free of cost and free from all encumbrances, the owner shall be entitled for TDR or DR irrespective of the FSI permissible or development potential of such land to be surrendered and also that of land surrounding to such land at the rate given below :-

Area Designated on DP	Entitlement for TDR / DR
Non-Congested Area	2 times the area of surrendered land.
Congested Area	3 times the area of surrendered land.

Note :-

- i) The quantum of Transferable Development Rights (TDR) generated for reservation in area having total legal impediment / constraint on construction or development like CRZ / Hazardous zone / Low Density zone, shall be 50% of TDR generated as prescribed above.
- ii) The quantum of Transferable Development Rights (TDR) generated for Bio Diversity Park reservation shall be 8% of gross area.

(Explanation :- Above entitlement may also be applicable to the compensation paid in the form of FSI to the owner to be utilised on unaffected part of same land parcel and in such cases the procedure of DRC shall not be insisted.)

Provided that, if levelling of land and construction/erection of the compound wall / fencing as per Clause (b) below to the land under surrender is not desirable considering the total area of reservation, the quantum of TDR shall be reduced to 1 : 1.85 and 1 : 2.85 in non-congested area and congested area respectively. In such cases, the owner shall have also an option of paying the cost of construction of compound wall (as decided by the Authority) without reducing the quantum of TDR.

Provided further that such construction / erection of compound wall / fencing shall not be necessary for area under development plan roads. In such cases TDR equivalent to entitlement as mentioned above shall be granted without any reduction.

Provided also that Additional / incentive Transferable Development Rights (TDR) or Development Rights (DR) to the extent of 5% of the surrendered land area shall also be allowed to the land owners who submit the proposal for grant of Transferable Development Rights (TDR) of land reserved in the development plan, within 2 years from the sanction of these regulations.

Provided that the quantum of generation of TDR as prescribed above, shall not be applicable for TDR generated from construction of amenity or construction of reservation / ⁽¹⁾ deemed reservations / roads, Slum TDR, Heritage TDR.

⁽¹⁾ Inserted vide Corrigendum / Addendum No.CR.121/21, dt.02nd December, 2021

⁽²⁾ Inserted Vide Notification u/s.37(1A)(c) bearing No.CR.53/24/UD-12, dt.04th October, 2024

- b. DRC shall be issued only after the land is surrendered to the Authority, free of cost and free from encumbrances and after levelling the land to the surrounding ground level and after constructing/ erecting a 1.5 m. high compound wall / fencing i.e. brick / stone wall up to 0.60 m. above ground level and fencing above that upto remaining height with a gate, at the cost of the owner and to the satisfaction of the Authority.
- c. If any contiguous land of the same owner / developer, in addition to the land under surrender for which Transferable Development Rights (TDR) is to be granted, remains unbuildable, the Authority may grant Transferable Development Rights (TDR) for such remaining unbuildable land also if the owner / developer hands it over free of cost and free from all encumbrance and encroachment. If such land is from the proposed roads then such land shall be utilised for road side parking, garden, open space or road side amenities including bus bays, public toilets or any compatible user as the Authority may decide and if the such land is from the proposed reservation then same shall be included in such proposed reservation and shall be developed for the same purpose.
- d. In case of lessee, the award of Transferable Development Rights (TDR) shall be subject to lessee paying the lessor or depositing with the Authority for payment to the lessor, an amount equivalent to the value of the lessor's interest to be determined by the Authority on the basis of Right to Fair Compensation and Transparency in Land Acquisition, Rehabilitation and Resettlement Act, 2013 against the area of land surrendered, free of cost and free from all encumbrances.
- e. Where the authority has taken the possession of the reserved land in development plan with the commitment of granting TDR / DRC in the past and DRC is not issued, in such cases, DRC shall be issued for the quantum as per this UDCPR.
- ⁽³⁾ f. In case of land owned by Government of Maharashtra but leased on a long term for a nominal lease rent with remaining tenure of lease more than 30 years, is required for reservation under Development Plan, TDR shall be payable to lease holder to the extent of 90% of otherwise due TDR for equivalent private land. If allotment on lease was done at a subsidized rate and not at full market value or RR value, then indexing of the TDR given for land shall be at similarly reduced rate. If there is any existing authorized construction done by lease required to be demolished or acquired then TDR shall be payable for the construction as is due for equivalent private property.

11.2.5 ^(#) Transferable Development Rights (TDR) against Construction of Amenity -

When an owner or lessee, with prior approval of Authority, develops or constructs the amenity on the surrendered plot, at his own cost subject to such stipulations as may be prescribed and to the satisfaction of the Authority and hands over the said developed/constructed amenity free of cost to the Authority, then he may be granted a Transferable Development Rights (TDR) in the form of FSI as per the following formula :-

Construction Amenity TDR in Sq.m. = A / B * ⁽²⁾ 1.35 Where,

A = cost of construction of amenity in rupees ⁽²⁾ for all type of buildings and roads, should be calculated as per the ⁽²⁾ DSR prepared by ⁽²⁾ Public Works Department for the year in which construction of amenity is commenced. ⁽²⁾ While preparing the estimate, the Planning Authority may consider the cost of the project comprehensively including cost of construction (for the civil works, electrical works, water supply, drainage, infrastructure, development works like site levelling, compound wall, parking, drive ways, ramps for the basement, infrastructure for the compliance of the Environment / MPCB Department etc.) as well as incidental costs for completion of project (all types of premium & charges payable to the

^(#) Clarifications issued by the Govt. vide letter No.CR.44/21 dt.10th June, 2021 & Order No.CR.58/22/UD-12, dt.04th September, 2023

⁽²⁾ Replaced Vide Notification u/s.37(1AA)(c) & 20(4) bearing No.CR.96/2024/UD-13, dt.05th September, 2024

⁽³⁾ Inserted Vide Notification u/s.37(1AA)(c) bearing No.CR.53/24/UD-12, dt.04th October, 2024

⁽²⁾ Planning Authorities, Fees / Cess / Taxes payable to the Government / Semi Government Authorities, Labour Insurance and all Consultants' fees, Cost of the BOCW etc. ⁽⁴⁾ (Deleted) ⁽⁴⁾ The cost of any movable items should not be considered for the calculation of cost of construction of amenity.

B = land rate per Sq.m. as per the Annual Statement of Rates (ASR) prepared by the Inspector General of Registration for the year in which construction of amenity is commenced.

In case of buildings like auditorium, assembly etc. wherein height of building is more, cost of the building may be worked out from the Public Works Department as per applicable DSR. Also expenses for ancillary requirements only of immovable items like acoustic etc. may also be included in such cost. Such expenses for ancillary requirement may also be considered for hospital and educational buildings.

⁽²⁾ Conditions :

- i. It is compulsory to obtain technical sanction from the same authority which is competent for the technical sanction of other civil projects run through the Planning Authority.
- ii. For the TDR calculation, the Planning Authority has to include all the necessary items from the project proponent as required for the effective compliance of the said project. In the said Technical Sanction, cost of movable items should not be considered by the project proponent. Also these movable items should not be included in the budget or TDR calculation. Such movable items will not be procured through this project.
- iii. While execution and implementation of the said project the concerned authorized officer of the said Planning Authority should follow the requisite procedure for maintaining the records like measurement book, quality control and inspection of the record, preparation of bills, preparation of possession receipt, issuance of commencement certificate etc. However, the compensation for the Construction Amenity TDR is payable to the extent of actual expenditure on the said project. At the same time it will also be necessary to ensure at the time of disbursement that the cost of all the items completed by the project proponent is included.

⁽³⁾ Provided further, notwithstanding anything contained in these Regulations, for the purposes of medical, education or community hall, if the land belonging to SPA / ULB is already leased or allotted to a Public Charity Trust or a Government owned entity for the purposes of operations wherein construction of the amenity thereon is the responsibility of Special Planning Authority (SPA) or Urban Local Body (ULB), then to create or extend such facilities for the public at large, construction TDR may be granted to the Trust or Government entity for carrying out construction. However, in any case where construction TDR has been issued, the ownership of the construction shall lie with SPA / ULB and Trust or Government entity shall, post construction, hand over the construction to SPA / ULB and SPA / ULB may lease this construction back to the Trust or Government entity for a period co-terminus with the earlier lease and at such rate and conditions that earlier lease states. ⁽³⁾

If any person, with the consent of the authority, constructs D.P. road by obtaining development rights / consent of the other owners whose land is covered under the D.P. road, then such person may be entitled for construction amenity TDR subject to –

- i) This provision shall only apply to construction of new road proposed in the Development Plan.
- ii) One end of road should meet other existing public road.
- iii) The specifications for construction of road shall be as decided by the Authority.

⁽²⁾ Inserted vide Notification u/s.37(IAA)(c) & 20(4) bearing No.CR.96/2024/UD-13, dt.05th September, 2024

⁽³⁾ Inserted Vide Notification u/s.37(IAA)(c) bearing No.CR.53/24/UD-12, dt.04th October, 2024

⁽⁴⁾ Deleted vide Corrigendum No.CR.116/2024/UD-13, dt.11th October, 2024

11.2.6 Utilisation of Transferable Development Rights (TDR)

- i) A holder of DRC who desires to use FSI credit therein on a particular plot of land shall attach valid DRCs to the extent required with his application for development permission. Proposal for Transferable Development Rights (TDR) utilisation shall be submitted along with the documents as may be prescribed by the Authority or by the Government from time to time.

With an application for development permission, where an owner seeks utilization of DRC, he shall submit the DRC to the Authority who shall endorse thereon in writing in figures and words, the quantum of the TDR proposed to be utilised, before granting development permission.

Before issuance of Occupation Certificate, the Authority shall endorse on the DRC, in writing in figures and words, the quantum of TDR / DRs actually used and the balance remaining, if any

- ii) The Transferable Development Rights (TDR) generated from any land use zone shall be utilised on any receiving plot irrespective of the land use zone including development plan reservations of buildable nature and anywhere in congested or non-congested area or town planning scheme area earmarked on Development Plan. The equivalent quantum of Transferable Development Rights (TDR) to be permitted on receiving plot shall be governed by the formula given below :-

Formula: $X = (R_g / R_r) \times Y$ Where,

X = Permissible Utilisation of TDR / DR in sq.m. on receiving plot.

R_g = Rate for land in Rs. per sq.m. as per ASR of generating plots in generating year.

R_r = Rate for land in Rs. per sq.m. as per ASR of receiving plot in generating year.

Y = TDR debited from DRC in sq.m.

11.2.7 Utilisation of Transferable Development Rights (TDR) and Road Width Relation

- i) The total maximum permissible built-up area and utilisation of Transferable Development Rights (TDR) on receiving plot shall be, as per Regulation No.6.1, 6.2 and 6.3.
- ii) The quantum of maximum permissible TDR loading mentioned in Table 6-G of Regulation No.6.3 shall include minimum 30% and maximum 50% slum TDR / URT / Amenity TDR (wherever applicable). If such TDR is not available, the other TDR may be used. Moreover, this shall not be applicable for TDR loading mentioned in Regulation No.6.1.1. Table 6-A.
- iii) The utilisation of Transferable Development Rights (TDR) shall be permissible by considering ⁽¹⁾ the provision mentioned in Note (xiv) below Table No.6-G of Regulation No.6.3.

11.2.8 Areas Restricted from Utilisation of Transferable Development Rights (TDR)

Utilisation of Transferable Development Rights (TDR) shall not be permitted in following areas :-

- a. Agricultural / No Development / Green zone / Green Belt / Regional Park / HTHS Zone and Bio Diversity Park reservation in the Development Plan.
- b. Area within the flood control line i.e. blue line (prohibitive zone) as specified by Irrigation Department.
- c. Coastal regulation zone.
- d. Area having developmental prohibition or restrictions imposed by any notification issued under the provisions of any Central / State Act (like CRZ regulations, Defense restriction areas, etc.) or under these regulations.
- e. Koregaon Park area in Pune Municipal Corporation area.

⁽¹⁾ Substituted vide Corrigendum / Addendum No.CR.121/21, dt.02nd December, 2021

11.2.9 General stipulation

Development Rights (DRs) will be granted to an owner or lessee, only for reserved lands which are retainable and not vested or handed over to the Government / Urban Local Bodies and not exempted under section 20 or 21 of the then Urban Land (Ceiling and Regulations) Act, 1976 and undertaking to that effect shall be obtained, before a Development Right is granted. In the case of schemes sanctioned under section 20 or 21 of the said Act, the grant of Development Rights (DRs) shall be to such extent and subject to the conditions mentioned in in section 20 or 21 scheme and such conditions as the Government may prescribe. In case of non-retainable land (surplus land), the grant of Development Rights shall be to such extent and subject to such conditions as the Government may specify. The provisions of this Regulation shall be subject to the orders issued by the Government from time to time in this regard.

- ii) ^(#) In case of lands having tenure other than Class-I, ⁽¹⁾ i.e. Inam lands, tribal lands etc., N.O.C. from Competent Authority shall be produced by the land holder at the time of submission of application for grant of TDR.
- iii) DRC shall be issued by the Authority as a certificate printed on bond paper in an appropriate form prescribed by him. Such a certificate shall be a “transferable and negotiable instrument” after the authentication by the Authority. The Authority shall maintain a register in a form considered appropriate by him of all transactions, etc. relating to grant of, or utilisation of DRC.
- iv) The Authority shall issue DRC within 90 days from the date of application or reply from the applicant in respect of any requisition made by him, whichever is later.
- v) The TDR shall be granted only for those reservations which are developable for intended purpose under these regulations.

11.2.10 Transfer of DRC

The Authority shall allow transfer of DRC in the following manner :-

- i) In case of death of holder of DRC, the DRC shall be transferred only on production of the documents, as may be prescribed by him, from time to time, after due verification and satisfaction regarding title and legal successor.
- ii) If a holder of DRC intends to transfer it to any other person, he shall submit the original DRC to the Authority with an application along with relevant documents as may be prescribed by the Authority and a registered agreement which is duly signed by Transferor and Transferee, for seeking endorsement of the new holders name, i.e., the transferee, on the said certificate. The transfer shall not be valid without endorsement by the Authority and in such circumstances the Certificate shall be available for use only to the holder / transferor.

The utilisation of TDR from such certificate shall not be permissible during transfer procedure.

- iii) The Authority may refrain the DRC holder from utilizing the DRC in the following circumstances :-
 - a) Under direction from a competent Court.
 - b) Where the Authority has reason to believe that the DRC is obtained
 - a) by producing fraudulent documents
 - b) by misrepresentation,
- iv) Any DRC may be utilised on one or more plots or lands whether vacant, or already developed fully or partly by erection of additional storey, or in any other manner consistent with the these Regulations,

⁽¹⁾ Substituted vide Corrigendum / Addendum No.CR.121/21, dt.02nd December, 2021

^(#) Directives u/s.154 No.CR.07/2023, dt.27th February, 2023

- v) DRC may be used on plots/land having Development Plan reservations of buildable nature, whether vacant or already developed for the same purpose, or on the lands under deemed reservations, if any, as per these Regulations or on amenity space.
- vi) DRC may be used on plots / land available with the owner after surrendering the required land and construction to the Authority under the provisions of Accommodation Reservation. In such circumstances, for the purpose of deciding receiving potential of the plot for the Transferable Development Rights (TDR), the total area of the reservation before surrender shall be considered.

11.2.11 Infrastructure Improvement Charges -

No infrastructure improvement charges shall be paid for utilisation of TDR.

11.2.12 Vesting of Land :-

The Authority, before issuing DRC, shall verify and satisfy himself that the ownership and title of the land proposed for surrender is with the applicant, and get the Record of Right corrected in the name of Authority.

The Authority, before issuing DRC, shall verify and satisfy himself that the ownership and title of the land proposed for surrender is with the applicant, and get the Record of Right corrected in the name of Authority.

In case the Appropriate Authority for reservation is other than Authority, it shall be permissible for the Authority, on the request of such authority to grant TDR under this regulation and hold such possession as a facilitator.

Provided that, the Authority shall handover the possession of such land to concerned Appropriate Authority, after receipt of value of land, from such Appropriate Authority as per Annual Statement of Rates prevailing at the time of handing over possession of land under reservation.

Provided also that, if such Appropriate Authority is the State Government or State Government Department, the Authority shall handover the possession of such land to the concerned Department, free of cost.

11.2.13 Effect of this Regulation

DRC issued under the old regulations as per TDR zone, shall be utilised as per these regulation considering the year of generation of TDR mentioned on the original DRC and accordingly land rate in the relevant ASR shall be considered.

Provided also that old TDR purchased as per TDR zones for utilisation on a specific plot with registered documents of sale and / or specific proposal for utilisation of such TDR pending in the ULBs, shall be allowed completely as per the old regulations.

11.3 RESERVATION CREDIT CERTIFICATE (RCC)

The reservation credit certificate is a certificate specifying the amount of compensation in lieu of handing over of reserved land to the Corporation and shall be issued by the Authority. The amount mentioned in this credit certificate may be used for payment of various charges like development charges, premium, property tax, infrastructure charges etc. to the authority from time to time in future till exhausting the amount mentioned therein. Reservation Credit Certificate shall be issued subject to the following conditions.

- i) The authority shall acquire the land under reservation in lieu of RCC only when it is immediately required for development or creation of amenity or services or utilities.
- ii) Such certificate shall not bear any interest on the amount mentioned therein and shall be transferable. However, payment being made to the authority through the amount from RCC after six months from the date of issue of RCC shall be discounted @ 10% for the payments to be made under provisions of these UDCPR.

-
- iii) The amount of compensation to be paid to the owner shall be as per the provisions of the relevant Acts dealing with land acquisition as amended from time to time
 - iv) The land to be handed over to the Corporation shall be free from all encumbrances and procedure laid down in TDR regulations shall be followed.

The Authority shall endorse the entries of payment on such certificate from time to time. It shall maintain a record in a form considered appropriate by it of all transactions relating to grant of utilisation of reservation credit certificate.

_*_*_*_*_*_

CHAPTER - 12

STRUCTURAL SAFETY, WATER SUPPLY, DRAINAGE AND SANITARY REQUIREMENTS, OUTDOOR DISPLAY AND OTHER SERVICES

12.1 STRUCTURAL DESIGN

The structural design of foundations, elements made of masonry, timber, plain concrete; reinforced concrete, pre-stressed concrete and structural steel shall be carried out in accordance with Part-6. Structural design Section-1 - Loads, courses and effects, Section-2 - Soils and Foundation, Section-3 - Timber and Bamboo, Section-4 - Masonry, Section-5 - Concrete, Section-6 - Steel, Section-7 - Prefabrication, systems building and mixed / composite construction of National Building Code of India, amended from time to time. Proposed construction shall be as per the norms as specified by Bureau of Indian Standard, for the resistance of earthquake, Fire Safety and natural calamities. Certificate to that effect shall be submitted by the Licensed Structural Engineer of the developer / land owner, along with the proposal for development permission, as prescribed in these Regulations.

12.2 QUALITY OF MATERIALS AND WORKMANSHIP

- 1) All materials and workmanship shall be of good quality conforming generally to accepted standards of Public Works Department of Maharashtra and Indian Standard Specifications and Codes as included in Part-5 - Building Materials and Part-7 - Construction Practices and Safety of National Building Code of India, amended from time to time
- 2) All borrow pits dug in the course of construction and repair of buildings, roads, embankments etc. shall be deep and connected with each other in the formation of a drain directed towards the lowest level and properly stopped for discharge into a river stream, channel or drain and no person shall create any isolated borrow pit which is likely to cause accumulation of water which may breed mosquitoes.

12.3 ALTERNATIVE MATERIALS, METHODS OF DESIGN & CONSTRUCTION AND TESTS

- 1) The provision of the regulations are not intended to prevent the use of any material or method of design or construction, not specifically prescribed by the regulations, provided any such alternative has been approved.
- 2) The provision of these regulations is also not intended to prevent the adoption for architectural planning and layout conceived as an integrated development scheme.
- 3) The authority may approve any such alternative provided it is found that the proposed alternative is satisfactory and conform to the provisions of relevant parts regarding material, design, and construction and that material, method or work offered is, for the purpose intended, at least equivalent to that prescribed in the rules in quality, strength, compatibility, effectiveness, fire rating and resistance, durability and safety.
- 4) Tests : Whenever there is insufficient evidence of compliance with the provisions of the regulations of evidence that any material or method of design or construction does not conform to the requirements of the rules or in order to substantiate claims for alternative materials, design or methods of construction, the Authority may require tests sufficient in advance as proof of compliance. These tests shall be made by an approved agency at the expense of the owner.

- 5) Test method shall be as specified by the regulations for the materials or design or construction in question. If there are no appropriate test methods specified in the regulations, the Authority shall determine the test procedure. For methods of tests for building materials; reference may be made to relevant Indian standards as given the National Building Code of India, published by the Bureau of Indian Standards. The latest version of the National building Code of India shall be taken into account at the time of enforcement of these rules.
- 6) Copies of the results of all such tests shall be retained by the authority for a period of not less than two year after the acceptance of the alternative material.

12.4 BUILDING SERVICES

- 1) The planning, design and installation of electrical installations, air-conditioning and heating work shall be carried out in accordance with Part-8 - Building Services, Section-2 - Electrical and allied Installations, Section-3 - Air Conditioning, heating and mechanical ventilation of National building Code of India, amended from time to time.
- 2) The planning design including the number of lifts, type of lifts, capacity of lifts depending on occupancy of building; population on each floor based on occupant load, height of building shall be in accordance with Section-5 - installation of Lifts and Escalators of National Building Code of India, amended from time to time. In existing buildings, in case of proposal for one additional floor, existing lift may not be raised to the additional floor.
- 3) The lifts shall be maintained in working order properly.

12.5 WATER SUPPLY, DRAINAGE AND SANITARY REQUIREMENTS

- 1) The planning, design, construction and installation of water supply, drainage and sanitation and gas supply systems shall be in accordance with the provisions of Part-9 - Plumbing Services, Section-1 - Water Supply, Drainage and Sanitation, Section-2 - Gas supply of National Building Code of India as amended from time to time.
- 2) Requirements of Water Supply in Building.
The total requirements of water supply shall be calculated based on the population as given below :-

Occupancy	Basis
Residential Building	5 persons per tenement
Other Buildings	No. of persons on occupant load and area of floors given in Table No. ⁽¹⁾ 9-E

- 3) The requirements of water supply for various occupancies shall be as given in Table No.12-A and Table No.12-B or as specified by the Authority from time to time.

Table No.12-A		
Per Capita Water Requirements for Various Occupancies / Uses		
Sr. No.	Type of Occupancy	Consumption per head per day (in litres)
1	2	3
1	Residential	
	(a) in living units	135
	(b) Hotels with lodging accommodation (per bed)	180

⁽¹⁾ Substituted vide Corrigendum / Addendum No.CR.121/21, dt.02nd December, 2021

1	2	3
2	Educational	
	(a) Day Schools	45
	(b) Boarding Schools	135
3	Institutional (Medical Hospitals)	
	(a) No. of beds not exceeding 100	340
	(b) No. of beds exceeding 100	450
	(c) Medical quarters and hostels	135
4	Assembly :- Cinema theatres, auditorium etc. (per seat of accommodation)	15
5	Government and Semi-public business	45
6	Mercantile (Commercial)	
	(a) Restaurants (per seat)	70
	(b) Other business buildings	45
7	Industrial	
	(a) Factories where bathrooms are to be provided	45
	(b) Factories where no bath-rooms are required to be provided	30
8	Storage (including warehousing)	30
9	Hazardous	30
10	Intermediate / Stations (excluding mail and express stops)	45 (25) *
11	Junction Stations	70 (45) *
12	Terminal / Stations	45
13	International and domestic Airports	70

* - The value in parenthesis is for stations where bathing facilities are not provided.

Note : The number of persons for Sr.No.(10) to (13) shall be determined by the average number of passengers, handled by the station daily; due consideration may be given to the staff and workers likely to use the facilities.

Table No.12-B		
FLUSHING STORAGE CAPACITIES		
Sr. No.	Classification of building	Storage capacity.
(1)	(2)	(3)
1	For tenements having common convenience	900 litres net per w.c. seat.
2	For residential premises other than tenements having common convenience	270 litres net for one w.c. seat and 180 litres for each additional seat in the same flat.
3	For Factories and Workshops	900 litres per w.c. seat and 180 litres per urinal seat.
4	For cinemas, public assembly halls, etc.	900 litres per w.c. seat and 350 litres per urinal seat.

12.6 DRAINAGE AND SANITATION REQUIREMENTS

12.6.1 General

- 1) There should be at least one water tap and arrangement for drainage in the vicinity of each water-closet or group of waterclosets in all the buildings.
- 2) Each family dwelling unit on premises (abutting on a sewer or with a private sewage disposal system) shall have, at least, one water-closet and one kitchen type sink. A bath or shower shall also be installed to meet the basic requirement of sanitation and personal hygiene.
- 3) All other structures for human occupancy or use on premises, abutting on a sewer or with a private sewage disposal system, shall have adequate sanitary facilities, but in no case less than one water closet and one other fixture for cleaning purposes.

12.6.2 For Residences

- 1) Dwelling with individual convenience shall have at least the following fitments :
 - a) One bathroom provided with a tap and a floor trap,
 - b) One water-closet with flushing apparatus with an ablution tap; and
 - c) One tap with a floor trap or a sink in kitchen or wash place.
- 2) Dwelling without individual conveniences shall have the following fitments :
 - a) One water tap with floor trap in each tenement,
 - b) One water closet with flushing apparatus and one ablution tap, bath for every two tenements, and
 - c) One bath with water tap and floor trap for every two tenements.

Such fitments shall not be necessary where there is not water supply scheme of the authority.

12.6.3 For Buildings other than Residences

The requirements for fitments for drainage and sanitation in the case of buildings other than residences shall be in accordance with Table No.12-C to 12-P. The following shall be, in addition, taken into consideration :

- a) The figures shown are based upon one (1) fixture being the minimum required for the number of persons indicated or part thereof.
- b) Building categories not included in the tables shall be considered separately by the Authority.
- c) Drinking fountains shall not be installed in the toilets.
- d) Where there is the danger of exposure to skin contamination with poisonous, infectious or irritating material, washbasin with eye wash jet and an emergency shower located in an area accessible at all times with the passage / right of way suitable for access to a wheel chair, shall be provided.
- e) When applying the provision of these tables for providing the number of fixtures, consideration shall be given to the accessibility of the fixtures. Using purely numerical basis may not result in an installation suited to the need of a specific building. For example, schools should be provided with toilet facilities on each floor. Similarly toilet facilities shall be provided for temporary workmen employed in any establishment according to the needs; and in any case one WC and one washbasin shall be provided.
- f) All buildings used for human habitation for dwelling work, occupation, medical care or any purpose detailed in the various tables, abutting a public sewer or a private sewage disposal system, shall be provided with minimum sanitary facilities as per the schedule in the tables. In case the disposal facilities are not available, they shall be provided as a part of the building design for ensuring high standards of sanitary conditions in accordance with this section.

- g) Workplaces where crèches are provided, they shall be provided with one WC for 10 persons or part thereof, one washbasin for 15 persons or part thereof, one kitchen sink with floor tap for preparing food / milk preparations. The sink provided shall be with a drinking water tap.
- h) In all types of buildings, individual toilets and pantry should be provided for executives and for meeting / seminar / conference rooms, etc. as per the user requirement.
- i) Where food is consumed indoors, water stations may be provided in place of drinking water fountains.

12.7 SIGNS AND OUTDOOR DISPLAY STRUCTURES

12.7.1 The display of advertising signs on buildings and land, shall be in accordance with Part - 10, Section-2 "Signs and outdoor display structures" of National Building Code of India as amended from time to time and, shall be in accordance with respective rules / by-laws, directive given by Government, and also rules / by-laws framed by the Authority in this regards from time to time.

12.7.2 Prohibition of advertising signs and outdoor display structure in certain cases

Notwithstanding the provisions of sub-regulations, no advertising sign or outdoor display structures shall be permitted on buildings of architectural, aesthetical, historical or heritage importance as may be decided by the Authority or on Government Buildings save that in the case of Government buildings only advertising signs or outdoor display structure may be permitted if they relate to the activities for the said buildings' own purposes or related programmers.

Table No.12-C : Sanitation Requirements - Office Buildings					
Sr. No.	Fixtures	Public Toilets		Staff Toilets	
		Male	Female	Male	Female
(1)	(2)	(3)	(4)	(5)	(6)
i)	Executive Rooms and Conference Halls in Office Buildings Toilet suite comprising one WC, one washbasin (with optional shower stall if building is used round the clock at user's option) Pantry optional as per user requirement	Unit could be common for Male / Female or separate depending on the number of user of each facility		For individual officer rooms	
ii)	Main Office Toilets for Staff and Visitors				
	a) Water-closet	1 per 25	1 per 15	1 per 25	1 per 15
	b) Urinals	Nil up to 6 1 for 7-20 2 for 21-45 3 for 46-70 4 for 71-100	-	Nil up to 6 1 for 7-20 2 for 21-45 3 for 46-70 4 for 71-100	-
	Add @ 3% for	101-200		101-200	
	Add @ 2.5 %	Over 200		Over 200	

Table No.12-D : Sanitation Requirements – Factories

Sr. No.	Fixtures	Offices / Visitors		Workers	
		Male	Female	Male	Female
(1)	(2)	(3)	(4)	(5)	(6)
i)	Water Closets (Workers & Staff)	1 for up to 25 2 for 16-35 3 for 36-65 4 for 66-100	1 for up to 15 2 for 16-25 3 for 26-40 4 for 41-57 5 for 58-77 6 for 78-100	1 for up to 15 2 for 16-35 3 for 36-65 4 for 66-100	1 for up to 12 2 for 13-25 3 for 26-40 4 for 41-57 5 for 58-77 6 for 78-100
	For persons 101 - 200 add	3 %	5 %	3 %	5 %
	For persons over 200 add	2.5 %	4 %	2.5 %	4 %
ii)	Urinals	Nil up to 6 1 for 7-20 2 for 21-45 3 for 46-70 4 for 71-100	-	Nil up to 6 1 for 7-20 2 for 21-45 3 for 46-70 4 for 71-100	-
	For persons 101 - 200 add	3 %		3 %	
	For persons over 200 add	2.5 %		2.5 %	

Table No.12-E : Sanitation Requirements - Cinema, Multiplex Cinema, Concerts and Convention Halls, Theatres

Sr. No.	Fixtures	Public		Staff	
		Male	Female	Male	Female
(1)	(2)	(3)	(4)	(5)	(6)
i)	Water-closets	1 per 100 up to 400 Over 400, add at 1 per 250 or part thereof	3 per 100 up to 200 Over 200, add at 2 per 100 or part thereof	1 for up to 15 2 for 16-35	1 for up to 12 2 for 13-25
ii)	Urinals	1 per 25 or part thereof	-	Nil up to 6 1 for 7-20 2 for 21-45	-

NOTE - Male population may be assumed as two-third and female population as one-third.

Table No.12-F- Sanitation Requirements - Art Galleries, Libraries and Museums

Sr. No.	Fixtures	Public		Staff	
		Male	Female	Male	Female
(1)	(2)	(3)	(4)	(5)	(6)
i)	Water-closets	1 per 200 up to 400 Over 400 add at 1 per 250 or part thereof	1 per 100 up to 200 Over 200 add at 1 per 150 or part thereof	1 for up to 15 2 for 16-35	1 for up to 12 2 for 13-25
ii)	Urinals	1 per 50	-	Nil up to 6 1 per 7-20 2 per 21-45	-

Notes - Male population may be assumed as two-third and female population as one-third.

Table No.12-G Sanitation Requirements - Hospitals with Indoor Patient Wards

Sr. No.	Fixtures	Patient Toilets		Staff Toilets	
		Male	Female	Male	Female
(1)	(2)	(3)	(4)	(5)	(6)
i)	Toilet suite comprising one WC and one washbasin and shower stall	Private room with up to 4 patients		For individual doctor's / officer's rooms	
For General Wards, Hospital Staff and Visitors					
ii)	Water-closets	1 per 8 beds or part thereof	1 per 8 beds or part thereof	1 for up to 15 2 for 16-35	1 for up to 12 2 for 13-25
iii)	Urinals	1 per 30 beds	-	Nil up to 6 1 for 7 to 20 2 for 21-45	-
Note - Male population may be assumed as two-third and female population as one-third.					

Table No.12-H Sanitation Requirements - Hospitals - Outdoor Patient Department

Sr. No.	Fixtures	Patient Toilets		Staff Toilets	
		Male	Female	Male	Female
(1)	(2)	(3)	(4)	(5)	(6)
i)	Toilet suite comprising one WC and one washbasin (with optional shower stall if building used for 24 h)	For up to 4 patients		For individual doctor's / officer's rooms	
ii)	Water-closets	1 per 100 persons or part thereof	2 per 100 persons or part thereof	1 for up to 15 2 for 16-35	1 for up to 12 2 for 13-25
ii)	Urinals	1 per 50 persons or part thereof	-	Nil up to 6 1 per 7 to 20 2 per 21-45	-
Note - Male population may be assumed as two-third and female population as one-third.					

Table No.12-I Sanitation Requirements - Hospitals' Administrative Buildings

Sr. No.	Fixtures	Staff Toilets	
		Male	Female
(1)	(2)	(3)	(4)
i)	Toilet suite comprising one WC and one washbasin (with optional shower stall if building used for 24 h)	For individual doctor's / officer's rooms	
ii)	Water-closets	1 per 25 persons or part thereof	1 per 15 persons or part thereof
iv)	Urinals	Nil up to 6 1 per 7 to 20 2 per 21-45	-
Note - Some WC's may be European style if desired.			

Table No.12-J Sanitation Requirements - Hospitals' Staff Quarters and Nurses Homes

Sr. No.	Fixtures	Staff Quarters		Nurses Homes	
		Male	Female	Male	Female
(1)	(2)	(3)	(4)	(5)	(6)
i)	Water-closets	1 per 4 persons or part thereof	1per 4 persons or part thereof	1 per 4 persons or part thereof 2 for 16-35	1per 4 persons or part thereof 2 for 16-35

Table No.12-K Sanitation Requirements - Hotels

Sr. No.	Fixtures	Public Rooms		Non-Residential Staff	
		Male	Female	Male	Female
(1)	(2)	(3)	(4)	(5)	(6)
i)	Toilet suite comprising one WC, washbasin with shower or a bath tub	Individual guest rooms with attached toilets		-	

Guest Rooms with Common Facilities

ii)	Water-closets	1 per 100 persons up to 400 Over 400 add at 1 per 250 or part thereof	2 per 100 persons up to 200 Over 200 add at 1 per 100 or part thereof	1 for up to 15 2 for 16-35 3 for 36-65 4 for 66-100	1 for up to 12 2 for 13-25 3 for 26-40 4 for 41-57 5 for 58-77 6 for 78-100
iii)	Urinals	1 per 50 persons or part thereof	Nil, upto 6 persons 1 for 7-20 persons 2 for 21-45 persons 3 for 46-70 persons 4 for 71-100 persons	Nil up to 6 1 for 7 to 20 2 for 21-45 3 for 46-70 4 for 71-100	-

Note - Male population may be assumed as two-third and female population as one-third.**Table No.12-L Sanitation Requirements – Restaurants**

Sr. No.	Fixtures	Public Rooms		Non-Residential Staff	
		Male	Female	Male	Female
(1)	(2)	(3)	(4)	(5)	(6)
i)	Water Closets	1 per 50 seats up to 200 Over 200 add at 1 per 100 or part thereof	2 per 50 seats up to 200 Over 200 add at 1 per 100 or part thereof	1 for up to 15 2 for 16-35 3 for 36-65 4 for 66-100	1 for up to 12 2 for 13-25 3 for 26-40 4 for 41-57 5 for 58-77 6 for 78-100
ii)	Urinals	1 per 50 persons or part thereof	----	Nil up to 6 1 for 7-20 2 for 21-45 3 for 46-70 4 for 71-100	----

NOTE : Male population may be assumed as two-third and female population as one-third.

Table No.12-M Sanitation Requirements – Schools and Educational Institutions						
Sr. No.	Fixtures	Nursery School	Non-Residential		Residential	
			Boys	Girls	Boys	Girls
(1)	(2)	(3)	(4)	(5)	(6)	(7)
i)	Water Closets	1 per 15 pupils or part thereof	1 for 40 pupils or part thereof	1 per 25 pupils or part thereof	1 per 8 pupils or part thereof	1 per 6 pupils or part thereof
ii)	Urinals	----	1 per 20 pupils or part thereof	----	1 per 25 pupils or part thereof	----

Table No.12-N Sanitation Requirements – Hostels							
Sr. No.	Fixtures	Resident		Non-Resident		Visitor / Common Rooms	
		Male	Female	Male	Female	Male	Female
(1)	(2)	(3)	(4)	(5)	(6)	(7)	(8)
i)	Water Closet	1 per 8 or part thereof	1 per 6 or part thereof	1 for up to 15 2 for 16-35 3 for 36-65 4 for 66-100	1 for up to 12 2 for 13-25 3 for 26-40 4 for 41-57 5 for 58-77 6 for 78-100	1 per 100 up to 400 Over 400 add at 1 per 250	1 per 200 up to 200 Over 200 add at 1 per 100
iii)	Urinals	1 per 25 or part thereof	----	Nil up to 6 1 for 7-20 2 for 21-45 3 for 46-70 4 for 71-100	----	1 per 50 or part thereof	----

Table No.12-O Sanitation Requirements – Mercantile Buildings, Commercial Complexes, Shopping Malls, Fruit & Vegetable Markets							
Sr. No.	Fixtures	Shop Owners		Common Toilets in Market / Mall Building		Public Toilet for Floating Population	
		Male	Female	Male	Female	Male	Female
(1)	(2)	(3)	(4)	(5)	(6)	(7)	(8)
i)	Water Closets	1 per 8 persons or part thereof		1 for up to 15 2 for 16-35 3 for 36-65 4 for 66-100	1 for up to 12 2 for 13-25 3 for 26-40 4 for 41-57 5 for 58-77 6 for 78-100	1 per 50 (Minimum 2)	1 per 50 (Minimum 2)
iii)	Urinals	----	----	Nil up to 6 1 for 7-20 2 for 21-45 3 for 46-70 4 for 71-100	----	1 per 50	----

Table No.12-P Sanitation Requirements – Airports and Railway Stations

Sr. No.	Fixtures	Junction Stations, Intermediate Stations and Bus Stations		Terminal Railway and Bus Stations		Domestic and International Airports	
		Male	Female	Male	Female	Male	Female
(1)	(2)	(3)	(4)	(5)	(6)	(7)	(8)
i)	Water-closet	3 for up to 1000 Add 1 per additional 1000 or part thereof	4 for up to 1000 Add 1 per additional 1000 or part thereof	4 for up to 1000 Add 1 per additional 1000 or part thereof	5 for up to 1000 Add 1 per additional 1000 or part thereof	Minimum - 2 for 200 - 2 For 400 - 9 For 600 - 12 For 800 - 16 For 1000 - 18	Minimum - 2 For 200 - 2 For 400 - 9 For 600 - 12 For 800 - 16 For 1000 - 18
ii)	Urinals	4 for up to 1000. Add 1 per additional 1000	----	6 for up to 1000. Add 1 per additional 1000	----	1 per 40 or part thereof	----
iii)	Toilet for Disabled	1 per 4000	1 per 4000	1 per 4000	1 per 4000	1 per 4000 (Minimum 1)	1 per 4000 (Minimum 1)

****_**_

CHAPTER – 13

SPECIAL PROVISIONS FOR CERTAIN BUILDINGS

13.0 GENERAL

Special provisions shall be made in respect of certain buildings as given below. However, this provision shall stand superseded if new directions are issued by the Government.

13.1 PROVISIONS FOR BARRIER FREE ACCESS

Provisions for barrier free access in buildings for differently abled persons shall be as given below.

13.1.1 Definitions

- i) **Non-ambulatory Disabilities** :- Impairments that, regardless of cause or manifestation, for all practical purposes, confine individuals to wheelchairs.
- ii) **Semi-ambulatory Disabilities** :- Impairments that cause individuals to walk with difficulty or insecurity, individuals using braces or crutches, amputees, arthritics, spastics, and those with pulmonary and cardiac ills may be semi-ambulatory.
- iii) **Hearing Disabilities** :- Deafness or hearing handicaps that might make an individual insecure in public areas because he is unable to communicate or hear warning signals.
- iv) **Sight Disabilities** :- Total blindness or impairments, which affect sight to the extent that the individual, functioning in public areas, is insecure or exposed to danger.
- v) **Wheel Chair** :- Chair used by disabled people for mobility. The standard size of wheel chair shall be taken as 1050 mm. x 750 mm.

13.1.2 Scope

These regulations are applicable to all buildings and facilities used by the public such as educational, institutional, assembly, commercial, business, mercantile buildings constructed on plot having an area of more than 2000 sq.m. It does not apply to private and public residences.

13.1.3 Site development

Level of the roads, access paths and parking areas shall be described in the plan along with specification of the materials.

1. **Access Path / Walk Way** :- Access path from plot entry and surface parking to building entrance shall be minimum of 1800 mm. wide having even surface without any steps. Slope, if any, shall not have gradient greater than 5%. Selection of floor material shall be made suitably to attract or to guide visually impaired persons (limited to coloured floor material whose colour and brightness is conspicuously different from that of the surrounding floor material or the material that emits different sound to guide visually impaired persons; hereinafter referred to as “guiding floor material”. Finishes shall have a non-slip surface with a texture traversable by a wheel chair. Curbs wherever provided should blend to a common level.
2. **Parking** :- For parking of vehicles of handicapped people, the following provisions shall be made :-
 - a) Surface parking for two car spaces shall be provided near entrance for the physically handicapped persons with maximum travel distance of 30.0 m. from building entrance.
 - b) The width of parking bay shall be minimum 3.6 meter.

- c) The information stating that the space is reserved for wheel chair users shall be conspicuously displayed.
- d) Guiding floor materials shall be provided or a device, which guides visually impaired persons with audible signals, or other devices, which serves the same purpose, shall be provided.

13.1.4 Building Requirements

The specified facilities for the buildings for differently abled persons shall be as follows :-

- i) Approach to plinth level
 - ii) Corridor connecting the entrance / exit for the differently abled.
 - iii) Stair-ways
 - iv) Lift
 - v) Toilet
 - vi) Drinking Water.
- i) **Approach to plinth level :-** Every building should have at least one entrance accessible to the differently abled and shall be indicated by proper signage. This entrance shall be approached through a ramp together with the stepped entry.
 - ii) **Ramped Approach :-** Ramp shall be finished with non-slip material to enter the building. Minimum width of ramp shall be 1800mm. with maximum gradient 1 : 12. Length of ramp shall not exceed 9.0 m. having 800 mm. high hand rail on both sides extending 300 mm. beyond top and bottom of the ramp. Minimum gap from the adjacent wall to the hand rail shall be 50 mm.
 - iii) **Stepped Approach :-** For stepped approach size of tread shall not be less than 300 mm. and maximum riser shall be 150 mm. Provision of 800 mm. high hand rail on both sides of the stepped approach similar to the ramped approach.
 - iv) **Exit / Entrance Door :-** Minimum & clear opening of the entrance door shall be 900 mm. and it shall not be provided with a step that obstructs the passage of a wheel chair user. Threshold shall not be raised more than 12 mm.
 - v) **Entrance Landing :-** Entrance landing shall be provided adjacent to ramp with the minimum dimension 1800 mm. x 2000 mm. The entrance landing that adjoins the top end of a slope shall be provided with floor materials to attract the attention of visually impaired persons (limited to coloured floor material whose colour and brightness is conspicuously different from that of the surrounding floor material or the material that emits different sound to guide visually impaired persons hereinafter referred to as “guiding floor material”). Finishes shall have a non-slip surface with a texture traversable by a wheel chair. Curbs, wherever provided, should blend to a common level.
 - vi) **Corridor connecting the entrance / exit for the differently abled :-** The corridor connecting the entrance / exit for differently abled, leading directly outdoors to a place where information concerning the overall use of the specified building can be provided to visually impaired persons either by a person or by signs, shall be provided as follows :-
 - a) Guiding floor materials or device that emits sound to guide visually impaired persons shall be provided.
 - b) The minimum width shall be 1500 mm.

- c) In case there is a difference of level, slope ways shall be provided with a slope of 1 : 12.
- d) Hand rails shall be provided for ramps / slope ways.

vii) Stair-ways - One of the stair-ways - near the entrance / exit for the differently abled shall have the following provisions :-

- a) The minimum width shall be 1350 mm.
- b) Height of the riser shall not be more than 150 mm. and width of the tread 300 mm. The steps shall not have abrupt (square) nosing.
- c) Maximum number of risers on a flight shall be limited to 12.
- d) Hand rails shall be provided on both sides and shall extend 300 mm. on the top and bottom of each flight of steps.

viii) Lifts - Wherever lift is required as per regulations, provision of at least one lift shall be made for the wheel chair user with the following cage dimensions of lift recommended for passenger lift of 13 persons capacity of Bureau of Indian Standards.

Clear internal width	1100 mm.
Clear internal width	2000 mm.
Entrance door width	900 mm.

- a) A hand rail not less than 600 mm. long at 1000 mm. above floor level shall be fixed adjacent to the control panel.
- b) The lift lobby shall be of an inside measurement of 1800 mm. x 1800 mm. or more.
- c) The time of an automatically closing door should be minimum 5 seconds and the closing speed should not exceed 0.25 m. / sec.
- d) The interior of the cage shall be provided with a device that audibly indicates the floor, the cage has reached indicates that the door of the cage of entrance/exit is either open or closed.

ix) Toilets :- One special W.C. in a set of toilets shall be provided for the use of differently abled with essential provision of washbasin near the entrance for the handicapped.

- a) The minimum size shall be 1500 mm. x 1750 mm.
- b) Minimum clear opening of the door shall be 900 mm. and the door shall swing out.
- c) Suitable arrangement of vertical / horizontal handrails with 50 mm. clearance from wall shall be made in the toilet.
- d) The W.C. seat shall be 500 mm. from the floor.

x) Drinking Water :- Suitable provision of drinking water shall be made for the differently abled near the special toilet provided for them.

xi) Designing for Children :- In the buildings meant for the pre-dominant use of the children, it will be necessary to suitably alter the height of the handrail and other fittings & fixtures, etc.

Explanatory notes :-

1) Guiding / Warning Floor Material :

The floor material to guide or to warn the visually impaired persons with a change of colour or material with conspicuously different texture and easily distinguishable from the rest of the surrounding floor materials is called guiding or warning floor material. The material with

different texture gives audible signals with sensory warning when a person moves on this surface with walking stick. The guiding / warning floor material is meant to give the directional effect or warn a person at critical places. This floor material shall be provided in the following areas :-

- a) The access path to the building and to the parking area.
- b) The landing lobby towards the information board, reception, lifts, staircases and toilets.
- c) Immediately at the beginning/end of walkway where there is a vehicular traffic.
- d) At the location abruptly changing in level or beginning / end of a ramp.
- e) Immediately in front of an entrance / exit and the landing.

2) Proper signage :-

Appropriate identification of specific facilities within a building for the differently abled persons should be done with proper signals. Visually impaired persons make use of other senses such as hearing and touch to compensate for the lack of vision, whereas visual signals benefit those with hearing disabilities.

Signs should be designed and located so that they are easily legible by using suitable letter size (not less than 20 mm. high). For visually impaired persons, information board in brail should be installed on the wall at a suitable height and it should be possible to approach them closely. To ensure safe walking, there should not be any protruding sign which creates obstruction in walking. Public Address System may also be provided in busy public areas.

The symbols/information should be in contrasting colour and properly illuminated because people with limited vision may be able to differentiate amongst primary colours. International Symbol Mark for wheel chair be installed in a lift, toilet, staircase, parking areas, etc., that have been provided for the differently abled.

13.2 INSTALLATION OF SOLAR ASSISTED WATER HEATING (SWH) SYSTEM / ROOF TOP PHOTOVOLTAIC (RTPV) SYSTEM

SWH or RTPV systems shall be mandatory in all types of buildings to be constructed on plot area of more than 4000 sq.m.

In order to facilitate the installation of SWH / RTPV System, the new buildings shall have the following provisions :-

- i) All such buildings where SWH / RTPV are to be installed will have open sunny roof area available for the installation of SWH / RTPV.
- ii) The roof loading adopted in the design of such building should be at least 50 kg. Per sq.m. for the installation of SWH / RTPV.
- iii) At least 25% of the roof area shall be utilized for installation of the SWH / RTPV system.
- iv) Precaution should be taken that architectural elevation treatment should not cast shadow on terrace space. As far as possible, parapet of south, east and west sides of the terrace shall be of railing type (above 1 feet) such that it will not cast shadow on the solar collectors and maximum terrace space can be utilized.
- v) All such new buildings installed with SWH shall have an installed hot water line from the rooftop and insulated distribution pipelines to each of the points where hot water is required in the building.

13.3 RAIN WATER HARVESTING

The provision for Rain Water Harvesting shall be made as under :-

- a) All the layout open spaces / amenity spaces of housing societies and new constructions / reconstruction / additions on plots having area not less than 500 sq.m. shall have one or more Rain Water Harvesting structures having a minimum total capacity as detailed in Schedule.

Provided that the Authority may approve the Rain Water Harvesting structures of specifications different from those in Schedule, subject to the minimum capacity of Rain Water Harvesting being ensured in each case.

- b) The owner / society of every building mentioned in the (a) above shall ensure that the Rain Water Harvesting System is maintained in good condition for storage of water for non-potable purposes or recharge of groundwater at all times.
- c) The Authority may impose a levy of not exceeding Rs.1000/- per annum for every 100 sq.m. of built-up area for the failure of the owner of any building mentioned in the (a) above to provide or to maintain Rain Water Harvesting structures as required under these regulations. Failure to provide Rain Water Harvesting System shall be deemed to be breach of the conditions on which the development permission has been granted.

Schedule

Rain Water Harvesting in a building site includes storage or recharging the ground water by rainwater falling on the terrace or any paved or unpaved surface within the building site. The following systems may be adopted for harvesting the rainwater drawn from terrace and the paved surface.

- i) Open well of a minimum 1.0 m. diameter and 6.0 m. in depth into which rain water may be channelled and allowed to filter for removing silt and floating material. The well shall be provided with ventilating covers. The water from the open well may be used for non-potable domestic purposes such as washing, flushing and for watering the garden etc.
- ii) Rain Water Harvesting for recharge of ground water may be done through a bore-well around which a pit of 1.0 m. width may be excavated upto a depth of at least 3.0 m. and refilled with stone aggregate and sand. The filtered rain water may be channelled to the refilled pit for recharging the bore-well.
- iii) An impressive surface / underground storage tank of required capacity may be constructed in the setback or other open spaces and the rain water may be channelled to the storage tank. The storage tank shall always be provided with ventilating covers and shall have draw-off taps suitably placed so that rain water may be drawn off for domestic, washing, gardening and such other purposes. The storage tank shall be provided with an overflow.
- iv) The surplus rain water, after storage, may be recharged into ground through percolation pits or trenches or combination of pits and trenches. Depending on the geomorphological and topographical conditions, the pits may be of the size of 1.20 m. width X 1.20 m. length X 2.0 m. to 2.50 m. depth. The trenches can be of 0.60 m. width X 2.0 to 6.0 m. length X 1.50 to 2.0 m. depth. Terrace water shall be channelled to pits or trenches. Such pits or trenches shall be back filled with filter media comprising the following materials :-
 - a) 40 mm stone aggregate as bottom layer upto 50% of the depth.
 - b) 20 mm stone aggregate as lower middle layer upto 20% of the depth.
 - c) Coarse sand as upper middle layer upto 20% of the depth.
 - d) A thin layer of fine sand as top layer.

- e) Top 10% of the pits / trenches will be empty and a splash is to be provided in this portion in such a way that roof top water falls on the splash pad.
- f) Brick masonry wall is to be constructed on the exposed surface of pits / trenches and the cement mortar plastered. The depth of wall below ground shall be such that the wall prevents loose soil entering into pits / trenches. The projection of the wall above ground shall at least be 15 cm.
- g) Perforated concrete slabs shall be provided on the pits / trenches.
- h) If the open space surrounding the building is not paved, the top layer up to a sufficient depth shall be removed and refilled with coarse sand to allow percolation of rain water into ground.
- v) The terrace shall be connected to the open well / bore-well / storage tank / recharge pit / trench by means of HDPE / PVC pipes through filter media. A valve system shall be provided to enable the first washing from roof or terrace catchment, as they would contain undesirable dirt. The mouth of all pipes and opening shall be covered with mosquito (insect) proof wire net. For the efficient discharge of rain water, there shall be at least two rain water pipes of 100 mm. dia. for a roof area of 100 sq.m.
- vi) Rain Water Harvesting structures shall be sited as not to endanger the stability of building or earthwork. The structure shall be designed such that no dampness is caused in any part of the walls or foundation of the building or those of an adjacent building.
- vii) The water so collected / recharged shall as far as possible be used for non-drinking and non-cooking purpose. Provided that when the rain water in exceptional circumstances will be utilised for drinking and / or cooking purpose, it shall be ensured that proper filter arrangement and the separate outlet for bypassing the first rain water has been provided. Provided further that, will be ensured that for such use, proper disinfectants and the water purification arrangements have been made.

The structures constructed under this provision shall not be counted towards FSI computation.

13.4 GREY WATER RECYCLING AND REUSE

Grey Water - It means waste water from bathrooms, sinks, shower and wash areas, etc.

Applicability - These Regulations shall be applicable to all Developments / Redevelopments / part Developments for the uses as mentioned under Regulation No.13.4.1 to 13.4.6 shall have the provision for treatment, recycling and reuse of Grey Water. The applicant shall along with his application for obtaining necessary layout approval / building permission shall submit a plan showing the location of Grey Water Treatment Plant, furnishing details of calculations, implementation, etc. This Plan shall accompany with the applicant's commitment to monitor the system periodically from the date of occupation of the respective building.

13.4.1 For Layout Approval / Building Permission

- i) In case of Residential layouts, area admeasuring 10000 sq.m. or more, in addition to 10% open space, prescribed in the bye- laws, a separate space for Grey Water Treatment and Recycling Plant should be proposed in the layout. This may be proposed in amenity space as per Regulation No.3.5.
- ii) On the layout Plan, all Drainage lines, Chambers, Plumbing lines should be marked in different colour and submit the layout for approval to the Authority.

- iii) The recycled water shall be used for gardening, car washing, toilet flushing, irrigation, etc. and in no case for drinking, bathing, washing utensils, clothes etc.
- iv) A clause must be included by the owner / developer in the purchase agreement that the purchaser, owner of the premises / organization or society of the purchasers shall ensure that :
 - a) The recycled water is tested every six months either in municipal laboratory or in the laboratory approved by Authority or by State Government and the result of which shall be made accessible to the competent authority / EHO of the respective ward office.
 - b) Any recommendation from testing laboratory for any form of corrective measures that are needed to be adopted shall be compiled. Copy of any such recommendation and necessary action taken shall also be sent by the testing laboratories to the Competent Authority / EHO of respective Wards.
 - c) Maintenance of Recycling Plant should be done by the Developer or Housing Society or Owner.

13.4.2 Group Housing / Apartment Building

In case of Group Housing scheme or a multi-storeyed building having 100 or more tenements, Grey Water Recycling Plant as mentioned in Regulation No.13.4.1 above, should be constructed. In case of EWS / LIG tenements, this shall be provided for tenements 150 or more.

13.4.3 Educational, Industrial, Commercial, Government, Semi-Government Organizations, Hotels, Lodgings, etc.

For all above buildings having built-up area 1500 sq.m. or more or if water consumption is 20,000 litre per day whichever is minimum, then provision for Grey Water Treatment Plant as mentioned in Regulation No.13.4.1 is applicable.

13.4.4 Hospitals

Those Hospitals having 40 or more beds, Grey Water Recycling Plant as mentioned in Regulation No.13.4.1 is applicable.

13.4.5 Vehicle Servicing Garages

All Vehicle servicing garages shall ensure that the Grey water generated through washing of vehicles is treated and recycled back for the same use as mentioned in Regulation No.13.4.1.

13.4.6 Other Hazardous uses

All other Establishments / Buildings where chances of Waste Water generated containing harmful chemicals, toxins are likely and where such water cannot be directly led into municipal sewers, the concerned Competent Authority may direct the Owners, users of such Establishments, Buildings to treat their Waste Water as per the directions laid in Regulation No.13.4.1.

13.4.7 Incentive

The Owner / Developer / Society setting up and agreeing to periodically maintain such Grey Water Treatment and Recycling Plant entirely through their own expenditure shall be eligible for an incentive in the form of fiscal benefits in Property Tax to the extent of 5% to Tenement holder / Society.

13.4.8 Penalty Clause

Any person / Owner / Developer / Organization / Society violating the provisions of these bye-laws, he shall be fined Rs.2,500/- on the day of detection and if the violation continues, then he shall be fined Rs.100/- for every day as concrete action after written Notice from Authority.

If any person / Owner / Developer / Organization / Society fails to operate as determined by the Authorised Officer of the Authority and from the observations of test results and / or physical verification) the Recycling plant, then he will be charged a penalty of Rs.300/- per day and disconnection of Water connection also.

13.5 SOLID WASTE MANAGEMENT

It shall be mandatory for :-

- i) Housing complexes, Commercial establishments, hostels, hospitals having aggregate built-up area more than 4,000 sq.m. or more.
- ii) All three star or higher category hotels.

To establish a dedicated Solid waste management system to treat 100% wet waste being generated in such buildings.

The treatment of wet waste shall be done through an organic waste composters/ vermiculture pits or other similar technologies of suitable capacity installed through reputed vendors.

The disposal of dry waste, e-waste, hazardous waste shall be carried out through authorised recyclers or any other system as specified by the Authority

⁽¹⁾ 13.6 ⁽¹⁾ SPECIAL SAFETY CONTROL REGULATIONS FOR BUILDINGS VULNERABLE TO MAN-MADE DISASTERS

A) Applicability

- a. These Special Regulations shall be applicable to buildings vulnerable to terrorist attack / man-made disasters within the area under the jurisdiction of Municipal Corporations / Special Planning Authorities.
- b. Prevailing Development Control and Promotion Regulations of sanctioned Development Plan as amended from time to time shall be applicable mutatis mutandis except those expressly provided in these Special Regulations.
- c. These Special regulations shall be applicable for all buildings fulfilling the criteria of :
 1. Having built up area exceeding 10,000 sq.m. or occupancy over the 1000 persons, used for the following occupancies which are vulnerable to man-made disasters based on the Risk Assessment Score as per Annexure-A
 - i. Assembly buildings
 - ii. Institutional buildings of registered trusts which are used for medical or other treatments and hospitals
 - iii. Educational buildings of schools / colleges
 - iv. Buildings which attract or are likely to attract a large number of people / public such as shopping malls, markets, religious buildings, monuments, places of tourist importance, business buildings having headquarters of business houses (such as the World Trade Centre, Stock Exchange) etc.
 2. For Governorent buildings, which has been specifically identified as buildings vulnerable to man-made disasters by the Appropriate Authority of the State Government.
The Appropriate Authority of the State Government shall mean Additional Commissioner of Police, Protection and Security, Mumbai in Greater Mumbai and the Deputy Commissioner of Police, Special Branch in other Police Commissionerate of Maharashtra, and Superintendent of Police in Districts.

Special Regulations applicable to the buildings mentioned above shall be as per Annexure-B.

⁽¹⁾ Inserted vide Notification u/s.37(1AA)(c) bearing No.CR.45/2022/UD-11, dt.10th October, 2024

- B) Every Special building (as defined in UDCPR-2020) shall be provided with Fire Towers having minimum 2 hours fire resistance, consisting of a fireman evacuation lift with a ventilated lobby as an integral part of fire escape staircase, preferably at landing level.

Fire Tower may be provided as per sketches shown in the Annexure-C.

Note : Other provisions in the sanctioned DCPR with regards to the applicability of a second lift, second staircase for high-rise / Special buildings shall not be applicable after provision of a Fire Tower as given above.

- C) Special buildings (as defined in UDCPR-2020) with height 90 m. and above shall be provided with fire break water tank system with fire pumps at every 65 m. height interval from ground level.

The fire break water tank system may be provided at the service floor, the floor provided with refinge area or any other floor as per specification details shown in the schematic sketch in the Annexure-D.

- D) Details of qualifications, duties and responsibilities for Licensed Electrical Engineer are as specified in Annexure-E. Procedure of appointment, declaration etc. is as specified in Annexure E-1, E-2.1, E-2.2, E-2.3 and registration process and fees for Licensed Electrical Engineer / Consultant is as specified in Appendix-C of UDCPR-2020, as the case may be.

- E) Notice of intention to carry out development or redevelopment of a building to be submitted by the owner / developer shall be accompanied by a certificate of supervision in prescribed format by the Licensed Electrical Engineer with respect to planning, designing of electrical installations and also supervision of electrical installations during the progress of buildings.

- F) Owner / Developer shall submit a certificate from a Licensed Electrical Engineer in prescribed proforma with respect to completion of electrical installations while submission of proposal for occupation certificate.

- (1) G) In case of discrepancies observed in the planning, designing and execution and certification of electrical installations / services by the appointed registered Electrical Professional, the license issued shall be revoked and the Electrical Engineer / Consultant may be debarred from further practice / business for a period as may be decided by the Municipal Corporation / Authority.

- H) For planning, designing & execution and certification of the electrical installations / services by Electrical professionals, the various formats / check lists / diagrams, etc. are enclosed in Annexure F to O.

- I) Post completion of Building :

On completion of the buildings for which the criteria of this regulation is applicable shall observe the following perpetual conditions :

- i. The fire protection measures provided shall be well maintained by the Owner / Society / Organization as per the rules and policies prescribed by the concerned fire authority.
- ii. The electrical installations in the building including flats, shops, etc. shall be inspected periodically at least once in 5 year and the certificate to that effect shall be obtained from the Licensed Electrical Engineer. However, in case of any electrical repair / rectification / renovation work carried out in the building or part thereof, the certificate from Electrical Engineer shall be obtained after the completion of such work.

Notes :

- a. The conditions regarding maintaining the electrical and fire installations as mentioned above shall be incorporated in the Occupation / Complition Certificate issued by the Authority.
- b. The copy of above certificates shall be displayed at some conspicuous place of the building.

⁽¹⁾ Inserted vide Notification u/s.37(1AA)(c) bearing No.CR.45/2022/UD-11, dt.10th October, 2024

- c. Failure to maintain the fire installations and periodical certification may leads to withdrawal of Occupation Certificate by the Authority in addition to fine / penalty and other actions from the concern authorities.
- d. Failure to maintain the electrical installations and periodical certification may leads to disconnection of power supply by Power Supply Company till its rectification. ⁽¹⁾

_*_*_*_*_*_*

⁽¹⁾ Inserted vide Notification u/s.37(1AA)(c) bearing No.CR.45/2022/UD-11, dt.10th October, 2024

CHAPTER – 14

SPECIAL SCHEMES

14.1 INTEGRATED TOWNSHIP PROJECT (ITP)

⁽¹⁾ 14.1.1 For Regional Plan Area + Development Plan Area

14.1.1.1 Applicability :-

These regulations shall be applicable to the areas under Regional Plan ⁽¹⁾ or Development Plan, as the case may be, sanctioned under the provisions of Maharashtra Regional and Town Planning Act, 1966 (hereinafter referred to as “the said Act”).

Provided that, if the Development Control Regulations regarding development of Integrated Township Project for an area over which a Planning Authority / Special Planning Authority / Area Development Authority has been appointed or constituted or deemed to have been appointed are yet to be sanctioned, then in considering the application for permission, these regulations, shall be applicable, mutatis mutandis, till such Authority adopts the Regulations in this regard.

If the ITP falls within the jurisdiction of more than one authority then in such cases Government can issue directives at the time of Locational Clearance or at any time regarding as to which authority shall give permission and supervise the project subject to terms and conditions as may be specified.

14.1.1.2 Requirements of Site :-

The area proposed for Integrated Township shall fulfil the following requirements :-

- i) Any suitable area having area of 40 hect. (100 Acres) or more at one place.
- ii) The area shall be one, contiguous, unbroken and uninterrupted. Provided that, such area if divided by one or more water courses (such as nallah, canals, etc.), existing or proposed roads of any width or by railways, pipeline etc., shall be treated as one, contiguous, unbroken and uninterrupted, subject to condition that the Project Proponent/s shall construct necessary connecting roads or bridges as per site requirements at his own cost with due permission from concerned authorities. Integrated Township area may also include;
 - a) Lands in afforestation zone provided that such land is not a forest land and subject to no construction being allowed on land having slope more than 1:5.
 - b) Lands within the buffer zone of National Park subject to restriction on development permissible in such buffer zone and subject to NOC of Forest Department.
 - c) Tribal land subject to permission granted under M.L.R. code, Government lands allotted to project proponent subject to Regulation No.14.1.1.13(ii).
 - d) Private forest land that have been restored back after completion of section 22(a) Enquiry of Maharashtra Private Forest Act, 1975 shall be allowed to be part of the ITP with the condition that development permission shall be granted on such land only after necessary permission under the provision of Forest Conservation Act, 1980.
 - e) Buffer zone of Eco-sensitive Zone notified subject to all restriction on development and FSI permissible in such buffer zone ⁽¹⁾ and buffer zone of mangroves / CRZ outside HTL, subject to all restriction on development as per MoEF Notification as amended from time to time.

⁽¹⁾ Modified vide Notification u/s.37(1AA)(c) & 20(4) bearing No.CR.105/2022/(Part-2)/UD-13, dt.05th September, 2024

- f) Areas under flood line / flood zone subject to ⁽¹⁾provisions mentioned in Regulation No.3.1.3 of these Regulations (UDCPR).
- g) Areas under Hill Top / Hill Slope Zone, and (b), (e), (f) mentioned above as shown on Regional Plan / Development Plan subject to condition as mentioned in Regulation No.14.1.1.7(i)(c). However total of these areas shall be restricted to maximum 40% of total area under ITP.
- iii) If the Integrated Township area is more than 200 ha., it can be segregated as long as each parcel is more than 40 ha. and is located within a radius of 5 kms. Provided that the land use mix is maintained in each parcel.
- iv) The area shall have an access by means of an existing, or proposed road having minimum width of 18.0 m. In case of proposed road, such area shall have an access by existing road having width 12.0 m. for the purpose of declaration locational clearance and LoI of such project but it is necessary for the project proponent to have an existing access of 18.0 m. before sanction of Commencement Certificate to the FSI beyond 25% of project.
- Provided that Government land or land belonging to tribal can be considered for the purpose of road if there is a registered Agreement. However development permission shall be granted only after due permission of appropriate authority is given.
- ⁽¹⁾ Provided that, if the access to the ITP is from any public road or Development / Regional Plan road then, such road shall be developed on priority by the concerned Authority.
- v) The ITP Area shall not include the area under :-
- Notified forest, (excluding the private forest land subject to NOCs of forest Department)
 - Water bodies like river, creek, canal, reservoir, etc. ⁽¹⁾Mangroves, Tidal Zone, Mud Flats, ⁽¹⁾ area within HTL
 - The area under Notified National Parks
 - Defence Estates
 - Cantonment Boards
 - Any restricted area
 - Quarry Zone, Notified SEZ, designated port/harbour areas, wildlife corridor and biosphere reserves, Gaothan / Congested Area.
 - The historical and archaeological places notified under the relevant act
 - Any other area that may be declared by the Govt. of Maharashtra from time to time.

14.1.1.3 Ownership of Lands :-

The project proponent/s shall have the ownership of all the land parcels under project.

(Explanation) - for this clause, ownership includes rights accrued vide one or more registered Development Agreement/s or Power of Attorney (PoA) for such development and disposal, on behalf of land owner / owners).

14.1.1.4 Permission and Declaration of Project by State Government :-

- The Project Proponent/s shall apply to the State Government for obtaining permission and declaration of such project to be a "Integrated Township Project". Such application shall be accompanied by the following attested documents in two sets :-
 - Details of ownership of land viz. extracts of V.F.No.7/12 or Property Register Cards, in original having date not more than six months prior to the date of submission. In case of rights accrued through registered Development Agreement or PoA, attested copies of such documents.

⁽¹⁾ Modified vide Notification u/s.37(1A)(c) & 20(4) bearing No.CR.105/2022/(Part-2)/UD-13, dt.05th September, 2024

- b) Self-attested list of S.No. / G.No. / CTS showing name of owner as per record of rights, total area of such land parcel, area owned by the applicant in such land parcel, the name of person / company owning the Development Rights, area proposed to be included in project from such land parcel.
- c) Part plan of sanctioned Regional Plan, ⁽¹⁾ or Development Plan, as the case may be, showing all the lands falling in the project.
- d) No Objection Certificate from the officer at Divisional level, Water Resources Department in respect of lands falling in “Command Area” of any Irrigation Project unless these powers are exercisable by the higher authority.
- e) Village maps showing the lands falling in the project.
- f) Certificate from concerned Forest Officer not below the rank of Dy. Conservator of Forests at Divisional level (unless these powers are exercisable by higher authority), showing that the lands under project do not form part of and not included in reserved forest or protected forest or non-classified forest or not acquired under the provisions of the Maharashtra Private Forest (Acquisition) Act, 1975 and also, confirming that such lands do not form part of the Notified National Parks, prohibited area of Notified Wildlife Sanctuaries and Notified Bird Sanctuaries.
- g) Certificate from the concerned revenue officer not below the rank of Tahasildar, showing the lands under project do not include lands belonging to tribal or that tribal lands included in ITP have necessary permission under M.L.R. code.
- h) Certificate from the Director of Archaeological Department, Maharashtra State, showing that the lands under project do not include monuments notified by the Archaeological Department, Heritage buildings and Precincts. Such certificate should also mention the distance to be kept around such places, if any.
- i) Receipt of processing fee (non-refundable) paid, at the concerned branch office of the Town Planning Department, at the rate of Rs.5000/- per ha. for the current year with the yearly rise of Rs.500/- per ha. starting from the month of January every year.
- ⁽¹⁾ j) Area Statement showing the following details :-
 - a) Total Area under ITP.
 - b) Area covered by Hill Top, Hill Slope, CRZ, ESZ etc.
 - c) Area under various D.P. / R.P. Reservations.
 - d) Plot Area of 2% Amenity Space, if any.
 - e) Plot Area and Built Up Area Allocation of each Mandetory Town Level Amenities as per Clause No.14.1.1.7(iii).
- ii) On receipt of an application under Clause (i) above, the Government ⁽¹⁾ after consulting ⁽¹⁾ the High Power Committee (HPC) appointed by the State Government for Scrutiny, Monitoring, Promotions, Transitions and Review of ITPs, by notification in the Official Gazette, grant the Locational Clearance and declare such project to be a “Integrated Township Project”, subject to such general and / or special conditions or, reject the application, under the provisions of Section 18(3) ⁽¹⁾ and / or Section 44(2), as the case may be, of the said Act, within a period of 90 days from the date of receipt of application or reply from the Project Proponent/s in respect of any requisition made by the Government, whichever is later. If the project proponent fails to comply with the conditions specified while granting location clearance within the specified time limit, then in such cases location clearance given earlier stands automatically cancelled and no refund or adjustment of premium / fees / expenses etc. shall be eligible.

⁽¹⁾ Modified vide Notification u/s.37(1AA)(c) & 20(4) bearing No.CR.105/2022/(Part-2)/UD-13, dt.05th September, 2024

⁽¹⁾ The High Power Committee (HPC) for Scrutiny, Monitoring, Promotions, Transitions and Review of ITPs shall consist of following members :-

- a) Principal Secretary – UD-1 – Chairman
- b) Director of Town Planning, Maharashtra State, Pune – Member
- c) Concerned Collector / Concerned Planning Authority - Member
- d) Joint Secretary / Director – UD – Member Secretary

Locational Clearance for all new ITPs proposals and proposals as per Transition Policy is to be granted by the State Government after consulting the above High Power Committee (HPC).

(Explanation) - In circumstances described in Clause (ii) above, such grant of permission and declaration of project shall be made under the provisions of Section 18(3) ⁽¹⁾ and / or Section 44(2), as the case may be, of the Maharashtra Regional and Town Planning Act, 1966)

iii) Every such permission and declaration shall remain in force for a period of two years, if not applied for Letter of Intent under Regulation No.14.1.1.5, from the date of issue of Locational Clearance Notification and thereafter it shall lapse.

Provided that, the Director of Town Planning, Maharashtra State, Pune may, on application made by Project Proponent/s before expiry of the above period extend such period by two years in aggregate. Provided also that, it is not mandatory on Project Proponent/s to submit all the papers afresh as prescribed under Clause (i) above, however the affidavit regarding the ownership of land about any dispute shall be mandatory.

iv) Such lapse shall not bar any subsequent application for fresh proposal.

v) The Director of Town Planning, Maharashtra State, on the request of Project Proponent/s, by notification in the Official Gazette, may grant to add or delete any area, not exceeding 50% of the total area under Locational Clearance, subject to condition that the remaining area shall not be less than 40 ha. The permissible FSI and other parameters shall increase or decrease accordingly.

14.1.1.5 Letter of Intent (LOI) by the Collector :-

i) The Project Proponent/s shall apply to the Collector for obtaining the Letter of Intent for such project. Such application shall be accompanied by the ownership documents as prescribed in Regulation No.14.1.1.4(i)(a) & (i)(b) and with locational clearance notification issued by the Government.

ii) The Collector shall verify and satisfy himself that Ownership and Development Rights of all the lands under project are with the Project Proponent/s before issuing the Letter of Intent.

iii) On receipt of an application under Clause (i) above, the Collector shall grant the Letter of Intent for the whole area or separately for any part thereof, which shall not be less than 40 ha. at the first instance, subject to conditions as may be deem fit, or reject the application, within a period of 45 days from the date of receipt of application or reply from the Project Proponent/s in respect of any requisition made by the Collector, whichever is later.

Provided that, in case of rejection, the Collector shall mention the grounds for such refusal.

iv) Every such Letter of Intent shall remain in force for a period of two year, if not applied for Development Permission under Regulation No.14.1.1.6, from the date of issue of Letter of Intent, unless renewed. Provided that, the Collector may, on application made by Project Proponent/s before expiry of the above period extend such period by two years in aggregate. Provided also that letter of intent granted by collector under earlier regulations may also be extended subject to other conditions of these regulations.

⁽¹⁾ Modified vide Notification u/s.37(1A)(c) & 20(4) bearing No.CR.105/2022/(Part-2)/UD-13, dt.05th September, 2024

14.1.1.6 Master Layout Plan Approval by the Collector ⁽¹⁾ or by the Planning Authority, as the case may be :-

- i) The project proponent/s shall apply to the concerned Collector ⁽¹⁾ or to the Authority, as the case may be, for obtaining the approval to the Master Layout Plan of the entire area as per Letter of Intent. Such application shall be accompanied by the documents in two sets as prescribed below :-
 - a) Attested copy of Gazette Notification issued by the Government under Regulation No.14.1.1.4(ii).
 - b) Attested copy of Letter of Intent issued by Collector under Regulation No.14.1.1.5.
 - c) Part plan of sanctioned Regional Plan ⁽¹⁾ or Development Plan, as the case may be, showing the lands under the Master Layout Plan.
 - d) Village Map showing the lands under the Master Layout Plan.
 - e) In case, project has no access from existing road having right of way of 18.0 m. then documents showing the ownership of Project Proponent/s in lands proposed for 18.0 m. wide access road.
 - f) Bank Guarantee of requisite amount as prescribed in Regulation No.14.1.1.12(vi).
 - g) Undertaking and Affidavit as may be prescribed by the Collector ⁽¹⁾ or by the Authority, as the case may be.
 - h) Copies of Master Layout Plan with or without Building Plans in three sets prepared and signed by expert in respective field and team headed by an Architect or Town Planner registered with Institute of Town Planners India (ITPI) with sign of owner / developer.
 - i) ⁽¹⁾ Location Marking on Contour map showing contour levels of lands under Master Layout Plan. Trueness of the contour shall be certified and attested by the surveying agency and the Project Proponent/s under their signature and seal.
 - j) Colored Google earth image / Bhuvan image / Drone survey image etc. showing lands under Master Layout Plan ⁽¹⁾ signed by the project proponent/s.
 - k) Phased Program for development of physical infrastructure with amenities under project, along with the project cost details.
- ii) If the application is not accompanied by the documents mentioned in Regulation No.14.1.1.6(i) above, the Collector ⁽¹⁾ or the Authority, as the case may be, convey the same to the Project Proponent/s immediately within 10 working days giving specific time period for fulfilment of such documents and if the same are not submitted by the said project proponent in given time then return the proposal at his level only.
- iii) On receipt of application, complete in all respects, as prescribed under Regulation No.14.1.1.6(i) above, the Collector ⁽¹⁾ or the Authority, as the case may be, shall forward the same to the concerned Divisional Joint Director of Town Planning for technical consultation within 10 working days.
- iv) The office of the Divisional Joint Director of Town Planning shall send its remarks to Collector ⁽¹⁾ or the Authority, as the case may be, within two months from the receipt of proposal from the Collector ⁽¹⁾ or the Authority, as the case may be, or receipt of reply from the Project Proponent/s in respect of any requisition made by him, whichever is later. Such master layout approval will be given with the condition that project proponent will not commence work without environmental clearance. Such environmental clearance shall be submitted at the time of sanction to the building permission. Sanctioned master Plan layout along with complete set of drawings shall be endorsed to the concerned branch office of Town Planning Department, ⁽¹⁾ as required for the further permissions.

⁽¹⁾ Modified vide Notification u/s.37(1AA)(c) & 20(4) bearing No.CR.105/2022/(Part-2)/UD-13, dt.05th September, 2024

- v) Approval to the Master Plan :- The Collector ⁽¹⁾ or the Authority, as the case may be, shall grant approval to the master layout or reject the application, under Section 18 ⁽¹⁾ or section 45, as the case may be of the said Act, within one month from the receipt of reply from the Divisional Joint Director of Town Planning as mentioned in Regulation No.14.1.1.6 (iv) above.
- vi) Approval to the building plan :- Detailed building permission under the master layout plan sanctioned as per Regulation No.14.1.1.6(v) shall be granted by the Assistant Director of Town Planning / ⁽¹⁾ Town Planning / Town Planner of concerned Branch ⁽¹⁾ or by the Authority, as the case may be, with prior consultation as prescribed in proviso to Regulation 14.1.1.12 (iv), within 30 days from the receipt of the proposal from the project proponent as mentioned in (a) below.
- a) The Project Proponent/s shall apply to the concerned head of the Branch office of the Town Planning Department ⁽¹⁾ or to the Authority, as the case may be, for grant of building permission, alongwith all relevant documents and attested copy of Environment Clearance for the project from MoEF or the Authority empowered by the MoEF.
- b) ⁽¹⁾ The Project proponent/s shall give intimation through his Architect, in the prescribed form in Appendix - F of UDCPR to Concerned Branch Office of Town Planning or to the Authority, as the case may be, after completion of the work upto plinth level. This shall be certified by Architect / Licensed Engineer / Supervisor with a view to ensure that the work is being carried out in accordance with the sanctioned plans. After such intimation, the construction work shall be carried out further. The branch office of the Town Planning or the Authority, as the case may be, who are empowered to grant Development Permission, shall inspect about 10% of such plinth certified cases. If it is found that the construction of plinth is not as per the building permission sanctioned, the said office shall reject such plinth checking certificate. In such circumstances, the Project Proponent/s shall either demolish the said plinth or get the ⁽¹⁾revised plan sanction according to changes.

14.1.1.7 Planning Considerations :-

i) Permissibility in respect of Zoning :-

- a) Notwithstanding anything contained in any regulation for the time being in force, the project to be notified under this regulation may be permissible in any land-use zone/s of sanctioned Regional Plan / Development Plan, excepting areas mentioned in Regulation No.14.1.1.2(v).
- b) For the areas falling in zones, other than residential, commercial and ⁽¹⁾ U zone as per the sanctioned Regional Plan ⁽¹⁾ or Development Plan, as the case may be, the Project Proponent/s shall have to pay a premium for permitting project in such zones at the rates prescribed below in Table No.14-A ⁽¹⁾ This provision only applicable to new ITPs in Development Plan Areas. :-

Table No.14-A		
Sr.No.	Type of Zone	Premium Charges
1	Afforestation Zone, Hill Top & Hill Slope Zone as shown on Regional Plan / Development Plan.	15 %
2	Public / Semi-public Zone, Industrial Zone, T.H. & L.P.	8 %

⁽¹⁾ Modified vide Notification u/s.37(1A)(c) & 20(4) bearing No.CR.105/2022/(Part-2)/UD-13, dt.05th September, 2024

3	Agriculture / No Development Zone / G - 1 zone / Low Density Residential Zone / Buffer Zone of ESZ ⁽¹⁾ Mangroves / CRZ whether shown on Regional Plan / Development Plan or not and other zones excepting at Sr.No.a & b above.	10 %

Explanation : Premium charges shall be calculated by considering the agriculture land rate of the said land as prescribed in Annual Statement of Rates (ASR) without applying the guidelines. If agriculture land rate is not mentioned in ASR, in such cases the Agricultural land rate for such land will be decided by referring the matter to the Inspector General of Registration. Thereafter the premium will be calculated by considering the land rate given by IGR in such cases. Out of total premium 10% shall be paid at the time of Locational Clearance, 10% paid at the time of letter of Intent, 20% at the time of sanctioning of Master Layout Plan and remaining 60% shall be in four equal installments per year and subject to interest as per Prime Lending Rate. (PLR)

- c) Restriction on development-No construction shall be permitted on the lands within the HFL (Blue line), land in Hill Top & Hill Slope Zone and on lands having slope equal to or more than 1 : 5 in the said Project, whether specifically marked as such on the Regional Plan / Development Plan or not. No development of any sort and activity involving cutting / levelling / filling shall be permissible on such sloping lands. Provided that, it shall be permissible to use such lands for Plantation, Park, Garden purposes, access road to township development with minimum cutting and other users as otherwise permissible in respective Regional Plan / Development Plans and the FSI of such lands shall be permissible to the extent as prescribed in Regulation No.14.1.1.7(ii).
- d) In the Buffer zone of notified ESZ and in ESZ's, only those development activities and FSI as permissible under MoEF notification of the ESZ (as amended from time to time) under Environment Protection Act, 1986 shall be permitted. All the development in this buffer zones shall be in accordance with MoEF notifications.

ii) Permissible Floor Space Index (FSI) :-

- a) Notwithstanding anything contained in any regulation for the time being in force, if premium as mentioned in 14.1.1.7(i) (b) is paid by the project proponent then the basic permissible FSI for such project shall be 1.0 to be calculated on Gross Plot Area under Master Layout Plan without deducting any areas under the slopes within HFL, etc.
- b) Further, ⁽¹⁾100% additional FSI shall be permissible on payment of premium at the rate of 10% of the weighted average land rate of the said land as prescribed in Annual Statement of Rates for the relevant year, without applying the guidelines therein. Such premium shall be paid at the time of Building permission.
⁽¹⁾ (Table Deleted)
- ⁽¹⁾ It is proposed to permit Incentive FSI at par with the Provisions of UDCPR-2020 for construction of Green Buildings / ECGC Building in the ITPs.
- c) Over and above the FSI as prescribed above, an additional FSI in lieu of construction of tenements for social housing shall be permissible as prescribed in Regulation No.14.1.1.9, without charging premium.
- d) It shall be permissible to utilise the maximum permissible built-up area as prescribed above, anywhere in the area under sanctioned Master Layout Plan.
- ⁽¹⁾ Ancillary FSI is permissible in ITP. In the result, free of FSI items in the said scheme, if any, other than mentioned in UDCPR shall stand deleted.)

⁽¹⁾ Modified vide Notification u/s.37(1AA)(c) & 20(4) bearing No.CR.105/2022/(Part-2)/UD-13, dt.05th September, 2024

iii) Mandatory Town-Level Amenities - Area and FSI Allocations :-

Master Layout Plan shall provide for town-level area and FSI allocation, to be kept at one or more places, as follows :-

a) Spaces for Recreation

Table No.14-C			
Sr. No.	Particulars	Minimum Area Required	Conditions
i	Garden/s and Park/s	5% of Master Layout Area. (out of this 50% area may be allowed on Hill Top Hill Slope Zone, Buffer Zone of ESZ and within HFL)	Out of this at least 1000 sq.m. area shall be kept open for Town Plaza / Town Square, at one place and remaining area shall be kept open and may be allowed to be proposed at suitable places. Major public amenities / activities shall be cluster around this area.
ii	Play Ground/s	7.5% of Master Layout Area (may be allowed in Buffer Zone of ESZ having slope less than 1:5)	Maximum 10% of area under Play Ground which may accommodate indoor games, stadiums and allied users only.

Note - These spaces shall be exclusive of open spaces to be required at sector-level layouts. Notwithstanding anything contained ⁽²⁾ UDCPR, 10% open space shall be provided in sector level layout. Such open space shall be calculated by considering area of the sector excluding roads in Master Layout Plan and Town Level Amenity spaces excepting Economic Activities.)

b) Spaces for combined School/s (Primary School/s + High School/s) -

Table No.14-D			
Sr. No.	Particulars	Minimum Area Required	Minimum Built-up Area required
i	For Master Layout area of 40 Ha.	5,000 sq.m.	5,000 sq.m.
ii	For Master Layout area more than 40 ha.	To be increased proportionately with increase in Master Layout area and be proposed at one or more locations, as per requirements.	

Note –

- 1) The requirements prescribed above are by considering School to be run in double shift,
- 2) Requirement of plot area and built up area shall be exclusive of Play Ground spaces. Hence it is mandatory to show separate Play Ground adjoining to school building at the rate of 7 sq.m. / student.

c) Community Health Care Facilities :- Primary and Secondary Health Care Facilities like Dispensary, Maternity Home, Hospital etc.

Table No.14-E			
Sr. No.	Particulars	Minimum Area Required	Minimum Built-up Area required
i	For Master Layout area of 40 ha.	1,000 sq. m.	1500 sq. m.
ii	For Master Layout area more than 40 ha.	To be increased proportionately with increase in Master Layout area and be proposed at one or more locations, as per requirements.	

⁽²⁾ Substituted vide Corrigendum / Addendum No.CR.121/21, dt.02nd December, 2021

d) Community Market :-

Table No.14-F			
Sr. No.	Particulars	Minimum Area Required	Minimum Built-up Area required
i	General Market including Mutton and Fish Market		
	For Master Layout area upto & inclusive of 200 ha.	1000 sq.m.	As per requirement
	For Master Layout area more than 200 ha.	To be increased proportionately with increase in Master Layout area and be proposed at one or more locations, as per requirements.	
ii	Vegetable Market		
	For Master Layout area upto & inclusive of 200 ha.	1000 sq.m.	As per requirement
	For Master Layout area more than 200 ha.	To be increased proportionately with increase in Master Layout area and be proposed at one or more locations, as per requirements.	

Note - Users mentioned in (i) & (ii) above may be clubbed together for convenience purpose, without altering the requirements in plot area and built-up area.

e) Public Assembly Facilities :- Town Hall and / or Auditorium including Library

Table No.14-G			
Sr. No.	Particulars	Minimum Area Required	Minimum Built-up Area required
i	For Master Layout area of ^(a) 40 Ha.	^(a) 4000 Sq.m.	5000 Sq.m.
ii	For Master Layout area 200 hect upto 200 Ha.	^(a) 5000 Sq.m.	^(a) 5000 Sq.m.
iii	For Master Layout area more than 200 Ha.	To be increased proportionately with increase in Master Layout area and be proposed at one or more locations, as per requirements.	

f) Economic Activities :- Economic activities including users such as Market, Multiplex, Mall, Information Technology & Information Technology enabled Services (IT & ITES) including SEZs, Essential Shopping, Recreational Centres, Trade & Commerce, Education, Hospitals, Non-polluting Industries, Service Industries, Entertainment, Tourism, Star Category Hotels, Convention Centres, Gymnasiums, Socio-economic activities such as workshop, hostel for Autistic persons, challenged persons and Senior Citizens except independent residential tenements as per requirements.

^(a)

Table No.14-H			
Sr. No.	Particulars	^(a) (Deleted)	Minimum Built-up Area required
i	For Master Layout area of 40 ha.	^(a) (Deleted)	80000 sq.m.
ii	For Master Layout area more than 40 ha.	To be increased proportionately with increase in Master Layout area and be proposed at one or more locations, as per requirements.	

^(a) Modified vide Notification u/s.37(1AA)(c) & 20(4) bearing No.CR.105/2022/(Part-2)/UD-13, dt.05th September, 2024

Note :-

- ⁽ⁱ⁾ 1) No dedicated plot shall be insisted for economic activities. Such activity may be allowed in the ITP area at suitable location/s and in composite building also. Economic activities component users may be clubbed together with activities mentioned in c and d above, subject to condition that, total built-up area should not be less than the summation of minimum required for all such users and other use restrictions as mentioned in UDCPR.
- 2) However, for the additional FSI availed by paying premium, additional built-up area for economic activities shall be provided @ 10%.
- 3) If any area as mentioned in 14.1.1.2 is excluded by the project proponent for calculation of FSI, then the mandatory town level amenities and 2% area to be handed over to local authority shall be calculated on the net area by deducting such excluded area from the gross plot.

g) Public Utilities :- For Master Layout area up to & inclusive of 200 ha.

Table No.14-I			
Sr. No.	Particulars	Minimum Area Required	Permissible Built-up Area
i	Fire Brigade Station	3000 sq.m. or as prescribed by the Director of Fire Services, Maharashtra State / Chief fire Officer of the concern Authority.	As per recommendations of the Director of Fire Services, Maharashtra State / Chief fire Officer of the concern Authority.
ii	Sewage Waste Management Project (SWMP)	4000 sq.m.	As per requirements
iii	Cremation Ground	2000 sq.m.	As per requirements
iv	Burial Ground	2000 sq.m.	As per requirements
v	Bus Station / Transport Hub	3000 sq.m.	
vi	Police Station	1000 sq.m.	
vii	Electric Sub-station	As per requirement	
viii	Other Public Utilities	As per requirement	
ix	Public Parking Facilities	As per prevailing DCR	
x	Solid waste management	As per requirement	

Note :

- 1) If the facility of Cremation Ground / Burial Ground is available in the village where the Township is located in such case these requirements need not be insisted subject to NOCs ⁽ⁱ⁾ from respective ⁽ⁱ⁾ local Planning Authority, as the case may be.
- 2) If Police Station is available within 1km. area from the proposed Township, then such facility need not to be provided.

h) Transport & Communication :-

- i) The entire area of the project shall have a proper road pattern, taking into consideration the linkages with existing roads ⁽ⁱ⁾ or proposed Regional Plan / Development Plan roads, within the project and outside area as well. All such roads shall be developed by the Project Proponent/s as per standard prescribed by the Indian Road Congress.

⁽ⁱ⁾ Modified vide Notification u/s.37(1AA)(c) & 20(4) bearing No.CR.105/2022/(Part-2)/UD-13, dt.05th September, 2024

- ii) The width of the -
- Classified Road should not be less than as may be prescribed by concerned public authority;
 - Main / Arterial / Ring Road should be of minimum right of way of 18.0 m.
 - Other Sub-Arterial roads, Collector streets, local streets, etc. shall be proposed as per the requirements to cater to the need of occupancies on such roads including for pedestrians.
 - Network of cycle track in entire Township area of minimum width of 3.0 meter shall be provided without clashing with the vehicular traffic, to the extent possible.
- iii) It may be permissible for Project Proponent/s, to realign the Regional Plan / Development Plan Roads, and earlier existing roads passing through the project area, without changing the entry and exit points of such roads.
- iv) All the Regional Plan / Development Plan Roads and all the Main / Arterial / Ring Roads, shall always be open for general public, irrespective of the fact that, they resides in the project or not.

General Note for Amenities (a) to (h) :

- The requirements prescribed above for items (a) to ⁽¹⁾ (e) are by considering FSI proposed for the project is only 1.0. If the FSI proposed is increased or decreased then the only built up area requirement shall be increased or decreased proportionately.
- The requirements prescribed above for items (g) are for Master Layout area up to & inclusive of 200 ha. It shall be increased or decreased proportionately and may be proposed at one or more locations, as per requirements.

iv) Residential Activities :-

Table No.14-J			
Sr. No.	Particulars	Area	Built-up Area
i	Residential Activities (including lands required for social housing, infrastructure such as water storage, drainage and garbage disposal, etc.)	The land excluding the land required for purposes as shown (iii) (a) to (h).	Remaining built-up area subject to minimum 60% of the total proposed Basic Residential FSI.

(v) Share of Local / Planning Authority.

- ⁽¹⁾ (a) The integration of Integrated Township Projects included in the Local / Planning Authority, an area @ 2% of ⁽¹⁾ (--) area ⁽¹⁾ after deducting area of development plan / Regional Plan Reservation, if any (excluding D.P. / R.P. roads / road widening) shall be earmarked and shall be handed over free of cost to the respective Authority for development of the City Level Facilities. ⁽¹⁾ However this provision shall not be applicable to the 2% amenities space which is already handed over to the Planning Authority.

For determining eligibility of ITP, the above 2% area shall be considered in area calculation. This area shall not contain area under hill slopes, and shall be accessible by major road. Base FSI of such 2% land shall be made available to the ⁽¹⁾ project proponent/s on remaining land ⁽¹⁾ of the ITP area.

- ⁽¹⁾ (b) If the Project Proponent/s constructs the amenity as per norms prescribed by the Authority and handed over the same to the Authority then he shall be entitled for Amenity Construction TDR as per Regulation No.11.2 of UDCPR. Such TDR can be utilised within the same Local Planning Authority area or within the ITP area over and above ITP potential subject to other provisions of Regulation No.11 of UDCPR.

⁽¹⁾ Modified vide Notification u/s.37(1AA)(c) & 20(4) bearing No.CR.105/2022/(Part-2)/UD-13, dt.05th September, 2024

⁽ⁱ⁾ Also provided that, if the land is handed over to Planning Authority and Project Proponent is willing to construct the amenity in this land, then he will be eligible for the Amenity Construction TDR.

⁽ⁱ⁾ (vi) Accommodation Reservation (AR) Policy :-

The Development Plan reservations included in the ITP area may be developed as per the provisions of Accommodation Reservations (AR) i.e. Regulation No.11 of UDCPR subject to following conditions :-

- a) Area to be handed over to the Local Planning Authority and area to be retained with the Project Proponent/s as per AR Regulations shall be an integral part of ITP and area / construction allowed to the Project Proponent/s may be developed anywhere within the ITP boundary.
- b) If the area of Reservations (excluding D.P. Roads / Road Widening) is more than 51% of the area of the Master Plan Layout then such situation can be considered as hardship and a composite building may be allowed by charging premium for Land component @ 20% of the average ASR rate of ITP. However if area of reservations (excluding D.P. Roads / Road Widening) is more than 70% of the area of the Master Plan Layout then such premium shall be @ 10% of the average ASR rate of ITP.
- c) Construction TDR generated by implementation of AR Regulations may be allowed to be utilised within the same Local Planning Authority area or within the ITP area over and above ITP potential subject to other provisions of Regulation No.11 of UDCPR.
- d) Outside TDR shall not be applicable within ITP area.
- e) However, this provision of AR shall not be applicable for the area of Reservations which is already handed over to the Planning Authority.

14.1.1.8 Development Control Regulations :-

For those aspects which are not covered under this regulation, the prevailing provisions as prescribed in the ⁽ⁱ⁾ sanctioned UDCPR, as modified from time to time for Regional Plan or Development Plan, as the case may be, shall apply mutatis-mutandis. The provisions of MoEF CRZ notifications amended from time to time shall also be applicable.

⁽ⁱ⁾ Notwithstanding anything contained in UDCPR applicable for respective Authorities, the maximum height of building, as permitted by the Chief Fire Officer or Director, Maharashtra Fire Services shall be allowed, subject to provisions of Maharashtra Fire Prevention and Life safety measures Act 2006 and any restriction imposed by Chief Fire Officer.

14.1.1.9 Social Housing :-

- i) The Master Layout Plan shall provide sufficient space for construction of small tenements for persons from EWS and LIG categories (hereinafter referred to as the “Social Housing Component”), as a social responsibility with FSI as mentioned in Regulation No.14.1.1.9 (iii). Out of this Social Housing Component 25% FSI shall be utilised exclusively for construction of EWS tenements and remaining 75% FSI may be used for LIG tenements. Out of the total tenements constructed as Social Housing component, one third (1/3rd) tenements shall be kept for Rental Housing tenements which will be disposed on Rent only by the project Proponents.
- ii) Social Housing tenements shall be constructed with area as specified by the MHADA for EWS and LIG category respectively.
- iii) The minimum Social Housing component shall be constructed at 15% of the Residential basic FSI of the area available for Residential Development as prescribed in Regulation No.14.1.1.7(iv) (hereinafter referred to as the “Social Housing component”).

⁽ⁱ⁾ Modified vide Notification u/s.37(1A)(c) & 20(4) bearing No.CR.105/2022/(Part-2)/UD-13, dt.05th September, 2024

- iv) Social Housing tenements shall be constructed as per the general and special specifications prescribed by concerned unit of MHADA for their projects.
- v) The Project Proponent/s, after getting commencement certificate of Social Housing component as mentioned above shall immediately intimate to MHADA regarding the numbers of Social Housing Component to be disposed by them to the allottees. Upon such intimation, MHADA within a period of six months, from the date of receipt of such intimation after following procedure of lottery system shall prepare the list of the allottees from the district as far as possible and forward it to the Project Proponent/s. The project proponent shall dispose of such housing tenements to the allottees at the construction cost mentioned in ASR applicable of the year of disposal (date of occupancy certificate) plus 25% additional cost. Out of this 25% additional cost, 1% shall be paid to MHADA towards administration charges.
If the allottees fail to deposit the amount within specified time limit, then the allotment shall stand cancelled and MHADA can give fresh names of allottees from waiting list within one month.
Provided that if the MHADA is unable to provide the list of the allottees as mentioned above then the project proponent shall dispose of such social housing tenements in the market at the construction cost in ASR applicable to the land of the year of disposal plus 20% additional cost.
- vi) Every Occupation Certificate for the regular tenements shall be granted only alongwith the Occupation Certificate in proportionate with Social Housing component.
- vii) Amalgamation of such Social Housing tenements shall not be permitted in any case.
- viii) The purchaser of tenement under social housing shall deposit an amount equivalent to 10% of the construction cost of tenement, as prescribed in Annual Statement of Rates prevailing at the time of occupation, with the Project Proponent/s as one-time maintenance deposit for onsite infrastructure maintenance.
- ix) The Project Proponent/s shall maintain the premises and common spaces outside the building/s of social housing including concerned all basic infrastructure and amenities, in good condition in the same manner with the maintenance of remaining area of the project.
- x) The purchaser of tenement under social housing shall have to pay all the government taxes, duties like stamp duty, GST etc. and also the fees charged for use of common amenities at actual, to the Project Proponent/s, as per the requirement, from time to time.

14.1.1.10 Liability of Project Proponent/s :-

- i) The entire project shall be an integrated one with all facilities within the boundaries of such project. All the on-site infrastructure i.e. internal roads, approach road, street lights, water supply and drainage system shall be mandatory and constructed / maintained in future by the Project Proponent/s. Proposed internal roads and Open Spaces in the layouts shall be used only for ITP.
- ii) ⁽¹⁾ The Development Plan / Regional Plan Reservations, as the case may be, which are included in ITP shall be developed and handed over by the Project Proponent to the concern Authority, for the use of general public in lieu of TDR or as per regulations of Accommodation Reservation, such Reservation may be allowed to be developed. Such reservations may be allowed to be shifted within Township Area, preferably along the boundary facing developed area so that general public can access these Reservations / Amenities without entering ITP area. In case of Regional Plan such relocation shall be carried out in consultation with the concerned Divisional Joint Director of Town Planning and in case of Development Plan in Consultation with concerned Planning Authority.

⁽¹⁾ Modified vide Notification u/s.37(1AA)(c) & 20(4) bearing No.CR.105/2022/(Part-2)/UD-13, dt.05th September, 2024

- iii) It shall be the responsibility of the Project Proponent/s to develop and maintain all the infrastructure in good condition till handing over to the appropriate authority.

The project proponent may collect periodical contribution or raise corpus funds for the maintenance of infrastructure from the purchasers of tenements or statutory bodies of the purchasers of tenements formed by the developer for this purpose.

Provided that, the Project Proponent/s shall handover the infrastructure, for maintenance purpose, only after the completion of the project, to the Urban Local Body or appropriate authority, when constituted in the area comprised by the project along with the unutilized corpus fund collected for maintenance of common infrastructure.

- iv) Project Proponent/s shall mandatorily provide facilities for making the Township SMART-
- a) For the people residing in the project area, an efficient and timely public transportation system up to the nearest public transportation station / hub / depot / stand. He shall develop it himself or tie with Government / Semi Government ⁽¹⁾ / Planning Authority or private transport agency for such efficient public transportation. The number of buses and trips will be decided by MSRTC / Local Transport Authority;
 - ⁽¹⁾ **National highways and state highways** : Lands underneath shall be transferred to concerned authorities by project proponent in lieu of compensation. Such lands however shall be counted towards the requirement of minimum area of ITP.
 - ⁽¹⁾ **Other DP roads** : Land underneath shall be transferred to SPA or local authority by project proponent in lieu of FSI. Such lands however shall be counted towards the requirement of minimum area of ITP. Also, if project proponent so desires, then with the approval of SPA / local authority project proponent may construct the road in lieu of construction TDR as per the design and specification approved by SPA / local authority.
 - b) Continuous unobstructed footpath of minimum 2.0 m. width on either sides of all street / roads of width ROW 12.0 m. or more and of a lesser width for roads / Streets of ROW less than 12.0 m;
 - c) Dedicated and physically segregated bicycle track with a width of 3.0 m. or more, should be provided for entire Township Area;
 - d) Pedestrian friendly pathways, encouragement to non-motorized transport, intelligent traffic management, non-vehicle street / zones, smart parking, energy efficient street lighting visible improvement in the area i.e. replacing existing overhead electric wiring with underground wiring, encroachment free public areas;
 - e) Arranging generation of power through non-conventional energy sources like solar, wind and other shall be mandatorily provided with at least 10% of total requirement of common physical infrastructure of the project;
 - f) To provide energy management by adopting advanced technology like installing Solar Water Heating System, Solar Lamps / Lights in common areas, LED Lamps, auto-operated street lights, solar pumps, etc. all external lighting shall be of LED, Solar Water Heating System, Solar Lamp shall be compulsorily provided;
 - g) To provide effective water management by adopting water harvesting techniques like rain water harvesting, recycling of used water, metered water supply to the users under project, double plumbing pipeline. The recycled water shall be used for flush system, gardening, carwash and industrial use;
 - h) To provide effective safety & security measures like CCTV surveillance at strategic locations, centralized control room, etc.;
 - i) Arranging smart and fast internet / broad band connectivity to all residences, e-governance online system for grievance redressal;

⁽¹⁾ Modified vide Notification u/s.37(1A)(c) & 20(4) bearing No.CR.105/2022/(Part-2)/UD-13, dt.05th September, 2024

- j) Encouraging and providing platform for citizens participations in decision making about public community issues;
 - k) Arranging real time environmental monitoring i.e. air pollution, noise pollution etc. shall be observed;
 - l) Encouraging and providing platform for e-DCR for building plans with BIM, 3-D maps on GIS of the utility services network and properties in the city, central command, control and emergency response center for all infrastructure facilities. Project Proponent/s shall also provide urban design concept plans along with Master Plan;
 - m) It shall be obligatory on the part of Project Proponent/s to provide the infrastructure and green building norms that are necessary as per the guidelines as may be laid down by the Government, under the policy of development of 'Smart City' from time to time;
 - n) Ensure that the buildings have at least 3 star ratings from GRIHA / ⁽²⁾ Silver from IGBC / Silver from LEED / equivalent rating from the ASSOCHAM GEM.
- v) **Project Proponent/s shall also mandatorily provide for :-**
- a) **Water Supply** - Safe and potable drinking water at the rate of 90 liters per capita per day, exclusive of requirement of water for fire fighting and gardening purposes. The storage capacity of the same shall be at least 1.5 times of the actual required quantity as determined by expected population (Resident and Floating) and other uses. The Project Proponent/s would be required to develop proper internal distribution with double pipe plumbing for reuse of treated water at appropriate places and maintenance system along with smart metering and shall specially undertake rain water harvesting, groundwater recharging and waste water recycling within the project.
Provided that, the Project Proponent/s should not use groundwater as a source of water, to meet the above requirement.
 - b) **Drainage and Garbage Disposal** - The Project Proponent/s shall make suitable and environment friendly arrangements for the disposal and treatment of sewage and solid waste generated in the project at source, as per the norms of the Maharashtra Pollution Control Board. The Project Proponent shall provide zero discharge in ITP for solid as well as liquid waste.
The Project Proponent/s should provide facilities for water conservation by different means such as Rain Water Harvesting, Recycling of Waste Water, etc. and also set-up, in the project area itself, the Solid Waste Management Project (SWMP) with a sufficient capacity for processing of 100% garbage and solid waste.
 - c) **Power** - The Project Proponent/s shall ensure continuous and quality power supply for the project area. The Project Proponent/s may draw the power from any existing supply system or may go in for arrangement of captive power generation with the approval from the concerned authority. If power is drawn from any existing supply system, the Project Proponent/s shall, before commencement of development, procure a firm commitment of power for the entire Township from the power supply company.

14.1.1.11 Occupancy Certificate :-

- i) Application for obtaining the Occupancy Certificate for buildings in project, in full or part shall be submitted by Project Proponent/s to the concerned branch Officer of Town Planning ⁽¹⁾ or to the concerned Authority, as the case may be. Such application shall be accompanied by -
 - a) All the relevant documents alongwith coloured Google Earth / Bhuvan / Drone survey image showing the area under Master Layout Plan;

⁽²⁾ Inserted vide Corrigendum / Addendum No. CR 121/21, dt. 02nd December, 2021

⁽¹⁾ Modified vide Notification u/s.37(1A)(c) & 20(4) bearing No.CR.105/2022/(Part-2)/UD-13, dt.05th September, 2024

- b) Documents showing compliance of the conditions prescribed while according sanctions from time to time;
- c) Appropriate declaration/s and undertaking/s made by the Project Proponent/s and his technical personnel's;
- d) Any other requirement as may be prescribed by the Collector.
- ii) The concern Branch Officer of Town Planning ⁽¹⁾ or to the concerned Authority, as the case may be, shall grant Occupancy Certificate or reject the application giving specific reason within one month from the receipt of application.
- iii) The ⁽¹⁾ concerned Collector ⁽¹⁾ or the Authority, as the case may be, before issuing the Occupancy Certificate for the project as a whole, shall verify and satisfy himself about the completion of erection / development / construction of all the basic required infrastructure in Master Layout plan. In case, an application for part occupancy, such completion shall be as prescribed in phase programme.

14.1.1.12 General Stipulations :-

- i) Development of basic infrastructure and amenities shall be completed by the Project Proponent/s to the satisfaction of the Collector ⁽¹⁾ or the Authority, as the case may be either for whole or as per phases, of the project.
- ii) It shall not be mandatory for the Project Proponent/s to provide Amenity Space as otherwise required as per regulation of Regional Plan / Development Plan, if any.
- iii) The Project Proponent/s shall plant indigenous trees at the rate of at least 150 trees per ha. and maintain it properly. The certificate to that effect issued by the Deputy Conservator of Forest or an Officer nominated by him for this purpose shall be produced by Project Proponent/s at the time of application for Final Occupation Certificate under Regulation No.14.1.1.11.
- iv) All the powers and functions that are supposed to be exercised by the Collector under this regulation shall be exercised by the ⁽¹⁾ Authority of the concerned Planning Authority wherever applicable, excepting the powers to grant Letter of Intent under Regulation No.14.1.1.5 of this regulation.

Provided that, before grant or refusal to the Master Layout Plan, the ⁽¹⁾ Authority shall, consult the concerned Divisional Joint Director of Town Planning as prescribed in Regulation No.14.1.1.6 (iii) and (iv), if the Planning Officer posted in such Authority is below the rank of Joint Director of Town Planning, and to the concerned branch office of Town Planning as prescribed in Regulation No.⁽²⁾14.1.1.6(vi) and Regulation No.14.1.1.11, if the Planning Officer posted in such Authority is below the rank of Assistant Director of Town Planning.

- v) All the amounts of scrutiny fees, charges, premium etc. payable to the Government shall be deposited with the concerned Branch office of the Town Planning. In circumstances described in proviso of Regulation No.14.1.1.12(iv) above, 50% of such amount shall be deposited with the concerned Branch office of the Town Planning, and 50% to the concerned Planning Authority.
- vi) The Project Proponent/s shall submit a bank guarantee of an amount equal to the 15% of estimated development cost required for development of the basic Physical infrastructure such as roads, water supply, drainage & garbage disposal, Trunk installations for power supply, fire brigade station & fire engines. Such development cost be worked out as

⁽²⁾ Inserted vide Corrigendum / Addendum No.CR.121/21, dt.02nd December, 2021

⁽¹⁾ Modified vide Notification u/s.37(1A)(c) & 20(4) bearing No.CR.105/2022/(Part-2)/UD-13, dt.05th September, 2024

per respective phases taking into consideration the phased programme for development of infrastructure with amenities under project as submitted and as required under Regulation No.14.1.1.6(i). Certificate regarding estimated development cost shall be produced by the respective Architect of the project. If Bank Guarantee as mentioned above is submitted then separate security deposit shall not be insisted by the authority.

- ⁽¹⁾ i) Bank Guarantee shall be released as per stages of infrastructure development.
- ii) If the basic infrastructure of the development is done before the commencement of the building, then no need of the bank guarantee at the time of Master Plan. If the infrastructure is getting built before taking the building permission then in such cases also there is no need of Bank Guarantee.
- vii) The Project Proponent/s shall construct and maintain the Fire Station building & Infrastructure at their cost. The project proponent shall post well-trained staff at fire station as per the recommendations of the Director of Fire Services, Maharashtra State / Chief Fire Officer of the concerned Authority or the cost of staff appointed by Chief Fire Officer for this purpose shall be borne by the Project Proponent. The amount of all expenditure on such staff shall be the responsibility of the Project Proponent/s. After completion of fire station and as per requirement such fire brigade / station shall be handed over to the nearest respective authority on the terms and condition decided by the respective authority and project proponent.
- ⁽¹⁾ Provided that, if such fire station building and infrastructure is handed over to the concerned Planning Authority, in such cases, the expenditure on establishment and expenditures shall be borne by the concerned Planning Authority.
- viii) Developer shall complete the Special Township Project within 10 years or such period as allowed by the Government from the approval to the master plan. Developer shall develop and maintain the all infrastructure (internal street light, roads etc.) upto the completion of the ITP project. Within such period or till the authority is formed as per Regulation No.14.1.1.12(ix), the concession in property tax levied by the respective Grampanchayat or the respective Planning Authority shall be 66% of normal rate as prescribed under the Grampanchayat Act or under Maharashtra Municipal Council, Nagar Panchayat and Industrial Town ship Act, 1965 or Maharashtra Municipal Corporation ACT. Such property tax shall be levied from date of Occupancy Certificate. Respective Grampanchayat / Planning Authority shall provide mandatory provisions like Birth and Death Registration Certificate etc. for the same period in such ITP. Provided that the utilities like fire brigade, police station/Chowky etc. shall be handed over to the nearest respective Authority at the terms and condition decided by the respective authority.
- ix) A local Authority shall be formed under section 3 read with section 341 of the Maharashtra Municipal Council, Nagar Panchayat and Industrial Town ship Act, 1965 according to population of such township. The newly formed respective authority shall take over the operation maintenance of infrastructure in the Integrated Township Project area with the previous approval of Government. However, if the area under ITPs merged in any Local Authority then operation and maintenance of infrastructure in such Integrated Township Project area shall be made by the respective Local Authority.
- x) Licensing to the Project Proponent/s - The respective Authority shall provide licenses to the Project Proponent/s for telephone Connection, Power and other utilities in the Township area as per existing rules & regulations. After granting the license from the respective Authority, the project proponent/s shall provide utilities in the Township area as per the conditions laid down by the respective authority.

⁽¹⁾ Modified vide Notification u/s.37(1AA)(c) & 20(4) bearing No.CR.105/2022/(Part-2)/UD-13, dt.05th September, 2024

- xi) It shall be mandatory for the Project Proponent/s to provide appropriate width of road to the land not owned by the project proponent which is surrounded by the Township Area.

14.1.1.13 Special Concessions :-

- i) **Deemed conversion for Non-Agricultural (N.A.) Use :-** The lands under approved Master Layout Plan shall be considered as deemed N.A. No separate permission shall be required under the provisions of Maharashtra Land Revenue Code, 1966. The amount of non-agricultural assessment shall be exempted to the extent of 50% of the normal rate for the land under Integrated Township Project.
- ii) **Grant of Government land :-** The Government land/s, if surrounded or adjacent by the lands owned by the Project Proponent/s, may preferably be granted to the Project Proponent/s, as per the rules and regulations to that effect, by the Revenue and Forest Department of the State Government. Maximum 10% of the total area under township shall be allowed to be included in such township.
- iii) **Concession in Stamp Duty :-** For the purchase of land by project proponent for township area or for the first transaction from Project Proponent/s to Purchaser of any unit under any user from approved Master Layout Plan or subsequent building plan under this Regulation, concession of 50% of stamp duty as otherwise required under the Mumbai Stamp Act, shall be granted. This concession will be available only at one stage i.e. either at the time of land purchase or at the time of sale of units. Also, if the project proponent assigns the rights to his own subsidiary companies for the running of the Amenities in such Township project as per the approved plan in such cases concession of 50 % of stamp duty as otherwise required under the Mumbai Stamp Act, shall be granted.
- iv) **Exemption in payment of Development Charges :-** 50% of the amount of Development Charges under sub-section (3) of Section 124-F of the said Act shall be exempted for institution use or, change of use of any land or building or, development of any land or building, proposed for project undertaken by a Project Proponent/s under this Regulation.
- v) **Relaxation from Mumbai Tenancy and Agriculture Land Act :-** The condition that, only the agriculturist will be eligible to buy the agriculture land shall not be applicable to the Project Proponent/s for purchasing agriculture land for Integrated Township under this Regulation.
- vi) **Exemption from Ceiling for holding agriculture land :-** The limit for holding agriculture land, stipulated in the Maharashtra Agricultural Lands (Ceiling and Holdings) Act, 1961 shall not be applicable to the Project Proponent/s for development of Integrated Township Project under this Regulation.
- vii) **Exemption from scrutiny fee :-** The amount of scrutiny fee shall be exempted to the extent of 50% of the normal rate for building permission under Integrated Township Project.
- viii) **Exemption from royalty on minor minerals :-** The amount of royalty on minor minerals as per the Maharashtra Minor Mineral Extraction (Development and Regulation) Rules shall be exempted to the extent of 50% for the earth which is extracted while developing the land within Township area and fully exempted if the said excavated material is used in the same project.

14.1.1.14 Transition Policy :-

- i) It shall be permissible for the Project Proponent/s, to whom Special Township Project ⁽¹⁾ITP as per earlier Regulations has already been granted location clearance and / or LOI or the project is on-going wherein part Occupancy Certificate is granted ⁽¹⁾ as per then prevailing Regulation before coming in to force of this Regulation. -

⁽¹⁾ Modified vide Notification u/s.37(1AA)(c) & 20(4) bearing No.CR.105/2022/(Part-2)/UD-13, dt.05th September, 2024

- a) Continue such Special / Integrated Township Project under the erstwhile regulations under which LC is granted without considering these regulations.
- b) If the project proponents wish to develop township according to this regulations then he may apply for grant of ⁽¹⁾ revised Locational Clearance from State Government as per Regulation No.14.1.1.4 alongwith the additional documents mentioned at Sr.No.(j) therein.
- ii) If in case as described in Regulation No.14.1.1.14(i)(b), the construction of the project is on-going and the Occupation Certificate, either in fully or partly has granted or not been granted, it shall be permissible for the Project Proponent/s to choose an option to prefer this regulation subject to payment of premium as prescribed in Regulation No.14.1.1.7(i) and (ii). In such cases premium shall be calculated on balance area which shall be the difference of FSI permitted as per earlier regulation and that being availed as per this regulation.

14.1.1.15 Appeal :-

Anyone aggrieved by an order passed under prevailing byelaws may within forty days of the date of communication of the order prefer an appeal to the Director of Town Planning, Maharashtra State, Pune. The appeal shall be decided within 60 days.

14.1.1.16 Control by the State Government :-

Director of Town Planning, M.S., Pune is authorised on behalf of Government to monitor the Township Project and submit his report once in six months to Government.

14.1.1.17 Government may relax any provisions from these regulation considering the site condition of the particular project.

14.1.1.18 Read the concern Planning Authority / Special Planning Authority constituted under relevant Acts instead Collector, wherever applicable ⁽¹⁾ except the powers to grant Letter of Intent under Regulation No.14.1.1.5.

14.1.1.19 The rate of premium mentioned in the Regulation No.14.1.1.7(i)(b) and 14.1.1.7(ii)(b) can be revised by the Government from time to time.

⁽¹⁾ **Note :-** These proposed modifications are related to the ITP policy of UDCPR and for the effective implementation of UDCPR, these proposed modifications will be applicable to the prevailing ITP policy of the respective DCR of NAINA, CIDCO, MSRDC & PMRDA and the prevailing provisions of ITP policy of respective DCR of NAINA, CIDCO, MSRDC & PMRDA will continue wherein no modifications are proposed.

⁽¹⁾ 14.1.2 ⁽¹⁾ For Development Plan area

⁽¹⁾ Deleted.

14.2 TRANSIT ORIENTED DEVELOPMENT (TOD)

The following regulations in respect of Transit Oriented Development shall be applicable for the areas mentioned herein under. These provisions shall come in to operation where Authorities either have or proposed RTS / Metro-rail / BRTS corridors in their Development Plans and have started implementing them.

14.2.1 ^(#) ⁽¹⁾ For Pune Municipal Corporation Area

⁽¹⁾ 14.2.1 ⁽¹⁾ TRANSIT ORIENTED DEVELOPMENT (TOD)

The planning authority shall ensure execution of complete street design for the success of TOD and enable construction of street oriented buildings while achieving optimum densities in residential, commercial and office buildings.

^(#) Clarification issued Vide Letter No.CR.236/18 (Part 1), dt.14th January, 2021

⁽¹⁾ Inserted vide Notification u/s.37(1AA)(C) & 20(4) No.CR.158/19, dt.10th October, 2022

⁽¹⁾ Modified / Deleted vide Notification u/s.37(1AA)(c) & 20(4) bearing No.CR.105/2022/(Part-2)/UD-13, dt.05th September, 2024

- (i) The Planning authority shall also ensure complete pedestrianisation in the TOD zones for easy movement of the pedestrians to & from station within a period of 1 year from sanction of this regulation.

14.2.1.1 Definitions

- (i) TOD zone :- It is the area 500 m. around the proposed Metrostation boundary as will be delineated by the Planning Authority with the approval of the State Government. Wherever any reservation / amenity space within such distance is utilized for the purpose of transportation as prescribed in these regulations, and the distance of 500 m. shall stand relaxed up to 30%. The TOD zone shall be delineated on ground by the Planning Authority in time bound manner i.e. within 2 months from this notification.
- (ii) Base permissible FSI :- It is the FSI that is otherwise permissible on any land with respect to zone shown as per the sanctioned development plan and the relevant provision of the Principal DCPR excluding the TDR and the premium FSI, redevelopment incentive FSI that can be received.
- (iii) Gross plot area :- Gross Plot Area means total area of land after deducting area under reservation or deemed reservation like amenity space if any, area under D.P. Road and Road widening.
- (iv) Principal DCPR :- Principal DCPR means the UDCPR sanctioned vide notification dt.02.12.2020 and as amended from time to time.

14.2.1.2 Maximum Permissible FSI

The maximum permissible total FSI in TOD zone shall be 4.00 including the base permissible FSI, subject to condition that, the additional FSI over and above the base permissible FSI shall be allowed within the overall limit of maximum permissible FSI, as given in the Table below -

Sr. No.	Road width in m.	Maximum Permissible FSI
1	2	3
1	9.0 m. and up to 12.0 m.	2.50
2	12.0 m. and up to 15.0 m.	3.00
3	15.0 m. and up to 24.0 m.	3.50
4	24.0 m. and above	4.00

Note : The Regulations as pertaining to Ancillary FSI as listed in the principle DCPR shall be applicable on the above mentioned FSI. The Built-up Area Calculation shall be in accordance with Regulation 6.6 of UDCPR.

14.2.1.2.1 Premium to be Paid

Additional FSI Over and above the base permissible FSI of respective land use zones as per principal DCPR may be permitted on the payment of premium.

Rate of premium for the additional F.S.I. as mentioned in Column No.3 above shall be 30% for FSI to be used for tenements of size equal to or less than 60 sq.m. and 35% for remaining FSI to be used for residential and / or commercial use, of the rate of the said land mentioned in Annual Statement of Rates without considering the guidelines therein.

In the area of Planning Authority, 50% of the amount of premium collected should be paid to the Planning Authority in the area concerned with the Urban Transport Project and remaining 50% to the Project Implementing Authority.

In the area of Regional Plans, 50% of the amount of premium collected should be paid to the Government through the District offices of Town Planning and Valuation Department and remaining 50% to the Project Implementing Authority.

⁽¹⁾ Inserted vide Notification u/s.37(1AA)(C) & 20(4) No.CR.158/19, dt.10th October, 2022

(1)

Impact Assessment and Integrated Mobility Plan**14.2.1.2.2**

Such additional FSI over and above the base permissible FSI, shall be granted by the Authority from where the Metro Rail is passing through, after taking into account the Impact Assessment of the implementation of these regulations, regarding the impact on the city and sector level infrastructure and amenities as well as traffic and environment. Such Impact Assessment shall also contain measures to be undertaken to mitigate its likely impact and the Action Plan for implementation of such measures in a time bound manner.

There shall be an Integrated Mobility Plan envisaging inter-linkages between different modes of mass transport, parking management, traffic management and pedestrianisation, non-motorized transport network, last mile connectivity, traffic calming, inter-connected street networking etc.

The impact assessment analysis shall be done by Planning Authority within 4 months containing the remedial measures required regarding upgradation of infrastructure etc. taking into consideration the impact analysis and provisions of sanctioned Development Plan and need of such area falling in TOD Zone. Local Area Plans shall be prepared by Planning Authority with participation of local residents within a period of four (4) months. Such Local Area Plans shall contain complete street design to achieve optimum densities and also to ensure complete pedestrianisation.

14.2.1.2.3

Entire area of plot may be considered for calculating the potential of plot in respect of premium FSI + TDR, but not the basic FSI. Basic FSI shall be calculated on area of the plot remaining with the owner after deducting area under D.P. road / road widening / reservations and amenity space. This shall be applicable in cases where reservation area or amenity space is handed over to the authority.

14.2.1.2.4

In case of plot / plots falling partly within the TOD zone, the FSI permissible shall be as follows, provided that the total area of the plot (plot falling within TOD zone plus plot falling outside TOD zone) shall be as prescribed in the table in regulation no.14.2.1.2 :-

(i) Where 50% or more area of such plot / plots falls within TOD zone, these regulations including FSI shall apply to the total area of such plot / plots.

(ii) Where less than 50% area of such plot / plots falls within TOD zone, these regulations including FSI shall be applicable to the part of plot / plots falling within TOD zone, whereas for the part of plot / plots falling outside TOD zone, these regulations except provisions regarding FSI shall be applicable. The FSI permissible for the part falling outside TOD zone shall be as per Principal DCPR.

Notwithstanding anything contained in any other provisions of these regulations, TDR shall be allowed to be received on the plots within TOD zone, irrespective of its location in congested area / non-congested area as per the Development Plan of Pune subject to condition that it shall be utilised in 1/4th share with premium FSI at every stage of utilization. Such share shall be calculated on the potential remaining after utilizing the in-situ FSI towards Development Plan road, reservation, amenity space, if any, on such land.

However in case of non-availability / shortage of TDR, the Authority, after considering the local situation, may allow utilisation of entire potential with premium FSI. The Planning Authority shall compensate for the same to Metro Project Implementing Authority as per the sharing formula decided by the Government from time to time.

(iii) In case of plot / plots which marginally fall in TOD Zone i.e. less than 10% or 500 sq.m., whichever is less, the land owner / developer shall decide to follow this TOD Regulations or Principal DCPR.

(1) Inserted vide Notification u/s.37(1AA)(C) & 20(4) No.CR.158/19, dt.10th October, 2022

(#) Clarification issued by the Govt. vide Order No.CR.54/2023/UD-13, dt.28th August, 2023

⁽¹⁾ 14.2.1.3 Tenement Size

For any development or redevelopment within TOD zone, size of tenement shall be minimum 25 sq.m. and maximum 120 sq.m. of carpet area and out of total proposed tenements, the tenements equivalent to at least 50% of total FSI shall be of a size equal to or less than 60 sq.m. carpet area except the projects in which rehabilitation of existing tenements is undertaken. In case of redevelopment scheme, size of tenement can be relaxed for Rehab Component subject to other provisions of Principal DCPR. However for free sale component 50% of residual FSI shall be utilise for tenements of size equal to or less than 60 sq.m. carpet area. These tenements shall not be allowed to be clubbed / amalgamated in any case. However, this restriction for the residual FSI shall not be necessary in case of single building redevelopment projects on plots below 1000 sq.m.

In case of building with mixed use, 50% of FSI utilized for residential purpose shall be considered for calculating requirement of tenements of a size equal to or less than 60 sq.m. carpet area.

If the holder / owner of the property needs to build this 50% component at some other location(s) within the same TOD zone / circle, the difference between rate of sale of tenements as mentioned in Annual Statement of Rates shall be paid by the developer to the Municipal Corporation as premium.

14.2.1.4 Permissible mixed use in TOD zone

Mixed use in the form of residential and commercial may be permissible on the residential plot in TOD zone fronting on the road width of 12 m., and above and mix use on plot / plots in commercial plot in TOD zone shall be permissible as per the Principal DCPR and the maximum permissible FSI under this regulation shall be allowed on the payment of premium. Purely Mercantile building office building, schools, colleges, hospitals, hotels, assembly buildings will be permissible on independent plot & Information Technology building will be permissible on independent plot subject to payment of premium. For I.T. Buildings the rate of premium for additional FSI up to 200 % shall be as per regulation No.7.8 of Principal DCPR and for additional FSI over it shall be as required under this regulation.

14.2.1.5 Marginal Distances

Marginal Distances Shall be applicable as per provisions in principle DCPR.

14.2.1.6 Parking

Parking provisions in the TOD Zone shall be at 50% of those as mentioned in UDCPR.

Note : No on-street parking shall be permissible, unless specifically allowed in the integrated mobility plan report.

14.2.1.6.1 Incentive for providing Public Parking in the area falling within the radius of 200 m. from the Metro / MRTS Station.

If the owner / developer of the plot falling within the radius of 200 mt. from the Metro Station is willing to provide Public Parking space over and above the parking spaces required as per regulation No.14.2.1.6 of this regulation, the same shall be allowed without charging premium for such additional area and in that case the overall premium shall be discounted on 50 % of such parking area while calculating premium for additional FSI allowed over and above the base FSI, subject to following conditions :-

- a) Such parking area shall be in the built-upform and shall be handed over to Planning Authority free of cost before granting the Occupation Certificate to the project. The Planning Authority should enter into an agreement with owner / developer for such parking space at the time of granting Commencement Certificate to the project. Such Public Parking area shall be clearly shown on the proposed building plan / layout and a condition to above effect shall be incorporated in the Commencement Certificate.

⁽¹⁾ Inserted vide Notification u/s 37 (1AA)(C) & 20(4) No.CR 158/19, dt. 10th October, 2022

- (i)
- b) The parking area shall have independent access from major road adjacent to the plot and with proper entry and exits.
 - c) The parking area to be made available at individual site shall be at minimum 100 sq.mt. at one place either at Ground floor / Stilt floor or first floor.
 - d) The maximum parking area that can be provided shall be decided by the Authority, as the case may be, on considering the location of such site and the parking requirement.
 - e) A board showing the location of such public parking space should be displayed at suitable places by the Planning Authority.
 - f) Area covered under such parking shall not be counted towards FSI consumption.
 - g) Concerned land owner / developer / society / public company shall not be allowed to operate the public parking.
 - h) The proposed development shall be further subject to such conditions as may be decided by the Authority.

14.2.1.7 In case of development or redevelopment, proposed by the Authority / individual applicant / any other Planning Authority, from the edge of the Metro Rail, within 20 mt. distance on its either side, the concerned Planning Authority before granting such permission for development / redevelopment shall seek prior NOC from the concerned Metro Railway Authority as required under the Metro Railways (Construction of Works) Act, 1978 from the point of view of safety of the Metro Railway and such other related matters.

14.2.1.8 For the matters not provided in this regulation, the relevant provisions of Principal DCPR shall apply. However, in case of any conflict between this Regulation and any other Regulation/s of the Principal DCPR, this Regulation shall prevail for the TOD zone.

14.2.1.9 No Compound wall / fencing shall be permissible on the boundary of plot facing the road and 50% front marginal distance (subject to minimum of 3.0 mt.) shall be kept accessible to the pedestrians to be used as foot paths. However, it shall be permissible for the applicant to construct / erect fencing, on the receded boundary, after leaving the space for pedestrians as specified above.

14.2.1.10 Large wholesale stores having built-up area of more than 500 sq.mt., car dealer showrooms, warehouses / storages, auto service centres, Garages etc. shall not be permissible in TOD zone.

14.2.1.11 Provision of Inclusive housing shall not be applicable in TOD zone.

14.2.1.12 For Gunthewari development regularized under the provisions of Maharashtra Gunthewari Development Act, 2001 and falling in TOD zone, seeking permission for development / redevelopment, these regulations shall apply.

14.2.1.13 In case of independent unit / Bungalow for self-use, such Development / Redevelopment may be allowed within base FSI subject to Principal DCPR.

Notwithstanding anything contained in this regulation, if any development on plot in TOD zone is proposed within base permissible FSI (without TDR or Premium FSI) as per provisions of Principal DCPR, all other provisions of Principal DCPR shall be applicable.

14.2.1.14 The layout of building / group housing layout or standalone building on a plot / plots situated in TOD zone / Circle, over which any development permission granted or any development proposal for which any action is taken and for which occupancy certificate is not granted, may be revised and balance potential, as per this regulation, if any, may be allowed subject to structural stability criteria and provisions in Regulation 1.5 of Principle DCPR and subject to following -

⁽ⁱ⁾ Inserted vide Notification u/s 37 (1AA)(C) & 20(4) No.CR 158/19, dt. 10th October, 2022

- ⁽¹⁾
- a) Parking - For the ongoing buildings, the requirement of parking as per this regulation shall be applicable for the balance building potential.
 - b) Tenement size - For the ongoing buildings, the requirement of tenement size as per this regulation shall be applicable for the balance building potential.

14.2.1.15 The Amount received as scrutiny fee, hardship premium, and premium for additional FSI etc. in TOD zone / circle shall be kept in separate head at Authority level and shall be utilized for development of metro project as per directives issued by Government from time to time.

14.2.1.16 These TOD provisions will also be made applicable to other MRTS projects such as BRTS. The scale of FSI availability will be notified later by the Government for such other projects.⁽¹⁾

^(#) **14.2.2 Pune Metropolitan Region Development Authority area**

For this area, the regulations specified in Regulation No.14.2.1 are applicable *mutatis – mutandis*.

14.2.3 For Nagpur Municipal Corporation and Nagpur Metropolitan Region Development Authority

Following Regulations are applicable for Development / Redevelopment of building falling within Nagpur Metro Rail Corridor (NMRC)

i) Definitions

- a) **Nagpur Metro Rail Corridor (NMRC)** - It is the area falling within 500 m. distance on either side of the Nagpur Metro Rail measured from its Centre line and also includes the area falling within 500 m. distance from the longitudinal end of the last Metro Railway Station. This regulation is also applicable for all the Planning Authorities from where the Metro Rail is passing through.
- b) **Base permissible FSI** - It is the FSI that is otherwise permissible on any land with respect to zone shown as per the sanctioned development plan and the relevant provision of the Principal DCR excluding the TDR and the premium FSI, redevelopment incentive FSI that can be received.
- c) **Gross plot area** - Gross Plot Area means total area of land after deducting area under reservation or deemed reservation like amenity space if any, area under D.P. Road and Road widening.

ii) Maximum Permissible FSI

The maximum permissible total FSI in NMRC shall be 4.00 including the basic permissible FSI, subject to condition that, the additional FSI over and above the basic permissible FSI shall be allowed within the overall limit of maximum permissible FSI, as given in the Table No.14-O below :-

Table No.14-O			
Sr. No.	Minimum Road Width	Plot Area	Maximum Permissible FSI
1	9.00 m.	Below 1000 sq.m.	2.00
2	9.00 m.	1000 sq.m. or above	3.00
3	12.00 m.	2000 sq.m. or above	3.50
4	15.00 m.	2000 sq.m. or above	4.00

Explanation :-

- 1) The maximum permissible FSI as per the above Table shall be determined by satisfaction of both the criterias viz. Minimum Road width as well as plot area,

^(#) Clarification issued Vide Letter No.CR.236/18 (Part 1), dt.14th January, 2021

⁽¹⁾ Inserted vide Notification u/s 37 (1AA)(C) & 20(4) No.CR 158/19, dt. 10th October, 2022

simultaneously. However in case, both these criterias are not satisfied simultaneously, the maximum permissible FSI shall be the minimum of that permissible against each of these two criterias, as illustrated below;

2) Land owner / Developer shall not have option to use TDR in NMRC.

Illustrations : -

Table No.14-P				
Plot Area	Road width			
	Less than 9.0 m.	9.0 m. & above	12.0 m. & above	15.0 m. & above
below 1000 sq.m.	As mentioned in Chapter 6	2.0	2.0	2.0
1000 sq.m. up to 2000 sq. m.	As mentioned in Chapter 6	3.0	3.5	3.5
Above 2000 sq.m.	As mentioned in Chapter 6	3.0	3.5	4.0

a) Premium to be Paid

Additional FSI over and above basic permissible FSI of respective land use zones as mentioned in Chapter 6 may be permitted on the payment of premium as may be decided by the Govt. from time to time.

i) The additional FSI as prescribed in the Table under provision ⁽¹⁾ (ii) above, in case of development / redevelopment proposed in the NMRC with minimum tenement density per hectare of the gross plot area as given below.

Minimum Numbers of Tenements = Gross Plot Area x Maximum Proposed FSI for Residential use x 200 Tenement per Hector.

ii) However, subject to the provisions of regulation ⁽¹⁾ 14.2.3(iii) herein below, if the tenement density proposed is less than that stipulated under ⁽¹⁾ provision (ii)(a)(i), the premium to be paid in that event shall be the additional premium as may be decided by the Govt. from time to time and such premium shall be chargeable on the total additional FSI to be availed beyond the basic permissible FSI.

iii) For construction of buildings mentioned in Chapter 7, the rates of premium shall be as mentioned in the said Chapter.

b) Impact Assessment and Integrated Mobility Plan

Such additional FSI over and above the base permissible FSI, shall be granted by the Commissioner, Nagpur Municipal Corporation / Chairman, Nagpur Improvement Trust, any Planning Authorities from where the Metro Rail is passing through after taking into account the Impact Assessment of the implementation of these regulations regarding the impact on the city and sector level infrastructure and amenities as well as traffic and environment on such NMRC.

Such Impact Assessment shall also contain measures to be undertaken to mitigate its likely impact and the Action Plan for implementation of such measures in a time bound manner. It shall also contain Integrated Mobility Plan envisaging therein inter-linkages between different modes of mass transport, parking management, traffic management and pedestrianisation.

c) The maximum permissible FSI as given in Table under Regulation No.(ii) above shall be calculated on the gross plot area.

d) In case of plot / plots falling partly within the NMRC, the FSI permissible shall be as follows, provided that the total area of the plot (plot falling within NMRC plus plot falling outside NMRC) shall be as prescribed in the table in Regulation No.(ii) above :-

⁽¹⁾ Substituted vide Corrigendum / Addendum No.CR.121/21, dt.02nd December, 2021

- (i) Where 50% or more area of such plot / plots falls within NMRC, these regulations including FSI shall apply to the total area of such plot / plots.
- (ii) Where less than 50% area of such plot / plots falls within NMRC, these regulations including FSI shall be applicable to the part of plot / plots falling within NMRC, whereas for the part of plot / plots falling outside NMRC, these regulations except provisions regarding FSI shall be applicable. The FSI permissible for the part falling outside NMRC shall be as mentioned in chapter 6.

Moreover, the owner shall have option of either to opt for UDCPR provisions in toto or opt for TOD regulations in toto. In case, the owner opts for development as per UDCPR provisions, then he may be allowed to utilise FSI as per TOD regulations over and above the maximum potential mentioned in Table 6-A or 6-G.

- e) Notwithstanding anything contained in any other provisions of these regulations, TDR shall not be allowed to be received on the plots within NMRC, irrespective of its location in congested area / non-congested area as per the Sanction Development Plan of Nagpur.

iii) Permissible mixed use in NMRC :

Mixed use in the form of residential and commercial, fully commercial use may be permissible on the residential plot in NMRC fronting on the road width of 12.0 m. and above. Mix use on plot / plots in commercial zone of sanction Development Plan falling under NMRC shall be permissible as per these Development Control and Promotion Regulations and the FSI permissible as per his Regulation over and above as mentioned in Chapter 6 shall be allowed on the payment of premium, as per subject to Maximum building potential as mentioned in Regulation No.(ii) above.

- iv) Other provisions regarding marginal open spaces shall be governed by the proposed height of structure, as given in the provisions (v) below and should conform to the Maharashtra Fire Prevention and Life Safety Measures Act, 2006 (Maharashtra Act No.III of 2007) as amended from time to time. No building permission shall be issued without NOC of the Fire Officer. Other regulations regarding room sizes, apertures for light and ventilation shall be as per these Development Control and Promotion Regulations in force.

v) Marginal Spaces :

Table No.14-Q			
Sr. No.	Building Height	Side and Rear Margins	Remark
a	15.0 m. and below	H/2-4	Minimum 3.0 m. for Residential minimum 4.5 m. for Commercial and Minimum 6.0 m. for Special Buildings.
b	Above 15.0 m. and upto 24.0 m.	H/5	Minimum 4.5 m. for Residential and Commercial Building and 6.0 m. for Special Building.
c	Above 24.0 m.		Minimum 6.0 m.

Note - 1. Maximum Side / Rear / Front Margin shall be 12.0 m. However if Developer / Owners provides more than 12.0 m. side and rear margins it may be allowed.

Note - 2. The Municipal Commissioner may relax the side & rear marginal distances as per Regulation No.2.4 of UDCPR subject to following provisions.

A) If clear minimum marginal distance is proposed from one side as per these Regulation then other side marginal distance may be relaxed up to 50%.

B) Front margin relaxation to allow additional FSI may be granted subject to condition that the Minimum road width shall be 12.0 m. and above.

Note - 3. In case semi-detached construction as per these regulations, common wall constructed is allowed and marginal distance shall be provided for other side as per these regulations.

(v)(a) No projections shall be allowed in one side marginal spaces as mentioned in Note No.2(A) above so that this marginal spaces remain free from all encumbrances for the movement of fire tenders. However open balconies may be allowed in the marginal spaces where concession as mentioned in Note No.2(A) above is allowed, after leaving minimum 3.0 m. distance from the plot boundaries, subject to Fire NOC.

In case if ramp is necessary from accessibility, such ramp may be allowed after living 6.0 m. clear margin. However such Ramp may be allowed in side margin where relaxation is to granted as per provision mentioned in Note No.2(A) above subject to NOC of the Fire Department.

(v)(b) For calculation of marginal distances, the height of the parking floors (Maximum two floors above the Ground Level) shall not be taken in account, However height of such parking floors will be counted towards the total height of the building for deciding the building as high rise building and for civil Aviation purpose.

(v)(c) Car lift / mechanical parking shall be permissible, as per these regulations as amended from time to time.

vi) Parking :

Parking in the NMRC shall be provided as per the table given below :-

Table No.14-R					
Sr. No.	Occupancy	One parking space for every	Transit Oriented Development Influence Zone		
			Car	Scooter / Motorcycle	Cycle
1	Residential	(a) Tenements having carpet area -			
		From 25 and upto 40 sq.m.	0	1	2
		For 2 units above 40 and upto 60 sq.m.	1	1	2
		For every unit above 60 and upto 80 sq.m.	1	1	2
		For every unit above 80 sq.m.	1	2	1
2	Govt. & Semi Govt. Private business buildings	100 sq.m. carpet area or fraction thereof	1	2	2

Note :-

- 1) Parking spaces for differently-abled persons shall be provided as stipulated in these regulations in each new construction / development / re-development in the NMRC.
- 2) On street parking shall not be permissible, unless specifically allowed in the impact assessment and mobility report.

- (vi)(a)** Incentive for providing Public Parking in the area falling within the radius of 200 m. from the Metro Station.

If the owner / developer of the plot falling within the radius of 200 m. from the Metro Station, is willing to provide Public Parking space over and above the parking spaces required as per the table given in Regulation No.(vi) above of this regulation, the same shall be allowed and in that case the premium to be paid by such developer / owner as per Regulation No.14.2.3(ii)(a) shall be reduced by the amount equal to the premium worked out for 25% of the area earmarked for such additional Public Parking space, subject to following conditions:-

- i) Such parking area shall be in the built-up form and shall be handed over to Planning Authority free of cost before granting the Occupation Certificate to the project. The Planning Authority should enter into an agreement with owner / developer for such parking space at the time of granting Commencement Certificate to the project. Such Public Parking area shall be clearly shown on the proposed building plan / layout and a condition to above effect shall be incorporated in the Commencement Certificate.
 - ii) The parking area shall have independent access from major road adjacent to the plot and with proper entry and exits.
 - iii) The parking area to be made available at individual site shall be at minimum 100 sq.m. at one place either at Ground floor / Stilt floor or first floor.
 - iv) The maximum parking area that can be provided shall be decided by the Commissioner, Nagpur Municipal Corporation / the Chairman, Nagpur Improvement Trust, as the case may be, on considering the location of such site and the parking requirement.
 - v) A board showing the location of such public parking space should be displayed at suitable places by the Planning Authority.
 - vi) Area covered under such parking shall not be counted towards FSI consumption.
 - vii) Concerned land owner / developer / society / public company shall not be allowed to operate the public parking.
 - viii) The proposed development shall be further subject to such conditions as may be decided by the Municipal Commissioner / Chairman, NIT, as the case may be.
- vii)** In case of development or redevelopment, proposed by the Authority / individual applicant / any other Planning Authority, from the edge of the Metro Rail, within 10.0 m. distance from the Metro Rail, on its either side, the concerned Planning Authority i.e. Nagpur Improvement Trust / Nagpur Municipal Corporation before granting such permission for development / redevelopment shall seek prior NOC from the Nagpur Metro Railway Corporation Ltd as required under the Metro Railways (Construction of Works) Act, 1978 from the point of view of safety of the Metro Railway and such other related matters.
- viii)** The provisions of these UDCPR shall be applicable except, express provisions of these TOD regulations. However in case of any conflict between TOD Regulations and any other Regulation/s of UDCPR, TOD Regulations shall prevail for the NMRC.
- ix)** No Compound wall / fencing shall be permissible on the boundary of plot facing the road and 50% front marginal distance (subject to minimum and maximum of 3.0 m.) shall be kept accessible and to be used as foot paths for pedestrians. However, it shall be permissible for the applicant to construct / erect fencing, on the boundary, after leaving the space for pedestrians as specified above.

However for the plots situated on 9.0 m., 12.0 m. & 15.0 m., wide Roads having 100% residential use therefore above rule shall not be made applicable.

- a) Large wholesale stores, auto dealer showrooms, warehouses / storages, auto service centres, Garages etc. shall not be permissible in NMRC.
- b) Provision of Inclusive housing shall not be applicable in NMRC.
- c) For Gunthewari development regularized under the provisions of Maharashtra Gunthewari Development Act, 2001 and falling in NMRC, seeking provisions for Development / redevelopment, these regulations shall apply.
- d) The width of passage shall be minimum 1.2 m. for residential use & 2.0 m. for commercial use.
- e) Above regulation shall be applicable to all the buildings (i.e. newly proposed buildings as well as old buildings for utilization of FSI) in TOD.
- f) In case of redevelopment scheme, size of tenement can be relaxed for Rehab Component subject to other provisions of UDCPR. However for free sale component TOD Regulation shall be made applicable.
- g) In case of independent unit / Bungalow for self-use, such Development / Redevelopment may be allowed within base FSI subject to UDCPR.
- h) The layout of building / group housing layout or standalone building on a plot / plots situated in NMRC over which construction is started and for which occupancy certificate is not granted may be revised and balance potential if any may be allowed as per the above provisions subject to following :-

Marginal Distance – The existing marginal distances including front margin may be allowed for higher floor / floors and necessary relaxation to that extent may be granted by the Municipal Commissioner subject to compliance of all fire requirements and fire NOCs by charging hardship premium. Hardship premium is to be decided by Municipal Commissioner. In any case sanctioned existing marginal / front margin distance shall not be reduced.

14.2.4 For other Municipal Corporations and other Metropolitan Region Development Authority ⁽¹⁾ and CIDCO area

For these areas, the regulations specified in Regulation No.14.2.1 shall be applicable.

14.2.5 Regulations for BRT Corridor in Pimpri-Chinchwad Municipal Corporation.

FSI receiving or development potential of the plot shall be as below.

Sr. No.	Road width in meters	Basic FSI	FSI on payment of premium	Maximum permissible TDR loading	Maximum building potential on plot including in-situ FSI
1	2	3	4	5	6
1	Below 9 m.	1.00	--	--	1.00
2	9 m. and above but below 12 m.	1.00	0.50	0.75	2.25
3	12 m. and above but below 15 m.	1.00	0.50	1.00	2.50
4	15 m. and above but below 24 m.	1.00	0.50	1.25	2.75
5	24 and above but below 30 m.	1.00	0.50	1.50	3.00
6	30 and above	1.00	0.50	1.75	3.25

⁽¹⁾ Inserted vide Notification u/s 37 (1AA)(c) No.CR 236/18 (Part 6), dt. 12th October, 2022

14.3 AFFORDABLE HOUSING SCHEME

- i) The Authority may permit implementation of Affordable Housing Scheme in accordance with the provisions of these Regulations. Affordable Housing Scheme (hereinafter referred to as 'the Scheme') shall be permissible only on the lands situated within the limits of Municipal Corporation.
- a) Affordable Housing Scheme shall be permissible in Residential Zone only and on plots having access from an existing or proposed Development Plan Road having width equal to or in excess of 18.0 m. or an existing road in respect of which Regular Line of Street has been declared under the relevant provisions of Maharashtra Municipal Corporation Act, for a width of 18.0 m. or more. However in case of a proposed road, the land under the said proposed road shall be acquired before the approval of building plans for the Affordable Housing Scheme.
- b) Minimum plot area for the Affordable Housing Scheme shall be 4000 Sq.m., excluding area under D.P. Roads and D.P. Reservations, if any.
- c) The plot under the Scheme shall be independent, unencumbered and contiguous.
- d) The Scheme shall not be permissible in congested areas, demarcated as such on the Development Plan.
- e) Maximum permissible FSI (including the basic FSI of 1.00) under the Scheme shall be 3.00 on the gross plot area, including mandatory layout recreational open space and Amenity Space. The FSI to be utilized shall be in the proportion of 1:3 for the Affordable Housing Component and the Free Sale Housing Component on $\frac{1}{4}^{\text{th}}$ and $\frac{3}{4}^{\text{th}}$ part of the land respectively. Thus Affordable Housing and Free Sale Housing shall be proposed on the same plot of land but on two separate independently buildable pockets.
- f) Under Affordable Housing Scheme, upto 15% of the total built-up area of the Affordable Housing Component may be used for construction of shops / commercial use as per the direction of Urban Local Body and such commercial built-up area shall be handed over to the concerned ULB free of cost.
- g) An Affordable Housing Unit shall be a self-contained dwelling unit of 27.88 sq.m. carpet area. However the carpet area of a Housing Unit shall be 160 sq.ft. / ⁽¹⁾ 25 sq.mt. where the construction under the Rental Housing Scheme/ ⁽¹⁾ Affordable Housing Scheme, as the case may be, has already commenced.
- h) The amenity space for Affordable Housing shall be as per these regulations and it shall be proportionately provided in the area earmarked for the Affordable Housing Component and the area kept for Free Sale Housing component.
 Provided that where the Scheme is to be implemented on a plot in Industrial Zone where the Planning Authority has duly permitted Residential user under the relevant provisions of the Development Control Regulations :-
 - i) no further area shall be required to be kept as amenity space under this Regulation for the Scheme if the area prescribed to be kept as amenity space while permitting residential user in Industrial Zone is equal to or more than 10% of the gross plot area.
 - ii) only the balance area shall be required to be kept as amenity space under this Regulation for the Scheme if the area of amenity space prescribed by the Planning Authority, while permitting residential user in Industrial zone, falls short of 10%.
- ii) a) Notwithstanding anything contained in the relevant provisions of the Development Control Regulations for the respective Municipal Corporation regarding the provision of Amenity Space in general, and also regarding permitting Residential User in Industrial Zone, it shall be obligatory on the Developer / Owner to develop the amenity space for users (hereinafter referred to as prescribed amenity users) such as School, Play Ground,

⁽¹⁾ Inserted vide Corrigendum / Addendum No.CR.121/21, dt.02nd December, 2021

Garden, Health Care Facilities, Multipurpose Hall, Auditorium, etc. with the approval of Authority as per the specifications prescribed by the said Authority, subject to the condition that atleast 50% of such amenity space shall be kept for open users, before seeking Occupancy Certificate for the Free Sale Housing Component of the Scheme, failing which the land under such amenity space shall be handed over free of cost to the Planning Authority and such land shall be developed by the Authority for the aforesaid prescribed amenity users only.

No compensation in the form of TDR shall be admissible to the Owner / Developer for development of such prescribed amenities under this Regulation.

- b) Irrespective of whether the Owner / Developer develops the prescribed amenity users as per the provisions of ⁽ⁱ⁾ Clause (ii) above or fails to do so, the process of handing over the land under such amenity space, along with the developed prescribed amenities, where such prescribed amenities have been developed, shall be completed within one month from the date of application by the Developer / Owner for seeking Occupancy Certificate for the free sale housing component of the Scheme and if such handing over process is not completed within the said period, the occupancy certificate for the free sale housing component of the Scheme shall be withheld by the Authority till such amenity space, along with developed prescribed amenities, where such prescribed amenities have been developed, is handed over to the Authority.
- c) Under the Affordable Housing Scheme, there shall be a welfare hall and a Balwadi at the rate of 30.0 sq.m. for every multiple or part of 200 residential units and an office for Co-operative Housing Society at the rate of 30.0 sq.m. per every multiple or part of 500 residential units which shall be treated as a part of Affordable Housing Component and shall not be counted towards the FSI while computing 3.00 FSI on the site and shall be given along with layout / D.P. roads and shops, free of cost to the concerned ULB. These facilities shall be constructed at locations as suggested by the concerned ULB and shall be transferred free of cost to it.
- iii) Under the Affordable Housing Scheme, off-site infrastructure charges at the rate of 5% of the land rate as given in the Annual Statement of Rates (ASR) prepared by the Inspector General of Registration, Maharashtra State, for the year in which Commencement Certificate is issued (without applying guidelines of ASR), subject to a minimum of Rs.2000/- per Sq.m., shall be paid by the Developer for the built up area, over and above the normal permissible FSI. This amount shall be paid to the concerned ULB.
- iv) **Release of FSI under the Scheme shall be as follows :-**
FSI for Affordable Housing Component and the Free Sale Housing Component under the Scheme shall be released in accordance with the following ⁽ⁱ⁾ Table No.14-S.

Table No.14-S			
Sr. No.	Stages of Release of FSI	Affordable Housing Component*	Free Sale Component*
1.	On Grant of Building Permission / Commencement Certificate up to plinth by Commissioner to the Affordable Housing Project	3.00	1.00
2.	On Completion of 50% BUA of Affordable Component	--	0.75
3.	On Completion of 100% BUA of Affordable Component	--	0.75
4.	On handing over of 25% land and completed Affordable Component	--	0.50
	Total	3.00*	3.00*

⁽ⁱ⁾ Substituted vide Corrigendum / Addendum No.CR.121/21, dt.02nd December, 2021

*** Explanation** - The FSI of 3.00 is to be calculated separately on the one-fourth of plot area for Affordable Housing Component as well as three-fourth of plot area for Free-Sale Housing component.

- v) The Affordable Housing Component under the Scheme shall be handed over along with the $\frac{1}{4}$ th part of the total plot of land, free of cost to the concerned ULB.
- vi)(a) The affordable housing stock created under the scheme shall be allotted by the concerned ULB as follows :-

Table No.14-T			
Percentage	Allotment to	Category of stock	Rate of allotment
50	Respective ULBs for use as PAP ownership free of cost tenements or staff quarters or transit accommodation.	Ownership	Free of cost
25	Government of Maharashtra and its statutory bodies / Govt. undertaking for use as PAP tenements or staff quarters or transit accommodation	Ownership	Free of cost
25	As affordable housing by MHADA subject to the general or specific direction of the Government	Ownership	Free of cost to MHADA which shall dispose of the same as per its policy and drawl of lots

- (b) The affordable housing stock shall be disposed of as per the prevailing policy of MHADA regarding pricing and disposal of its housing stock meant for affordable housing. Each project approved under the Scheme shall be brought to the notice of the Government of Maharashtra and its statutory bodies / Government undertakings by means of press advertisement and if the Government of Maharashtra or any of its statutory bodies / Government Undertakings doesn't place firm requirement for the housing stock earmarked for them in the Scheme before the completion certificate / occupation certificate for the said scheme is issued, the same shall come to the share of MHADA for outright sale as per the prevailing policy of the MHADA.
- vii)(a) The other aspects of the development of affordable housing scheme, not specifically dealt with hereinabove, shall be as per the relevant provisions of UDCPR.
- b) It shall also be permissible for the developer / owner to utilise the FSI available for free sale housing component, fully / partly for any other user otherwise permissible as per UDCPR.
- c) In case owing to genuine hardship and site conditions, relaxation in marginal open spaces is sought by the developer / owner, the authority may consider such request, using its discretionary powers under the UDCPR, subject to the condition that in no case shall the clear marginal open space be reduced below 6.0 m. No premium shall be charged for granting such relaxation in marginal open spaces in respect of affordable housing component of the scheme.

14.4 PRADHAN MANTRI AWAS YOJANA

14.4.1 For Development Plan area

i) For developable zone

In any developable zone such as Residential / Commercial / Public semi-public / Urbanisable Zone / Urbanisable Zone U - 1, U - 2 / Industrial etc., Affordable Housing for

the Economically Weaker Sections (EWS) & Low Income Group (LIG), undertaken by Government / any Institutions authorized by the Government or Owner / any Private Developer (hereinafter referred to “the Project Proponent”), shall be permitted, subject to the following conditions -

Conditions :-

1. These Regulations shall only be applicable for development undertaken under "Pradhan Mantri Awas Yojana" wherein all the tenements shall be constructed for EWS / LIG with the use of latest technology, subject to condition no.3 herein below.
2. Such Development shall be permitted in Industrial Zone only after leaving amenity space as per Regulation No.4.8.1. However, no premium shall be charged for allowing residential use in the form of PMAY in Industrial Zone.
- (#) 3. The permissible FSI for such projects shall be the maximum building potential on the plot mentioned in Regulation No.6.1 or 6.3 subject to maximum 2.5 which shall be treated as allowable basic FSI for such project. No premium FSI or TDR shall be required to be loaded for availing this FSI upto 2.5. However, where building potential as per Regulation No.6.1 or 6.3 exceeds 2.5, in such cases permissibility of availing building potential above 2.5 shall be in the form of premium FSI or TDR or both which may be utilised for the permissible uses under this UDCPR.
4. Out of the FSI allowed in PMAY, 10% of the basic FSI mentioned in Regulation No.6.1 or 6.3, shall be allowed for commercial use.
5. The Municipal Commissioner / Metropolitan Commissioner / Chief Executive Officer / Chief Officer, before granting development permission, shall verify and satisfy himself in respect of the feasibility of providing basic infrastructure facilities like electricity, water supply, sewerage etc. required for the project.
6. The project proponent shall plan proper internal Road network including major linkage upto outside roads, wherever necessary.
7. The project proponent shall provide all the basic facilities and utilities, on-site infrastructure such as Road, Water Line, Drainage Line, Street Light, Waste Water Recycling Plant etc. at his own cost to the satisfaction of the Authority. In no case the burden of providing infrastructure shall lie with the Authority.
Provided that the project proponent shall lay the water, drainage/sewage lines up to the nearest existing lines which are laid by the concerned Planning Authority.
8. The carpet area of the tenement shall not be more than the carpet area as may be decided by the Government of Maharashtra from time to time in respect of EWS / LIG Housing.
9. Amalgamation of two or more tenements shall not be permissible under any circumstances.
10. All other guidelines and norms shall be followed as may be decided by the Government of India or State Government, from time to time in respect of “**Pradhan Mantri Awas Yojana**”.

ii) For No Development Zone / Agricultural Zone / Green Zone - 1

All above Regulation No.14.4.1(i) with following modification shall be applicable for Pradhan Mantri Awas Yojana to be permitted in No Development Zone / Agricultural Zone / Green Zone - 1.

- a) The minimum width of approach road shall be 9.0 m.
- b) The permissible FSI for such projects shall be 1.0 on gross plot area.

^(#) Clarification issued vide Order No.CR.236/18 (Part 2), dt.23rd December, 2021

14.4.2 For Regional Plan area

The Regulations No.14.4.1 shall be applicable for Pradhan Mantri Awas Yojana to be permitted in following areas of Regional Plan, irrespective zones.

i) In Mumbai Metropolitan Regional Plan area

- a) PMAY shall be permissible in urbanisable zone U - 1, U - 2 / Urbanisable Zone of entire Mumbai Metropolitan Regional Plan, with FSI and other provisions mentioned in Regulation No.14.4.1(i).
- b) PMAY shall be permissible in zones, other than urbanisable zone U-1, U-2 / Urbanisable Zone, within distances mentioned in following table, with FSI and other provisions mentioned in Regulation No.14.4.1(ii).

ii) In other Regional Plan Area

PMAY shall be permissible in respective zones, within distances mentioned in following table with FSI and other provisions mentioned in Regulation No.14.4.1(i) & (ii).

Sr. No.	Within distance from	Outer peripheral distance from the Boundary of the Urban Local Bodies where PMAY is permissible
1	Municipal Corporations	2.0 k.m.
2	Municipal Councils / Nagarpanchayats	1.0 k.m.

14.5 CONSERVATION OF HERITAGE BUILDINGS / PRECINCTS / NATURAL FEATURES

14.5.1 Applicability

This regulation will apply to heritage sites which means, artefacts, structures, areas and precincts of historic and / or architectural and / or cultural significance (hereinafter as 'Listed Buildings / Heritage Buildings and Listed Precincts / Heritage Precincts') and those natural features of environmental significance including sacred graves, hills, hillocks, water bodies (and the areas adjoining the same) etc. within the areas of Planning Authorities and Regional Plan.

14.5.2 Preparation of List of Heritage Buildings, Heritage Precincts and Natural Features

The Authority on advice of Heritage Committee shall prepare heritage list and shall issue public notice in the local newspapers declaring his intention to include the buildings or modify such list of buildings, structures artefacts, areas and precincts of historic and /or cultural significance and the list of natural features of environmental significance, including sacred groves, hills, hillocks, water bodies etc. and invite objections and suggestions from any person in respect of the proposed inclusion within a period of 30 days from the date of such notice.

While preparing the list, the authority shall strictly insure that such structure / precinct has heritage value and is liable for inclusion in the list in view of its national, regional, or local importance as specified in Regulation No.14.5.8. The structure / precinct which do not comply the requirements specified in the said regulation shall not be included in the list. Generally, the following aspects shall be ascertained while preparing the list.

- a) Its value for architectural, historical or cultural reasons.
- b) The date and/or period and / or design and / or unique use of the building or artefact.
- c) Relevance to social or economic history.
- d) Association with well-known persons or events.
- e) A building or groups of buildings and / or areas of a distinct architectural design and / or style, historic period or way of life having sociological interest and / or community value.

- f) The unique value of a building or architectural features or artefact and / or being part of a chain of architectural development that would be broken if it were lost.
- g) Its value as a part of a group of buildings.
- h) Representing forms of technological development.
- i) Vistas of natural/scenic beauty or interest, including water front areas, distinctive and/or planned lines of sight, street line, skyline or topographical features.
- j) Open spaces sometimes integrally planned with their associated areas having a distinctive way of life and for which they have the potential to be areas of recreation.
- k) Industrial sites of historical interest.
- l) Archaeological sites.
- m) Natural heritage sites.
- n) Sites of scenic beauty.

All such heritage structures shall be documented in the Heritage List Card as given in Appendix-L and the Heritage List Card shall be duly authenticated by the authorised heritage conservationist upon his site visit, stating the significance of heritage site for its appropriate grading.

The Authority shall issue notice to the owner of the buildings, artifacts, areas and precincts of historic and / or cultural significance etc. and invite objections and suggestions from such person in respect of proposed inclusion within 30 days from the date of such notice.

The Authority, in respect of any objections or suggestions, shall decide the same after giving hearing to such persons and send the list as finalised by him to the State Government for approval. The State Government may sanction the said heritage list with modification, if required. This list will be called Final Heritage List. For this, modification under section 37 or 20 of the Maharashtra Regional and Town Planning Act, 1966 need not be necessary.

Thereafter, the Authority may amend the Final Heritage List from time to time as and when required, on the advice of the Heritage Committee. In such case it shall not be necessary to follow the procedure under Section 37 or section 20 of the Maharashtra Regional and Town Planning Act of 1966, but the procedure as laid down above in this regulation shall be followed.

The heritage lists which have been approved by the Government before coming into force these regulations, shall remain valid and shall be the part of these regulations.

14.5.3 Restriction on development, Redevelopment / repairs etc.

No development or redevelopment or engineering operations or addition, repairs, renovation including the painting of buildings, replacement of special features or plastering or demolition of any part thereof of the said listed buildings, or listed precincts or listed natural features shall be allowed except with the prior written permission of the Authority. Before granting any such permission, the Authority shall consult the Heritage Conservation Committee to be appointed by the State Government (hereinafter referred to as 'the said Heritage Conservation Committee') and shall act on the advice of the Heritage Conservation Committee.

Provided that before granting any permission for demolition or major alterations/ addition to listed buildings (or buildings within listed precincts) objections and suggestions from the public shall be invited and duly considered by the Heritage Conservation Committee.

Provided that, in exceptional cases for reasons to be recorded in writing the Authority may overrule the advice of the Heritage Conservation Committee.

Provided further that the power to overrule the advice of the Heritage Conservation Committee shall not be delegated by the Authority to any other officer.

If the application for development, alteration, modification of the Heritage precincts or listed building is rejected under this regulation or while granting such permission any conditions are imposed on the owner which deprives him to use the FSI, the said owner shall be compensated by grant of Development Right Certificate.

14.5.4 Incentive uses for Heritage Buildings

After the commencement of this Regulation, the Heritage Precincts or the Listed Buildings shall not be permitted to be used for any commercial or office purpose except with the concurrence of the Heritage Conservation Committee. However, in cases of buildings included in the Heritage Conservation List, if the owner /owners agree to maintain the listed Heritage Building in an ideal state of preservation with due repairs / restorations and if the owner / owners give a written undertaking to that effect, may be allowed by the Authority in consultation with Heritage Conservation Committee to convert part or the whole of the building to commercial / office use / any other different use that is beneficial to the preservation of the same Provided that, if the heritage building is not maintained suitably or if the heritage value of the building is allowed to be spoiled in any manner, the Authority shall withdraw the permission forthwith.

14.5.5 Grant of Transferable Development Rights to Owners / Lessees of Heritage Buildings / Heritage Precincts

If the owner is deprived of using permissible FSI on the said plot or development permission is granted to him with conditions which deprive him of use of permissible FSI, then he shall be entitled for TDR as decided by the Authority in consultation with Heritage Conservation Committee. The utilization of this TDR shall be as per TDR Regulation.

14.5.6 Maintaining Skyline

Building included in heritage precinct shall maintain the skyline, roof profile, built form edges, and respect the architectural style (without any high-rise development) as may be existing in the surrounding area, so as not to diminish or destroy the value and beauty of the said heritage building / heritage precinct. The development within the precinct shall be in accordance with the guidelines framed by the Authority on the advice of the Heritage Conservation Committee.

14.5.7 Restrictive Covenants

Covenants, terms and conditions, imposed under Regulations existing as on the date of this Regulation, on the leasehold plots either by the State Government or by the Planning Authority, shall continue to be imposed, in addition to the UDCPR. However, in case of any conflict with the heritage preservation interest / environmental conservation and the said Development Control and Promotion Regulations, this heritage regulation shall prevail.

14.5.8 Grading of the Listed Buildings / Listed Precincts

Grade - I	Grade - II	Grade - III
(A) Definitions		
Heritage Grade - I comprises Buildings and precincts of National or Historic importance, excellence in architectural style, design technology and material usage and / or aesthetics; associated with a great historic event, personality, movement or institution. They have been and	Heritage Grade - II (A and B) comprises buildings and precincts of Regional importance, possessing special architectural or aesthetic merit, or cultural or historical significance though of a lower scale than Heritage Grade - I. They are local landmarks, which	Heritage Grade - III comprises buildings and precincts of local importance for townscape, they evoke architectural, aesthetic, or sociological interest though not as in Heritage Grade - II. These contribute to determine the character of the locality and can be representative of life-style of a

are the prime landmarks of the city and of National importance.	contribute to the image and identity of the region. They may be the work of master craftsmen or may be models of proportion and ornamentation or designed to suit a particular climate.	particular community or region and, may also be distinguished by setting on a street line or special character of the façade and uniformity of height width and scale.
(B) Objective		
Heritage Grade - I richly deserves careful preservation.	Heritage Grade - II deserves intelligent conservation.	Heritage Grade - III deserves intelligent conservation (though on a lesser scale than Grade - II and special protection to unique features and attributes.)
(C) Scope for Change		
No interventions be permitted either on exterior or interior unless it is necessary in the interest of strengthening and prolonging the life of the buildings or precincts or any part of features thereof. For this purpose absolutely essential and minimum changes would be allowed and they must be in accordance with the original. Repairs shall be with the use of like to like material.	Grade - II (A) Internal changes and adaptive reuse and external changes may by and large be allowed but subject to strict scrutiny. Care would be taken to ensure the conservation of all special aspects for which it is included in Heritage Grade - II Grade - II (B) In addition to the above, extension of Additional building in the same plot or compound, in certain circumstances be allowed, provided that, the extension / additional building is in harmony with (and does not detract from) the existing heritage buildings or precincts especially in terms of height, and facade.	External, internal changes and adaptive reuse would by and large be allowed. Changes can include extensions, and additional buildings in the same plot or compound. However any changes should be such that they do not detract from the existing heritage building / precinct.
(D) Procedure		
Development permission for the changes would be given by the Authority on the advice of the Heritage Conservation Committee.	Development permission for the changes / additional construction would be given by the Authority on the advice of Heritage Conservation Committee.	Development permission for the changes / additional construction would be given by the Authority on the advice of the Heritage Conservation Committee.
(E) Vistas / Surrounding Development		
All developments in areas surrounding Heritage Grade - I shall be regulated and controlled by ensuring that it does not mark the grandeur of or view from Heritage Grade - I		

14.5.9 Signs and Outdoor Display Structures

No display or advertising signs and outdoor display structures on listed building and/or the Heritage Precincts shall be permitted except accordance with part X (sign and outdoor display structure) National Building Code of India.

Prohibition of advertising signs and outdoor display structure in certain cases :

Notwithstanding the provisions mentioned above no advertising sign or outdoor display structures shall be permitted on buildings of architectural, aesthetic, historic or heritage importance as may be decided by the Authority, Committee or also on Government buildings, save that in the case of Government buildings only such advertising signs or outdoor display structures may be permitted that relate to the activities of the said buildings and related programs.

Provided that, if the Heritage Conservation Committee so advises, the Authority shall refuse permission for any sign or outdoor display structure.

14.5.10 Composition of Heritage Conservation Committee

There shall be Heritage Conservation Committee for the areas within the jurisdiction of Planning Authority and Regional Plan area. This Committee shall be constituted by the Government in consultation with the Authority. The committee shall comprise of the following members:-

i)	Chairman Appointed by the Government	Chairman
ii)	Joint Director of Town Planning of the Concerned Division (For the areas excluding Municipal Council and Regional Plan area) (Assistant Director of Town Planning of the District for Municipal Councils)	Member
iii)	Divisional / District officer of Archaeological Survey of India	Member
iv)	Divisional / District officer of Archaeological Survey of Maharashtra	Member
v)	Convenor, INTACH Local Chapter	Member
vi)	Heritage Conservation Architect having more than 10 years of experience and membership of the Council of Architecture	Member
vii)	Historian having experience of more than 10 years in the field of History.	Member
viii)	Structural Engineer having experience of more than 10 years and member of Institute of Engineers.	Member
ix)	City Engineer (Planning Authority) / Chief Planner (Metropolitan Authority or SPA or NTDA) / Chief Officer (Municipal Council) / Assistant Director of Town Planning of the District (Regional Plan area)	Member secretary

The tenure of the Chairman and Members of categories (vi) to (viii) above shall change after every three years provided however that, the same person shall be eligible for re-appointment as Member.

The Heritage Conservation Committee shall come into existence with effect from the date of its publication in the official Gazette. However, Heritage Committees constituted by the Government before coming into force of these regulation, shall remain in operation till further period as may be specified.

No act of the Committee done in good faith, shall be deemed to be invalid by reason only of some defect subsequently discovered in the organization of the Committee or in the Constitution of the Committee or in the appointment of the Member or on the ground that such member was disqualified for being appointed.

The Chairman and in his absence the chosen Member of the Committee shall preside over the meeting of the Committee.

14.5.11 The Terms of reference of the Committee :-

- i) To advise whether development permission should be granted under this Regulation and the conditions of such permission.
- ii) To prepare a list or supplementary list of buildings, artefacts, structures, areas/ precincts of historic, aesthetic, architectural, cultural significance and a supplementary list of natural features of environmental significance including sacred groves, hills, hillocks etc., water bodies (and the areas adjoining the same) to which this regulation would apply.
- iii) To advise whether any relaxation, modification, alteration, or variance of any of the Development Control and Promotion Regulations is called for.
- iv) To suggest amendments, changes or special regulations or modification to regulations for listed buildings and the heritage precincts regulated under these regulations
- v) To advise on the extent of Development Rights to be granted to the owners of listed Buildings or Heritage Precincts.
- vi) To advise whether development Rights Certificates may be allowed to be consumed in a heritage precinct.
- vii) To advise whether to allow commercial / office user of any listed building of Heritage Precincts and when to terminate the same.
- viii) To advise on erection of outside advertisement / bill boards.
- ix) To recommend guidelines to be adopted by those private parties or any other agency, who sponsor beautification schemes at public intersections and elsewhere.
- x) To advise on the cost of repairs to be given to the owners to bring the existing building back to the original condition. For this purpose, the Committee may suggest ways to raise funds through private sources.
- xi) To advise on special designs and elements and guidelines for listed buildings and control of height and essential façade characteristics such as maintenance of the buildings and to suggest suitable design adopting new materials for replacements keeping the old form intact to the extent possible.
- xii) To advise on preparation of guideline relating to design elements and conservation principles to be adhered to and to advise on other guideline for the purpose of this regulation.
- xiii) To consider any other issue as may be required from time to time during course of scrutiny of development permissions and in overall interest of heritage / environmental conservation.

In the absence of Heritage Conservation Committee, the Authority shall consult the Government before giving such permission.

14.5.12 Heritage Conservation Fund

- i) Heritage buildings included in the said list shall be maintained by the owners of the said buildings themselves, with a view to give monetary help for such maintenance/repairs a separate fund may be created which would be kept at the disposal of the Authority, who will utilise these funds on the advice of the Heritage conservation Committee. The Authority may, in such cases disburse appropriate amount to the owner or may get maintenance/ repair work done through Planning Authority / Collector.

- ii) 2% of total development charges collected shall be transferred to the Heritage Conservation Fund.
- iii) The fund may also be used to support the cost of listing of heritage sites and cost towards expert guidance and fees for architects, engineers and other expert.
- iv) The Authority shall have right to remove any unauthorized construction in the property enlisted as heritage property and recover the expenses of such removal/ demolition work from the owner as per provisions of the Act.
- v) The Authority shall have right to enter into any such heritage property to repair such property to avoid any damage or injury, and the amount shall be spent from Heritage Conservation Fund and shall be recovered from the owner as arrears of taxes due to the Authority.
- vi) If Heritage structure listed in Grade - I needs conservation, preservation and immediate repairs and if the structure is affected due to vandalism by occupier / owner, then the Authority shall have right to acquire such heritage property and conserve its heritage value.

14.6 SLUM REHABILITATION SCHEME FOR PUNE, PCMC, PCNTDA AND NAGPUR

The slum Rehabilitation Scheme Regulations for ⁽¹⁾ (--) Nagpur Municipal Corporation shall be applicable as sanctioned by the Government from time to time.

⁽¹⁾ (The Development Control Regulations for Slum Rehabilitation Authority, Pune and Pimpri-Chinchwad Area has been sanctioned by the Government in Urban Development Department vide Notification No.1822/ 251/C.R.09/2023/UD-13, Dt.05th December, 2023)

⁽¹⁾ {14.6

⁽¹⁾ DEVELOPMENT CONTROL REGULATIONS FOR SLUM REHABILITATION AUTHORITY, PUNE AND PIMPRI CHINCHWAD AREA, PUNE.	
INDEX	
14.6.1 - SHORT TITLE, EXTENT AND COMMENCEMENT	
14.6.2 - DEFINITIONS	
14.6.3 - APPLICABILITY	
14.6.4 - INTERPRETATION	
14.6.5 - DELEGATION OF POWERS	
14.6.6 - DISCRETIONARY POWERS	
14.6.7 - DEVELOPER'S REGISTRATION	
14.6.8 - PARAMETERS OF DEVELOPMENT OF SLUM REHABILITATION AREA	
14.6.9 - ELIGIBILITY	
14.6.10 - OBLIGATORY PARTICIPATION	
14.6.11 - INITIATION OF SLUM REHABILITATION SCHEME	
14.6.12 - SANCTION TO THE SRS	
14.6.13 - CLEARANCE ORDER	
14.6.14 - TRANSIT CAMP ACCOMODATION	
14.6.15 - DEVELOPMENT CONTROL RULES	
14.6.16 - REGULATIONS RELATING REHABILITATION AND FREE SALE COMPONENTS	
14.6.17 - PAYMENTS TO BE MADE TO SRA AND INSTALMENTS	
14.6.18 - BUILDING CONTROL REGULATIONS FOR SRS	
14.6.19 - SLUM AND DEVELOPMENT PLAN RESERVATIONS	
14.6.20 - CLUBBING OF TWO SCHEMES	
14.6.21 - SOCIAL AMENITIES AND RELIGIOUS STRUCTURES	
14.6.22 - FORMATION OF CO-OPERATIVE SOCIETY	
14.6.23 - RESPONSIBILITY OF THE CO-OPERATIVE SOCIETY	

(1)	14.6.24 - INALIENABILITY
	14.6.25 - POSSESSION OF THE TENEMENTS / SHOP
	14.6.26 - ALLOTMENT OF THE TENEMENTS TO PROTECTED OCCUPIERS
	14.6.27 - ALLOTMENT OF THE TENEMENTS TO NON PROTECTED OCCUPIERS
	14.6.28 - DE-NOTIFICATION OF SLUM REHABILITATION AREA
	14.6.29 - PREMIUM FOR OWNERSHIP AND TERMS OF LEASE

14.6.1 SHORT TITLE, COMMENCEMENT AND EXTENT

1. The said Regulations shall be called as “**The Development Control Regulations for the Slum Rehabilitation Authority, Pune & Pimpri-Chinchwad Area, Pune, 2022** (hereinafter called “ the said regulations”)
2. The said Regulations shall be applicable to the area under jurisdiction of SRA, Pune i.e. the entire area of *Pune Municipal Corporation (P.M.C.), Pimpri-Chinchwad Municipal Corporation (P.C.M.C.) and P.M.R.D.A. (restricted to earlier P.C.N.T.D.A. Area) and M.I.D.C. area in P.M.C. & P.C.M.C.* as notified under sub-section 1 of Section 3(A) of Maharashtra Slums Areas (Improvement, Clearance and redevelopment) Act 1971 from time to time by the State Government.
3. The said Regulations shall come into force on the date of its notification by the State Government in the Official Gazette. The said Regulations shall replace all the existing Development Control Regulations for Slum Rehabilitation Areas for Pune and Pimpri-Chinchwad Municipal Area, Pune.

14.6.2 DEFINITIONS

- (a) “**Amenity Component**” shall mean any constructed amenities, prescribed by C.E.O., S.R.A. for rehabilitation of the hutment dwellers in any S.R.S.
- (b) “**Annual Statement of Rates (A.S.R.)**” is the annual statement of rates of lands and properties, prepared annually by the Inspector General of Registration and Controller of Stamps, Maharashtra State, Pune.
- (c) “**Beneficiary**” shall mean hutment dwellers found eligible as protected occupiers, as defined in the Slum Act and /or orders issued thereunder.
- (d) “**Built up area**” means the area covered by a building on all floors including ⁽²⁾ (---) Mezzanine floor, if any, but excepting the areas excluded specifically from F.S.I. under the said Regulation.
- (e) “**Composite Building**” shall mean a building comprising both Rehabilitation component and Free-Sale component or Built Up Amenity component
- (f) “**Developer**” means such agency as may be appointed or registered under section 3-B by Chief Executive Officer of Slum Rehabilitation Authority to implement Slum Rehabilitation Scheme.
- (g) “**Floor Space Index**” (F.S.I.) or Floor Area Ratio (F.A.R.) shall mean the quotient obtained by dividing the combined built up area on all floors, (excepting the areas specifically exempted from computation of F.S.I. under the UDCPR and the said Regulations) by the area of the plot.
- (h) “**Free Sale Component**” of S.R.S. is the built up area that can be constructed against the incentive F.S.I., in accordance with the said Regulations, available in the form of F.S.I. or T.D.R. out of the total permissible F.S.I. of the S.R.S. (rehabilitation component plus incentive sale component as per the ratios prescribed in the said Regulations) after deducting F.S.I. required for Rehabilitation.
- (i) “**Gross Plot Area**” shall mean total plot area.

⁽²⁾ Deleted vide Order No.C.R.116/2024/(Part-2)/UD-13, Dt.11th October, 2024 under Clause (C)-RoD of Notification bearing No.CR.09/2023/UD-13, Dt.05th December, 2023

- (l) (j) **“Hazardous building”** shall mean any building or part thereof which is used for the storage, handling, manufacturing or processing of any Hazardous Material as defined in the UDCPR.
- (k) **“Net Plot Area”**, for the purpose of the said Regulations, shall mean the balance area derived after deduction of area earmarked for reservations, D.P. Roads, Road Widening under Development Plan of the concerned Planning Authority.
- (l) **“Pavement”** shall mean any Municipal / Government / Semi-Government pavement, and shall include such stretch of pavement as may be considered viable for the purpose of the S.R.S.
- (m) **“Rehabilitation Component”** shall mean and include the area of all residential tenements as well as non-residential built-up premises to be given to the eligible hutment dwellers in accordance with the provisions of the said Regulations and shall be inclusive of common areas, lobbies, staircase/s, lift/s and machine room/s, passage/s, welfare center/s, balwadi/s, women's welfare center/s, society office/s, incentive commercial area/s (if any), eligible amenity structure/s (if any) and permitted religious structure/s, more particularly described in the said Regulations.
- (n) **“Recreation Ground”** (R.G.) shall mean, any common open space required to be kept in any layout and left permanently open to the sky, having access from any public pathway or public road.
- (o) **“Slum Rehabilitation Scheme”** shall mean a scheme for rehabilitation of hutment dwellers of one or more slum rehabilitation areas in accordance with the provisions of the said Regulations and shall include transit camps, infrastructure, amenities, Rehabilitation component and Free sale component of the development, as permitted on the area of Slum Rehabilitation Scheme (S.R.S.) by the C.E.O., S.R.A.
- (p) **“Slum Transferable Development Rights”** (Slum T.D.R.) shall mean the F.S.I. remaining out of the total permissible F.S.I. of the S.R.S. after utilizing in-situ F.S.I. on site as per the provisions of the said Regulations or shall mean the F.S.I. made available in the form of Transferable Development Rights in lieu of the unencumbered land spared for rehabilitation of hutment dwellers on land vitally required for public purpose or ecologically fragile locations.

Terms and expressions other than those specifically defined herein shall have the same meaning as defined in,

- (i) Maharashtra Regional and Town Planning Act, 1966,
- (ii) The Maharashtra Slum Areas (Improvement, Clearance and Redevelopment) Act 1971,
- (iii) Development Control Regulations of the concerned Planning Authority and the Rules framed thereunder.
- (iv) National Building Code (2016) as amended from time to time.
- (v) Unified Development Control and Promotion Regulations.

14.6.3 APPLICABILITY

1. Provisions of the said Regulations shall be applicable to :

- (A) The slums which have been declared and notified as “SLUMS” by the Competent Authority under the provisions of the Maharashtra Slum Areas (Improvement, Clearance and Redevelopment) Act, 1971, as well as;
- (B) Any area which, the Competent Authority may declare as “Slum Rehabilitation Area” as per the provision contained in Section 3-C of the Slum Act 1971; and also

- (1) (C) The hutment dwellers in such Slums or Slum Rehabilitation Areas, who are Protected Occupiers as defined in Chapter I-B of the Slum Act and orders issued thereunder and the hutment dwellers who are Non-Protected Occupiers under clause (f) of sub-section (5) of section 3-B of the Slum Act.

2. The provisions which are mentioned in the said Regulations shall prevail over the corresponding provisions of the Unified Development Control and Promotion Regulations (hereinafter referred to as “UDCPR”). In case of any conflict or ambiguity, in respect of any matters not specifically mentioned in the said Regulations, the relevant provisions of the UDCPR, as modified from time to time; shall be applicable.

3. The Slums On Non Buildable Area / Reservations :

- (A) The provisions for implementing in-situ rehabilitation scheme, of the said Regulations shall not apply to slum areas existing on any lands earmarked as Hill Tops / Hill Slopes, Green Belts, River or Nallah beds including those falling in blue flood line, Canal banks, No Development Zone in the Development Plan, in Open Spaces of approved layouts and slums on lands required for vital public purpose or on hazardous locations. Such slums are to be evicted on priority.
- (B) It shall be an obligatory duty of the “C.E.O., S.R.A.” to rehabilitate slums mentioned in clause (A) above on other buildable sites under the provisions of the said Regulations. The C.E.O., S.R.A. shall prepare an Action Plan and identify all such slum areas and grant approval for relocation and rehabilitation of such slums for environmental and ecological reasons in a time bound manner, in accordance with the provisions of the said Regulations including open spaces in M.I.D.C. and P.M.R.D.A. (Restricted to earlier P.C.N.T.D.A. area) areas. The C.E.O., S.R.A. shall take a decision in this regard in consultation with the concerned Municipal Commissioner.
- (C) On relocation and rehabilitation of hutment dwellers of such slums, unencumbered lands thus vacated shall be handed over to the Local Authority or the Authority concerned for the development of vital public purpose against compensation as may be permissible as per the corresponding regulations.
- (D) The slums existing on reservations shall be allowed to be rehabilitated as per the provisions of the said Regulations. If any previous S.R.S. had been sanctioned on any reservation under the earlier provisions, such S.R.S. can be implemented further under the said Regulations, considering such land as deemed to be de-reserved as per previous sanction.
4. Anything done or any action taken in respect of S.R.S. prior to the commencement of the said Regulations shall be deemed to have been done or taken under the corresponding provisions of the said Regulations and provisions of the said Regulations shall be made applicable in relation thereto only to the extent, such application does not adversely affect the same.

Nothing contained herein shall adversely affect the approval and implementation of Slum Rehabilitation projects approved under BSUP, JNNUR Mission by the Central Sanctioning and Monitoring Committee, Ministry of Housing and Urban Poverty Alleviation, Government of India, or any such government schemes approved from time to time.

5. Transition Policy:

The S.R.S. already sanctioned under the earlier provisions can be allowed to be developed under the said Regulations in case the full occupation certificate has not been issued and compliance in respect of payment against Operation and Maintenance Corpus and Infrastructure Development Charges (I.D.C.) has been done; provided that the C.E.O., S.R.A. shall have the powers to give approval to changes in building height and internal

- (1) modifications with appropriate relaxation in set back and margins of the restructured building subject to N.O.C. from C.F.O. and fulfilment of other requirements and to impose any conditions as may be expedient for him to do so; provided however that nothing in the said Regulations shall adversely affect all slum rehabilitation schemes previously sanctioned.
6. Eligible hutment dwellers may, at the discretion of the C.E.O., S.R.A., be rehabilitated in-situ as far as possible within the area under consideration for the implementation of the Slum Rehabilitation Scheme. Such rehabilitation shall be governed by the provisions of the said Regulations.
 7. Eligible hutment dwellers may also be rehabilitated by relocation to another plot in the concerned Municipal Area. Such rehabilitation shall be governed by the provisions of the said Regulations.
 8. If any hutment dweller is a protected occupier of a slum structure, but his name is on the electoral roll on or prior to 1st January, 2000 at another slum / pavement site within the jurisdiction of Pune and / or Pimpri-Chinchwad Municipal Corporation, he shall be considered eligible but only at the place of his present residence. In case of doubt or dispute, C.E.O., S.R.A. shall get an inquiry made as may be considered necessary, and give a decision thereon, which shall be final and binding on all parties concerned.
 9. Allotment of tenements either in-situ or otherwise, on ownership or on rent, to the other Non-Protected Occupiers up to the 1st January 2011, subject to the availability of tenements shall be done, as per the terms, conditions and guidelines so notified in the Official Gazette, by the Chief Executive Officer with the prior approval of the State Government;

14.6.4 INTERPRETATION

The Terms and expressions not defined in the said Regulations shall have the same meanings as in the Slum Act, 1971 or M.R. & T.P. Act, 1966 or The Maharashtra Municipal-Corporation Act, 1949 (M.M.C. Act, 1949) or N.B.C. (2016), UDCPR and amendments made therein from time to time, as the case may be, unless the context otherwise requires.

If any question or dispute arises with regard to interpretation of any provision of The said Regulations, the matter shall be referred to the State Government in Urban Development Department which, after considering the matter and, if necessary after giving hearing to the parties, shall give a decision on the interpretation of the provisions of The said Regulations. The decision of the Government on the interpretation of The said Regulations shall be final and binding on the concerned party or parties.

14.6.5 DELEGATION OF POWERS

Except where special permission is expressly stipulated, the powers or functions vested in the C.E.O. by the said Regulations may be delegated to any officer of the Authority under his control, subject to the revision if necessary and to such conditions and limitations, if any, as may be prescribed under the said Regulations.

14.6.6 DISCRETIONARY POWERS

1. In conformity with the intent and spirit of the said Regulations, the C.E.O., S.R.A. may modify the limit of a zone where the boundary line of the zone divides a plot, village boundary, C.S. / C.T.S. No. as per records of revenue by a special permission, with prior consent of concerned Municipal Commissioner, and
2. In specific cases where a clearly demonstrable hardship is caused, the C.E.O., S.R.A. may for reasons to be recorded in writing, by special permission permit any of the dimensions prescribed by the said Regulations to be modified, except those relating to floor space indices

- (1) unless otherwise permitted under the said Regulations, provided that the relaxation will not affect the health, safety, fire safety, structural safety and public safety of the inhabitants of the building and the neighbourhood.

14.6.7 DEVELOPER'S REGISTRATION

1. Only a Developer registered with S.R.A. shall be eligible to submit a slum rehabilitation scheme. So also registered developer only shall be appointed by S.R.A., in case S.R.A. wish to develop any Slum Rehabilitation Area where no proposal is submitted.
2. Owner of the land who is competent and have resources to develop slum on land owned by him shall be allowed to register himself as registered developer, but only for development of slum on land belonging to him.

14.6.8 PARAMETERS OF DEVELOPMENT OF SLUM REHABILITATION AREA

1. Eligibility for rehabilitation scheme

- a. A person eligible for redevelopment scheme shall mean a Protected Occupier as defined in chapter 1-B of the Slum Act and Non-Protected Occupier, as mentioned in clause (f) of sub-section (5) of Section 3-B of the said Act.
- b. Subject to the foregoing provisions, only the actual occupants of the hutment shall be held eligible and the so called structure-owner other than the actual occupant if any, even if his name is shown in the electoral roll for the structure, shall have no right whatsoever to the reconstructed tenement against that structure.

2. Joint ownership with spouse

The reconstructed tenement provided to protected occupier shall be of the ownership of the hutment dweller and spouse conjointly, and shall be so entered and be deemed to be so entered in the records of the co-operative housing society, including the share certificates or all other relevant documents.

3. Right of the Hutment Dwellers

- a. Hutment-dwellers, in the slum or on the pavement, eligible in accordance with the provisions herein shall in exchange of their protected dwelling structure, be given free of cost a residential tenement having a carpet area of 27.88 Sq.m. (300 Sq.ft.) including balcony, bath and water closet but excluding common areas. For this purpose 'Carpet area' means the net usable floor area within a tenement excluding the covered by the walls or any other areas specifically exempted from FSI computation as per the said Regulations.
- b. Even those protected dwelling structures having existing residential areas more than 27.88 Sq.m. (300 Sq.ft.) will be eligible only for 27.88 Sq.m. (300 Sq.ft.) of carpet area in the rehabilitation component.
- c. All eligible hutment dwellers taking part in the S.R.S. shall have to be rehabilitated in accordance with the provisions of the Scheme. It may be in situ and in the same plot as far as possible.
- d. Pavement dwellers and hutment dwellers in the slum on land required for vital public purpose or such location which are otherwise unsuitable for human habitation or where there is any restriction shall not be rehabilitated in-situ but in other available location and in accordance with the Scheme.
- e. Competent Authority, on the basis of verification of prescribed documents, shall decide eligibility of slum dwellers. The slum dweller held eligible on 1st January 2000 shall be Protected Occupier. However the slum dweller held eligible on 1st January 2011 shall be

- (1) Non-Protected Occupier, but shall be rehabilitated on payment of the cost of the tenement as prescribed by the C.E.O. as per government resolutions issued from time to time.
- f. The eligibility of a person including a transferee, under a scheme of Slum redevelopment shall be established in accordance with Chapter-1-B of the Slum Act.
- g. Restriction on Transfer of Tenements :
As provided by the Slum Act, the tenement obtained under this scheme cannot be sold / leased / assigned or transferred (except to legal heir) in any manner for a period of ten years from the date of allotment / possession of the tenement. In case of breach of conditions, except transfer to legal heir, the tenement will be taken over by S.R.A. Transfer of the rehabilitation tenement may be permitted by C.E.O., S.R.A. after completion of ten years from the date of occupation by charging a premium equal to 25% of the prevailing market value of the tenement as given in the ASR for the respective year, during which transfer application is processed.
- h. An individual agreement shall be entered into by the owner / developer / co-operative housing society with the hutment-dwellers in the slum / pavement.
- i. An individual agreement entered into between hutment-dweller and the owner / developer / co-operative society / N.G.O. shall be in the joint names of pramukh hutment dweller and spouse for every protected dwelling structure and non-protected dwelling structure up to 1st January 2011.
- j. Recovery of pending dues such as assessment, compensation, occupational charges, non-agricultural tax / dues etc. pending with public authorities such as State Govt. and / or concerned Municipal Corporation shall be dealt with separately and not be linked to grant of approval or building permission to the Slum Rehabilitation Projects.

4. Duties of the Hutment Dwellers :

- a. The hutment dweller shall be responsible to pay the electricity and other government charges regularly, and maintain his rehab unit and do necessary minor repairs as and when so required at his own cost. However, for carrying out any major changes in the structure of the building in whatsoever nature, the permission of the C.E.O., S.R.A. in writing shall be required.
- b. The eligible hutment dwellers shall form their cooperative society as soon as possible and in any case not later than within three months of handing over of rehab units' possession to them.
- c. The hutment dweller shall pay monthly contribution to his co-operative society @ Rs. 500 per month or the amount as decided by his cooperative society whichever is more for common monthly charges against the common electricity and water usage, operation and maintenance of common amenities like lift, generator, S.T.P. plant etc.
- d. The slum dweller is duty bound to keep the premises of his rehab unit including common areas and surroundings of the rehab buildings clean, hygienic and untidy.
- e. The slum dweller shall not keep or carry any hazardous material in the rehab unit which may cause injury or endanger to life and safety of other residents of the premises.

14.6.9 ELIGIBILITY

1. Protected Occupiers

Inhabitants of the slums or slum rehabilitation areas residing on 1st January 2000 shall be Protected Occupiers as defined in Chapter I-B of the Slum Act and orders issued thereunder and shall be eligible for rehabilitation under the Slum Rehabilitation scheme, in accordance with the provisions of this Scheme. The eligibility of such Protected Occupiers shall be decided as per the guidelines provided by the Government Resolutions issued from time to time.

(1)

2. Non-Protected Occupiers

Inhabitants of the slums or slum rehabilitation are as residing on 1st January 2011, shall be Non-Protected Occupiers as defined in the Slum Act and shall be eligible for rehabilitation under the Slum Rehabilitation scheme, in accordance with the provisions of this Scheme. The eligibility of such Non-Protected Occupiers shall be decided as per the guidelines provided by the government resolutions issued from time to time.

3. Ineligible Occupiers

The occupants of slum who are neither held eligible as Protected Occupiers nor Non-Protected Occupiers shall be held ineligible and they will not be entitled for rehabilitation under any Slum Rehabilitation Scheme. However they may avail the benefits of any other housing scheme of the Government such as P.M.A.Y., if independently held eligible therein.

4. Provision relating to allotment of tenements either in situ or otherwise, on ownership free of cost to the protected occupiers

The protected occupiers shall be rehabilitated in situ and they will be allotted rehabilitation tenement free of cost. However, in case the slum is situated on non-buildable area or the area under slum is required for any vital public project, then they will be rehabilitated by relocation. Such relocation shall be made on a land near the slum pocket as far as practicable, but within the same Municipal limit.

5. Provision relating to allotment of tenements either in situ or otherwise, on ownership or on rent to the other non-protected occupiers

The non-protected occupiers shall as far as possible be rehabilitated in situ after the protected occupiers in the slum under the scheme and those in nearby non buildable slum are rehabilitated. They will be allotted rehabilitation tenement on payment of cost of tenement as prescribed by the Government Resolutions issued from time to time.

6. Subject to the foregoing provisions, only the actual occupants of the hutments shall be treated as eligible for rehabilitation under the S.R.S. and any person claiming ownership of such structure who is not the actual occupant of the same, shall have no right whatsoever to allotment of rehabilitation tenement.

7. The hutment dweller actually residing at present, who has purchased the censused structure with photo pass, if any, from any of the categories above shall be held eligible for rehabilitation under S.R.S., provided such transfer has been regularized. Provided further that the original owner of the censused structure who has sold the said, but shall be deemed to be ineligible for any alternative subsidized accommodation in any of the government scheme.

8. The names of the eligible hutment dwellers on private, Municipal and Government lands shall be duly certified by the Competent Authority in S.R.A. or any officer whom the State Government by notification appointed as the Competent Authority for the purpose of the Slum Act.

9. All eligible hutment dwellers residing on the area of the S.R.S. shall have to be accommodated on the same plot as far as possible.

10. Any hutment dweller who is in actual occupation or possession of more than one hutment within the jurisdiction of S.R.A. Pune shall not be held eligible for more than one rehab unit.

11. The eligibility of a person including transferees in case of Protected Occupier under the S.R.S. shall be established in accordance with the orders issued vide G.R. mentioned in clauses 1 above. The Hutment dweller, for establishing his eligibility shall submit his application in prescribed form along with Annexure for Self Declaration and Self Declaration for Self Attestation and the copies of the documents of evidence in the manner as prescribed by State Government.

- (1) 12. The eligibility of a person including transferees in case of Non Protected occupier under the S.R.S. shall be established in accordance with the orders issued vide G.R. mentioned in clause 2 above. Hutment dweller, for establishing his eligibility shall submit his application in prescribed form along with Annexure for Self Declaration and Self Declaration for Self Attestation and the copies of the documents of evidence in the manner as prescribed by State Government.

14.6.10 OBLIGATORY PARTICIPATION The participation of landowners and slum dwellers in Slum Rehabilitation Scheme shall be obligatory. This participation shall be governed by following regulations,

(A) Landowners

The land owner shall be given first preference to implement scheme on his / her land. However landowner in same survey number or part of it having title of an area exceeding 50% shall be given the preference, if he / she is ready to pay an amount of compensation for remaining land. The amount of compensation to be offered shall be decided as per the provisions u/s 17 of the Slum Act.

Such a land owner by registering himself as a Registered Developer, or through a Registered Developer may submit the scheme with the consent of 51% of the slum dwellers for the implementation of such scheme. The scheme so submitted shall forthwith be accepted by C.E.O. and C.E.O. will order preparation of the Eligibility List by the Competent Authority concerned.

In case a proposal submitted by the landowner is devoid of the consent of slum dwellers, the C.E.O. shall publish a notice to invite slum dwellers to come forward within 90 days of publication of such notice, through a society registered, to submit rehabilitation scheme. If the slum dwellers submit a scheme in response to such a notice, then the C.E.O. will give a reasonable opportunity of being heard to both owner and slum dwellers along with developer engaged. The C.E.O. after taking into account the scheme so submitted and the experience and the capacity of the developer pass a reasoned order to accept one of the proposals. Such decision of the CEO shall be final and binding upon the parties concerned. In case the slum dwellers fail to submit such a scheme, the C.E.O. shall accept the proposal submitted by the land owner.

(B) Slum Dweller

In case the concerned landowner has failed to submit the scheme as per the preceding regulation and the slum dwellers have come forward through a Registered Co-operative Society or through a Registered Developer whom 51% of them have given consent, the C.E.O., S.R.A. shall acquire the land under the slum, at the instance of Co-operative Society or Registered Developer. The C.E.O. will simultaneously issue order to the Competent Authority concerned to prepare and submit the Eligibility List. (Annexure II)

(C) Registered Developer

A Developer registered with S.R.A. as Registered Developer previously shall be permitted to submit Slum Rehabilitation Scheme in following manner

1. The Registered Developer, who has been appointed by S.R.A. through competitive bid to develop a particular scheme/s, shall submit the scheme which may be accepted by the C.E.O.
2. The Registered Developer with acquired rights from the owner/s of the slum land and who hold consent of 51% slum dwellers shall be allowed to submit the scheme as prescribed in preceding regulation. Such a scheme shall be accepted by C.E.O. and the C.E.O. will order Competent Authority to prepare eligibility list of slum dwellers in Annexure II.

(1)

3. In case the Registered Developer holds the rights from the owner/s of the slum land, but does not have consent of the slum dwellers; submit a scheme, the C.E.O. shall give a 90 days public notice in the slum area for the slum dwellers to come forward for the development. In case hutment dwellers fail to come up with a scheme within the stipulated period of 90 days, C.E.O., S.R.A. may accept the scheme submitted by the registered developer having land ownership or concurrent development rights. In case, upon such notice slum dwellers come forward with a scheme, the C.E.O. as per clause (A) above, after giving a reasonable opportunity to both the parties of being heard, shall accept one of the proposals, taking into account the capacity and experience of registered developers involved in such proposals. The decision of the C.E.O. shall be final and binding upon the parties. And after the scheme is accepted, the C.E.O. will order Competent Authority to prepare eligibility list of slum dwellers in Annexure II.
4. In case the Registered Developer have consent of 51% slum dwellers, but does not hold right to develop the land; C.E.O., S.R.A. shall give him preference and the land owner shall be entitled to compensation payable under the provisions of Slum Act or the said Regulations. In case of dissent of the land owner for this valuation, C.E.O., S.R.A. may forward the land acquisition proposal to the State Government on behalf of the applicant developer and the Hutment Dwellers' Co-operative Housing Society. Simultaneously, the C.E.O. will order Competent Authority to prepare eligibility list of slum dwellers in Annexure II.
5. In case two or more registered developers submit a scheme on same land; then such proposals will be scrutinized chronologically on the basis of the land development rights acquired by the developer and the consent of hutment dwellers.
6. The developer shall before acceptance of his scheme/s by C.E.O., S.R.A., open and maintain a separate account for each scheme and such account shall only be exclusively used for all receipts and expenditure of the scheme.

(D) (C.E.O., S.R.A.)

In case the C.E.O., S.R.A. is of the opinion that a slum on private land is required to be developed in the larger public interest, out of concern for public health and safety of the slum and nearby areas, C.E.O., S.R.A. may invite land owner or hutment dwellers to come forward with the scheme for redeveloping the slum through a developer registered with S.R.A., by issuing a public notice of not less than 30 days. In case, land owner or hutment dweller's Co-operative Housing Society does not come forward with response to the notice so issued, the C.E.O., S.R.A. may, by order, determine to redevelop such land by entrusting it to any agency or registered developer through competitive bid process. In such an eventuality, the Land owner shall be entitled to compensation as contemplated by section 17 of the Maharashtra Slum (Improvement, Clearance and Redevelopment) Act, 1971 or as per the said Regulations. However, before passing any such order, the C.E.O., S.R.A. shall give an opportunity of being heard to the concerned land owner.

Nothing in these provisions shall restrain the C.E.O. from issuing of orders for preparation of the eligibility list (Annexure II) in relation to any Slum declared u/s 4 of the Slum Act or Slum Rehabilitation Area declared u/s 3-C of the said Act, wherein a proposal is submitted or not. Thus the fixing of eligibility (Annexure II) will be independent of any scheme submitted.

(1) 14.6.11 INITIATION OF SLUM REHABILITATION SCHEME

The Slum Rehabilitation Scheme under the jurisdiction of SRA shall be undertaken in the manner laid down herein,

1. The C.E.O., S.R.A. shall publish intention of the S.R.A. to declare Slum land or any other land as Slum Rehabilitation Area in the Official Gazette as prescribed u/s 3-C of the Slum Act. A copy of such notification shall be published in two News Papers of circulation in the area along with fixing a copy at conspicuous place in or near such slum area. The concerned owners, land holders or occupants of Slum area or areas mentioned therein; shall be given a period not more than 120 days to come forward as prescribed in sub section (1) of Section 13 of the Slum Act with a rehabilitation scheme in accordance with the provisions contained in the said Regulations.

2. Compulsory acquisition of slum land

Upon failure of the concerned land owner, land holders or occupants to come forward with a rehabilitation scheme in accordance with the provisions contained in this Scheme, the C.E.O., S.R.A. may proceed further to acquire the land wherein the amount of compensation shall be determined as per the provisions contained in the Chapter-V of the Slum Act.

If the landowner of slum occupied land voluntarily transfers the said land to S.R.A. for slum redevelopment, he shall be given T.D.R. equivalent to 1.0 index of the area of his land so transferred in non-congested area and 1.5 index of the area of his land so transferred in congested area. In such cases, however, the developer shall pay to S.R.A., premium equal to 25% of A.S.R. value.

However in case of the lands belonging to Government, Semi-Government Undertakings and Local Bodies S.R.S. shall be taken up by S.R.A. through tendering process.

3. The land owner or his power of attorney holder or the lease holder with at least 5 years of un-expired lease period and concurring with lease terms of the land, shall be allowed to redevelop the slum area either directly upon registration with Slum Rehabilitation Authority or through a developer registered with Slum Rehabilitation Authority, subject to the provisions laid down in the said Regulations.
4. Slums on the lands belonging to the Government, Semi-Government Bodies, Municipal Corporations, Public Authorities and Trusts shall be rehabilitated under the provisions of this Scheme either by themselves or S.R.A., through a private developer registered with S.R.A.
5. The Slum Rehabilitation Scheme submitted by the developer registered with S.R.A. shall be strictly in accordance with the provisions of the said Regulations.
6. The Developer or the Owner submitting the Scheme will submit it in the Form and the Annexure prescribed along with all relevant documents to the C.E.O., S.R.A. Forms and Annexure prescribed by the C.E.O. shall be made available to the Registered Developer / Owner on payment of fees as decided by C.E.O., S.R.A. Pune.
7. The Developer submitting the scheme shall also furnish Scrutiny Fee as prescribed and as decided by the C.E.O., S.R.A. Pune from time to time.

14.6.12 SANCTION TO THE SRS The following procedure shall be adopted while examining and sanctioning any S.R.S. in accordance with the provisions of the said Regulations,

- 1) Approval to the S.R.S. shall be given by the C.E.O., S.R.A. in accordance with the said Regulations.
- 2) The consent of hutment dwellers or the resolution of their co-operative society shall be taken into account at the time of submission of S.R.S. The consent shall be confirmed at the time of preparation of Eligibility list in Annexure II. For the approval of the S.R.S., consent of

- (1) the hutment dwellers shall not be necessary. Competent Authority as notified under Slum Act shall finalize the list of eligible hutment dwellers with reference to the area proposed under the S.R.S. and it shall be obligatory for all slum dwellers to participate in the Slum Rehabilitation Scheme, once the same is approved by the C.E.O., S.R.A.
- 3) The C.E.O., S.R.A. after accepting the scheme submitted shall order preparation of the list of eligible slum dwellers. The Competent Authority, shall as far as practicable within 90 days finalize Annexure II and submit it to the C.E.O. The eligibility of a person including transferees under the S.R.S. shall be established in accordance with the provisions of the Slum Act and orders issued there under. Nothing in the said regulations shall restrain the C.E.O. from issuing of orders for preparation of the eligibility list (Annexure II) in relation to any slum wherein a proposal is submitted or not. Thus the fixing of eligibility (Annexure II) will be independent of any scheme submitted.
- Provided, in case of slums on lands falling in areas mentioned in Section 3-Z-6 of Slum Act, if the land owning agency gives N.O.C., then the C.E.O., S.R.A. Shall conduct the survey and order preparation of Annexure II on such lands.
- 4) Where 51% or more of the eligible hutment-dwellers in a slum or pavement in a viable stretch at one place agree to join a S.R.S., it may be considered for approval. Provided that nothing contained herein shall apply to Slum Rehabilitation Schemes undertaken by the State Government or a Public Authority or, as the case may be, a Government Company, as defined in Section 617 of the Companies Act, 1956 which is owned and controlled by the State Government.
- 5) The hutment dwellers shall be rehabilitated in the same S.R.S. wherein the hutments are situated, except in case where relocation is warranted on account of non-buildability or in case of clubbing of schemes or composite scheme as per the provisions contained in the said Regulations.
- 6) Pavement-dwellers and hutment dwellers in the slum situated on lands required for vital public utility / purpose or on hazardous location or on amenity / open spaces or plots, shall not be rehabilitated in-situ but in other available plots within the jurisdiction of S.R.A.
- 7) The Slum Rehabilitation Scheme for rehabilitation of protected and non-protected hutment dwellers residing upon such areas may be allowed to be implemented under the provisions of the said Regulations. Preference will be given to protected hutment dwellers on non-buildable Slum Areas nearby before non-protected hutment dwellers are accommodated. The C.E.O., S.R.A. shall be competent to approve the proposed Slum Rehabilitation Schemes.
- 8) Industrial user as may be permitted by Maharashtra Pollution Control Board (M.P.C.B.) may only be allowed to be re-accommodated under the S.R.S. However, if the Industrial unit is hazardous or polluting, the concerned person may be provided a commercial unit or built-up area for conforming non-hazardous/non-polluting industrial unit in the Rehabilitation Component of the S.R.S.
- 9) All eligible hutment dwellers in the Slum Rehabilitation Scheme shall be rehabilitated according to the provisions in the said Regulations and as per Rehabilitation option exercised by the C.E.O., S.R.A. under the said Regulations.
- 10) Unauthorized Commercial activities such as go-downs, Cow sheds / gothas, scrap godowns / yards; hazardous users / structures excluding community economy activity area as defined under the Slum Act shall not be permitted in the S.R.S. These shall be evicted and shall be moved away from the Slum Rehabilitation Area as non-conforming users.

- (1) 11) All economic activities which existed on the date of eligibility shall be allowed to be relocated within the area of the S.R.S., regardless of the non-conforming nature of such activities, excepting those which are hazardous and polluting. Where alternative accommodation has been allotted elsewhere by the Planning Authority, further relocation shall not be permitted.
- 12) On compliance of the terms and conditions of approval to the S.R.S. and the requirements of the provisions contained in this Scheme, the necessary building permission u/s 45 of M.R. & T.P. Act, 1966 shall be admissible in accordance with the provisions to construct the Rehabilitation Component of the S.R.S. as well as the Free Sale Component of the S.R.S.
- 13) In case where Sale building is proposed along with Rehab building in S.R.S., it shall be obligatory on part of the developer to submit RERA registration of the scheme, as applicable. The developer shall abide to all orders and directions issued by RERA Authority, if applicable, in respect of the free sale building.
- 14) The decision of C.E.O., S.R.A. shall be final and binding on all the concerned regarding the proportion and location of the land area to be used for the Rehabilitation Component, Amenity Component and the Free-Sale Component.
- 15) **Area Entitlement of Eligible Hutment-dwellers (Residential User) :** A Hutment dweller having residential user in the slum or on the pavement, who is eligible in accordance with the provisions of the said Regulations, shall, in lieu of his structure, be given free of cost (in case of Protected Occupier) / at subsidized rate (in case of Non-Protected Occupier), a residential tenement having carpet area of 27.88 Sq.m. (300 Sq.ft.) which shall include living room, bedroom, kitchen / alcove, bath and water closet and balcony (if any), but shall exclude common areas. However the projects for which the commencement certificate have already been issued, as per erstwhile Regulations, the residential tenement shall be as per earlier area entitlement with carpet area of 25 Sq.m. (269 Sq.ft.) which shall include living room, bedroom, kitchen / alcove, bath and water closet and balcony (if any), but shall exclude common areas. The slum dwellers belonging to schemes wherein the commencement certificate is already issued before coming into force of said regulations may be provided a residential tenement having a carpet area of 27.88 Sq.m. (300 Sq.ft) (Instead of 25 Sq.m. (269 Sq.ft.) as per the discretion of the developer depending upon the feasibility of structural alterations at the site. In such cases revised plans shall have to be approved by C.E.O., S.R.A.
- 16) **Area Entitlement of Eligible Hutment dwellers (Non-Residential User) :** An eligible hutment dweller, having existing carpet area up to 25.0 Sq.m. (269 Sq.ft.) for commercial / industrial / economic / office activity that existed prior to 1st January 2000, or the date decided by the Government time to time, and is certified by the Competent Authority, shall be entitled to get one non-residential unit of actual carpet area or 27.88 Sq.m. (300 Sq.ft.), whichever is less, free of cost, under the Slum Rehabilitation Scheme.
- Such area may be allowed on any side of the plot abutting 3.0 m. wide pathway and deriving access from 3.0 m. wide pathway / open space. Back to back shopping on ground floor shall be allowed for the purpose of rehabilitation. After exhausting these provisions, such area may be allowed on the first floor, to the extent necessary. The provisions of the said Regulations may also be applicable for Rehabilitation of Street Vendors.
- 17) **Area Entitlement of Eligible Hutment dwellers (Mixed User) :** In case a hutment dweller in the area of any S.R.S. has both, residential and commercial premises, without a common wall between such residential and commercial premises, in respect of which the S.R.S. is being or to be implemented, he shall be eligible for a residential tenement of 27.88 Sq.m.

- (1) (300 Sq.ft.) carpet area free of cost, and he shall also be entitled to purchase a commercial unit admeasuring up to 6.0 sq.m. at the cost of construction as per A.S.R. The purchase price of such commercial unit shall be paid to the developer. The area of such commercial shall not be entitled for incentive F.S.I. for free sale component. The slum dwellers belonging to schemes wherein the commencement certificate is already issued before coming into force of said regulations may be provided a residential tenement having a carpet area of 27.88 Sq.m. (300 Sq.ft.) (Instead of 25 Sq.m. (269 Sq.ft.) and a commercial unit admeasuring up to 6.0 Sq.m. as per the discretion of the developer depending upon the feasibility of structural alterations at the site. In such cases revised plans shall have to be approved by C.E.O., S.R.A.

Such area may be allowed on any side of the plot abutting 3.0 m. wide pathway and deriving access from 3.0 m. wide pathway / open space. Back to back shopping on ground floor shall be allowed for the purpose of rehabilitation. After exhausting these provisions, such area may be allowed on the first floor, to the extent necessary.

- 18) After declaration of Slum Rehabilitation area as "Clearance Area" u/s 3-D of the Slum Act, the C.E.O., S.R.A. shall take all required actions against the non-participating occupiers. The eligible occupiers shall be forced to participate and the non-eligible shall be forcefully evicted.
- 19) The conveyance of the land under rehab component shall be done in favor of the Slum Dwellers Co Operative Society.
- 20) Recovery of pending dues such as assessment, occupational charges, non-agricultural tax / dues etc. of the State Government, P.M.C. / P.C.M.C. / P.M.R.D.A. (restricted to earlier P.C.N.T.D.A. area) / M.I.D.C. shall not be linked to grant of approval or building permission to the S.R.S.

14.6.13 CLEARANCE ORDER After an order declaring any Slum area as Slum Rehabilitation Area under section 3-C of the Slum Act and after sanction to S.R.S. as per the provision above, the C.E.O. shall proceed to issue Slum Clearance order in following manner –

1. The Slum Clearance Order may be passed for total area or in parts as per the provisions contained in sub section (1) of section 12 of the Slum Act.
2. All the slum dwellers in the area under notification shall be given a period of 30 days from the date of such order to vacate the structures. The Protected and Non Protected occupiers shall be provided transit accommodations or entitled compensation in lieu of transit accommodation by the developer. The other ineligible dwellers shall make their own arrangements, even if their claims for eligibility are pending in appeal for decision.
3. In case there is any public structure like common toilets, community hall etc. provided by the Municipal Corporation concerned, it shall be vacated and demolished by the concerned authority within the period provided in the clearance order. The C.E.O., S.R.A. shall vacate and demolish the same, in case the concerned authority fails to vacate and demolish the said structure within stipulated time period.
4. The structures which have been vacated shall be demolished by the developer implementing the scheme, within 50 days of the Slum Clearance Order. The period of 50 days if required can be extended up to 60 days by an order of C.E.O., S.R.A.
5. The hutment dwellers who have not vacated their structures or who are not willing to vacate their structures shall be forcefully evicted.
6. However before such an eviction is done, the slum dweller residing in such structure shall be given notice u/s 33-A read with sub section (8) of section 12 and an opportunity of being heard by the C.E.O., S.R.A. or the Competent Authority authorized by the C.E.O., S.R.A.

- (1) 7. The C.E.O., S.R.A. or the Competent Authority authorized by the C.E.O., S.R.A. after such hearing pass such order and proceed to forcefully vacate and demolish the structure as per the Clearance Order.
8. The Clearance Order of C.E.O., S.R.A. or order u/s 33-A read with sub section (8) of section 12 shall be final subject to any order in appeal preferred before the Apex Grievance Redressal Committee.
9. Nothing in the forgoing provisions shall restrain the C.E.O. or the Competent Authority authorized by the C.E.O., S.R.A. from initiating action u/s 3-Z in relation to any Protected or Non-Protected Occupier or ineligible occupiers and pass suitable order making him liable for eviction without being relocated and rehabilitated.
10. **In respect of those eligible hutment-dwellers who are not willing to join the S.R.S., the following steps shall be taken :-**
- (A) Provision for all of them shall be made in the rehabilitation component of the Scheme.
- (B) The details of the actual tenements to be allotted by lottery system and the transit tenements to be allotted or the compensation in lieu of transit accommodation to such unwilling hutment dwellers shall be communicated to them by the Developer, in writing, so as to show the benefit on the same basis as for those who have joined the scheme to gain their willing participation in the scheme. However, in case of any dispute regarding the same, decision of the C.E.O., S.R.A. shall be final and binding on all the parties concerned. The Developer shall ensure that no obstruction is caused to the Scheme of the majority of hutment-dwellers who have participated willingly.
- (C) The unwilling eligible hutment dwellers shall not be held entitled either for allotment of transit tenement or the allotment of rehabilitation tenements by draw of lots. They shall only be entitled for what is available after others have exercised their choices through lottery, which may be or may not be on the same site.
- (D) If such unwilling hutment dwellers do not join the scheme till the building permission to the S.R.S. is given, they shall lose their right to any built-up tenement for rehabilitation, permanently and their tenements shall be taken over by the C.E.O., S.R.A. in possession of S.R.A. and shall use the same for the purpose of accommodating pavement-dwellers and other hutment dwellers who cannot be accommodated in-situ etc. on other sites.
- (E) If the built-up tenement is not occupied and transit camp is not vacated within 30 days from the drawl of lottery, then the eligible hutment dweller shall lose his right to rehabilitation permanently. No appeal in this regard or shall be entertained by the C.E.O., S.R.A. or the Competent Authority authorized by the C.E.O., S.R.A.
- After occupation of rehabilitation tenement, if any hutment dweller reconstructs or occupies any new hutment or structure; such unauthorized structure shall immediately be evicted and demolished by the C.E.O., S.R.A. without giving prior notice.

14.6.14 TRANSIT CAMP ACCOMODATION

1. "Temporary Transit Tenement" shall mean habitable residential or non-residential accommodation for eligible S.R.S. beneficiary constructed from detachable material such as tubular / prefabricated light structures or such other material, in such a manner that it ensures safety of the inhabitants. Design criteria for structural elements of transit accommodation shall be similar to those of the rehabilitation tenements, with a maximum carpet area of 16.72 Sq.m. (180 Sq.ft.) for residential and 9.29 Sq.m. (100 Sq.ft.) for non-residential tenement for each transit tenement / unit.

- (1)
2. The Temporary Transit Tenements for rehabilitation of hutment dwellers may be allowed to be constructed on Rehabilitation site itself, or on any other buildable or non-buildable land except within river bank and Blue line or any other ecologically fragile or any restricted areas, located within P.M.C. / P.C.M.C. / P.M.R.D.A. (restricted to earlier P.C.N.T.D.A. area) / M.I.D.C. area, as the case may be.
 3. The temporary transit camp for rehabilitation of slum dwellers may be provided in the transit rehabilitation tenements allotted by C.E.O., S.R.A. or otherwise.
 4. The eligible Slum Dwellers shall be shifted to temporary Transit Camp or on minimum monthly rent as may be mutually decided by C.E.O., S.R.A. with proposed society and developer and shall be paid by the developer to the eligible slum dwellers to be temporarily shifted for allowing construction on site till allotment of permanent rehabilitation tenements.

14.6.15 DEVELOPMENT CONTROL REGULATIONS

1. **F.S.I. permissible on the Plot under S.R.S. :** Admissible F.S.I. in respect of the Slum Rehabilitation Scheme in congested and non-congested area shall include the admissible FSI for the Rehabilitation Component as well as the Free-Sale Component. The ratio, between the two components shall be as contained in Regulation No.14.6.16. Such F.S.I. may be utilized mainly for in-situ rehabilitation of slum dwellers, Convenience Shopping, non-combustible / non-polluting type Commercial godowns of slum dwellers. Such commercial users shall be permitted only on the lower, upper ground floor, irrespective of whether the site is located in R-1 or R-2 zone. FSI available for Free sale component may be utilized in-situ for residential, commercial or any other use as may be permissible under the UDCPR. As such, the permissible in-situ F.S.I., partly or fully, shall be allowed for rehabilitation, residential / non-residential / commercial or mixed users, as otherwise permissible in the UDCPR.
2. **Maximum F.S.I. permissible for consumption on the plot :** F.S.I. that can be sanctioned on any slum site shall be 4.00 or sum total of rehabilitation component plus free sale component whichever is more with minimum rehabilitation tenement density of 450 T/Ha. Due to local planning constraints and viability of the Slum Rehabilitation Project the density norms of 450 T/Ha. may be reduced up to 20% by the C.E.O., S.R.A. subject to minimum tenement density of 360 T/Ha.
3. The total permissible F.S.I. (Rehabilitation component plus Free sale component) for a slum rehabilitation scheme can be utilized on any slum site for construction of rehabilitation plus free sale component as mentioned in clause (2) and the difference between the total permissible F.S.I. of the S.R.S. and maximum in-situ consumed F.S.I., may be made available in the form of Transferable Development Right (T.D.R.), in accordance with the said Regulations.

Provided further that exemption of areas like staircase, lift, lobbies, machine room, passage, refuge area, ⁽³⁾ balcony from computation of F.S.I. shall be restricted to ⁽³⁾ 60% of built-up area (i.e. carpet area of rehabilitation component including ⁽³⁾ (---) area under walls ⁽³⁾ but excluding balcony⁽³⁾) of rehabilitation component and any rehabilitation component area, claimed above this restriction, shall not be eligible for any incentive towards the free sale component area to be calculated.

- ⁽³⁾ Provided that, the provisions shall be applicable to all the schemes where full occupancy certificate is not taken.

Provided further that, the SRS converted and complied according to 2022 regulations, where 15% balcony is calculated in FSI, shall be eligible for the revised calculations as above. ⁽³⁾

⁽³⁾ Replaced / Inserted / Deleted vide Order No.C.R.116/2024/(Part-2)/UD-13, Dt.11th October, 2024 under Clause (C)- RoD of Notification bearing No.C.R.09/2023/UD-13, Dt.05th December, 2023,

(1)

Notwithstanding above if the developer does not desire to consume the full permissible in-situ F.S.I. on the same site, in such case the free sale component partly or fully shall be granted in the form of slum T.D.R. (Total sanctioned F.S.I. of S.R.S. minus consumed in-situ F.S.I.) by the concerned Authority with the recommendation of C.E.O., S.R.A.

4. Notwithstanding the provisions in clause mentioned above, if the developer does not desire to consume the full permissible in-situ F.S.I. on the same site, in such a case :

a. the free sale component partly or fully shall be granted in the form of Slum T.D.R. (total sanctioned F.S.I. of S.R.S. - consumed in-situ F.S.I.) by the concerned Authority with the recommendation of C.E.O., S.R.A.

b. the Rehabilitation component shall be increased to utilize admissible in situ F.S.I., so that more number of Rehabilitation tenements are constructed on the plot. Such additional tenements shall be handed over to S.R.A. free of cost, to accommodate identified eligible non protected occupants of other schemes, identified P.A.P. of slums or shall be utilized as stock for housing for dishoused, Transit accommodation as per the policy approved by Government in that behalf. Additional Rehabilitation component built by the Developer shall be included in the proposed Rehabilitation component of the scheme and additional incentive area according to the provisions laid down herein in the form of T.D.R. shall be admissible to compensate the Developer.

5. The Slum T.D.R. to be sanctioned in accordance with the said Regulations and generated from the slum rehabilitation schemes shall be allowed to be utilized in Pune and Pimpri-Chinchwad Municipal Corporation (old and new limits) respectively, excluding heritage structures and land of S.R.D. or S.R.A. projects. This shall be applicable to Schemes on lands in P.M.R.D.A. (Restricted to earlier P.C.N.T.D.A. area) and M.I.D.C. area also. In these cases, the Slum T.D.R. generated shall be allowed to be utilized under these norms within the area of respective planning authority.

6. The utilization of Slum T.D.R. on a receiving plot in the area of P.M.C. or P.C.M.C. (old and new limits), P.M.R.D.A. (Restricted to initial P.C.N.T.D.A. area) and M.I.D.C. areas shall be as per the provisions of UDCPR or DCPR of concerned Planning Authority, as the case may be. The utilisation of Transferable Development Rights (T.D.R.) shall be permissible by considering Gross Plot Area including area affected by D.P. road / road widening or amenity space / reservations or deemed reservation, if any, if the area under the same is handed over to the concerned Planning Authority.

7. The Slum T.D.R. shall be released in stages as under :-

- i. After issue of plinth completion certificate of rehabilitation building/s, 25% of total Slum T.D.R. permissible shall be released.
- ii. After completion of R.C.C. and brickwork of rehabilitation building/s, 35% of total Slum T.D.R. permissible shall be released.
- iii. After issue of occupation certificate of rehabilitation building/s, and formation and registration of Co-operative Housing Society 30% of total Slum T.D.R. permissible shall be released.
- iv. After completion of procedure of rehabilitation of eligible slum dwellers in building, and conveyance of rehabilitation area to the Co-operative Housing Society of hutment dwellers, balance 10% of total Slum T.D.R. permissible shall be released.

If any changes are required in the above provision, Government will issue orders in this regard, from time to time.

(1)

8. **UTILIZATION OF SLUM T.D.R. :** Difference in Total Permissible F.S.I. allowed for S.R.S. as per the said Regulations and F.S.I. actually utilized in the Slum Rehabilitation Scheme, due to constraints of different provisions of DCPR or otherwise, shall be converted into SLUM T.D.R. and shall be utilizable in any land use zone as per the provisions in the UDCPR or DCPR of the concerned Planning Authority, subject to following manner and restrictions prescribed herein below :

- i. The Development Rights Certificate (D.R.C.) shall be recommended by the C.E.O., S.R.A. and the Concerned Authority shall issue concerned D.R.C. to the developer within a period of one month from the receipt of the proposal. The F.S.I. credit in square meters of built up area shall be stated in the D.R.C. in figures and in words, along with details of the place from where T.D.R. is generated; and where it may be utilized.
- ii. The built up area for grant of D.R.C. shall be equal to the built-up area of the sanctioned slum rehabilitation scheme, allowed to be taken in the form of Slum T.D.R.
- iii. Where a buildable amenity on the reserved plot for which slum rehabilitation scheme is sanctioned, is handed over, free of cost to the concerned Authority, the concerned Authority may grant a further T.D.R. on account of construction of the said amenity, in accordance with the provisions in the UDCPR in this regard.

iv. **It shall be permissible to utilize the Slum T.D.R. in any land use zone as per given formula below, subject to restrictions as mentioned in clause 5 & 6 herein above.**

Formula ; $X = (R_g / R_r) \times Y$

Where, X = permissible utilization of T.D.R. / D.R. in Sq.m. on receiving plot.

R_g = rate for land in Rs. per Sq.m. as per A.S.R. of generating plots in generating year.

R_r = rate for land in Rs. per Sq.m. as per A.S.R. of receiving plot in generating year.

Y = T.D.R. debited from D.R.C. in Sq.m.

- v. The D.R.C. may be used on one or more plots of land, whether vacant or already developed, by erection of additional floors, or in any other manner consistent with UDCPR or DCPR of concerned Planning Authority, as the case may be, but not so as to exceed the F.S.I. prescribed herein, subject to the condition that when T.D.R. is to be utilized by erection of additional floors, it shall only be allowed to the extent and after satisfying the structural stability, bearing capacity of existing structure.
9. The site of S.R.S. may be developed with layout of buildings. For the computation of F.S.I. and tenement density on a site, the net plot area shall be the balance plot area after deducting the area covered by amenity space and Development Plan reservations / roads if any, from the total area of the plot.
10. All the plots involved in any S.R.S. under which ex-situ rehabilitation of hutments dwellers is envisaged shall be notionally treated as one for the purpose of computation of F.S.I.
11. Boundaries and measurement of the areas of plots under the S.R.S. shall be certified by the Competent Authority after actual verification on site measurement of the areas of plots. Such certified boundaries and areas of plots shall be the basis for calculation of tenement density, F.S.I. and other aspects of planning.

12. Layout Open and Amenity Space :

- (A) For sites with area admeasuring 4000 Sq.m. and above, 10% open spaces shall be provided and be maintained as per the UDCPR or DCPR of concerned Planning Authority, as the case may be, and structures permissible in open spaces as per the UDCPR or DCPR of concerned Planning Authority, as the case may be, will be permissible in the open spaces of the Slum Rehabilitation Scheme.

- (1) (B) For plots with area exceeding 2 Hectare and above, 5% Amenity Space shall also be provided and for development of such Amenity Space, the provisions in 14.6.21 of the said Regulations shall apply.
13. Roads in the layouts of the sites of S.R.S. shall be of widths prescribed in the UDCPR or DCPR of concerned Planning Authority, as the case may be, for their corresponding lengths. The area of such internal layout roads shall not be deducted in the computations of the net plot area for determining the permissible F.S.I. and tenement density.
- 14. The Minimum Tenement Density to be achieved in S.R.S. :**
- (A) Minimum tenement density of 450 T/Ha. shall be provided on the net plot area used for rehabilitation of hutment dwellers (including residential rehabilitation and non-residential rehabilitation units). If the number of rehabilitation tenements needed to be provided to the hutment dwellers in any S.R.S. is such that the corresponding tenement density is less than the minimum specified tenement density, the required number of balance tenements shall be constructed so as to achieve the said minimum tenement density and shall be handed over free of cost to S.R.A. The C.E.O., S.R.A. may use such tenements for the purpose of transit tenements or for accommodating the Project Affected Persons (P.A.P.) or the pavement dwellers or as may be decided by the C.E.O., S.R.A.
- (B) The minimum tenement density for rehabilitation shall be 450 T/Ha. and maximum tenement density for rehabilitation and free sale tenements / units shall be 1440 T/Ha. Due to local planning constraints and viability of the Slum Rehabilitation Project the density norms of 450 T/Ha. may be relaxed by C.E.O., S.R.A. subject to minimum tenement density of 360 T/Ha. In such cases, C.E.O., S.R.A. shall pass a reasoned order for the same.
15. All non-residential built-up area shall be included in the computation of tenement density, by counting an area of 25.00 Sq.m. (or such area as may be notified by the Government from time to time), per tenement.
16. For computation of the tenement density, the net plot area shall be considered after deducting development plan reservations and amenity space.
17. The permissible ground coverage shall be total plot area after deducting required marginal open space / setback areas from the plot boundaries.
18. The maximum permissible height of the rehabilitation buildings shall be up to 70 meter. Building height is restricted / retained up to 45 meter on road width below 9 meter. Building height more than 45 meter shall be permissible on roads having width between 9 meter to 12 meter, subject to minimum front margin as per the said regulations and subject to condition that, such road shall be widened to 12.0 meter under the provisions of Municipal Corporation Act, by prescribed line of street before granting occupation certificate to such building / s of slum Rehabilitation Scheme this shall be subject to Fire Prevention and life safety requirements and obtaining fire NOC from chief Fire Officer.
19. The Front and Side and Rear marginal distances of in-situ Rehabilitation or composite or free sale buildings shall be as per Regulation No.14.7.11 of UDCPR. The rear and side marginal distances may be relaxed by the C.E.O., S.R.A. on the merits of each case after obtaining fire N.O.C. from concerned Authority.
- (A) Where the plot abuts a Nallah / non-buildable reservation or zone / open space; the marginal open space along it shall be 3.0 m. from the edge of the trained Nallah / non-buildable reservation or zone / open space.

- (1) (B) Minimum distance between two Rehabilitation or composite / free sale buildings shall be as follows :
- i. For buildings with Height up to 40.0 m. :- Min. 6.00 m.
 - ii. For buildings with Height above 40.0 m and up to 50.0 m. :- Min. 7.50 m.
 - iii. For buildings with Height above 50.0 m. :- Min. 9.00 m.
- (C) The open space around the building should be paved up to 1.0 m. width. Where the dimensions prescribed are for the pathway and the marginal distances, the larger of the two shall prevail. The pathway shall serve as access wherever necessary. The construction of buildings may be permitted abutting the pathways.
20. In the event of any proposed road widening, the computation of permissible F.S.I. shall be made on gross plot area without deducting the area under such proposed road widening and the height of a building shall be relaxed by the C.E.O., S.R.A. on the merits of each case for such road area going under road widening as per the Development Control Regulations of the concerned Municipal Corporation.
21. The construction of the building for the rehabilitation of slum dwellers and the tenements to be made available to the S.R.A. shall be as per the designs and specifications approved by the C.E.O., S.R.A.
22. After approval is granted to the Slum Rehabilitation Scheme (S.R.S.), the land earmarked for S.R.S. may be further subdivided, if necessary, to carve out separate plots for the Rehabilitation Component, Free-Sale Component and the Amenity Component. Both, the Plot area and the Built-up area of the said plots shall be mentioned separately in Sq.m. in the lease agreements as well as Record of Rights.

14.6.16 REGULATIONS RELATING TO REHABILITATION AND FREE SALE COMPONENTS –

The total permissible built up area for any S.R.S. of Pune and Pimpri-Chinchwad S.R.A. areas shall be the sum total of Rehabilitation component area and Free sale component area, calculated as per the ratios prescribed herein below :

1. If the rehabilitation component is 10.0 sq.m., then; an additional incentive built up area permitted to subsidise rehabilitation component which shall be calculated as per the following formula

Rehab : Incentive built up area shall be 1 : R

Where $R = [2.8 - (n \times 0.3)]$

Where $n = (Y / X) - 2$

Where Y = Rate of Residential Flat per Sq.m. and

X = Rate of Construction per Sq.m.

Both the rates are considered as mentioned in applicable A.S.R. (Annual Statement of Rates) for the scheme plot on the date of granting Commencement Certificate (C.C.) to the project.

In difficult or dense areas wherein the existing density either in-situ or after clubbing or after relocation-rehabilitation, as the case may be, is more than 650 T/Ha. & up to 850 T/Ha., further, additional 20% incentive on free sale component shall be permissible and if such density is more than 850 T/Ha., additional 30% incentive on free sale component shall be permissible.

Additional incentive for Cluster Redevelopment : The total permissible built up area for Cluster S.R.S. of Pune and Pimpri-Chinchwad S.R.A. areas shall be the sum total of Rehabilitation component area and Free sale component area, calculated as per the ratios

- (1) prescribed hereinabove plus additional 10% F.S.I. of free sale component area as an incentive for undertaking cluster redevelopment of slums will be permissible. Cluster here shall mean the slum area of at least 1.0 hectare of contiguous land, ⁽³⁾ (---) ⁽³⁾ irrespective of number of land parcels and ownership etc. ⁽³⁾

Note :

- i) The Permissible incentive built up area may be utilized in site up to the maximum FSI limit permissible in the scheme plot.
 - ii) The minimum and maximum ratio of incentive built up area permissible as per the above formula shall be 1:1.50 and 3.0 respectively.
 - ⁽³⁾ iii) Provided further that, the additional incentive built up area as above can be permissible over and above the maximum permissible limit of 3. ⁽³⁾
2. If the S.R.S. in respect of a slum located on any land belonging to a public authority or a private owner, which is needed for a vital public purpose or which is on uninhabitable locations / ecologically fragile / environmentally sensitive locations or wherein in-situ rehabilitation is not feasible for any reason, is taken on an unencumbered plot, then in congested area T.D.R. equal to three times and in non-congested area T.D.R. equal to two times the gross area of the land spared (unencumbered plot) for this purpose shall be permissible to the land owner / lessee or if the landowner has assigned the rights to slum project implementing developer to receive T.D.R. compensation, to the concerned developer after handing over of the said plot to S.R.A. and if the rehabilitation component is constructed by the developer, in addition, ⁽²⁾ TDR in lieu of construction of rehabilitation component shall be calculated as per ratio prescribed in Regulation 14.6.16(1) of the SRA Regulation-2022 to the developer of the said unencumbered plot.
- Provided that, such TDR shall be applicable only in case of scheme involving identified beneficiaries.
- In such cases, if the tenement density provided is more than 650 T/Ha. & up to 850 T/Ha., additional 10% incentive T.D.R. shall be permissible and if such density is more than 850 T/Ha., additional 20% incentive T.D.R. shall be permissible.⁽²⁾
- (2) (---)
3. Relocation henceforth shall be preferably on lands already earmarked in the D.P. for E.W.S. / MHADA, Housing for dishoused (H.D.H.) or High Density Housing (H.D.H.) or Slum Improvement Zones (S.I. zone).
 4. The identified land for slum relocation under S.R.S. shall be conveyed in favor of S.R.A. upon approval of such S.R.S. The T.D.R. for the unencumbered land spared for this purpose as mentioned above (hereinafter referred as Land T.D.R.) shall thereafter be granted to the unencumbered plot.
 5. Land T.D.R. shall be released in two stages - 75% after conveyance of land and 25% after physically rehabilitating the identified beneficiaries in the S.R.S.
 6. The land after relocation of such slum shall be handed over free of cost as the case may be to the respective Municipal Corporation / Public Authority for vital public purpose.
 7. However, the S.R.S. sanctioned prior to coming into force of the said Regulations may continue to be implemented as per the prevailing Regulations applicable at the time of approval of that S.R.S.

⁽³⁾ Replaced / Inserted / Deleted vide Order No.C.R.116/2024/(Part-2)/UD-13, Dt.11th October, 2024 under Clause (C) - RoD of Notification bearing No.C.R.09/2023/UD-13, Dt.05th December, 2023

⁽²⁾ Replaced / Inserted / Deleted vide Directives alongwith Notice u/s.37(1AA) bearing No.C.R.116/2024/UD-13, Dt.11th October, 2024

- (1) **8. Area / Tenements to be given to S.R.A. free of cost :** On considering the maximum F.S.I. on net plot area and on distributing the same in proportion for rehabilitation and sale component, the 10.0 Sq.m. component is to be mainly used for construction of rehabilitation component, required to accommodate only the existing slum dwellers from the same site and the balance area from this 10.0 Sq.m. component shall be handed over to the S.R.A. free of cost, in the form of tenements. If exactly 10.0 Sq.m. components are required for rehabilitation of existing slum dwellers from the same site, the S.R.A. will not be entitled to any area. If requirement of area for rehabilitation of existing slum dwellers from the same site exceeds the aforesaid 10.0 Sq.m. component, the owner / developer / Co-operative Housing Society shall be entitled to T.D.R. as per provisions in the said Regulations and in such case, the S.R.A. will not be entitled to any area, provided that this provision shall not be applicable for the schemes undertaken as per the Regulation for Clubbing of schemes or Composite S.R.S.
9. At least 40% of the built-up area (Basic FSI) in a Composite Building under the S.R.S. shall be towards the Rehabilitation Component.
10. The C.E.O., S.R.A. shall use the tenements received by him free of cost as per the provisions hereinabove for the purpose of transit or for project affected persons or slum dwellers from other slum locations.
- The procedure laid down herein shall be adopted for allotment of such tenements.
- (A) On receipt of application from the developer concerned, an account of all available tenements shall be drawn and communicated to the developer. After obtaining his consent, an order for the allotment shall be issued.
- (B) Where the tenements are given on rent by S.R.A. to the developer for Transit accommodation or otherwise, the developer concerned shall pay yearly rent in advance to S.R.A. and for that purpose an agreement for Leave and License shall be executed between the concerned developer and the concerned officer of S.R.A. for the period of minimum 11 months. However, if the developer applies for any extension, the similar procedure shall be followed.
- (C) It shall be the duty of the developer to take care of the licensed premises including day-to-day maintenance of the tenements allotted on rent and common areas. Common maintenance charges may be shared by the developer with the cooperative society, if any.
- (D) Charges for common use of electricity and water tax shall be borne by the developer. The charges for electricity and water for individual tenements shall be borne by slum dweller. However If slum dweller fails to pay such charges the developer shall pay to the concerned authority.
- (E) The developer shall be responsible for replacement or repairs of any damage occurred during the period of license.
- (F) The charges for documentation and registration fee shall be borne by the developer.
- (G) The possession of the rented transit tenements to the developer shall only be given after registration of leave and license agreement.
11. The terms and conditions for resettlement of such existing tenements shall be as governed by the Maharashtra Slum Areas (Improvement, Clearance and Redevelopment) Act, 1971.

(1)

PAYMENTS TO BE MADE TO SRA AND INSTALMENTS :**14.6.17**

1. No premium including fire premiums shall be charged for any relaxation / exemptions to be granted for construction of rehabilitation component under S.R.S. No hardship premium shall be charged for any relaxation to be granted for construction of composite buildings in the Scheme, provided that such composite building has a minimum 40% of the total built-up area under rehabilitation component. Premium shall not be charged for all or any of the relaxations given herein for rehabilitation component as well as free sale component. Provided that, concession in premium may be granted to the extent of proportion of rehabilitation component in the composite building.

Further the developer shall be allowed to pay installments as provided in UDCPR Regulation 2.2.14.

2. Premium shall be charged for any relaxation other than the provisions of the said Regulations to be granted for construction of Free-sale component, at the rate prevailing then within the areas of respective Municipal Corporations for their areas.
3. Land Development charges shall not be charged for lands under declared slum rehabilitation areas. Building Development charges shall not be payable for rehabilitation component. However, infrastructural improvement charges shall be paid to S.R.A. and the concerned Planning Authority as per provision in clause (7) below, at the prevailing rates within the areas of respective Municipal Corporations for their areas for the built-up area, over and above the permissible F.S.I. of the zone. These charges shall also apply to the transit camp.
4. The Developer shall deposit with C.E.O., S.R.A., an amount of Rs.40000/- or 3% (for 15.0 m. height rehabilitation building) or 4% (for 24.0 m. height rehabilitation building) or 5% (for 45.0 m. height rehabilitation building) or 7% (for 45.0 m. and above height rehabilitation building) of the cost of construction as per the prevailing A.S.R. whichever is more, for each Rehabilitation Tenement as well as for the Welfare Center/s and Balwadi/s in the Rehabilitation Component of the S.R.S. This amount shall be kept in FD for a period of 10 years. The interest received on this amount, after deducting the reasonable expenses required by C.E.O., S.R.A. for performing the tasks as provided by, shall be handed over to the Co-operative Society for maintenance. The principal amount will be transferred to the account of Cooperative society on completion of the period of 10 years from the date of formation of society.
5. The developer shall be responsible for complete maintenance of the vacant tenements, till their allotments to eligible slum dwellers / S.R.A.
6. The developer shall not create any third party interest by any means except for free sale component or D.R.C. of the scheme. Any such act of the developer shall be liable for administrative action against him including criminal action under relevant law or Cr. PC for the misuse of public property.
7. The concerned developer shall have to pay Infrastructure Development Charges (I.D.C.) at the rate equal to prevailing rates within the areas of respective Municipal Corporations for their areas. Such I.D.C. shall be calculated on the difference of built-up area proposed for construction of rehabilitation component, free-sale component, transit camps, welfare hall, balwadi etc., if any, and built-up area as otherwise normally permissible on the land pertaining to the scheme under the provisions of prevailing D.C.P.R. for the concerned Authority. Sharing of such I.D.C. between S.R.A. and the concerned Authority shall be in proportion of 10 : 90 of the total leviable I.D.C. and the same shall be paid to the concerned Authority in accordance with the payment schedule as may laid down by the C.E.O., S.R.A.,

- (1) provided the installments shall not exceed beyond the completion of construction of the scheme. This amount shall be used for schemes to be prepared for the improvement of infrastructure in slums or slum rehabilitation areas.

14.6.18 BUILDING CONTROL REGULATIONS FOR S.R.S.

1. The developer shall abide by all the terms and conditions laid down in the Commencement Certificate and all N.O.C.s obtained by him while executing the scheme.
2. The R.C.C. work shall be carried out under the supervision of Structural Engineer appointed, and the developer shall abide to all the instructions given in this regards.
3. Habitable Rooms - Size and Width - The minimum size and width for any habitable room shall be as per the provisions of UDCPR.
4. For rehabilitation tenement, provision of a separate kitchen shall not be necessary where an alcove (cooking space with direct access from the main room without a communicating door); of size not be less than 2.40 Sq.m. with a minimum width of 1.20 m.) is provided. If a separate kitchen is provided, it shall not be lesser than 3.30 Sq.m. In area, having a minimum width of 1.80 m.
5. The width of pathways shall be as per the provisions of UDCPR.
6. In water closets, flushing cistern shall not be essential and toilets without this provision may be permitted. The water Closet seat shall be of minimum of 0.46 m. (18 inches) in length.
7. There shall be no size restriction for bath or water closet unit. Moreover, for bathroom, water closet and for kitchen there shall be no stipulation of one wall abutting open space, etc. as long as artificial light and ventilation through any means are provided.
8. The minimum internal size of ventilation shaft shall be 1.50 m. x 2.40 m.
9. **Common Passage :** The minimum width of Common Passage in the Rehabilitation Component shall be 1.50 m. and the maximum shall be 1.80 m., in case of singly loaded corridor floor arrangement, and the same shall be minimum 1.80 m. and maximum 2.40 m. in case of doubly loaded corridor floor arrangement. The area of common passage, not exceeding the prescribed limits in width, provided in Rehabilitation Component shall not be counted towards the computation of permissible in situ F.S.I.
- 10.(A) The minimum plinth height shall be 45 cm. and in flood prone areas, the plinth shall be at least 30 cm. higher than the Highest Flood Level for Ground floors and it shall be minimum 15 cm. in case of building on stilts.
- (B) The minimum clear floor height (finished floor to finished ceiling) of rehabilitation tenement room shall be 2.75 m. and any toilet shall have a clear minimum floor height of 2.40 m.
- (C) The minimum width of each flight, mid-landing and corridor of the staircase shall not be less than 1.50 m. The area of staircase, not exceeding the prescribed limits in width, provided in Rehabilitation Component shall not be counted towards the computation of permissible in situ F.S.I.
- (D) The maximum height of all risers shall be of 15 cm. in a residential building.
- (E) The minimum width of the tread without nosing shall be 25 cm. for any staircase in a residential building, other than stairs provided in fire escapes.
- (F) The minimum head-room in a passage under the staircase and under the staircase shall be 2.20 m.
- (G) The ordinal number of each floor shall be conspicuously displayed in figures of the size of at least 15 cm. on the wall facing the flights of a stairway or at such suitable place as is distinctly visible from the flights.

- (I) (H) Handrails having a minimum height of 0.90 m. from the center of the treads shall be provided.

- (I) **Provisions of Lifts for people as well as accommodating stretcher in any building under the Rehabilitation Component shall be as per the following Table :**

Sr. No.	Height of Building	Minimum No. of Lifts	
		General Lift	Stretcher Lift
1	Up to G + 4 storeys	-	-
2	Up to G + 9 storeys	1	1
3	Up to G + 16 storeys	2	1
4	Above G + 16 storeys	2	2

- (J) For every rehabilitation tenements, ⁽³⁾ (---) 1 Parking Space ⁽³⁾ (---) for two wheeler shall be provided. ⁽³⁾ (---) ⁽³⁾ In addition 1 parking space for three wheeler vehicle for every 20 rehabilitation tenements shall be provided. ⁽³⁾

- (K) The planning, design and construction of any building under S.R.S. shall be such as to ensure safety from fire. For this purpose, the provisions of the Maharashtra Fire Prevention and Life Safety Act, 2006 and the relevant provisions of the National Building Code 2005, as amended from time to time, shall apply.

- (L) RAMP :

- i. For Four wheeler vehicles :- For parking spaces in a basement and upper floor, at least two ramps of minimum 3.0 m. width or one ramp of 6.0 m. width and slope not more than 1:8 shall be provided preferably at the opposite ends.

- ii. For Two wheeler vehicles :- Ramp : Min 3.0 m. width.

All ramps provided shall be within the building line.

11. All provisions mentioned herein above shall be applicable to the buildings under the Rehabilitation Component as well as Composite buildings under S.R.S.
12. In case of multi-storied structures constructed for rehabilitation of the slum dwellers and for the tenements to be made available to the appropriate authorities, as mentioned in The said Regulations, the provision of the said Regulations shall not apply if multi- storied building does not contain at least 40% of the built-up area as rehabilitation component.
13. The above special regulations can be further relaxed by the C.E.O., S.R.A. under written permission in specific cases of demonstrable genuine hardship. In order to make the S.R.S. viable, the C.E.O., S.R.A. shall be competent to award any relaxation/s, wherever necessary, for reasons to be recorded in writing. The C.E.O., S.R.A. may delegate any of the powers conferred upon him under the provisions of the said Regulations and the said Act, except power of relaxation, to any of the officers of the S.R.A., by a general or special order in this behalf.
14. **(A) Amalgamation / Subdivision of Plots and F.S.I. thereon :** Any land declared as S.R.S. area shall be notionally treated as one plot, even if it is spread on part or parts of boundary of different C.S.Nos., Khasara Nos. or Survey Nos. Separate approval shall not be necessary for such deemed amalgamation and such notionally amalgamated plot shall be treated as a single plot for the purpose of F.S.I. computation. However, such an amalgamation shall not include existing nallah, water body or transmission line zone if any.

- (B) Boundaries and measurement of Area Under S.R.S. :** The areas of plots under the S.R.S. shall be certified by the Competent Authority after actual on-site measurement of the

³⁾ Deleted / Replaced / Inserted vide Order No.C.R.116/2024/(Part-2)/UD-13, Dt.11th October, 2024 under Clause (C) - RoD of Notification bearing No.C.R.09/2023/UD-13, Dt.05th December, 2023,

(1)

areas of plots. Such certified boundaries and areas of plots shall be the basis adopted for planning purposes, for calculation of tenement density and F.S.I. and other aspects of planning.

(C) After approval is granted to the Slum Rehabilitation Scheme (S.R.S.), the land earmarked for S.R.S. area may be further subdivided, if necessary, to carve out separate plots for the Rehabilitation Component, Free-Sale Component and the Amenity Component. Both, the Plot area and the Built-up area of the said plots shall be treated as independent plots and mentioned separately in Sq.m. in the lease agreements. However sub-division of the plot for the rehabilitation component and free sale component shall have the proportionate areas of open space/amenity space (if any) vis-à-vis their respective built up areas.

(D) The Collector / City Survey Officer, as the case may be, on payment of such fees as may be applicable in this behalf, shall ensure that the city survey sheets and property cards are corrected accordingly and fresh property cards are opened for each of the plots giving details regarding the area of the plots and the total area of the floors of the built-up property i.e. the F.S.I. used on that plot.

(E) The C.E.O., S.R.A. may, if required, adjust the boundary of the plot declared as slum rehabilitation area so as to suit the building design and provide proper access to the Project.

(F) In case, the land on which any S.R.S. is undertaken is adjoining railway tracks, a boundary wall of minimum 2.40 m. in height shall be constructed on the side of the plot abutting the railway line. The Developer shall be required to furnish a No Objection Certificate (N.O.C.) from the concerned Railway Authority while seeking permission for construction of any building under the S.R.S. within a distance of 30 m. from the railway boundary. Any development on such plot shall be subject to the terms and conditions stipulated by the concerned Railway Authority.

15. C.E.O., S.R.A. shall conduct periodical quality audit of the rehab component from the date of commencement certificate till its completion. Suitable and competent agencies can be hired for this purpose by C.E.O., S.R.A.
16. The developer shall at his own cost ensure comprehensive annual maintenance of lifts, S.T.P. Plant, fire extinguishing, water pumping and generator backup systems for minimum 5 years from the date of occupancy certificate of the rehab building/s so as to avoid any structural and other major defects in the buildings and related services.

In addition, the developer, at his own cost, shall also get the insurance done for the buildings in the rehabilitation component in favor of the Co-op. society for the said period of 5 years.

14.6.19 SLUM AND DEVELOPMENT PLAN RESERVATIONS

Existing hutments in the slum pockets occupying lands in dangerous locations such as hill slopes, marshy lands, or in close proximity of water bodies, or lands abutting Railway tracks or sites immediately required for the public and semi-public projects may be relocated on other suitable locations with the prior approval of C.E.O., S.R.A.

1. Slums situated on the lands falling under any reservations in the Development Plan and / or Town Planning Scheme shall be developed as follows :-

Out of the total area under reservation, 40% of the area shall be earmarked for reservation and rest shall be put to slum rehabilitation in schemes where the existing tenement density of slums is less than 450 T/Ha. The area earmarked for reservation may be reduced to 33 %, where existing tenement density is more than 450 T/Ha. Remaining land under reservation shall be handed over to the concerned Planning / Appropriate Authority as per provision in UDCPR. Provision of Accommodation Reservation shall not be applicable.

- (1)
2. Slums situated on lands under industrial and public / semipublic Zone / Slum Improvement Zone or under reservations for Economically Weaker Section Housing (E.W.S.), High Density Housing (H.D.H.) / Housing for dishoused (H.D.H.) shall be allowed without charging any premium on area of reservation for conversion or accommodation and for allowing redevelopment.
 3. Wherever D.P. Road passes through slum; entire 100 percent F.S.I. of the road may be given for utilization in the same site on the remaining area of such plot.
 4. S.R.S. can be taken up on Town Planning Scheme plots and reservations as well, in accordance with the said Regulations. Contravening structures in the adjoining final plots, if declared as slum area by the Competent Authority or Slum rehabilitation area by the C.E.O., S.R.A. shall be included in the slum rehabilitation scheme (S.R.S.) in the relevant final plot of the Town Planning Scheme.
 5. It shall be an obligatory duty of the Competent Authority to ensure de-notification of the entire slum area, by including all eligible slum dwellers falling in the proposed buildable site, contravening structures, hutments on adjacent non-buildable areas like roads / No Development Zones / Green Belts / reservations, for the purpose of in-situ rehabilitation of such eligible slum dwellers on balance buildable land as per The said Regulations.

14.6.20 CLUBBING OF TWO SCHEMES

1. Clubbing of two or more Slum Rehabilitation Schemes, proposed within a radius of 5 km. aerial distance, may be allowed by keeping the ratio of rehabilitation component to sale component as permissible on the proposed scheme plot. In such a case, the rehabilitation component can be proposed on one land and the sale component on the other. Slum T.D.R. generation in such case shall be as per the incentive of the proposed scheme plot. Provided that this approval shall be subject to payment of difference in the Rate as per A.S.R. of built-up premises for sale components, proposed to be exchanged.
2. The S.R.S. proposal shall be allowed to be executed as Composite proposal, with adjacent encumbered or unencumbered buildable lands. In such a case, the developer may execute the S.R.S. along with any other encumbered or unencumbered buildable land, by availing benefits under the said Regulations on any of the land, restricting the scheme to the rehabilitation component area that existed prior to such composition. This shall even mean allowing rehabilitation component on one land and entire permissible in-situ free sale F.S.I. i.e Maximum Building potential as per UDCPR, on the other land.
3. Development of slum and contagious non-slum area under any other provisions may be allowed together, in order to promote flexibility of design as well as to raise more resources, provided the F.S.I. i.e. maximum Building potential as per UDCPR on non-slum quantum of area shall be that permissible in the surrounding zone. Such a scheme shall be deemed to be a Slum Rehabilitation Scheme. The power under DCPR for shifting and / or interchanging the purpose of designations / reservations shall be exercised by the C.E.O., S.R.A. in respect of slum rehabilitation areas / projects.
4. All the plots involved in any S.R.S., under which ex-situ rehabilitation of hutments dwellers is envisaged, shall be notionally treated as one, for the purpose of computation of F.S.I.

14.6.21 SOCIAL AMENITIES AND RELIGIOUS STRUCTURES

1. Religious structures existing prior to rehabilitation, if allowed as part of rehabilitation in accordance with the guidelines issued by the Government from time to time, shall not exceed the area that existed prior to rehabilitation. However FSI required for the same shall not be counted in the in-situ permissible F.S.I. of slum rehabilitation scheme (S.R.S.).

- (1) 2. (A) There shall be a Welfare Center and Balwadi admeasuring 27.88 sq. m. (Carpet Area) each for every multiple or part of 100 hutment dwellers' families in every S.R.S., as part of the Rehabilitation Component. It shall be located so as to serve all the floors and buildings equitably. Further, two or more such welfare centers and Balwadis may be permitted to be clubbed together suitably for their better utility. Similarly, Health Post and Police Chowky, each of 27.88 sq.m. Carpet Area shall be provided, preferably on Ground Floor under SRS having more than 500 tenements. In case of misuse of the Welfare Centers and / or Balwadi by the members of the Co-operative Housing Society, it shall be taken over by C.E.O., S.R.A. who shall be entitled to allot the same to be run by any suitable organization / institution for public use.

(B) For all sites admeasuring more than 4000 Sq.m. in area, 2.5% of the rehabilitation component area shall be constructed for the Rehabilitation Co-operative Society in the form of Convenience Shopping, where such shops shall not be more than 10 Sq.m. in carpet area, with single floor height preferably on ground floor or first floor. Such area shall be utilized by the society for earning additional income to the society.

Convenience users like Vegetable market, Meat market, Fish market, Barber shop, Grocery shop, Milk Booth, Telephone Booth, Newspaper and Book stall, Stationery shop, Utility shop, Tailor shop, Canteen, Tea Stall etc. shall be permissible in these shops.

The Rehabilitation Co-operative Housing Society shall own these Convenience Shops and shall generate Operation and Maintenance costs for rehabilitation component through these, by way of transparent allotment and operation for which, accounting system may be prescribed by the C.E.O., S.R.A.

Provided that, in the situations where conveyance shopping is not desirable and specifically requested by majority of slum dwellers and such area can be proposed by any dimension as permissible and for any other commercial users like banks / offices / community hall / self help group etc. Provided further that, the modalities on operational aspects, additional uses and allotment process for occupation of such structure shall be decided by C.E.O., S.R.A.

3. One society office of 12.0 Sq.m. (free of F.S.I.) per rehabilitation building for hutment dwellers shall be provided free of cost in every Slum Rehabilitation Scheme and attached toilet of 4.0 Sq.m. area (free of F.S.I.) may be permitted.
4. All the areas underlying welfare halls, society office, balwadi/s, religious structure/s and the commercial areas given by way of incentives to the Co-operative Housing Society shall be free of cost and shall form part of rehabilitation component and shall be considered for incentive F.S.I. computation for the free sale component as per the provisions in the said Regulations.
5. Welfare halls, society office, balwadi/s, religious structure/s, Health Posts, Police Chowky and the commercial areas given by way of incentives to the Co-operative Housing Society provided in the rehabilitation component shall not be counted towards the F.S.I.
6. Similarly, Health post as per the requirement of the concerned Municipal Corporation and Police Chowky of 27.88 Sq.m. Carpet area shall be provided as per the requirement of the Commissioner of Police under a Slum Rehabilitation Scheme. In case of misuse of these facilities, the same shall be taken over by the C.E.O., S.R.A. who shall be competent to allot the same to some other organization / institution for public use.
7. Convenience shopping as defined in the corresponding provisions of the D.C.P.R. of the concerned Authority shall be permitted along the layout roads within the S.R.S., having width of 9.0 m. and above, provided a setback of 3.0 m. is provided. This shopping provision would be in addition to the provision for shop area allowed according to the said Regulations.

(1)

FORMATION OF CO-OPERATIVE SOCIETY**14.6.22**

1. The developer and the beneficiaries of S.R.S. to form and register C.H.S.

A) The eligible hutment dwellers, including the P.A.P.s nominated by the C.E.O., S.R.A., will have to form a Co-operative Housing Society after all members have fully paid their dues to the Corporation, MHADA etc. All the cost involved in connection with registration of the Co-operative Housing Society will be borne by the eligible hutment dwellers and the Developer shall register a Co-operative Housing Society (C.H.S.) of the rehabilitated hutment dwellers within 60 days from the date of issuance of the commencement certificate to the project of Rehabilitation Tenements by the hutment dwellers. Stamp Duty payable under Bombay Stamp Act, 1958 for registration of documents of allotment of such rehabilitation tenements or registration of Co-operative Housing Society shall be fully exempted.

B) The Managing Committee of the registered Co-operative Housing Society of hutment dwellers shall be constituted in accordance with the provisions of Maharashtra Cooperative Societies Act, 1960.

C) The rehabilitation tenement shall be jointly owned by the Pramukh hutment dweller and the spouse, if applicable. The details of ownership including Share Certificate and other relevant documents, shall be so entered and shall be deemed to be so entered in the records of the Co-operative Housing Society. The membership of the Co-operative Housing Society should be finalized based on eligibility criteria as per the provisions of the said Regulations and as specified by C.E.O., S.R.A.

2. The developer registered with S.R.A. shall enter into individual agreement with the eligible hutment dweller of each structure in the slum area under the S.R.S., regarding allotment of his respective Rehabilitation Tenement. Such agreement will be in the joint name of Pramukh hutment dweller and the spouse, if applicable, for every Rehabilitation Tenement.

3. The rehabilitation tenement shall be in the joint ownership of the hutment dweller and the spouse; and shall be so entered and be deemed to be so entered in the records of the co-operative housing society of eligible slum dwellers, including the share certificate and all relevant documents. Such tenement shall not be sold or leased by the hutment dweller up to 10 years from the date of allotment. Such provision shall be included in the Agreement between the hutment dweller and the Developer.

⁽³⁾ 4. (---)

5. The Developer shall register a Conveyance Deed in favor of the Co-operative Housing Society of the rehabilitated hutment dwellers, formed for the constructed rehabilitation built-up area and the land spared for the same, along with common areas, access, marginal spaces left for the building, immediately after such rehabilitated hutment dwellers occupy the building/s in the Rehabilitation Component.

14.6.23**RESPONSIBILITY OF THE CO-OPERATIVE SOCIETY**

1. The Co-operative Society shall be responsible for maintenance of facilities provided within the area leased to the society. The maintenance shall involve sweeping and cleaning of pathways, collection of household garbage and carrying it to the nearest municipal dustbin, maintenance and replacement of common conveniences, etc. The Co-operative Housing Society shall be entitled to levy a suitable service charge on its members for this purpose.
2. Internal roads, pathways, common amenities etc. as shown in the layout of the colony shall be provided as part of the original project. However the Co-operative Housing Society shall be responsible for maintaining the same.

⁽³⁾ Deleted vide Order No.C.R.116/2024/(Part-2)/UD-13, Dt.11th October, 2024 under Clause (C) –RoD of Notification bearing No.C.R.09/2023/UD-13, Dt.05th December, 2023

- (1) 3. The Co-operative Housing Society shall be responsible for payment of municipal taxes and service charges such as those for water supply etc. and for any dues of any other competent authority from time to time.
4. Individual maintenance including electricity bill and water charges if any, etc. of tenements shall be done by the slum dweller to whom the tenement is allotted.

14.6.24 INALIENABILITY

C.E.O., S.R.A. shall issue Identity Cards to each rehabilitated family in the name of the head of the family, jointly with his / her spouse, if applicable. Selling / Transfer / Rent / Lease of the rehabilitation tenement shall not be allowed for a period of 10 years (except to their heirs), from the date of possession of the tenement. In case of breach, C.E.O., S.R.A. shall cancel the allotment in respect of the dweller and take over the tenement. The concerned dweller shall not be eligible for any rehabilitation tenement in any S.R.S. or other Schemes. These conditions shall appear on the identity card as well.

14.6.25 POSSESSION OF THE TENEMENTS / SHOP Possession of the rehabilitation tenement / shop shall be handed over to any eligible hutment dweller only after,

1. The Co-operative Housing Society of the rehabilitated hutment dwellers is registered; And
2. Agreement to lease the land is executed by land owning authority with the Co-operative Housing Society of the rehabilitated hutment dwellers after completing necessary formalities; And
3. After such hutment dweller has surrendered transit accommodation, if any, given to him / her, and has cleared all his / her dues to P.M.C. / P.C.M.C. / P.M.R.D.A. (Restricted to earlier P.C.N.T.D.A. area) / M.I.D.C. / M.H.A.D.A. / Government of Maharashtra.

14.6.26 ALLOTMENT OF THE TENEMENTS TO THE PROTECTED OCCUPIERS

1. The eligibility of the Protected Occupiers shall be decided by the Competent Officers as per the orders issued by the Government in this behalf from time to time.
2. The list of all Protected Occupiers and those held eligible in appeal proceedings shall be obtained from all concerned departments of S.R.A. by the officer drawing the lots. So also such officer shall obtain a copy of plans along with number of rehabilitation tenements per floor from the technical department.
3. The Protected Occupiers evicted forcefully shall also be considered for allotment.
4. Public Notice of the drawing of lots shall be published by the officer 7 days prior to the date of actual allotment. Such a notice shall be published at a conspicuous place of the scheme and the transit camp or accommodation provided for Protected Occupiers by the developer. A suitable Panchanama shall be made of publication of such notice and maintained in official record.
5. The Widow of Protected Occupier / Widow who is Protected Occupier, and the family / families having Blind and Physically Handicapped members, shall be given a preference to select tenement of their choice as far as possible. However in case where same tenement is preferred by more than one such eligible dweller, the decision shall be taken by drawing of lots among themselves.
6. There after remaining tenements shall be allotted to the remaining Protected Occupiers by drawing of lots in the presence of the Protected Occupiers who are present at the time of such allotment. As far as practicable a suitable video recording of the process shall be done, the cost of which shall be borne by the developer concerned.

(1)

7. The list of tenements allotted to eligible slum dwellers shall be prepared, a copy of which shall be forwarded for registration and actual possession of the tenement to the developer, who in turn will file compliance along with the documents.
8. The Occupancy Certificate shall be issued, after the completion of procedure laid down herein above.
9. The agreement and registration of the tenements as per the allotment order shall be carried out by the developer in favor of individual Protected Occupier.
10. The non-residential units of all concerned eligible slum dwellers shall be earmarked along with their respective allotted unit numbers in the building plan at the time of obtaining the commencement certificate only.
11. The C.E.O., S.R.A. shall be competent to take forcible action including an action to disqualify against any protected or Non-protected slum dweller who is not complying the lawful orders passed by him in the interest of the slum rehabilitation scheme. Reasonable opportunity shall be given by C.E.O., S.R.A. to such slum dweller before passing any order in this regard.

14.6.27 ALLOTMENT OF THE TENEMENTS TO THE NON PROTECTED OCCUPIERS

1. The eligibility of the Non Protected occupiers shall be decided by the Competent Officers as per the orders issued by the Government in this behalf from time to time.
2. The allotment shall be subject to payment of subsidized cost of the tenement to be paid by the Non Protected occupier to the S.R.A. Such cost shall be determined taking into account the values prescribed in the A.S.R. for the year in which such an allotment is done.
3. The amount or the Cost of tenement shall be calculated by the C.E.O., S.R.A. as per the policy sanctioned by the State Government in this behalf.
4. Preparation of the list as per seniority of the Non Protected occupiers, allotment of the tenements, recovery of costs and allotment by draws wherever required shall be regulated by a special cell called P.M.A.Y. cell to be formed at the level of S.R.A. The C.E.O. with prior sanction of Government, create such posts required for smooth functioning of such cell.
5. The P.M.A.Y. cell shall maintain a register of Non Protected occupiers in which the seniority of the beneficiary shall be decided on the basis of date on which he has vacated his structure (hutment) in the Rehabilitation Area. In case more than one structure is vacated on the same date, then the seniority will be decided on the basis of the existence of the structure based on proofs submitted by the dweller for deciding his eligibility to the competent authority.
6. In addition to the register prescribed in clause 5 above, the P.M.A.Y. cell shall also maintain another register of tenements available for the allotment.
7. In case where the number of Non Protected occupiers exceeds the number of tenements opted by them in a scheme available for allotment, then the allotment shall be done according to seniority. And in case more than one Non Protected occupier has the same seniority, the allotment shall be done by drawing of lots. In case of dispute in this regard, the decision of the C.E.O., S.R.A. shall be final and binding on all the parties concerned.
8. The tenements available in a scheme shall be allotted to the Protected and Non Protected occupiers in the manner provided herein after –
 - a. The Protected occupier of the said scheme shall be accommodated first.
 - b. The Protected occupiers of adjoining / nearby non buildable Slum Rehabilitation Area shall be accommodated thereafter.
 - c. The Non Protected an occupier of the Slum Rehabilitation Area on which scheme is sanctioned shall have the first priority amongst all such Non Protected occupiers who

- (1) have opted to Rehabilitation by payment of cost in the tenements available in the said scheme. All other Non-Protected occupiers shall be given preference as per their seniority thereafter.
- d. Any disputes raised regarding the allotment of any tenement to any Non Protected occupier shall be decided by The C.E.O., S.R.A. and the decision in such case shall be final and binding upon the Non Protected occupiers.

14.6.28 DE-NOTIFICATION OF SLUM REHABILITATION AREA

1. The C.E.O., S.R.A. shall de-notify partly or fully the Slum Rehabilitation Area as per provisions of Slum Act, on being satisfied that it is necessary to do so or when directed by the State Government.
2. The concerned Ward Officials of respective municipal area and the concerned Police Inspector of the local area shall ensure effective uninterrupted implementation of S.R.S. It shall be their obligatory duty to take required action immediately against Slum lords as well as non-participant and / or obstructionist persons obstructing the sanctioned S.R.S. In case of failure, C.E.O., S.R.A. shall recommend action against such persons under the provisions of the Slum Act and / or applicable Law.

14.6.29 PREMIUM FOR OWNERSHIP AND TERMS OF LEASE

1. Where S.R.S. is proposed to be undertaken on lands owned by the Government, Semi-Government Undertakings and Local Bodies, the developer registered with S.R.A. shall pay premium at the rate of twenty five percent of the land cost as per A.S.R. ⁽³⁾ or in-situ construction area equivalent to such premium where premium and construction cost both are calculated as per A.S.R. in addition to compensation for land calculated as per Section 17 of the Slum Act, 1971.

However, in case of higher density of hutments where no in situ construction is possible, only premium shall be paid.

The premium shall be paid in instalments as mentioned below :-

Sr. No.	Stage of the Scheme	Premium amount to be paid
1	At the time of approval of the Scheme but before issuing of the letter of IoD.	10% of premium amount
2	Before issuing of letter of Commencement of Rehab. building.	10% of premium amount
3	Before issuing of Completion Certificate of Rehab. building.	80% of premium amount

The aforesaid premium charges shall be allowed to be paid in the installments with interest @ 8.5% p.a. as per Regulation No. 2.2.14 of UDCPR.

However the delay payment charges @ 8.5% shall be paid by the developer on premium amounts mentioned in Sr.No. 2 & 3 above from the date of issuing of the letter of IoD till actual payments made to Slum Rehabilitation Authority.

2. The amount of compensation calculated as per Section 17 of the Slum Act, 1971 shall be paid to the land owning department of the Government or Semi-Government Undertakings and Local Bodies.
3. The decision of C.E.O., S.R.A. regarding possibility of in-situ construction depending on slum location shall be final and binding on all the parties concerned.
4. The part of the land belonging to the Government / Semi-Government / U.L.B. / Public Trusts / M.H.A.D.A. / P.M.C. / P.C.M.C. / P.C.N.T.D.A. / M.I.D.C., on which the

⁽³⁾ Inserted vide Order No.C.R.116/2024/(Part-2)/UD-13, Dt.11th October, 2024 under Clause (C) – RoD of Notification bearing No.C.R.09/2023/UD-13, Dt.05th December, 2023,

- (1) rehabilitation project will be constructed shall be leased by the concerned land owning authority to the Co-operative Housing Society of slum dwellers for a period of 30 years at lease rent of Rs.1001 for 4000 sq. m. of land and part thereof, which shall be renewable for further periods of 30 years at a time. The same dispensation shall apply to the land under the free sale component and such land shall be leased directly, and not through the slum dwellers, to the registered Co-operative Housing Society / Association of the purchasers of tenements in the free sale component and, pending the formation of such Cooperative Housing Society / Association of the purchasers of tenements in the free sale component, such land shall be leased to the developer. The said lease deed shall be executed within 60 days from the date of issuing building permission to the project.
5. Recovery of pending dues such as assessment, compensation, occupation charges, usage charges, revenue or non-agricultural tax/dues etc., pending with public authorities such as the State Government, M.H.A.D.A., M.S.E.D.C.L. and / or Municipal Corporation, although binding on the Developer, shall not be linked to grant of approval or building permission and implementation of the Slum Rehabilitation Scheme. The Developer will have to settle all pending dues before issue of occupancy certificate by S.R.A. Any revenue assessments, permissions, orders to be made for any land under S.R.S. shall not be linked to the issue of any certificate or N.O.C. relating to the S.R.S.
6. **Automatic cancellation of restricted Land Tenure :** If any land or part of any land on which slum is located is under restricted land tenure, the said tenure / lease created by the concerned Public Body shall stand automatically terminated as soon as S.R.S., which is a public purpose, is prepared on such land and submitted for approval to the C.E.O., S.R.A. Any arrears of dues to be collected for such land shall not be linked to the issue of any certificate or N.O.C. relating to the S.R.S.} ⁽¹⁾

14.7 SLUM REHABILITATION SCHEME FOR OTHER MUNICIPAL CORPORATIONS

Slum rehabilitation scheme for other Municipal Corporations, excluding covered in Regulation No.14.6, shall be as below.

14.7.1 Eligibility for redevelopment scheme

- i) A person eligible for redevelopment scheme shall mean a protected occupier as defined in Chapter-IB of Maharashtra Slums Areas (Improvement, Clearance and Redevelopment) Act, 1971 as amended time to time, (hereinafter referred to as the Slum Act) and orders issued there under.
- ii) Subject to the foregoing provisions, only the actual occupants of the hutment shall be held eligible, and the so-called structure-owner other than the actual occupant if any, even if his name is shown in the electoral roll for the structure, shall have no right whatsoever to the reconstructed tenement against that structure.

14.7.2 Definition of Slum, Pavement, and Structure of hut

- i) Slums shall mean those censused, or declared and notified, in the past or hereinafter under the Slum Act. Slum shall also mean area/pavement stretches hereinafter notified or deemed to be and treated as Slum Rehabilitation Areas.
- ii) If any area fulfils the condition laid down in section 4 of the Slum Act, to qualify as slum area and has been censused or declared and notified shall be deemed to be and treated as Slum Rehabilitation Areas.
- iii) Slum Rehabilitation area shall also mean any area declared as such by the SRA though preferably fulfilling conditions laid down in section 4 of the Slum Act, to qualify as slum area and/or required for implementation of any slum rehabilitation project. Any area

where a project under Slum Rehabilitation Scheme (SRS) has been approved by CEO, SRA shall be a deemed slum rehabilitation area.

- iv) Any area required or proposed for the purpose of construction of temporary or permanent transit camps and so approved by the SRA shall also be deemed to be and treated as Slum Rehabilitation Areas, and projects approved in such areas by the SRA shall be deemed to be Slum Rehabilitation Projects.
- v) A pavement shall mean any Municipal/Govt. /Semi-Govt. pavement, and shall include any viable stretch of the pavement as may be considered viable for the purpose of SRS.
- vi) A structure shall mean all the dwelling area of a protected occupier as defined in Chapter I-B of Slums Act, and orders issued thereunder.
- vii) A composite building shall mean a building comprising both rehab and free-sale components and part thereof in the same building.
- viii) Censused shall mean those slums located on lands belonging to Govt., any undertaking of Govt., or Corporation and incorporated in the records of the land-owning authority as having been censused in 1976, 1980, or 1985 or prior to 1st January, 1995, and 1st January, 2000

14.7.3 Joint ownership with spouse

The reconstructed tenement shall be of the ownership of the hutment dweller and spouse conjointly, and shall be so entered and be deemed to be so entered in the records of the co-operative housing society, including the share certificates or all other relevant documents.

14.7.4 De-notification as Slum Rehabilitation Area

SRA on being satisfied that it is necessary to do so, or when directed by the State Govt., shall de-notify the Slum Rehabilitation Area.

14.7.5 Applicability

The following provisions will apply for redevelopment / construction of accommodation for hutment / pavement-dwellers through owners / developers / co-operative housing societies of hutment / pavement-dwellers/public authorities such as MHADA, MIDC, MMRDA etc. / Non-Governmental Organizations anywhere within the limits of Municipal Corporation. However, NGO should be registered under the Maharashtra Public Charitable Trusts Act, 1961 and the Societies Registration Act, 1960 at least for the last five years and should also be approved by SRA.

14.7.6 Right of the Hutment Dwellers

- i) Hutment dwellers, in the slum or on the pavement, eligible in accordance with the provisions of this Regulation shall in exchange of the protected dwelling structure, be given free of cost a residential tenement having a carpet area of 27.88 Sq.m. including balcony, bath and water closet, but excluding common areas.

For this purpose, “carpet area” means the net usable floor area within a tenement excluding that covered by the walls or any other areas specifically exempted from floor space index computation as per prevailing Regulation.

- ii) Even those protected dwelling structures having residential areas more than 27.88 Sq.m. shall be eligible only for 27.88 Sq.m. of carpet area where Carpet area means area of tenements as mentioned in (i) above.
- iii) All eligible hutment dwellers taking part in the SRS shall have to be rehabilitated in accordance with the provisions of these Regulations. It may be in situ and in the same scheme as far as possible.

-
- iv) Pavement dwellers and hutment dwellers in the slum on land required for vital public purpose or such location which are otherwise unsuitable for human habitation or non-suitable due to other statutory restriction shall not be rehabilitated in-situ but in other available location and in accordance with these Regulations. Competent Authority appointed by the State Government in Housing Department shall on the basis of verification of documents, as may be prescribed, shall decide on the eligibility of hutment dwellers.
 - v) The eligibility of a person including a transferee, under a scheme of Slum redevelopment shall be established in accordance with Chapter-IB of Slum Act, and orders issued thereunder.
 - vi) An individual agreement shall be entered into by the owner / developer / co-operative housing society / NGO with the eligible hutment-dwellers in the slum / pavement.
 - vii) An individual agreement entered into between hutment-dweller and the owner / developer / co-operative society / NGO shall be in the joint names of pramukh hutment dweller and spouse for every protected dwelling structure
 - viii) Hutments dwellers in category having a differently abled person or female headed households shall be given first preference in allotment of tenements. Thereafter lots shall be drawn for allotment of tenements from the remaining tenements to the other eligible hutment-dwellers before grant of occupation certificate to rehab Building.
 - ix) Transfer of Photo passes- Since, only the actual occupant at present will be eligible for redevelopment; there shall be no need to regularize the transfers of photo passes that have occurred so far. A photo pass will be given after the new tenement has been occupied.
 - x) Any person who owns a dwelling unit on ownership basis in Municipal Corporation areas shall not be held eligible under the scheme. Any person, who can be held eligible under more than one SRS, shall be held eligible in only one scheme.
 - xi) Premium for ownership and terms of lease-That part of Government / Municipal Corporation / MHADA land on which the rehabilitation component of the SRS will be constructed, shall be leased to the Co-operative Housing Society of the slum-dwellers on 30 years lease period. Annual lease rent of Rs.1001/- for 4000 per Sq.m. of land or part thereof shall be payable and lease shall be renewable for a further period of 30 years at a time. Simultaneously land under free sale component shall be leased directly to the Society / Association of the purchasers of the tenement under free sale component for 30 years with a provision for further renewal for a period of 30 years at a time. The lease rent for the free sale component shall be fixed by SRA.

Further, the Developer/Co-op. Housing Society shall pay premium at the rate of 25% of ASR of the year of issue of LOI, in respect of SRS proposed to be undertaken on lands owned by Government, Semi-Government undertakings and Local Bodies and premium shall go to land owing authority such as MHADA, Municipal Corporation, MMRDA, as the case may be. The premium instalment so recovered shall be remitted to concerned land owing authority within 30 days from the date of recovery.

In the case of Government land, the premium shall be deposited in Nivara Nidhi.

The amount of premium shall be recovered in instalment as may be prescribed by Govt. from time to time. Land owning authority such as Municipal Corporation, MMRDA, MHADA shall not recover land premium in any other form. Proposals for SRS on land owned by Central Government shall not be accepted unless NOC for the scheme is obtained from Central Government.

- xii) Automatic cancellation of Vacant Land Tenure and leases- If any land or part of any land on which slum is located is under vacant land tenure, the said tenure / lease created by

Municipal Corporation or Authority shall stand automatically terminated as soon as letter of Intent is issued by SRA for a SRS, which is a public purpose, on such land is prepared and submitted for approval to the SRA. Any arrears of dues to be collected by Municipal Corporation shall not be linked to the issue of any certificate or NOC relating to the Slum Rehabilitation Scheme.

On sanction of SRS, rights of Imlamalik, municipal tenants or any other tenancy shall stand terminated in respect of the sanctioned SRS.

- xiii) Recovery of pending dues such as assessment, compensation, occupational charges, non-agricultural tax / dues etc. pending with public authorities such as State Govt., MHADA, and / or Municipal Corporation shall be dealt with separately and not be linked to grant of approval or building permission to the slum rehabilitation projects.
- xiv) A Slum Rehabilitation Project shall be considered preferably when submitted through a proposed or registered co-operative housing society of hutment dwellers on site. The said society shall include all the eligible hutment on site while submitting the S.R. Scheme and give an undertaking to that effect to SRA.
- xv) Where 51% percent or more of the eligible hutment-dwellers in a slum and stretch of road or pavement contiguous to it at one place agree to join a rehabilitation scheme, it may be considered for approval, subject to submission of irrecoverable written agreements of eligible hutment-dwellers before LOI. Provided that nothing contained herein shall apply to Slum Rehabilitation Projects undertaken by the State Government or Public authority or as the case may be a Govt. Company as defined in Sec.617 of the Companies Act, 1956 and being owned & controlled by the State Government
- xvi) In respect of those eligible hutment-dwellers on site who do not join the Project willingly the following steps shall be taken :
 - a) Provision for all of them shall be made in the rehabilitation component of the scheme.
 - b) The details of the tenement that would be given to them by way of allotment by drawing lots for them on the same basis as for those who have joined the Project will be communicated to them in writing by the Managing Committee of the Cooperative Housing Society if it is registered, or the developer. In case of dispute, decision of the CEO, SRA shall be final and binding on all the parties concerned.
 - c) The transit tenement that would be allotted to them or rent payable would also be indicated along with those who have joined the Project.
 - d) If they do not join the scheme within 15 days after the approval has been given to the Slum Rehabilitation Project on that site, then action under the relevant provision including Sections 33, 33(A) and 38 of the Slum Act, as amended from time to time, shall be taken and their hutments will be removed, and it shall be ensured that no obstruction is caused to the scheme of the majority of persons who have joined the scheme willingly.
 - e) After this action under the foregoing clause is initiated, they will not be eligible for transit tenement along with the others, and they will not be eligible for the reconstructed tenement by lots, but they will still be entitled only to what is available after others have chosen which may be on the same or some other site.
 - f) If they do not join till the building permission to the Project is given, they will completely lose the right to any built-up tenement, and their tenement shall be taken over by the SRA, and used for the purpose of accommodating pavement-dwellers and other slum dwellers who cannot be accommodated in-situ etc.

- xvii) The Managing Committee of the proposed as well as registered Co-operative housing society of hutment dwellers shall have women to the extent of one-third of the total strength of actual members on the committee at any time.
- xviii) Restriction on Transfer of Tenements; the tenement obtained under this scheme cannot be sold/leased/assigned or transferred (except to legal heir) in any manner for a period of ten years from the date of allotment/possession of the tenement. In case of breach of conditions, except transfer to legal heir, the tenement will be taken over by SRA.

14.7.7 Building Permission for Slum Rehabilitation Project

- i) The proposal for each Slum Rehabilitation Project shall be submitted to the SRA with all the necessary documents, no-objection certificates, and the plans as may be decided by the SRA from time to time.
- ii) Approval to the Project shall be given by the SRA within a period of 60 days from the date of submission of all relevant documents. In the event of failure by SRA to do so, the said approval shall be deemed to have been given, provided the Project is in accordance with the provisions of these Regulations.
- iii) The SRA while giving the approval may lay down terms and conditions as may be necessary.
- iv) The SRA shall adopt the procedure laid down in the M.R. & T.P. Act, 1966 for giving building permission to any Slum Rehabilitation Project under this Scheme.
- v) On compliance with the terms and conditions, the building permission shall be given, in accordance with the provisions under section 45 of the M.R. & T.P. Act, 1966 to the Project under the SRS, first to the Rehabilitation component and thereafter to the free-sale component subject to the provisions in clause below.
- vi) Correlation between Rehabilitation and free-sale components: Building permission, for 10 percent of BUA of both the rehab and free-sale components may be given simultaneously and thereafter proportionately or as may be decided by the CEO, SRA.
- vii) Where the Project is being implemented directly by an NGO approved by SRA, CEO (SRA) may sanction 20 percent of the free-sale component without waiting for any expenditure on the rehabilitation component. The approval for remaining part of free-sale component will be given only after at least 30 percent of rehabilitation component is completed on site.
- viii) As soon as the approval is given to the Project, the NOC for building permission of the landowning authority shall be given in respect of that slum located on lands belonging to any department, undertaking, agency of the State Govt. including MHADA, or any local self-Government such as the Municipal Corporation within 60 days after the intimation of such approval to the Project is communicated. In the event of its refusal to grant NOC, reasons thereof shall be stated and in the event of its not being given within the period, it shall be deemed to have been given'.
- ix) Occupation certificate shall not be held up only for want of lease documents to be executed, in all slum rehabilitation projects taken up on lands belonging to any department, undertaking, agency of the State Govt., including MHADA, and any local self-Government such as the Municipal Corporation.

14.7.8 Rehabilitation and Free-Sale Component

- i) FSI for rehabilitation of eligible slum/pavement-dwellers includes the FSI for the rehab component, and for the free-sale component. The ratio between the two components shall be as laid down herein below.
- ii) Built up area (BUA) for rehabilitation component shall mean total construction area of rehabilitation component, excluding what is set down in Regulation 14.7.9(vi) of these

Regulations, but including areas under staircases, passages, anganwadi, health center / outpost, community hall / gymnasium / fitness center, skill development center, women entrepreneurship center, yuva Kendra / library, Balwadi/s society office, religious structures as permitted under Government Home Department Resolution dt.05/05/2011 and 18/11/2015, other social infrastructure like School, Dispensary, Gymnasium run by Public Authority or Charitable Trust, 5 percent incentive commercial areas for the Co-operative society, and the further 5 percent incentive commercial area for the NGO, Govt. / Public Authority / Govt. Company wherever eligible.

- iii) The incentive FSI / BUA shall depend on size of the scheme and rate of developed land and rate of construction as per ASR of year in which LOI is sanctioned.

⁽¹⁾ Basic Ratio (LR / RC*)	Incentive as per scheme				
	Upto 0.20 ha.	More than 0.20 ha. upto 0.40 ha.	More than 0.40 ha. upto 1 ha.	More than 1 ha. upto 5 ha.	For more than 5 ha.
Above 2.00	⁽¹⁾ 1.50	⁽¹⁾ 1.60	⁽¹⁾ 1.75	⁽¹⁾ 2.00	⁽¹⁾ 2.25
Above 1.50 and upto 2.00	⁽¹⁾ 1.60	⁽¹⁾ 1.75	⁽¹⁾ 2.00	⁽¹⁾ 2.25	⁽¹⁾ 2.50
Above 1.00 and upto 1.50	⁽¹⁾ 1.75	⁽¹⁾ 2.00	⁽¹⁾ 2.25	⁽¹⁾ 2.50	⁽¹⁾ 2.75
upto 1.00	⁽¹⁾ 2.00	⁽¹⁾ 2.25	⁽¹⁾ 2.50	⁽¹⁾ 2.75	⁽¹⁾ 3.00

*RC is the rate of construction in respect of RCC Construction and LR is the Land Rate of open Land. FSI to be sanctioned on a Slum Rehabilitation scheme site may exceed ⁽¹⁾ 4.00.

⁽¹⁾ Note - 1 : In Case of any Slum Redevelopment Scheme is in progress and any Slum redevelopment scheme where LOI has been issued, envisaging construction of rehabilitation tenements having individual carpet area of 25.0 sq.mt., if full occupation permission has not been granted and if it is structurally not feasible to provide rehabilitation tenements having individual carpet area as per these regulation, without having completely pull down and reconstructed the on-going rehabilitation building(s). Permissible sale component vis-à-vis rehab component shall be 1.25:1 subject to maximum in-situ FSI of 4.0.

- iv) ⁽¹⁾ Maximum FSI permissible that can be sanctioned on any slum site shall be 4.0 or sum of total of rehabilitation BUA plus incentive BUA, whichever is more, with minimum tenement density of 650 per net hectare. Due to local planning constraints and viability of Slum Rehabilitation Project, the tenement density norms of 650 per net hectare may be reduced upto 25% by Chief Executive Officer, SRA, subject to minimum tenement density of 500 per net hectare. In such cases, maximum permissible in-situ / total FSI shall be restricted to sum of rehabilitation and incentive BUA which may be generated in the scheme after such relaxation of tenement density. ⁽¹⁾ The computation of FSI shall be done for both rehab and free-sale components in the normal manner, that is giving the benefit of what is set down in Regulation No.14.7.9(vi). While the areas referred in sub Regulations No.14.7.11(vi) and 14.7.13(ii) of this Regulation shall not be included for computation of FSI, and the said areas shall be included for computation of the rehab component. In all cases where permissible in-situ FSI cannot be utilised in situ the difference between permissible FSI and that can be constructed in-situ, will be made available in the form of TDR in accordance with the provisions of Regulation 11.2.
- v) Notwithstanding the provisions in (iv) above, the slum dweller society / NGO / Developer undertaking the scheme may opt to claim TDR in lieu of sale component available for the scheme, on account of constraints such as height restrictions, uneconomical site conditions, etc.; if the full permissible FSI cannot be used on the same site, TDR may be allowed as may

⁽¹⁾ Inserted vide Notification u/s 37 (IAA)(c) & 20(4) No.CR 236/18 (Part-3), dt.3rd February, 2022

be necessary without consuming permissible FSI on the same site. However, TDR may be allowed only when the frame work for one complete building in rehab component is constructed or when 10% of the rehab component has been constructed on site and the said TDR will not exceed 50 percent of the construction of rehab component at any point of time till the total rehab component has been completed. On completion of the total rehab component balance TDR will be allowed.

- vi) The rehabilitation component shall mean all residential tenements as well as non-residential built-up premises given free of cost in accordance with the provisions of the SRS outlined in this Regulation excluding what is set down in Regulation 14.7.9(vi) and including anganwadi, health centre / outpost, community hall / gymnasium / fitness centre, skill development centre, women entrepreneurship centre, yuva kendra / library existing eligible religious structure, school, dispensary, gymnasium run by Public Authority or charitable trust etc. as per provision of 14.7.13(i) & (ii) but excluding built-up area given for buildable DP reservations.
- vii) Notwithstanding anything contained in this regulation, if rehabilitation project of a slum located on land belonging to public authority and needed for a vital public purpose and where eligible slum dwellers which cannot be accommodated in the in- situ SRS of land under non-buildable reservations, is taken up on an unencumbered plot, TDR as per Regulation No.11.2 for the area of the land spared for this purpose shall be sanctioned to the owner of the said unencumbered plot and the TDR in lieu of cost of construction of BUA as per Regulation No.11.2 shall be permissible. For the purpose of this regulation BUA shall be as per Regulation No.14.7.8(ii) of this Regulation. Following conditions shall be applicable for such scheme.
 - a) The Rehabilitation Project is approved by the SRA.
 - b) The tenements so constructed in execution of the Project are offered to slum dwellers located on land belonging to Govt. or Public Authority and needed for vital public purpose and within 270 days from the date of issue of LOI the Agency shall identify the slum dwellers.
 - c) If the Agency fails to identify the slum dwellers needed to be shifted for a vital public purpose, as above, then the tenements so constructed shall be offered;
 - i) To the slum dwellers located on land belonging to Government or Public Authority within a distance of 2 km. from the land on which the Project is undertaken, or
 - ii) To the slum dwellers located anywhere in the Corporation limit on lands belonging to Govt. or Public Authority,
 - d) Further provided that in all above cases the relocation of slum dwellers in any case will be undertaken not with reference to individuals but reference to assembly of slum dwellers for the purpose of releasing the plot of land wholly from slums and not only the patches of land.
 Provided further that, these provisions are also applicable to lands belonging to or leased out to or leased out by a Public Authority, a Statutory Authority, a Public Sector undertaking or any Department of Government of India and a Joint Venture with any of them, subject to payment of premium for infrastructure development as applicable under Regulation No.14.7.14(ii) of this Regulation.
 - e) No sale component shall be permissible.
 - f) In case of slums on municipal lands, there will be as option to exercise the powers of CEO, SRA by the Municipal Commissioner with the prior approval of the Government.

- viii) All non-residential built-up areas shall be included in the computation of minimum density but on the scale of 20.90 sq.m. of carpet area being one tenement.
- Provided further that in case of slum redevelopment where there are no eligible commercial slum dwellers and where it is possible to provide commercial tenements on ground floor, then in such cases commercial PAP tenements of size of carpet area 20.90 Sq.m. (225 Sq.ft.) or of required size shall be provided as decided by CEO (SRA) and same shall be handed over free of cost to SRA.
- Provided if SRS is undertaken by a Federation, Co-Op. Housing society consisting of members who are serving or retired State Govt. Employees / Employees of the State Govt. Undertakings / Employees of local bodies of State Government for providing housing to its members, such tenements which are generated over and above the tenements to be provided to the existing eligible hutment dwellers, shall be handed over back to the said Federation / Co.-operative Housing Society for providing housing to its above mentioned members and subject to further additional terms and conditions as would be imposed by the CEO, SRA to ensure adequate membership of class III and class IV employees.
- ix) Any land declared as slum rehabilitation area or on which slum rehabilitation project has been sanctioned, if it is spread on part or parts of C.S. Nos. or CTS Nos. or S.Nos. or F.P. Nos. shall be treated as natural amalgamation / subdivision/s of that C.S. or CTS or S.No. or F.P.No. for which no separate approval for amalgamation / subdivision of land would be necessary.
- x) Boundaries and the Slum Rehabilitation Area shall be declared by the competent authority after actual measurement of plot area on site and the same shall be adopted for planning purpose for calculation of density and floor space index.
- xi) The CEO, SRA may if required, adjust the boundary of the plot declared as slum rehabilitation area so as to suit the building design and provide proper access to these Scheme. Provided further that the encumbered area under D.P. Road / Sanctioned Regular line road abutting the SRS shall be included in the scheme to be developed.
- xii) After approval is given to the Slum Rehabilitation scheme, the area may be further subdivided if necessary to earmark separate plots for the rehab component and the free sale component. The Plot area and the built-up area in terms of square meters on the said plot shall be separately mentioned in the lease agreements and Record of Rights.
- xiii) The CTSO / SLR, of the district on payment of such fees as may be decided by the Govt. ensure that the City Survey sheet and property cards are corrected accordingly and fresh property cards are opened for each of the plots giving details regarding the area of the plots and the total area of the floors of the built-up property and TDR given that is, the FSI used on that plot.

14.7.9 Temporary Transit Camps

- i) The multi-storeyed temporary transit camp shall be provided on the site itself or outside the SRA project site on portion of plot which is not designated / reserved for public purpose or not affected by road widening and is preferably close to the site.
- ii) The eligible slum dwellers shall be shifted to temporary transit camp or on rent as may be mutually decided between the proposed society and developer.
- ii) The area of temporary transit tenements shall be excluded from the computation of FSI, but the safety of the structure shall be ensured by a license structural consultants. The minimum area of individual transit tenement shall be 14.5 Sq.m.

- iv) Such building permission shall be given within 15 days from the date of application and after approval to the project by Slum Rehabilitation Authority, failing which it shall be deemed to be given.
- v) On any nearby vacant site without any reservation in the DP construction of temporary transit tenements made of light material with the consent of the landowners, shall be allowed upto an FSI of 3.0 and this shall be applicable. Temporary shall mean made of detachable material such as tubular / prefabricated light structures.
- vi) In all such cases where the temporary transit camp is erected, the condition shall be that the structures shall be demolished by the Developer / Society / NGO within 30 days of granting Occupation Certificate to the rehab buildings and the site should be brought back to the original state. Till the transit camps are fully demolished, development rights for the free sale area shall not be permitted to be used beyond 75% of the total admissible free sale area permissible under this Regulation.

14.7.10 Commercial / Office / Shop / Economic Activity Free of Cost

- i) The eligible existing area under commercial / office / economic activity shall be computed on actual measurement / inspection, and / or on the basis of official documents such as License under the Shops and Establishment Act, Electricity bills, Photo pass etc.
- ii) In the rehabilitation component, the BUA for commercial / office / shop / economic activity that existed prior to the date as decided by the Government subject to the provisions in the sub-regulation below shall be given. Where a person has both residential and commercial premises without common wall between residential and commercial premises, for commercial / office / shop / economic activity in the slum / pavement, he shall be considered eligible for a residential / Commercial unit including BUA for commercial / office / shop / economic activity, both free of cost and carpet area of such unit shall not exceed 27.88 sq.m.
- iii) BUA for commercial / office / shop / economic activity upto 20.90 sq.m. (225 sq.ft.) carpet area or actual area whichever is less, shall be provided to the eligible person free of cost as part of the rehabilitation project. Any area in excess of 20.90 sq.m. to the extent of existing area may, if required, be sold on preferential basis at the rate for commercial area in the free-sale component.
For this purpose, “carpet area” as per (i) and (ii) above means the net usable floor area within a tenement excluding that covered by the walls or any other areas specifically exempted from floor space index computation as per prevailing Regulation.
- iv) Such area may be allowed on any side of the plot abutting 3.0 m. wide pathway and deriving access from 3.0 m. wide pathway / open space. Back-to-back shopping on ground floor shall also be allowed for the purpose of rehabilitation. After exhausting these provisions, it may be allowed on the first floor to the extent necessary.
- v) All activities which were previously existing shall be allowed to be relocated regardless of the non-conforming nature of the activities, except those which are hazardous and highly polluting, and except in cases where the alternative accommodation has already been allotted elsewhere by the Municipal Corporation.
- vi) Convenience shopping in the free-sale component shall be permitted along the layout roads. The CEO, SRA may add to alter or amend the said list for convenience shopping.
- vii) Incentive Commercial Areas for Society and NGO -
 - a) The scheme, when undertaken by a Co-operative Housing Society of slum dwellers, may provide an additional 5 percent built-up area on the rehabilitation area free of cost

for commercial purpose. This area will be at the disposal of the Co-operative Housing Society of the hutment-dwellers. The corpus amount shall not be spent, but the income from the property / corpus alone shall be used by the Society for maintenance of the building and premises, and such other purposes as may be laid down by the SRA.

- b) Where the scheme is undertaken by a Non-Government Organization Govt. or Public Authority or Govt. Company another additional 5 percent BUA on the rehabilitation area may be given free of cost for commercial purpose. This area shall be at the disposal of the Non-Governmental Organization Govt. or Public Authority or Govt. Company in consultation with the co-operative housing society.

14.7.11 Relaxation in Building and Other Requirements

- i) Separate kitchen shall not be necessary. Cooking space (alcove) shall be allowed without any minimum size restrictions. Where a kitchen is provided, the minimum area shall be 5.0 Sq.m. provided the width shall be at least 1.5 m.
- ii) There shall be no size restriction for bath or water closet unit. Moreover, for bathroom, water closet or kitchen, there shall be no stipulation of one wall abutting open space, etc. as long as artificial light & ventilation through any means are provided.
- iii) In water closet flushing system shall be provided with minimum seat size of 0.46 m. (18 inches).
- iv) A septic tank filter bed shall be permitted with a capacity of 150 liters per capita, where the municipal services are likely to be available within 4-5 years.
- v) In the rehabilitation component, lift shall not be insisted upon, upto ground plus five floors.
- vi) Notwithstanding anything contained in this regulation, areas of common passages not exceeding 2.0 m. in width provided in rehabilitation component to give access shall not be counted towards FSI even while computing FSI on site.
- vii) Where the location of the plot abuts a nallah, the marginal open space along the nallah shall not be insisted upon beyond 3.0 m. from the edge of the trained nallah, provided at least on one side of nallah, marginal open space of 6.0 m. is provided.
- viii) The distance between any two rehab. / composite buildings shall be as follows -
 - a) For building with height up to 40.0 m. – Min. 6.0 m.
 - b) For building with height above 40.0 m. upto 50.0 m. – Min. 7.50 m.
 - c) For building with height above 50.0 m. upto 70.0 m. – Min. 9.0 m.
 - d) For building with height above 70.0 m. – Min. 12.0 m.

⁽¹⁾ The marginal distances from the front side and rear boundaries of the plot shall be maintained as follows -

 - a) If the slum rehabilitation site fronts on one or more roads, every side abutting on such roads shall be treated as front side & marginal distances prescribed below for such front side shall apply. The front marginal distance shall be measured from the proposed road widening line in the plot, if any.
 - b) In congested area, the front marginal distance shall be minimum 1.5 m.
 - c) In non-congested area the front marginal distance shall be minimum 4.5 m. for purely residential building and 6.0 m. for mixed use buildings.
 - d) Side and rear marginal distances from the side and rear boundaries of the plot shall be minimum 3.0 m. for height upto 24.0 m. It shall be increased proportionately with

⁽¹⁾ Inserted Vide Corrigendum / Addendum No.CR 79/2021, dt. 02nd December 2021.

- increase in height above 24.0 m., but shall not exceed 6.0 m. for height upto 45.0 m. For building height more than 45.0 m. relaxation to the extent of 50% in all marginal distances may be given, subject to minimum 6.0 m.
- e) Front marginal open spaces for building having height upto 24.0 m. in the rehab-component or composite building shall be 4.5 m. & 6.0 m. for buildings having height more than 24.0 m.
 - ix) A composite building shall contain at least 50 percent of the built-up area as rehabilitation components.
 - x) Wherever more than the minimum front and marginal spaces have been provided, such additional area provided may be considered as part of the amenity open space in the project comprising both rehabilitation and free sale components, and without charging any premium.
 - xi) Even if the amenity space is reduced to make the project viable a minimum of at least 8% of amenity open space shall be maintained at ground level.
 - xii) Between the dimensions prescribed for the pathway and marginal distances, the larger of the two shall prevail. The pathway shall act as access wherever necessary. The building shall be permitted to touch pathways.
 - xiii) The means of access shall be normally governed by the provisions of Regulation No.3.2. However, in the project, wherever the design of the buildings in the same land requires relaxation, it may be given. Access through existing pathways including the roads maintained under relevant section of the MMC Act, 1949 but not less than 3.6 m. in width, shall be considered adequate for any slum rehabilitation project, containing buildings having height up to 24.0 m. including stilts.
 - xiv) Premium shall not be charged for exclusion of staircase and lift-well etc.
 - xv) All relaxations outlined hereinabove shall be given to the rehabilitation component, and also to the composite buildings in the project. Premium shall not be charged for all or any of the relaxations given hereinabove. Provided that if any further relaxation in open spaces is granted by Chief Executive Officer then the same shall be subject to compliance of CFO requirement and recovery of premium at the rate 2.5% of ASR. In case of Slum Rehabilitation Schemes under this regulation, the amount of premium shall be computed as per the ASR rate prevailing at the time of issue of IOA and the same shall be recovered at the time of grant of full occupation permission to the respective building. All other redevelopment schemes shall be governed by their respective regulations.
 - xvi) Relaxations for the free sale component - Relaxation contained in sub Regulation No.(viii) above, as well as other necessary relaxation shall be given to the free sale components on payment of premium at the rate of 2.5% of Ready Reckoner Rate or 10% of normal premium whichever is more.
 - xvii) In order to make the SRS viable, the CEO of SRA shall be competent to make any relaxation wherever necessary for reasons to be recorded in writing.
 - xviii) For rehabilitation tenements, car parking at the rate mentioned in these Regulation shall be provided or one parking spaces per tenement for two-wheeler shall be provided. The above parking spaces may be provided in any combination.

14.7.12 Slums and Development Plan Reservations :

Slums situated in lands falling under various reservations/zones in the D.P. shall be developed in accordance with the following provisions.

-
- i) Slums in any zone shall be allowed to be redeveloped in-situ without going through the process of change of zone. In the free-sale component in any zone, in addition to residential uses, all the uses permitted for the original zone shall be permitted. For industrial uses, the segregating distance shall be maintained from the existing industrial unit.
 - a) Any plot / layout having area under non-buildable / open space reservations admeasuring up to 500 Sq.m. shall be cleared by shifting the slum-dwellers from that site.
 - b) Where the area of site having non-buildable / open space reservation, is more than 500 Sq.m. such sites may be allowed to be developed for slum redevelopment subject to condition that the ground area of the land so used shall not be more than 65% of the reservation and leaving 35% rendered clear thereafter for the reservation.
 - ii) Existing slum structures on lands reserved for Municipal School / Primary and secondary school or a Higher Education may be developed subject to the following :-
 - a) In case of land reserved for Municipal School, Primary and secondary school in the D.P., a building for accommodating such number of students as may be decided by the Municipal Commissioner, nor in any case for less than 500 students, shall be constructed by the owner or developer at his cost according to the size, design, specification and conditions prescribed by the Municipal Commissioner. The built-up area occupied by the constructed building shall be excluded for the purpose of FSI computation, and where it is intended for a Municipal School, the building or part thereof intended for the school use shall be handed over free of cost and charge to the Corporation. Thereafter, the land may be allowed to be redeveloped with the full permissible FSI of the plot according to this Regulation.
 - b) In the case of lands affected by the designation or reservation of a Higher Education in the D.P., a building for accommodating such number of students as may be decided by the Municipal Commissioner, not in any case for less than 800 students, shall be constructed by the owner or developer at his cost according to the size, design, specification and conditions prescribed by the Municipal Commissioner, the built-up area occupied by the constructed building shall be excluded for the purpose of FSI computation. The constructed building shall be handed over to the Corporation free of cost and charge and the Authority may hand over the same or part thereof intended for the School use to a recognized and registered educational institution for operation and maintenance on terms decided by him. Thereafter the land may be allowed to be redeveloped with full permissible FSI of the plot according to this Regulation.
 - c) In case area under reservation of Municipal School / Primary and secondary school or a Higher Education is spread on adjoining plot and the plot under development, then in such cases Commissioner with special permission may insist upon construction of Municipal School or a Higher Education in proportion to the area under reservation affecting the plot under development. Requirements of Play Ground as per these regulations may not be insisted for (i) above.
 - iii) For other buildable reservations excluding Municipal School or a Higher Education on lands under slum built-up area equal to 25 percent of the area under that reservation in that plot, shall be demanded free of cost by the Slum Rehabilitation Authority for the Municipal Corporation or for any other appropriate Authority.
 - iv) In case of the plot reserved for the Parking Lot 125% built up area as per zonal basic permissible FSI of such reserved area shall be handed over to the Municipal Corporation.
The developer / owner shall be entitled for the Built up Area (BUA) in lieu of cost of construction against handing over of built up amenity.
-

- v) Existing slum structures on lands reserved for Rehabilitation & Resettlement shall be treated as sites for development of slum structures and shall be allowed for redevelopment according to this Regulation.

vi) **Slum Rehabilitation Permissible on Town Planning Scheme Plots :-**

Slum Rehabilitation scheme can be taken up on the final plots of the Town Planning Scheme, as per these regulations and further as per conditions given below.

- a) Such slum should be notified slum.
- b) If the owner of a final plot in the Town Planning Scheme has already accepted or accepts the possession of the plot along with encroachments and has developed / develops the remaining vacant plot with full permissible FSI of the entire Final Plot retaining encroachments on his plot, then the slum rehabilitation scheme on encroached plot shall be developed as follows :-
 - i) The Slum Rehabilitation Scheme shall be entitled for FSI as per these regulations.
 - ii) The owner of Final plot can develop the slum rehabilitation scheme subject to condition that in-situ FSI of the scheme shall be reduced to the extent of the FSI of such encroached plot already utilized in the remaining vacant plot.
- iii) The owner shall demarcate the area in his plot which is occupied by the slum encroachments and transfer such land in the name of the Authority. The Authority on its own or through the Co-Op Housing of Hutment dwellers may initiate Slum Rehabilitation Scheme on the encroached area of Final Plot. Further, the Authority shall record the number of tenements, names of occupiers, area occupied of the time of granting permission.

14.7.13 Anganwadi, Health Centre / Outpost, Community Hall /Gymnasium / Fitness Centre, Skill Development Centre, Women Entrepreneurship Centre, Yuva Kendra / Library Society Office, and Religious Structures :

- i) There shall be Balwadi, Welfare hall and any of two amenities mentioned above. There shall be health Centre / outpost, Anganwadi, skill development centre, women entrepreneurship centre, yuva kendra / library of size 27.88 sq.m. for every multiple or part of 250 hutment dwellers. In case of misuse, it shall be taken over by the SRA which will be competent to allot the same to some other organization /institution for public use. Balwadi shall also be provided for on a similar scale. An office for the Co-operative housing society shall be also constructed for every 100 rehab tenements in accordance with these Regulations. However, if the number of rehab tenements exceeds 100 then for every 100 rehab tenements such additional society office shall be constructed. There shall be a community hall for rehab bldg. of the Project as a part of the rehabilitation component. The area of such hall shall be 2% of rehab built up area of all the buildings or 200 Sq.m. whichever is less.

Religious structures existing prior to redevelopment, if allowed in accordance with the guidelines issued by Government from time to time as part of redevelopment shall not exceed the area that existed prior to redevelopment. Other social infrastructure like School, Dispensary and Gymnasium run by Public Authority or Charitable Trust that existed prior to the redevelopment shall be allowed without increase in existing area.

However, it is provided that in the slum rehabilitation project of less than 250 hutments, there shall be Balwadi, Welfare hall and any of two amenities mentioned above, as decided by co-operative housing society of slum dwellers, of size of 27.88 Sq.m. and office for the Co-operative housing society in accordance with these Regulations. CEO, SRA may permit accumulation of the amenities mentioned above but ensure that it shall serve equitably to the rehab area.

- ii) All the areas underlying Anganwadi, health centre / outpost, community hall / gymnasium / fitness centre, skill development centre, women entrepreneurship centre, yuva kendra / library community hall/s, society office, balwadi/s, religious structure/s, social infrastructure like School, Dispensary, Gymnasium run by Public Authority or Charitable Trust, the commercial areas given by way of incentives to the co-operative society and the non-government organisation shall be free of cost and shall form part of rehabilitation component and it is on this basis the free-sale component will be computed.
- iii) Anganwadi, health centre / outpost, community hall / gymnasium / fitness centre, skill development centre, women entrepreneurship centre, yuva kendra / library society office, Balwadi/s and religious structures, social infrastructure like School, Dispensary and Gymnasium run by Public Authority or Charitable Trust in the rehab component shall not be counted towards the FSI even while computing permissible FSI on site.

14.7.14 Payments to be made to SRA and Instalments :

- i) An amount of Rs.40,000/- or such an amount as may be decided by the Planning Authority from time to time per tenement including the welfare hall and balwadi in the rehab component as well as in the case of permanent transit camp tenements will have to be deposited by the owner / developer / society with the Slum Rehabilitation Authority, in accordance with the time-schedule for such payment as may be laid down by the CEO, SRA. However, by the time of completion of construction for occupation of tenements by the hutment dwellers, the total amount at the rate of Rs.40,000/- per tenement completed should have been deposited in full. The building permission for the last 25 percent of the free-sale component would be given only after all the required amount is deposited in full with SRA.
- ii) An amount at the rate of 2% of ready reckoner rate as prevailing on the date of issue of LOI per Sq.m. such an amount as may be decided by GOM from time to time shall be paid by the Owner / Developer / Society / NGO for the BUA over and above the Zonal (basic) FSI, for the rehabilitation and free-sale components. This amount shall be paid to the SRA in accordance with the time-schedule for such payment as may be laid down by the CEO, SRA provided the instalments shall not exceed beyond the completion of construction. This amount shall be used for Schemes to be prepared for the improvement of infrastructure in slum or slum rehabilitation areas. These infrastructural charges shall be in addition to development charges levied as per section 124 of M.R. & T.P. Act, 1966.

Provided that out of amount so recovered as Infrastructural charges, 90% amount will go to Municipal Corporation and 10% amount will remain with SRA.

14.7.15 Conversion of Old Project into New Project :

- i) Projects, where LOI has been granted, shall be treated as per the provisions existing on the date of LOI. In case such a project comes up for revised LOI or change of developer or any other change, including recording and resubmission without change in slum boundary, these regulations shall apply. Provided further that for amalgamation of schemes being sought and for schemes that have been sanctioned under different regulations (earlier as well as current one), FSI calculations shall apply as per these regulations.
- ii) **Exceptions**
 - a) Schemes approved prior to coming into force of these Regulations :-
The slum rehab schemes where LOI has been issued by SRA prior to the date of coming into force of these Regulations and which is valid may continue to be governed by the regulation applicable prior to these Regulations.

- b) Wherever the S.R. Scheme sanctioned by CEO (SRA) is under progress on reservations shall be valid & continue.
- iii) In case of conversion of old SRD Scheme to new S.R.Scheme on land owned by Govt. Semi Govt. undertaking and local bodies, the developer shall pay the premium at the rate of Twenty Five percent of land value as per the ASR in proportionate to difference of FSI sanctioned in old SRD Scheme and new S.R.Scheme. Payment of premium shall not be applicable to those schemes wherein lease already executed by concerned authorities.

14.7.16 Provision relating to Permanent Transit Camp Tenements for Slum Rehabilitation Scheme implemented on open plot / non-slum plot.

Total FSI on plot area may be allowed to be exceeded upto 4 for construction of Transit Camp tenements for SRA.

- i) The FSI and distribution of additional FSI for the construction of Transit Camp Tenements shall be as shown below –

Minimum Road Width	Total Permissible FSI	Zonal FSI	Additional FSI	RSI for transit tenements for SRA of total additional FSI	% FSI for sale component of total add FSI
Below 9.00 m.	upto 3.00	1.00	upto 2.00	50%	50%
9.00 m. and above	upto 4.00	1.00	upto 3.00	50%	50%

- ii) Such schemes shall not be permissible on lands reserved in the Development Plan and Zone in which Residential development is not permissible.
- iii) Transit tenements for SRA out of additional FSI could be used for construction of Transit Camp of tenements having carpet area of 27.88 Sq.m. Ground floor shall be used for commercial tenement having carpet area of 20.90 Sq.m. (225sq.ft.) for project affected commercial tenements and same shall be handed over free of cost to SRA. Alternatively, residential tenements can be used for Government Staff Quarters etc.
- iv) Provision of Anganwadi, Health Centre / Outpost, Community Hall / Gymnasium / Fitness Centre, Skill Development Centre, Women Entrepreneurship Centre, Yuva Kendra / Library, Society Office, Balwadi, shall be as per Regulation No.6.14.4 of this DCR to these transit camps 25% of basic FSI shall be exclusively used for the purpose of shops along layout road for use of residential occupants of layout.
- v) Additional FSI over and above basic FSI may be released in co-relation to the BUA of the tenements that are required to be handed over free of cost to SRA / Authority as the case may be. Alternatively, TDR in lieu of unconsumed sale component of additional FSI, as per this Regulation, may be permitted for Permanent Transit Camp (PTC) for which SRA will be the Planning Authority.
- vi) Only after the Transit Camps are handed over free of cost to the SRA, the Occupation Certificate, water connection, power connection etc. for the other portion shall be given by the Appropriate Authority.
- vii) Clubbing - The entire rehabilitation components including base FSI may be categorised as rental housing and permanent transit component as applicable and the corresponding sale components from the additional FSI amongst two or more schemes under this regulation can be permitted to be interchanged. A developer / developers making an application under this regulation may club more than one plot belonging to single or multiple owners and offer permanent transit component on a single plot while shifting sale component as well as base FSI of the plot to other plot agree and make a joint application. However, clubbing

shall be allowed only if it leads to an independent plot / building / wing as the case may be with permanent transit component being handed over to Authority.

The developer shall have to pay premium equal to 40% of unearned income calculated with the rates of construction as well as sale given in ASR of the year of payment. The unearned income shall be computed by calculating valuation of sale component awarded in lieu of component for Authority after deducting cost of construction of sale as well as Authority's component and the cost incurred to various authorities towards statutory payments relating to Authority as well as sale component. In case there is shifting of base FSI within plots in clubbing scheme, difference of land valued in ASR shall be taken into account while finalising unearned income, and this difference shall be calculated as 100% towards premium.

Such clubbing can be allowed for the schemes falling within the distance of 5 Km.

The premium shall be paid to the Authority in two stages 50% at the time IOA and 50% at the time of issuing C.C. for the incentive FSI, or the developer has to surrender equivalent sale FSI in form of constructed BUA to the extent of premium in the scheme to be valued at ASR rate of sale in the year of such surrender of built-up area.

Note - Out of the total premium amount so collected under rehabilitation scheme under this these Regulations, 2/3rd shall be kept in a separate account to be utilized as shelter fund for the State of Maharashtra and 1/3rd shall be deposited at the District Office of the Town Planning Department.

14.8 Urban Renewal Scheme

Urban Renewal Scheme (URS) shall be applicable for all Corporations as given below.

14.8.1 Urban Renewal Scheme (URS) for Municipal Corporation Area –

- i) “Urban Renewal Scheme” (URS) means any scheme for redevelopment of a cluster or clusters of buildings and structures in Municipal Corporation Area, over a minimum area of 10,000 sq.m., in non-congested area and 4000 sq.m. in congested area, bounded by existing distinguishing physical boundaries such as roads, Nallahs, railway lines etc. accessible by an existing or proposed D.P. road which is at least 18.0 m. wide and identified for urban renewal-

⁽²⁾ However, in specific cases, in which URS is not bounded by roads, Nallahs and railway lines etc. and/or, areas of any vacant or encroached land situated in the periphery of 400 mt. belonging to Municipal Corporation / any Public Authority / Planning Authority / Special Planning Authority, which is not contiguous, is proposed to be included in the URS, then the boundaries of such cluster having non-contiguous area can be decided / finalised the by Municipal Commissioner, in consultation with High Power Committee (H.P.C.).⁽²⁾

However, in specific cases, in which URS is not bounded by roads, Nallahs and railway lines, then the boundary of the cluster can be decided / finalised by Municipal Commissioner, in consultation with High Power Committee (H.P.C.)

In case of demonstrable hardship such as natural sub division by roads, Nallahs, river, railway lines, the area of the cluster can be allowed up to an area of 8000 Sq.m. in non-congested area which shall be allowed by Municipal Commissioner in consultation with H.P.C.

However no forest land shall be included in such URS.

⁽²⁾ Provided that, encroached forest land may be included in such URS for clearance of encroachment on such forest land with NOC of Forest Department. However after clearance of encroachment, such forest land shall be used as mentioned in regulation 14.8.7(i)(g) with NOC of Forest Department.⁽²⁾

⁽²⁾ Inserted vide Notification u/s 37 (1AA)(c) & 20(4) No.CR 236/18 (Part-4), dt.28th December, 2022

ii) Such URs may be :-

- a) Under the Development Plan (D.P.), where the D.P. contains such well-defined Clusters; or
- b) Under the Urban Renewal Plan (URP) for the concerned area, prepared and notified by the Commissioner, who may revise the same, as and when required; or
- c) By the Promoter of the Urban Renewal Scheme over a cluster or clusters of buildings, where such clusters are not shown on the D.P. and the URP is yet to be prepared. If such plans are submitted and approved, these shall mean to be URP within the meaning of this Regulation.

iii) Building Age Criteria for URC shall be as under :-

The Urban Renewal Cluster (URC) may consist of a mix of structures of different characteristics such as -

- a) Unauthorized buildings which are at least 30 years of age;
- b) Authorized dilapidated buildings, as determined by ⁽¹⁾ the Designated Officer appointed by Municipal Commissioner or as per the Regulation of Redevelopment of Dilapidated Buildings;
- c) Authorized buildings which are at least 30 years of age;
- d) Buildings belonging to the Central Government, the State Government, Semi-Government Organizations and Municipal Corporations, as well as Institutional Buildings, Office Buildings, tenanted Municipal Buildings, Staff Quarter Buildings of Municipal Corporation, that are at least 30 years of age with prior consent of the respective Authority;
- e) Any land belonging to the State Government, any Semi-Government Organization, Municipal Corporation and MHADA (either vacant or built upon) which falls within the area of the proposed Urban Renewal Scheme including that which has been given on lease or granted on the tenure of Occupant Class II, provided that if built upon, these building shall be at least 30 years of age;
- f) Any other buildings which may be less than 30 years of age but which by reasons of disrepair or because of structural / sanitary defects, are unfit for human habitation or by reasons of their bad or sub-optimal configuration or the narrowness of streets are dangerous or injurious to the health or safety of the inhabitants of the area, as certified by the ⁽¹⁾ by the Designated Officer appointed by Municipal Commissioner or as per the Regulation of Redevelopment of Dilapidated Buildings;
- g) Slum areas declared as slums under section 4 of the Maharashtra Slum Areas (Improvement, Clearance and Redevelopment) Act, 1971 or slums on Public lands prior to 1st January, 1995 or such other reference date notified by the Government. However such slum area shall be maximum 25% of cluster area;

In case of Ulhasnagar Municipal Corporation, minimum area shall be 4000 Sq.m. for non-congested and congested area.

⁽²⁾ Notwithstanding Anything Contained in these regulation, it shall not be permissible to develop declared slum under Regulation No.14.7 which is included in URP / URS prepared & notified as per Regulation No.14.8.1(ii). ⁽²⁾

- h) The lands belonging to MIDC can be included in the URS after obtaining necessary clearance from Industries Department.

⁽¹⁾ Substituted vide Corrigendum / Addendum No. CR 121/21, dt. 02nd December, 2021

⁽²⁾ Inserted vide Notification u/s 37 (1AA)(c) & 20(4) No.CR 236/18 (Part-4), dt.28th December, 2022

Explanation - 1. - Age of a building shall be as on the 1st of January of the year in which URC involving such building, complete in all respect is submitted to the Commissioner or prepared and notified by the Commissioner and shall be calculated from the date of occupation certificate or, where such occupation certificate is not available, from the date of assessment as per the property tax record in respect of such building, available with the Municipal Corporation.

Explanation - 2. - Whenever any authorized building, more than 30 years of age, is included in a URC, the same shall not be done without evaluation of its state of dis-repair by Municipal Corporation and if such building is found in a state of disrepair, only after giving the owner / occupier(s) thereof, a notice of three months to cause any repairs needed. At the end of three months, if such building is found to be habitable and safe, such building shall be treated at par with authorized buildings which are less than 30 years of age. If at the end of three month, such building is found and certified by ⁽¹⁾ the Designated Officer appointed by Municipal Commissioner or as per the Regulation of Redevelopment of Dilapidated Buildings as dilapidated and unsafe for habitation, such building shall be included in the URC without the requirement of consents.

Explanation - 3. - If some authorized buildings which are less than 30 years of age or buildings which are developed or in the process of development, under the different provisions of the DCR, are required to be included in the URC for the purpose of wholesome planning, they may be so included, provided the area under such buildings does not exceed 40% of the total area of URC. If any such building is included in the URC without the requisite consent of 70% of all title holders of such building, the Commissioner shall retain such building while designing/ sanctioning URS and area of such building shall be excluded from calculation of FSI under this Regulation.

However, the area under slum mentioned in Regulation No.14.8.1(iii)(G) and area under authorised structure mentioned above shall not be more than 50% in aggregate.

Explanation - 4. - When any private land owner / developer submits such scheme will be given priority while implementation.

14.8.2 Eligibility for Urban Renewal Cluster (URC) –

i) For Buildings outside Slums -Every occupant of every building falling under a URC on the date of sanction of this Regulation (hereinafter referred to as the cut-off date), shall be eligible for rehabilitation and relocation under the Scheme, in accordance with the provisions of Regulation No.14.8.4 and 14.8.5, subject to the ineligibility criteria mentioned herein below.

a) No new Tenancy, occupancy or any other right created after the cut-off date shall be taken into account in any illegal or unauthorized construction. No unauthorized construction made after the cut-off date in any existing building or in the form of new building shall be considered while doing computation of existing FSI or liability of rehabilitation on the URC.

b) Any occupant, who has been allotted any subsidized housing in the ⁽¹⁾ respective Metropolitan Region, or in the Corporation area as the case may be, by any public or semi-public authority in the past shall not be eligible for subsidized rehabilitation under a URC as mentioned in Regulation No.14.8.5. For this, a self-declaration in the form of Registered Affidavit shall be considered sufficient which, if ever found to be false, shall render the concerned allottee liable for eviction and prosecution as per law.

⁽¹⁾ Substituted vide Corrigendum / Addendum No. CR 121/21, dt. 02nd December, 2021

c) Subject to the forgoing provisions, only the actual ⁽¹⁾ owners of residential unit of authorized building and the occupants of unauthorized buildings fulfilling the eligibility criteria mentioned under this Regulation shall be held eligible for rehabilitation and any person, other than the actual occupant, claiming rights as owner / promoter / developer / lessee over any land / building / structure included in the URC, shall have no right whatsoever to rehabilitation under the URC in the reconstructed tenements against such land / building / structure. In case of an unoccupied building or a building occupied illegally, no one shall have right whatsoever to rehabilitation under the URC, against such building / structure.

ii) **Slum Areas** - Whenever a Slum area or part thereof is included in a URC, eligibility of the hutment dwellers of such slum area rehabilitation under the URC, shall be governed by corresponding provisions of Slum Rehabilitation Scheme. Eligibility of any hutment dweller of a Slum area included in the URC shall be certified by the Competent Authorities as notified under the Maharashtra Slum Areas (Improvement, Clearance and Redevelopment Act, 1971). For slum dwellers not covered under Slum Rehabilitation Scheme, the eligibility for rehab area shall be the same as under Slum Rehabilitation Scheme.

14.8.3 Determination of eligibility and requirement of Rehabilitation and Relocation areas under URS –

- i) Municipal Commissioner shall initiate the process for determination of eligibility and requirement of alternative area of Rehabilitation and relocation of each occupant under any URS, along with determination of rights over lands falling under the Urban Renewal Cluster(s) and the consideration thereof.
- ii) Municipal Commissioner shall designate officer(s), not below the rank of Assistant Municipal Commissioner, who shall be called Authorized Officer(s) and shall cause to be done the survey required for the purpose mentioned in Clause (i) above and declare and publish the list of buildings / structures and their owners / lessees, occupants / tenants etc., for inviting suggestions and objections along with relevant records, within one month of such publication for determination of entitled area and the consideration to be offered to the owners / lessees and other right-holders as well as eligibility and admissible area for the occupants, in accordance with the provisions in this Regulation. Authorized Officer(s) shall, after due enquiry and hearing, finalize the said list(s) and cause the same to be published. Appeal against any decision leading to finalization of the said list shall lie with an officer not below the rank of Deputy Municipal Commissioner who is authorized in this regard by the Municipal Commissioner, in writing.

14.8.4 Entitlement of Rehabilitation –

- i) All the eligible occupants of the building(s)/slums undergoing redevelopment under a URC shall be rehabilitated in the redeveloped building(s) :
Provided that the Municipal Commissioner may also rehabilitate, in the rehabilitation buildings of the URC, one or more persons declared eligible for allotment of tenement under any other Scheme or Project of the Government or Corporation, Project Affected Persons, outside the area of URC.
- ii) Each eligible residential occupant, other than occupants of Slums included in URC, shall be rehabilitated on a carpet area equivalent to the area occupied by such occupant in the old building. However in case of residential occupants, such carpet area shall not be less than 30 sq.m. and in case of commercial, such carpet area shall be as per actual area in possession.

And further the residential occupants belonging to authorised buildings shall be entitled additional 25% of the eligible area.

- iii) Any occupant of a slum structure included in URC, either residential or commercial, whether eligible under Slum Rehabilitation Scheme or not but eligible under this Regulation, shall be entitled for a carpet area as prescribed in Slum Rehabilitation Scheme.
- iv) All the eligible occupants shall be rehabilitated in the redeveloped buildings of URC as far as possible. However at the request of or with the consent of an occupant, he may be allotted alternative rehabilitation in a location outside URC, up to the extent of his eligibility, at the discretion of the Municipal Commissioner. Request or consent under this provision shall however be irrevocable.

Explanation - Though Commissioner shall endeavour to make provision for rehabilitation areas as per the entitlement of each and every eligible occupant, whenever such area, whether for residential user or non-residential user, within a range of 10% of the individual entitlement of any occupant, is not available in the URC, he shall be entitled for rehabilitation in an available tenement of immediately next higher area, subject to the allottee paying for the differential area.

If the beneficiary refuses to pay the specified amount towards such differential area, he will be entitled for an available rehabilitation tenement of immediately lower area, without any consideration towards such reduction in area.

14.8.5 Terms of Allotment of Rehabilitation Tenements –

- i) Allotment of rehabilitation tenements for owners belonging to authorised buildings shall be free of cost and without any consideration for the original area and additional 25% area over and above the eligible area. Shall be allowed for the occupants of the authorised buildings, free of Cost.

If any non-residential unit holder demands residential unit against his non-residential previous holding, such request may be considered by Commissioner in consultation with HPC. However to consider such request shall not be obligatory on the part of the Commissioner.

Allotment of rehabilitation tenements to occupants belonging to unauthorized / illegal buildings and slums shall be at a consideration in accordance with the following Table No.14-X :-

Table No.14-X		
Minimum Carpet Area of Rehab Tenement	Type of Rehab Tenement	Consideration (i.e. Amount payable by the Allottee to Municipal Corporation)
(1)	(2)	(3)
For Slum Area		
27.88 sq. m.	Residential	Zero Payment if eligible under Slum Rehabilitation Scheme Or else Construction Cost as per ASR rates or as per any policy decided by the Government of Maharashtra under the Slum Act, 1971.
For Non-Slum Area		
30 Sq.m.	Residential	Free of Cost
> 30 Sq.m. but less than or equal to 50 Sq.m.	Residential	Upto 30 Sq.m. as above. Beyond 30 Sq.m. at Construction Cost as per ASR rates.

> 50 Sq.m.	Residential	Upto 50 Sq.m. as above. Beyond 50 Sq.m. at Full Market Rate as per ASR.
Non-Residential Commercial Area /		
16.75 Sq.m.	Non-Residential / commercial Area	Free if eligible under Slum Rehabilitation Scheme. Or else, Construction Cost as per ASR rates.
> 16.75 Sq.m. but less than or equal to 40 Sq.m.	—do—	Upto 16.75 Sq.m. as above and beyond 16.75 Sq.m. at 100% of Construction Cost as per ASR rates
> 40 Sq.m.	—d—	Upto 40 Sq.m. as above and Beyond 40 Sq.m. at 100% of market rate as per ASR.

Note for Thane Corporation Area - The erstwhile structures within the gaothans which subsequently merged with the Municipal Corporation in 1982 will be considered as protected and legal structures.

- ii) If an eligible occupant finds it financially unaffordable to pay the amounts as mentioned herein, Commissioner may allot him a tenement of immediately lower area. If any eligible beneficiary finds it financially unaffordable to pay even the amount required for the minimum area, or fails to make payment as per the Schedule of payment given by the Commissioner, the Commissioner may allot him a tenement of minimum area on hire-cum-purchase basis, till such allottee pays the requisite amount in one or more instalments or through EMI payments. Rent in such cases would be decided by Municipal Commissioner and EMI shall be calculated for such number of years at such rate of interest as may be fixed by Municipal Commissioner.
- iii) Any existing amenity in the URC on the date of coming into force of this regulation which is under control of a private person / organization and Charitable Trust / religious organization shall be entitled for an area equal to the existing area of such amenity, subject to the following :-
 - a) for an amenity being used for non-residential activities and under the control of private person(s) / organization(s), allotment of equivalent area under URS shall be at 50% of ASR Rate for commercial area up to 40 Sq. Meters and at 100% of ASR Rate for commercial area above 40 Sq.m.;
 - b) for an amenity being used for non-residential and in control of any Charitable Trust or religious organization for purpose of raising fund for public welfare activities, such allotment shall be free for area up to 40 Sq. meters and at 50% of ASR Rate for construction above 40 Sq. Meters.
 - c) for an amenity having users like (e.g. Educational / Health-care facility etc.) and under control of private person(s)/ organization(s) such allotment shall be at 25 % of ASR Rate for constructed area up to 40 Sq. Meters and at 50% of ASR Rate for constructed area above 40 Sq. Meters.
- iv) **Process of Allotment to Beneficiaries and Conditions thereof :-**
 - a) Process of allotment of tenements to beneficiaries, lease conditions including those pertaining to transfer, formation of co-operative housing societies and policy of maintenance of common amenities of buildings and layout as well as policy regarding any other relevant matter shall be as determined by Corporation from time to time.

- b) Allotment of land shall be on lease for the period of 30 years, which shall be renewable for further period of 30 years at a time. However, Allotment of rehabilitation tenements for owners and beneficiaries shall be on ownership basis. This provision of lease shall not apply for the authorised building constructed on private land.
- c) Rehabilitation tenements allotted to beneficiaries shall not be transferable for first fifteen years, except with prior permission of Commissioner, who may grant such permission in case of hardship, on payment of premium as below :
- i) For the transfer of Rehabilitation tenements allotted to Occupants belonging to the authorised buildings, no premium shall be charged;
 - ii) For carpet area less than 30.00 Sq.m. premium shall be 10% of the differential amount calculated as per clause (iv) below;
 - iii) For the transfer of Residential and non-residential Rehabilitation tenements other than those covered under (a) and (b) above, premium shall be 25% of differential amount calculated as per explanation below;
 - iv) Differential amount for the purpose of clause (ii) and (iii) shall be equal to difference in the Annual Statement of Rates (ASR) valuation in the year of transfer and the original consideration paid for the allotment of a Tenement brought forward to the year of transfer through capital inflation index.

Provided that, In case of unauthorized transfer of any Rehabilitation tenement, the Commissioner may regularize the transfer by charging double the premium as mentioned above, with 12% interest from the date of transfer.

Provided further that, If the transferee refuses to pay the premium demanded within 3 months of demand, the Commissioner shall initiate process of vacating the premises, though in cases of willingness but hardship, Commissioner may grant instalments with 12% interest rate.

- ⁽²⁾ v) After consideration for land falling under URC to the person(s) having legal rights in land as per regulation No.14.8.8(iv)(c) is offered and provision for rehabilitation all the eligible beneficiaries of the building(s) under URC is proposed in redeveloped building(s) in URC area as per Regulation No.14.8.4.

In respect of those eligible beneficiaries of ⁽³⁾ (--) unauthorized / illegal buildings and slums entitled for rehabilitation tenement in URC, who do not join the scheme willingly, the following steps shall be taken :-

- i) Provision for all of them shall be made in the rehabilitation component of the scheme.
- ii) The details of the tenement that would be given to them by way of allotment on the same basis as for those who have joined the scheme will be communicated to them in writing by the Implementation Agency.
- iii) The transit tenement that would be allotted to them would also be indicated along with those who have joined the scheme.
- iv) ⁽²⁾ If they do not join the scheme within 15 days after the approval for Implementation Agency has been given to the scheme, then action under the relevant provision of the M.R. & T.P. Act, as amended from time to time, shall be taken and their structures will be removed and it shall be ensured that no obstruction is caused to the scheme of the majority of persons, who have joined the scheme willingly.

⁽²⁾ Inserted vide Notification u/s. 37 (1AA)(c) & 20(4) No.CR 236/18 (Part-4), Dt.28th December, 2022

⁽³⁾ Word "Authorised" is deleted vide Corrigendum No. CR 236/18 (Part-4) dt. 11th January, 2023.

- v) After this action under the foregoing clause is initiated, they will not be eligible for transit tenement along with the others and they will not be eligible for the reconstructed tenement, but they will still be entitled only to what is available after others have chosen, which may be on the same or some other site.
- vi) If they do not join till the building permission to the scheme is given, they will completely lose the right to any built-up tenement and their tenement shall be taken over by the Commissioner and to be disposed off as per MMC Act or as per guidelines issued by the Government from time to time and used for the purpose of accommodating Project Affected Persons and other beneficiaries etc.who cannot be accommodated in-situ. ⁽²⁾

14.8.6 The permissible FSI for URC –

- i) ⁽¹⁾ The FSI permissible in the URS shall be the FSI required for rehabilitation of existing occupiers / tenants + incentive FSI under this Regulation, or 4.00 whichever is higher. Provided that Incentive FSI ⁽⁴⁾ component on rehabilitation area ⁽⁴⁾ shall be governed by the ratio of Land Rate (LR) (in Rs. Per Sq.m.) of the URC under redevelopment to the Rate of Construction (RC) (in Rs. Per Sq.m.), as per the Annual Statement of Rates (ASR) applicable to the area and size of the URC as given in table below.

Basic Ratio (LR / RC *)	Incentive as per scheme		
	More than 0.40 ha upto 1.0 ha.	More than 1.0 ha. upto 5.0 ha.	For more 5.0
Above 2.00	1.75	2.00	2.25
Above 1.50 and upto 2.00	2.00	2.25	2.50
Above 1.00 and upto 1.50	2.25	2.50	2.75
Upto 1.00	2.50	2.75	3.00

⁽¹⁾ Explanation :-

- (a) In case of different land rates area applicable to different parts of the URC, weighted average of all the applicable rates shall be taken for calculating the Average land rate and basic ratio.
- (b) The land rate and the rate of construction for calculation of the basic ratio shall be taken for the year in which the URS is approved by the competent authority and shall remain unchanged during the entire project cycle of the URS.
- FSI shall be calculated over the gross area of the URC, deducting area falling in CRZ and Forest areas if any. However, if the area in CRZ-II is upto 25% of the URC then the FSI shall be allowed to be used in non CRZ area. However no FSI shall be allowed for the area from CRZ-1. Out of the construction area allowed as per Global FSI, FSI that cannot be actually utilized in URC, due to constraints imposed by different provisions of UDCPR, or otherwise, shall be converted into Urban Renewal TDR (URT) which shall be utilisable on a receiving plot. ⁽¹⁾
- ii) The URT may be released by the Commissioner in stages to be decided by him but URT released at any point of time shall never exceed construction done in URC with respect to buildings where Occupation Certificates have been granted and 50% of construction done in URC with respect to buildings where Occupation Certificates are not granted.
- iii) The FSI for an Urban Renewal Scheme in CRZ area shall be governed by the MoEF Notifications issued from time to time, and the same shall be taken into account while computing permissible FSI as per Clause (i) above.

⁽¹⁾ Inserted vide Notification u/s 37 (1AA)(c) & 20(4) No.CR 236/18 (Part-3), dt.3rd February, 2022

⁽²⁾ Inserted vide Notification u/s. 37 (1AA)(c) & 20(4) No.CR 236/18 (Part-4), Dt.28th December, 2022

⁽⁴⁾ Inserted vide Addendum u/s.37(1AA)(c) & 20(4) No.CR.236/18 (Part-3), dt.27th October, 2023

Plot area, considered after deducting the area of URC falling in CRZ / Forest area and area under unbuildable reservations, etc. shall be primarily used for rehabilitation of existing occupants and development of buildable reservations and public amenities with required FSI. After the said development, if there are any eligible occupants left who could not be rehabilitated due to inability to construct the requisite area for rehabilitation and relocation, owing to constraints imposed by UDCPR, shall be rehabilitated in any nearby URS or in the PAP tenements available with the Corporation; as per the policy guidelines decided by the Corporation.

- iv) If after construction of rehabilitation tenements and other areas of entitlement as per the provisions of this Regulation, there is still some building potential left as per the ceiling of 4.0 FSI, construction can be done for free sale, either in independent buildings, or on sub-plots or in composite buildings or in undivided plots along with rehabilitation component.
- v) When the FSI available in URC in case less than 4.0 then 50 % of the difference in FSI shall be constructed in the form of EWS / LIG tenements and shall be handed over to the Commissioner. Commissioner may use these tenements preferably for transit accommodation, PAP tenements or staff quarters. However if tenements are not needed for above purpose then Municipal Commissioner shall after realisation of proceeds from disposal of these tenements, deposit such proceeds in Shelter Fund setup under this Regulation.

14.8.7 ^(#) Development of Reservations contemplated in Development Plan falling in the area of URC –

- i) All the reservations in the Development plan falling in the area of URC shall be provided and may be rearranged / relocated, under URS as follows :-
 - a) Redevelopment / reconstruction in any zone shall be allowed to be undertaken without going through the process of change of zone. However, for the industrial user, the existing segregating distance shall be maintained from the existing industrial unit.
 - b) Any land under non-buildable reservations, admeasuring only upto 500 sq.mt. may be cleared by shifting the existing tenants from that site.
 - c) If the area under a non-buildable reservation is more than 500 sq.mt. minimum 50% of the area under reservation shall be developed for the same purpose and handed over to Municipal Corporation, subject to minimum of 500 sq.mt. and remaining land shall be allowed for development.
 - d) For the reservation of parking lot on a land included in URC, built up area equivalent to zonal permissible FSI for the area under reservation in that plot shall be made available free of cost to the Corporation or to any other Appropriate Authority. Such built up area to be handed over shall be free of FSI.
 - e) For other buildable reservations on land, built up area equal to 60% of the zonal permissible FSI under such reservations or existing built up area of the amenity whichever is more, on that plot shall be made available free of FSI and free of cost to the Municipal Corporation or to the Appropriate Authority. The reservations of compatible nature can be preferably constructed in one or more separate blocks, depending on the area and nature of such reservations and Municipal Commissioner may permit composite development of reservations in case of such reservations.

However, if the HPC / Planning Authority requires built-up area under any designation / reservation in excess of the zonal permissible FSI, then such excess area shall be considered as rehabilitation FSI and incentive FSI as admissible under this Regulation shall be permissible.

^(#) Clarification issued vide Order No. CR 236/18 (Part 2), dt, 23rd December, 2021.

Provided that in case of development of reservations of PH / HDH & HD under the Urban Renewal Scheme, built-up area equal to 30% of the zonal permissible FSI shall be handed over to the Municipal Corporation free of FSI and free of cost, in addition to the rehabilitation of the existing tenements or users if any.

- f) Where a proposed Development Plan Road or Regular line of street passes through the Urban Renewal Scheme area, the entire FSI admissible under this Regulation for the area of the road may be given in the same Scheme.
- g) Builtup area required for development of public amenities / reservations shall not be counted while computing permissible FSI under URS. If URS includes areas falling under CRZ and Forest, subject to NOCs of the concerned Authority, these areas may be considered against the compulsory open space to be kept as per DCR.
- h) The multiuser mix user in High rise or composite building for public purpose amenities shall be permitted.
- ii) If the area under non-buildable reservation except Play Ground in the URS area is more than 2000 sq.m. minimum 50% of the area of such reservation or 2000 Sq.m. whichever is more shall be developed for the said purpose.

14.8.8 Preparation and Approval of URS –

- i) Subject to the provisions of Development Plan and the URP prepared and notified by the Commissioner, the Commissioner may prepare detailed plan, for one or more URCs contained therein, showing proposals for development/ reconstruction of cluster of buildings and/or structures, which in the opinion of the Commissioner should be developed or redeveloped under a URS. Such plan shall include -
 - (a) Plan for overall development/Redevelopment of specific areas for urban renewal.
 - (b) Strategies and plan for dealing satisfactorily with areas of bad layout, obsolete development and slum areas and relocation and rehabilitation of population.
 - (c) Open spaces, gardens, playgrounds and recreation areas.
 - (d) Area or areas required for making the implementation of such plan for Urban Renewal viable.
- ii) After preparation of detailed plans of URC(s), the Commissioner shall place the same for approval of a High Power Committee (HPC) constituted under this Regulation as follows-

Municipal Commissioner	-	Chairman
Collector	-	Member
Joint Director Town Planning of the Division	-	Member
DCP (Traffic)	-	Member
Chief Officer, MHADA	-	Member
Joint Director / Deputy Director / Assistant Director Town Planning of the Corporation	-	Member Secretary

After approval of detailed plans of URC(s) as aforesaid, the Commissioner shall proceed to select an Implementation Agency for executing URS in the manner described herein. Proposal to finalise Implementation Agency shall be put to HPC which will forward the same with the recommendations to the State Government for final approval.

iii) Entitlement for consideration under URS-

Anyone having any legal rights over any parcel of land falling under URS shall, after establishment of his rights, be offered consideration for such land as per the following provisions which, if declined by any rights holder(s), shall give liberty to the Commissioner to initiate process of acquisition of such rights under appropriate law. Implementation of URS shall be regarded as a public purpose.

iv) Consideration for Land falling under URS -

- a) Person(s) having legal rights in any land required for URS under this Regulation shall be offered ⁽¹⁾ consideration for the entitled area ⁽¹⁾ of land as provided hereinafter.
- b) Basis for determination of entitled area towards consideration under URS Scheme shall be as follows :-

- i) Person(s) in legal possession and ownership of unencumbered land :- Entitled area collectively against this parcel of land shall be equivalent to the area of the land.
- ii) Person(s) in legal possession and ownership of encumbered land where authorized buildings have consumed FSI less than the permissible FSI :- If liability of rehabilitation of the occupants of the building(s) / Structure(s) on the land in question is being taken on URS, entitled area collectively against such parcel of land shall be 25% of the area of encumbered land plus difference of FSI available on such parcel land and the encumbrance; if the occupants of the building(s) are being independently rehabilitated / compensated by the person(s) / rights holders in legal possession and ownership of the land, and not being rehabilitated in URS, entitled area collectively against such parcel of land towards consideration shall be equal to FSI available on the vacated land area.

Provided where the area of rehab is less than the component of free sale, the component for free sale could be enhance upto 30% by the Municipal Commissioner in consultation with HPC.

- iii) Person(s) in possession and ownership of authorized encumbered land where buildings have consumed FSI more than permissible FSI :- If liability of rehabilitation of the occupants of the building(s) / Structure(s) in question is on the land being taken on URS, entitled area collectively against such parcel of land shall be 25% of land area, if the occupants of the building(s) / Structure(s) are being independently rehabilitated / compensated by the person(s) / rights holder(s); in possession and ownership of the land, and not being rehabilitated in URS, entitled area collectively against such parcel of land towards consideration shall be equal to FSI ⁽¹⁾ (--) available on the vacated land area.
- iv) Person(s) having right over unauthorisedly encumbered land :- Entitled area collectively against this parcel of land shall be calculated at 50% of entitled area calculated as per clause (ii) and (iii) above, except when occupant(s) of building(s) are being rehabilitated / compensated by such Person(s) and are not being rehabilitated in URS, entitled area towards consideration shall be equal to FSI ⁽¹⁾ (--) available on the vacated land area.

c) Consideration for Acquisition of land under URP -

- i) Consideration for any land required to be procured for URP shall be either in terms of payment due for entitled area collectively against that parcel of land, as calculated in Regulation No.14.8.8(iv)(b) above as per ASR, along with 100% solatium, as applicable for the year of possession, along with 12% annual ⁽¹⁾ simple interest from date of possession to date of payment, or in terms of TDR equivalent to the entitled area ⁽¹⁾ as per TDR Regulation No.11.2 or in terms of equivalent area constructed in URS ⁽³⁾ or in terms of developed free sale vacant plot of area equal to 50% of entitled area calculated as per clause (i), (ii), (iii) and (iv) of Regulation No.14.8.8 (iv)(b) above, with base FSI of 1.1 in the same URC fronting on same road width as original plot, subject to availability of land. Concerned person(s) shall have option to choose from amongst these ⁽³⁾ four modes of consideration. The option once chosen shall be registered and shall be irrevocable.

⁽¹⁾ Inserted / Substituted / The word 'TDR' deleted vide Corrigendum / Addendum No. CR 121/21, dt. 02nd December, 2021

⁽³⁾ Inserted vide Notification u/s 37 (1A)(c) & 20(4) No.CR 236/18 (Part-4), dt.28th December, 2022

- ii) Once consideration as above, has been accepted by a person having any interest in the land on which any unauthorised construction exists or existed, the Commissioner may consider such person eligible for Compounding of any offence under relevant provisions of M.R. & T.P. Act with respect to the concerned land / plot.
- iii) Wherever any person having demonstrable legal rights over any area falling under URP rejects the consideration being offered, the Commissioner shall forward the proposal for Land Acquisition under “Right to Fair Compensation and Transparency in Land Acquisition, Rehabilitation and Resettlement Act, 2013” ⁽²⁾ read with section 126(1)(c) of Maharashtra Regional and Town Planning Act, 1966. In such an eventuality, the Commissioner may move the competent authority for advance possession of the land(s) so as to ensure smooth implementation of URS and shall pay requisite advance, rent etc. under the “Right to Fair Compensation and Transparency in Land Acquisition, Rehabilitation and Resettlement Act, 2013”, as determined by the Competent Authority.
If, however there is any dispute only about apportionment of consideration among person(s) having demonstrable legal rights over any land falling under URS, the Commissioner shall ask the disputing parties to approach Competent Civil Court to get their disputes resolved and to settle apportionment of consideration as offered under this Regulation. Till the final decision in this regard is received, in order to ensure that URS does not get delayed and adversely affect other parties to the URS; the Commissioner shall cause an area, equivalent to the entitled area corresponding to such land, to be constructed as part of URS and in case the claimant(s) of ownership finally declared eligible by the Competent Court decide upon an option other than constructed area and exercise such other option, as mentioned in Regulation No.14.8.8(iv)(b), the Commissioner shall pay consideration as per such option exercised and such reserved constructed area in URS shall vest with the Corporation.
- iv) In any proposed URC, any open plot is included and if the concerned owner is not willing to participate in URC, the compensation payable shall be as per Land Acquisition, Rehabilitation and Resettlement Act, ⁽²⁾ 2013 read with section 126(1)(c) of Maharashtra Regional and Town Planning Act, 1966.
- v) In case of buildings or lands belonging to the Central Govt., the State Government, Semi-Government Organizations and Municipal Corporation or MHADA or any Local Government or any Corporation or Company owned by the Central / State Government or any Local Government (hereinafter collectively referred to as Public Authority), prior consent of such Public Authority shall have to be obtained for their inclusion in the URS.

For such lands or buildings, the Commissioner may either offer Market Price, to be decided by mutual consent, subject to ratification by the Municipal Corporation, or may offer constructed area, in-situ or ex-situ, in a composite or independent building or may, alternatively, offer equivalent TDR as per TDR regulations ⁽²⁾No.11.2 or may offer an exchange of suitable land as per mutual consent, subject to ratification by the Municipal Corporation and thereafter such land(s) / building(s) shall vest with the Municipal Corporation and shall form the part of URS.

14.8.9

Planning for Rehabilitation and Free Sale Plots in URS –

- i) Net area of URC shall be calculated after deducting the area under CRZ and Forest, if any. Out of total net area of the URC, maximum of 50% area in terms of one or more plots, to be called Free Sale Plots, shall be carved out for raising resources to cover the cost of construction of rehabilitation component and development of all the reservations and

⁽²⁾ Substituted / Inserted vide Corrigendum / Addendum No. CR 121/21, dt. 02nd December, 2021

amenities. While carving out Free Sale Plots, due weightage shall be given to the fact that the higher is the percentage of these plots in terms of area, the more dense is the Rehabilitation Area, and in exceptional cases, Commissioner may reduce these Free Sale Plots to zero. The percentage of the free sale plot may be enhanced upto 50% subject to approval by the HPC by considering 100% in-situ Rehabilitation with consumption of minimum FSI of 2.5 and if net plot area excluding Recreation Ground area is more than 8000 Sq.mt. under URS. Constructed area available on this Free Sale Plot collectively shall be equal to that available over the whole URC minus that required for rehabilitation and relocation. If Free Sale Plots are more than one, the Commissioner may distribute the available free sale construction area under URS over such plots, as he may deem fit. Such Free Sale Plots shall be deemed to belong to C-1 / C-2 Zone for the purposes of permissible users thereon.

⁽²⁾ Provided that, in exceptional cases, the above percentage of free sale plot may further be enhanced beyond 50% in order to make scheme viable and minimize generation of URT, subject to fulfilment of following conditions, subject to the approval of HPC :-

- a) 100% in-situ rehabilitation;
- b) no dilution more than what is mentioned in Regulation No.14.8.7, in the area of development plan reservations. ⁽²⁾
- ii) After the development of reservations, any occupants who could not be settled due to non-buildability of required construction area for rehabilitation and relocation, owing to constraints imposed by DCR, shall be rehabilitated in the nearby URS or PAP tenements available with the Corporation; as per policy guidelines decided by the Corporation.
- iii) Two or more contiguous ⁽¹⁾ (--) URCs ⁽¹⁾ within a notified URP having different densities may be permitted to get clubbed for implementation purpose sharing the densities in order to ensure balanced development increasing the viability of clusters.

14.8.10 Selection of Implementation Agency –

If an owner or group of owners or proposed co-op. Hsg. Society of occupants or federation of occupants, either directly or through a Power of Attorney Holder, collectively owning more than ⁽¹⁾ 51% of the area of URC or a part thereof, come forward for implementation of URS as per the Detailed Plan prepared by the Commissioner for such URC, within 3 months of declaration of the detailed plans of URC, or within such extended period as may be granted by the Commissioner, they may be selected as Implementation Agency for implementation of URS on such URC. In such a case ⁽²⁾ the infrastructure should be developed by the Implementing Agency at their own cost, otherwise an Infrastructural charges at the rate of 10% of construction ⁽²⁾ cost of buildings of rehab & free sale component (excluding infrastructure) as per prevailing ASR to be received by the corporation. In case owners / stakeholders owning more than 51% of whole or part area of URS as mentioned above fail to come together, selection of an implementation agency for the URS shall be done through a transparent bid process.

14.8.11 URS by Private Promoters / MHADA / Co-operative Housing Societies –

- i) Whenever there is no URP made by Commissioner or wherever there is no URS floated by the Commissioner over one or more URCs falling under URP made by Commissioner, any Private Promoter, MHADA, Co-operative Housing Society, federation of occupants etc. may approach Commissioner with consent of owners / stakeholders of 51% of any area requiring Urban Renewal, for implementation of URS thereon and Commissioner may, after satisfying himself that conditions mentioned herein, which make an area fit for redevelopment under URS are met, decide to implement URS thereon and, subject to other

⁽¹⁾ Substituted / Inserted / Deleted vide Corrigendum / Addendum No. CR 121/21, dt. 02nd December, 2021

⁽²⁾ Inserted vide Notification u/s 37 (1AA)(c) & 20(4) No.CR 236/18 (Part-4), dt.28th December, 2022

conditions and processes mentioned in this Regulation, appoint such applicant as implementation agency at the Base Premium.⁽¹⁾The Authority shall decide base premium with the approval of High Power Committee (HPC).

- ii) In case where there are some owners (pertaining to less than 30% area) who have not given their consent to the Private Promoter, MHADA, Co-operative Housing Societies etc. for URS, who are appointed as per Clause (i) above by Commissioner as Implementing Agency, the Commissioner shall offer remaining owners and right holders consideration for their rights as mentioned in the provisions for URS being designed and implemented by Commissioner, and if these considerations are rejected by these dissenting owners or right holders the Commissioner shall forward proposals for Land Acquisition to competent authority. In such cases, if final compensation is in terms of money, the same shall be recovered from the Implementation Agency and if final compensation is in terms of TDR, market value of such plots as per ASR rates shall be recovered from the Implementation Agency, in addition to the Base Premium.
- iii) A Surcharge on Development undertaken by the promoter/Developer at the rate of 100% of Development charge shall be leviable, which may be paid in stages in proportionate with the progress of work. This surcharge shall not be applicable to the construction within basic FSI, the built up area to be handed over to Municipal Corporation or any Public Authority in lieu of any reservation and also to the amenity areas to be handed over to the Municipal Corporations per the requirement indicated by the Municipal Corporation or the High Power Committee.

Explanation - 1. - In case of inclusion of a Slum in URS, any person/ agency having consent of more than 51% eligible Slum dwellers shall be construed to be appropriate person/ agency to deal with the issues regarding the whole area of Slum for the purposes of this sub-section only. i.e. for the purposes of decision about Implementation Agency.

14.8.12 Transit Camps - For smooth implementation of the URS, construction of temporary transit camps may be permitted on the same land or a land situated elsewhere as given here-under :

- i) Irrespective of its land-use classification under Development Plan, construction of temporary transit tenements made of light detachable material such as tubular / prefabricated light structures shall be allowed upto an FSI of 4.0 on any nearby vacant site without any reservation in the Development Plan, with the consent of the land-owner.
- ii) The temporary transit camp shall be provided on or close to the site of URS itself. However in exceptional circumstances to be recorded in writing, construction of Temporary Transit Camps may be permitted on the area of open space required to be kept in accordance with Regulation No.3.4.
- iii) Multi-storeyed temporary transit tenements may be allowed to be constructed with 4.00 FSI on the site of URS.
- iv) The area of temporary transit tenements shall be excluded from the computation of FSI, but structural safety of such tenements shall be ensured.
- v) Building permission for Temporary Transit Tenements shall be given within 45 days from the date of application but only after approval to the URS, failing which such permission shall be deemed to have been granted.
- vi) If a site, reserved in Development Plan for any public purpose is vacant or partly encumbered, or it happens to be the unused portion of such public purpose for which such site is reserved, and there is no other option for locating temporary transit tenements, then such site or unused portion may be utilized for building temporary transit tenements, with

⁽¹⁾ Inserted / Deleted vide Corrigendum / Addendum No. CR 121/21, dt. 02nd December, 2021.

the permission of Commissioner, on payment of such rent and subject to such conditions as the Commissioner may prescribe.

- vii) Temporary transit camp erected, under this Regulation shall have to be demolished by the Developer within 30 days from grant of Occupation Certificate to the Rehabilitation buildings and the land there under shall be brought back to the original state.

14.8.13 Non-conforming activities - All activities which are existing shall be allowed to be re-accommodated regardless of the non-conforming nature of such activities, excepting those which are hazardous and highly polluting and those where alternative accommodation has already been provided elsewhere by the Promoter / Developer / Municipal Corporation.

14.8.14 Relaxation in Building and other requirements –

- i) The calculation of FSI for all purposes shall be on gross area i.e. without deducting any percentage for recreational open space. This shall not affect the requirement of physical open space in terms of keeping aside the said recreational open space on site as per the UDCPR.
- ii) The provisions in UDCPR relating to balcony shall apply to the URS with the modification that there shall be no restriction on Zone and balcony shall not reduce marginal open space to less than 3.0 m. However, at ground level, clear margin of minimum 4.5 m. shall be maintained. Enclosed balcony shall be included while calculating the entitled area.
- iii) Front and marginal open spaces : For a building in the Rehabilitation Component or composite building having height upto 24.0 m., front and marginal open space shall be 4.5 m. and for buildings having height more than 24.0 m., the same shall be 6.0 m.
- iv) Notwithstanding the provisions in UDCPR, where the plot abuts a D.P. Road having width of 18.0 m. and above, the front marginal open space shall not be insisted upon beyond 4.5 m., provided such road is not a Highway.
- v) Where the plot abuts a trained nallah, the marginal open space along the nallah shall not be insisted upon beyond 4.5 m. from the edge of the trained nallah or as per requirement of SWD Department of, whichever is greater.
- vi) The distance between any two rehabilitation buildings shall not be less than 6.00 mt.
- vii) If the height of a building in URS is more than 25 m., 6.0 m. wide marginal open space or marginal open space as per the requirement of CFO, whichever is greater, shall be considered.
- viii) A Composite building shall contain at least 50 percent of the built up area as Rehabilitation Component.
- ix) The means of access shall be normally governed by the provisions of UDCPR. However, in the URS, wherever the design of the buildings up to 24.0 m. height in the same land requires some relaxation, the same may be given by the Commissioner; buildings having height exceeding 24.0 m. Shall be permissible only on access having width of 9.0 m. or more.
- x) Even if the recreational open space is reduced to make the URS viable, a minimum of at least 10 percent of the area of URC shall be provided as recreational open space. In addition to this, 10 percent of URC area shall be earmarked for amenity space which can be adjusted against the D.P. reservation (excluding roads), if any provided the area of such reservation exceeds 25% of the area of the URP.
- xi) Amenities not available in the periphery of 400 m. from boundaries of URC shall be developed on Amenity Plot, subject to the minimum area specified for such amenities under

this Regulation and handed over free of cost to the Corporation without any consideration.

- xii) Area to be excluded from computation of FSI shall be as per these Regulations (UDCPR).
- xiii) In order to make the URS viable, the Municipal Commissioner shall be competent to sanction any relaxation in the parking requirements and marginal open spaces, except for front marginal open spaces, wherever required on account of bonafide demonstrable hardship and for reasons to be recorded in writing, which shall not affect general safety and fire safety requirements.
- xiv) All relaxations outlined hereinabove shall be admissible only to buildings in the Rehabilitation Component of URS and also to the composite buildings therein. Premium at the concessional rate shall be charged by the Municipal Commissioner for all or any of the relaxations given hereinabove or for any other mentioned in UDCPR.
- xv) The parking in the URS shall be provided as per the provisions of UDCPR.
- xvi) Any aspect of development under URS, which is not specified under this Regulation, shall be governed by the relevant provisions of the UDCPR.
- xvii) In order to facilitate redevelopment and to decongest the redeveloped area in the URC, the Commissioner may insist on additional road width, over and above that prescribed in the sanctioned D.P. or the width of the existing roads.
- xviii) Provisions of Public amenities and roads under the URS shall be considered at par with reservations and the roads in the Development Plan.
- xix) Portion of URC falling under No Development Zone, Buffer Zone, CRZ-I & III and Private Forest shall form a part of the required Recreational Area in the URS.

14.8.15 The approving / sanctioning authority for the building plans under the URS shall be the Municipal Commissioner as per the M.R. & T.P. Act, 1966, even if the URS partly consists of declared slums or slums on Municipal / Govt. lands, existing prior to 1st January, 1995 or such other reference date as may be notified by the Government.

14.8.16 Religious structures existing on the site of URS prior to redevelopment, if allowed to be redeveloped in accordance with the guidelines issued by the Government from time to time; following such redevelopment, shall not have area exceeding their area prior to redevelopment.

14.8.17 Heritage buildings of Grade - I and II may be included in the area of Urban Renewal Cluster, but have to be kept as they are, along with land appurtenant, but shall not be considered for FSI under this Regulation. As regards such Heritage Structures, the Promoter / Developer shall have to contribute Heritage Cess at 5% of ASR Rates on the basis of built-up area of the Heritage structure. Existing provisions under these Development Control Regulations shall apply to Heritage Buildings of Grade - III. However, before granting the approval for such buildings, the HPC shall consult the Heritage Committee appointed for that purpose.

14.8.18 If HPC approves areas for amenities such as Fire Stations / Hospitals / Police Stations / Schools, etc. other than reservations / designations as per Development Plan, such amenities shall be handed over to the concerned Authority, free of cost and the built up area of such amenity shall be considered as rehabilitation F.S.I. and incentive FSI as admissible under this Regulation shall be permissible.

The decision of HPC shall be appealable, as if, it is an appeal under section 47 of the M.R. & T.P. Act, 1966.

14.8.19 Formation of Co-operative Housing Societies, and their Federations for buildings in URS - Commissioner shall cause formation of Co-operative Housing Society for each and every building, either separately or collectively as he may deem fit and shall cause to be deposited 25% of the amount of consideration received from the allottees of such building, in a "Building

Maintenance Fund” to be utilised by the Co-operative Housing Society of the allottees of such Building, as per the guidelines framed by the Corporation. In addition, the Commissioner shall cause to be deposited 25% of the amount of consideration received from the allottees of each and every rehabilitation and relocation in URC building, in another Maintenance Fund called “URC Maintenance Fund” to be set up, by the Commissioner, for the dedicated use of maintenance of common facilities / amenities in the URC by the Corporation. The utilisation of the URC maintenance Fund shall be in accordance with the guidelines framed by the Corporation.

14.8.20 Formation of Shelter Fund -

Commissioner shall cause to be deposited 50% of amount of consideration received from the allottees and amount received from bidding process in a separate fund to be named as “Shelter Fund”, which may be used as per the policy to be formulated by the Corporation for payment of consideration for acquisition of land falling under URC, providing financial assistance to beneficiaries under URC, procurement of land for creation of affordable Housing, and promoting affordable housing in the city limits.

⁽¹⁾ Note - If any correction / changes are needed in URS Regulation for the benefit of URC or for success of URC scheme, the decision can be taken at HPC level and subsequently should be communicated to the Government to incorporate such decision in this Regulation.⁽¹⁾

14.9 DEVELOPMENT OF TOURISM AND HOSPITALITY SERVICES UNDER COMMUNITY NATURE CONSERVANCY AROUND WILD LIFE SANCTUARIES AND NATIONAL PARKS

14.9.1 Applicability - These regulations shall apply to the privately owned (not applicable to forest land) lands falling in Agriculture / No Development Zone situated within 5 km. distance from the boundaries of wildlife sanctuaries and national parks in the State of Maharashtra. The provisions of existing Regional Plans / Development Plans will prevail over these regulations, wherever lands are earmarked for urbanisable zones in such plans.

14.9.2 Regulation - For the lands situated within 5 km. distance (or up to a limit of notified eco-sensitive zone, whichever is more) from the boundaries of wildlife sanctuaries and national parks, if the land owner applies for development permission, for development of eco-tourism, nature tourism, adventure tourism, same may be allowed; provided the land under consideration has minimum area of one hectare in contiguous manner.

i) Permissible users and built up area -

The users permissible in Agricultural Zone / No Development Zone area shall be as follows:-

- a) Agriculture, Farming, development of wild animal shelters, plantation and allied uses.
- b) Tourist homes, Resorts, Hotels etc. with Rooms / suites, support areas for reception, kitchen, utility services etc. along with ancillary structures like covered parking, Watchman’s quarter, guard cabin, landscape elements, and only one observation tower per tourist resort up to the height of 15.0 m. with platform area up to 10 sq.m. in permanent / semi-permanent structural components.

ii) The norms for buildings shall be as follows -

- a) The construction activities shall be as per Zonal Master Plan / Regional Plan / Development Plan of the concerned protected area.
- b) The maximum permissible total built up area shall not exceed 10% of gross area with only G + 1 structure having height not more than 9.0 m. and it should blend with surrounding

⁽¹⁾ Inserted vide Notification u/s 37 (1A)(c) & 20(4) No.CR 236/18 (Part-4), dt.28th December, 2022

- c) The Fencing / fortification may be permissible for only 10% of total land area around built up structures in the form of chain link without masonry walls thereby keeping the remaining area free for movement of wildlife.
- d) Tourism infrastructure must conform to environment friendly, low height, aesthetic architecture, natural cross ventilation; no use of asbestos, no air pollution, minimum outdoor lighting and merging with the surrounding landscape. They should generate at least 50% of their total energy and fuel requirement from non-conventional energy sources like solar and biogas, etc.
- e) The owner shall establish effective sewage disposal and recycling system during the construction and operational phase of the development. No sewage shall be allowed to be discharged into natural stream.

If in cases, where lack of compliance is observed, the concerned authority should issue a notice to the resort owner / operator for corrective action within 15 days, failing to do so or having not been satisfied with the action taken or reply / justification received, any decision to shut down the unit may be taken, by the respective authority.
- f) The owner shall establish effective systems for collection, segregation, composting and / or reuse of different types of solid waste collected during the construction and operational phase of the development.
- g) The plastic components used within the area shall be recycled; failing which the resort shall be closed down within 48 hours.
- h) Natural streams / slopes / terrain shall be kept as it is, except for the built-up area.
- i) On the area other than 10% area, only local trees shall be planted and only natural vegetation shall be allowed.
- j) For the development of such type already taken place, Condition no.(c) above shall be applicable retrospectively to the extent of restricting the fencing and keeping the remaining area free for movement of wildlife.
- k) While allowing such development, principles given in the National Tiger Conservation Authority, New Delhi Notification No.15-31/2012-NTCA, dated 15/10/2012 published in the Gazette of India Ext. pt. III S-4 dated 08/11/2012 and Government of Maharashtra as amended time to time shall be used as guidelines.
- l) All regulations prescribed in Eco-Sensitive zone Notification of concerned National Park / Wildlife Sanctuary should be strictly followed and all clearances required should be taken.

14.10 INTEGRATED INFORMATION TECHNOLOGY TOWNSHIP (IITP)

Integrated Information Technology Township (IITP) shall be allowed in Residential, Commercial, Public Semi-public, Industrial and Agricultural Zone in Development Plan and Regional Plan areas and shall be governed by the provisions mentioned herein below.

14.10.1 Area Requirement

Any suitable area in Regional plan or Development plan having access by means of an existing road or a proposed Regional plan / Development Plan road having a minimum width of 18.0 m. can be identified for the purpose of development as Integrated IT Township. The area notified under the Integrated IT Township shall be one continuous, unbroken and uninterrupted and in any case shall not be less than ⁽¹⁾ 10 acres. (4 Ha.) at one place.

⁽¹⁾ Inserted / Substituted vide Notification u/s.37(1AA)(c) & 20(4) No.CR.97/2023/UD-13, dt.12th January, 2024

(Explanation - If such minimum ⁽¹⁾ 10 acres. (4 Ha.) area proposed to be developed under a Integrated IT Township is divided by one or more water courses (such as nallahs, canal, etc.) existing or proposed roads of any width or railways, etc. then such area shall be considered to be continuous, unbroken and uninterrupted, subject to the condition that the developer shall construct necessary connecting roads or bridges as per site requirements at his own cost with due permission from concerned authorities.) The area under any Integrated IT Township shall not include the area under notified forest, water bodies like river, creek, canal, reservoir, tribal lands, lands falling within the belt of 500 m. from the High Flood Line (HFL) of major lakes, lands in the command area of irrigation projects, land falling within the belt of 200 m. from the historical monuments and places of Archeological importance, Archeological monuments, heritage precincts and places, any restricted areas, notified national parks, gaathan areas or congested areas, Defense areas, Cantonment areas, truck terminus especially earmarked on Development plan, area under Eco-sensitive Zone, other environmentally sensitive areas, Quarry Zone, notified areas of Special Economic Zone (SEZ) and designated airport areas. However, such Integrated IT Township may include private land under Hill-Top and Hill-Slope Zone, whether earmarked on Regional plan / Development plan or not and private land in A forestation Zone.

Provided that, the area of lands in such Hill-Top and Hill-Slope Zone and a forestation Zone shall not exceed 40 percent of the gross area of the project and such area shall be shown towards 50% area to be kept permanently open where no development activity shall be permissible under such project. The said areas shall be developed for tree plantation as per the norms specified. However, for the purpose of calculation of Floor Space Index (FSI), such areas shall be excluded.

14.10.2 Planning Considerations

The project has to be an integrated project. The Integrated IT Township should necessarily provide land for following users :-

1. Information Technology (Industrial)
2. Residential
3. Commercial
4. Educational
5. Amenity Spaces
6. Health Facilities
7. Parks, Gardens & Playgrounds
8. Public Utilities
9. Transport and Communication

14.10.3 General Norms for Different Land Use

Out of the total area notified as "Integrated IT Township" ⁽¹⁾ 50% FSI shall be used for IT / ITES activities and ⁽¹⁾ 50% FSI for the development of residential and commercial activities provided that 20% area shall be kept for Park / Play Ground / Garden of total IITP.

Residential and commercial activities shall include malls, cinema, theaters, public auditorium and multiplexes, showrooms for all types of merchandise, hospitals, nursing homes, schools and colleges, training institutes and hostels related to them, hotels. The development of entire township, i.e., (1) 50% area for IT / ITES and (1) 50% other area can take place simultaneously but the developer will have to ensure that sale / lease of both areas is proportionate. To ensure this occupation certificate for commercial, residential and support services shall be given only after the development of infrastructure facilities on the area earmarked for IT / ITES activities and occupation certificate is granted by the Authority and after 1/3rd area kept for IT / ITES activity is occupied.

⁽¹⁾ Inserted / Substituted vide Notification u/s.37(1AA)(c) & 20(4) No.CR.97/2023/UD-13, dt.12th January, 2024

14.10.4 FSI In integrated I.T. Township

The maximum permissible FSI on the gross area of the notified Integrated IT Township shall vary as follows :-

For Integrated IT Township located in Pune, Pimpri-Chinchwad, Greater Mumbai, Thane, Navi Mumbai, Kalyan-Dombivali, Mira-Bhayandar, Ulhasnagar, Nagpur Municipal Corporations and Ambarnath Municipal Council limits the permissible FSI shall be 2.5. For rest of the areas in the State, the permissible FSI shall be 2.00. For land in Agricultural zone in all areas, it shall be 1.00. The premium chargeable shall be as ⁽ⁱ⁾ mentioned in Maharashtra's Information Technology / Information Technology Enabled Services Policy (IT/ITES) - ⁽ⁱ⁾ 2023 issued by Industries, Energy & Labour Department vide Government Resolution No. ⁽ⁱ⁾ ITP-2021/ CR-170) Ind-2, dated 27th June, 2023 as amended from time to time. Floating of FSI shall not be permissible from the area of IT / IT use to the area of Support Activities or vice versa, but floating of FSI shall be permitted within the respective areas of IT / ITES and Support Activities separately.

- 14.10.5**
- i) Provisions of these DCPR as well as provisions of MoEF and CRZ notification, wherever applicable, issued & as amended from time to time shall be applicable mutatis-mutandis to the Integrated IT Township except those expressly provided in these Regulations.
 - ii) In the event the Integrated IT Township contains sites reserved for public purposes (buildable reservations) in Regional plan / Development plan, for which the Appropriate Authority is any department of State Govt. / Central Govt. or any Government undertaking, the developer shall construct the amenity as per requirement of the concerned department and handover the constructed amenity free of cost to that Department. Upon such handing over the constructed amenity the developer would be entitled to utilise additional floor space over and above the FSI permissible within the Integrated IT Township (equivalent to the built up area of the constructed amenity) anywhere within the Integrated IT Township.
 - iii) In every Integrated IT Township proposal the Structural Designer of developer has to submit declaration with project report to the Authority about the construction of buildings below :
'I have confirmed that the proposed construction in the scheme is as per norms as specified by Bureau of Indian Standard for the resistance of earthquake, fire safety & natural calamities'.
 - iv) In Integrated IT Township being developed in Residential and other zones mentioned above and Agricultural / Green Zone / No Development Zone, trees at rate of minimum 100 trees per Ha. and 200 trees per Ha. respectively shall be planted and maintained by the developer.

14.10.6 Infrastructure Facilities

The entire onsite infrastructure in the Integrated IT Township along with access road shall be provided and maintained by the developer. However, it would be obligatory on the part of the developer to provide all basic infrastructures on at least 75% area under the Integrated IT Township within 3 years from the date of sanction of development proposals by the Authority; failing which bank guarantee submitted by the project proponent/s shall be forfeited.

The Project Proponent/s shall submit a bank guarantee of an amount equal to the 15% of estimated development cost required for development of the basic infrastructure such as roads, water supply, drainage & garbage disposal, installations for power supply, fire brigade station & fire engines. Such development cost be worked out as per respective phases taking into consideration the phased program for development of infrastructure with amenities under project as submitted. Certificate regarding estimated development cost shall be produced by the respective Architect of the project.

⁽ⁱ⁾ Inserted / Substituted vide Notification u/s.37(1A)(c) & 20(4) No.CR.97/2023/UD-13, dt.12th January, 2024

14.10.7 Water Supply

The developer shall be required to develop the source for drinking water (excluding the groundwater source) or secure firm commitment from any water supply Authority for meeting the daily water requirement of minimum 140 liters per capita per day, exclusive of requirement of water for firefighting and gardening. The storage capacity of the same shall be at least 1.5 times of the actual required quantity as determined by expected population (Resident and Floating) and other uses. The developer would be required to develop proper internal distribution and maintenance systems and shall specially undertake rain water harvesting, groundwater recharging and waste water recycling projects within the Integrated IT Township.

14.10.8 Drainage and Garbage Disposal

The developer shall make suitable and environment friendly arrangements for the disposal and treatment of sewage and solid waste as per requirements of Maharashtra Pollution Control Board. Recycling of grey water for gardening shall be undertaken by the developer.

The developer shall develop eco-friendly garbage disposal system by adopting the recycling and bio-degradation system in consultation with Maharashtra Pollution Control Board.

14.10.9 Power

The developer shall ensure continuous and good quality power supply to the Integrated IT Township area. The developer may draw the power from existing supply system or may go in for arrangement of captive power generation with the approval from concerned Authorities. If the power is drawn from an existing supply system, the developer shall before commencement of development, procure a firm commitment of power for the entire Integrated IT Township from the power supply company.

14.10.10 Environment

The development contemplated in Integrated IT Township shall not cause damage to ecology. In no case, it shall involve topographical changes, changes in alignment of cross-section of existing water course, if any in the scheme or adjustment to scheme area. Environmental clearance shall be obtained from the Ministry of Environment and Forest, Government of India as per directions issued by the MoEF's Notification dated 7th July, 2004 and as amended from time to time. The Integrated IT Township shall provide at least 20% of the total area as park / garden / playground, with proper landscaping and open uses designated in the Integrated IT Township shall be duly developed by owner / developer. This amenity shall be open to general public without any restriction or discrimination.

14.10.11 Special Concession

- a) N.A. Permission : Non-agriculture permission will be automatic. As soon as the scheme is approved, lands under such Integrated IT Townships area shall be deemed to have been converted into non-agriculture and no separate permission is required.
- b) Grant of Government Land : Any Government land falling under Integrated IT Township area shall be leased out to the developer at the prevailing market rate on usual terms conditions, without any subsidy.
- c) Relaxation from Mumbai Tenancy and Agriculture Land Act : The condition that only the agriculturist will be eligible to buy the agriculture land shall not be applicable in Integrated IT Township area.
- d) Ceiling of agriculture land : - There shall be no ceiling limit for holding agriculture land to be purchased by the owner / developer for Integrated IT Township project.
- e) Exemption from Urban Land (Ceiling and Regulation) Act, 1976 : Integrated IT Township

projects will be exempted from the purview of Urban Land (Ceiling and Regulation) Act, 1976.

- ⁽¹⁾ f) Staggered payment facility for premium to be paid for additional FSI shall be allowed to be paid in two installments but within a year or on the date of obtaining the Occupancy / Part Occupancy Certificate, which is earlier.

14.10.12 Sale Permission

It would be obligatory on the part of the developer firstly to provide for basic infrastructure and as such no permission for sale of plot / flat shall be allowed unless the basic infrastructure is provided by the developer to the satisfaction of the Authority. In case the development is provided in phases & sale permission is expected after completion of phase-wise basic infrastructure, such permission may be granted by the Authority. Before granting such sale permission, developer has to submit undertaking about the basic infrastructure to be provided and completed phase wise. The plots earmarked for amenities, facilities and utilities shall also be simultaneously developed phase-wise along with IT / support services development.

14.10.13 Implementation and Completion

- ⁽¹⁾ If the area of Integrated Information Technology Township is 10 acres (4 Hec.) to 25 acres (10 Hec.), the period of completion of the project shall be 7 ½ years and if the area is more than 25 acres (10 Hec.), this period shall be 10 years. In case of delay the extension shall be granted with the approval of Committee Constituted in this regard. ⁽¹⁾

14.10.14 Interpretation

If any question or dispute arises with regard to interpretation of any of these regulations, the matter shall be referred to the State Government. The Government after considering the matter and if necessary, after giving hearing to the parties, shall give a decision on the interpretation of the provisions of the Regulations. The decision of Government on the interpretation of these regulations shall be final and binding on all concerned.

14.11 INTEGRATED LOGISTIC PARK (ILP)

Integrated Logistic Park shall be allowed in Commercial, Industrial and Agricultural Zone in Development Plan and Regional Plan areas and shall be governed by the provisions mentioned herein below.

14.11.1 Eligibility for establishment of Logistic Park

Private land owner or developer appointed by him or any Company with legal entity may apply for permission for Integrated Logistic Park.

14.11.2 Activities Constituting Logistic Park

A logistic Park can include the following activities. (The list is indicative)

i) Logistic Services.

- a) Cargo aggregation / segregation.
- b) Sorting, grading, packaging/ repackaging, tagging/ labelling.
- c) Distribution / Consumer Distribution.
- d) Inter-model transfer of material and container.
- e) Open and closed storage for transit period.
- f) Custom bonded warehouse.
- g) Container freight station.
- h) Container terminals.
- i) Material handling equipment facilities for efficient movement and distribution of Semi-finished or finished products.

⁽¹⁾ Inserted / Substituted vide Notification u/s.37(1AA)(c) & 20(4) No.CR.97/2023/UD-13, dt.12th January, 2024

ii) Infrastructure

- a) Internal roads
- b) Power line
- c) Communication facilities
- d) Internal Public Transportation System
- e) Water distribution and water augmentation facilities
- f) Sewage and drainage lines
- g) Effluent treatment and disposal facilities
- h) Fire Tenders arrangements – Parking

iii) Business and commercial facilities

- a) Dormitories
- b) Guest Houses
- c) Canteen
- d) Medical Centre
- e) Petrol Pump
- f) Banking and finance
- g) Office Space
- h) Hotel
- i) Restaurants
- j) Hospital / Dispensary
- k) Administration office

iv) Common Facilities

- a) Weigh Bridge
- b) Skill Development center
- c) Computer center
- d) Sub contract exchange
- e) Container freight station
- f) Production Inspection Centre
- g) Repair workshop for vehicles & production machinery in the park.

The list of permissible activities as revise by the department of Industries, Government of Maharashtra, from time to time, shall be applicable.

14.11.3 Procedure for Development of Logistic Parks

Private land owner or developer appointed by him may apply to the Authority for development of Logistic Park under this Regulation. After sanction of permission by the Authority for setting up Logistic Park, such area shall be deemed to be converted for industrial use in the respective Development Plan or Regional Plan and shall be available for development of Logistic Park. However, in case of land in Agricultural zone, the premium shall be charged at the rate of 15% of land value as per ASR, without considering guideline therein.

14.11.4 Integrated Logistics Park (ILP)

An “Integrated logistic park” will be defined as one that is spread over a minimum of 5 acres of land and having minimum 15 meters wide access road. A minimum of 70% of the total area of ‘Integrated Logistic Park’ shall be used for providing logistic services, and remaining area shall be permitted for support services and common facilities. Floating of FSI shall not be permissible from the area of industrial zone to the area of support services or vice versa, but floating of FSI shall be permitted within the respective areas of industrial zone and support activity zone separately. The Integrated Logistics Park shall provide following minimum infrastructure and common facilities.

- i) Infrastructure :
 - a) Internal roads
 - b) Power line
 - c) Communication facilities
 - d) Water distribution and water augmentation facilities
 - e) Sewage and drainage lines
 - f) Effluent treatment & disposal facilities
 - g) Fire tender arrangements
 - h. Parking
- ii) Common facilities:
 - a) Dormitories
 - b) Canteen
 - c) Medical Centre
 - d) Weigh Bridge

The parking and other essential services mentioned in Regulation No.14.11.2(ii) will be free of FSI. The letter of Intent for development of an Integrated Logistics Park shall be issued by Directorate of Industries. The development in the said Logistics Park shall be completed within 5 years from date of issue of Letter of Intent (LOI). The extension to time limit upto a minimum of one year at a time and not more than 3 times may be granted on merits. Directorate of Industries will be the registering agency for all Integrated logistic parks. The procedure adopted for issue of letter of intent and registration would be in line with that adopted under the Integrated Industrial Area. The developer of Integrated Logistics Park will have to develop the infrastructure and create and maintain the facilities. Such facilities can be hired/leased/rented or put to own use by the Developer.

14.11.5 Logistics Park (LP)

Logistics park / building with a minimum of 20000 sq. feet Built up Area with basic FSI will be designated as Logistics Park (LP). The 80% of the total area of 'Logistic Park' should be used for providing logistic services and up to 20% of the total area will be permitted for support services and common facilities mentioned in Regulation No.14.11.2 (iii and iv). Logistics Parks will be allowed applicable FSI in these Regulations. The letter of Intent for development of a Logistics Park shall be issued by Directorate of Industries. The development in the said Logistics Park shall be completed within 3 years from date of issue of Letter of Intent (LOI). The extension to time limit upto a minimum of one year at a time and not more than 3 times may be granted on merits. Directorate of Industries will be the registering agency for all logistic parks. The procedure adopted for registration would be in line with that adopted under the IT / ITES Policy 2015. The developer of Logistics Park will have to develop the infrastructure and create and maintain the facilities. Such facilities can be hired / leased / rented or put to own use by the Developer.

14.11.6 Upto 200% Additional FSI for Integrated Logistics Park & Logistics Park

For Integrated Logistic Parks & Logistic Parks, the FSI permissible for Industrial Zone as per these regulations shall be applicable. Upto 200% of additional FSI shall be admissible over and above the basic FSI for development of Integrated Logistic Park & Logistics Park with or without premium as follows :-

Sr. No.	Location of Parks (As defined under PSI 2013)	Premium
1	No industries district and Naxalism affected areas	Nil
2	Areas other than PMC, TMC, Kalyan Dombivali, Mira Bhayendar, Panvel, Ulhasnagar, Ambarnath, Navi Mumbai Municipal Corporation, NID and Naxalism Affected Areas	10%

3	PMC, TMC, Kalyan-Dombivali, Mira Bhayendar, Panvel, Ulhasnagar, Ambarnath, Navi Mumbai Municipal Corporation	15%

Note : However premium charged will be limited upto the demand made by the developer for additional FSI.

14.11.7 Permissible Height

For Integrated Logistic Park & Logistics Park, height of building upto 24 m. or as per requirement shall be permitted.

14.12 INDUSTRIAL TOWNSHIP UNDER AEROSPACE AND DEFENSE MANUFACTURING POLICY

Industrial Township under Aerospace and Defense Manufacturing Policy shall be permitted in Commercial, Industrial and Agricultural Zone in Development Plan and Regional Plan areas. Other stipulations for Industrial Township under Aerospace and Defense Manufacturing Policy -2018, declared by the State Government in Industry, Energy Labour Department vide Government Resolution No.Asangho-2015/Pra.Kra.98/Udyog-2, dated 14/02/2018, shall be applicable.

The FSI permissible for this Industrial Township shall be as per FSI permissible in Industrial Zone. The lands which are included in Agricultural Zone in the Development or Regional Plan shall be treated as included in Industrial Zone after the permission is granted for this Industrial Township.

Provided that upto 20% of total built up area of such Industrial Township may be used for residential / commercial purpose / support activities.

Provided further that the Research and Development Institutions in such Industrial Township shall be eligible for additional 0.50 FSI over permissible FSI as per these Regulations.

14.13 DEVELOPMENT OF INTEGRATED INDUSTRIAL AREA

The development of Integrated Industrial Area within the jurisdiction of Maharashtra Industrial Development Corporation shall be allowed as per Urban Development Department's Notification No.TPB-4314/20/CR-32/2014/UD-11, dated 1st August, 2015. The Principal Regulation's referred in the said notification shall be deemed to have reference to provisions of UDCPR alongwith specific regulations related to MIDC mentioned in Chapter 10.

~*~*~*~*~

CHAPTER - 15

REGULATIONS FOR SPECIAL ACTIVITIES / PLANS

15.1 QUARRYING OPERATIONS

With the approval of the, Authority Mining or Quarrying operations may be permitted in Agriculture Zone on following conditions :

- 1) The quarrying and mining operations shall be permitted outside CRZ and notified eco-sensitive zone and heritage precinct but only at specific locations decided by the competent authority. The development permission shall be granted subject to production of order to carry out these activities from the revenue authority concerned under the Minor Minerals Act and NOC of the MPCB.
- 2) The application for Development Permission of quarrying shall include :
 - a) Original 7/12 extract along with a location plan at 1:5000 scale of the quarry site and an area upto 500 meters around the quarry site showing important natural and manmade features and contours;
 - b) A site plan at 1:500 scale showing site boundaries, contours, all existing natural and man-made features such as hills, water courses, trees and other important landscape features, access roads, building and other structures;
 - c) Proposed excavation plan and cross sections at 1:500 or larger scale showing proposed phasing; terracing; stepping; benching slopes; locations of process equipment; diversion of water courses; impounding lake; storage areas for top soil, waste material, quarried material; workers housing; landscaping including screen planting, mounding and measures against visual intrusion etc.;
 - d) A restoration plan including landscaping proposals, phasing and proposal for reuse of the area after quarrying;
 - e) A report supplementing the excavation and restoration plans, costs and implementation programme;
 - f) Scrutiny fee shall be paid by the owner;
 - g) Development Charge for the land under quarrying shall be paid by the owner, as per the provisions of section 124-B of the M.R. & T.P. Act, 1966, at 0.50% of the rates of developed land mentioned in the A.S.R. of the Registration Dept. of the year in which permission is granted.
- 3) No quarrying shall commence until the excavation plan is also approved by the Director of Geology and Mining, Government of Maharashtra.
- 4) The Restoration Plan approved by the Planning Authority shall be carried out in consultation with concerned Conservator of Forest or District Forests Officer, and the Revenue Authority.
- 5) Natural gradient of slope should be maintained during quarrying operations. Slope of the foot-wall side (Slope in the direction in which mining does not exist) should be properly organized by planting adequate trees of suitable species so as to have soil binding vegetation.
- 6) In the case of murum quarrying, entire weathered soil or murum shall not be excavated exposing hard rock; instead, a capping of at least half a meter be left so that it can support vegetation and plantation that be done later on. Similarly, these operations shall not cause depression below the average ground level.
- 7) Water course, if any from a higher slope, should be properly diverted out of quarry area so that minimum water flows into the quarry and is safely channelled out of any nearby human settlement.

- 8) During quarrying operations, the water should be sprayed at least once in a day over the roads at quarry sites and nearby area.
- 9) Kachha road leading to quarry site shall be invariably sprayed by water during the period when trucks carry murum. In addition, in order to minimize dust pollution, measures such as adoption of hoods at transfer points, vulcanizing of conveyor belt joints, under belt cleaning devices, apart from installation of dust extrication system for conveyance, shall be adopted. The kachha road leading to the quarry shall have roadside plantation in order to arrest the dust pollution.
- 10) No Quarrying and crushing shall be permitted if a highway or public road having width of 30 m. or more, railway line or any human settlement is located within 200 m. from the quarrying site. However, for quarrying with blasting operations, the distance shall be at least 500 m.
- 11) Residences for labourers and related temporary structures should be constructed at least 500 meters away from the place of blasting as well as from the place of quarrying. Heavy blasting by use of heavy machinery shall be prohibited
- 12) The development permission for quarrying shall be granted for period of 1 year and may be revalidated every year for a maximum period of 3 years. After this fresh permission for further quarrying will be necessary. In granting such fresh permission, the Authority shall have regard to the applicant's performance in observing the approved excavation and restoration plans, and in carrying out the quarrying operations in accordance with these guidelines.

15.2 ERECTION OF MOBILE TOWERS

Erection / setting up Telecommunication Cell Sites / Base Stations and installation of the equipment for Telecommunication network shall be permissible as per the norms of Department of Telecommunication / Information Technology or concerned Department of the Central / State Government.

^(#) Directives u/s.154 of the M.R. & T.P. Act, 1966 by the Govt. vide Order No.CR.179/2022/UD-13, dt.25th August, 2023 regarding inclusion of Addendum to Model Building Bye-Laws – 2016.

15.3 PREPARATION OF LOCAL AREA PLAN

A local area plan is a plan for comprehensive development of particular area in city / town, which may consist of detail provisions than that of development plan addressing the local requirements of the area. The Authority may prepare such plan consisting of planning requirement at micro level, local area specific regulations, urban design etc. The local area plan shall be prepared by following procedure similar to that of section 33 of the Maharashtra Regional and Town Planning Act, 1966. After approval to this plan by the State Government, it shall come into force. In the event of provisions of local area plan not consistent with UDCPR, the provisions of local area plan shall prevail.

15.4 GUIDELINES FOR STREET DESIGN IN CITY / TOWN.

The authority shall ensure complete design of street i.e. streets shall be designed to cater to the needs of all users and activities like smooth and convenient vehicular movement, safe and unhampered pedestrian movement for all age groups, safe and easy movement of differently abled persons, street furniture etc.

The street shall generally be designed to

- i) attract more users,
- ii) have provisions for pedestrian and cyclist,
- iii) increase retail activities,
- iv) to provide relevant street furniture and signage,
- v) plant trees,
- vi) make provisions for proper illumination,
- vii) have provisions for underground utilities,

⁽¹⁾ *The specimen plans for development of a street having road width 18 m. and up to 60. m. are given at Appendix-M. The authority shall develop the new roads as per these specimens.*

⁽¹⁾ Inserted vide Corrigendum / Addendum No. CR 121/21, dt. 02nd December, 2021.

..*..*..*..*


(Kishor Gokhale)
Under Secretary
Government of Maharashtra


(N. R. Shende)
Director of Town Planning and Joint Secretary
Government of Maharashtra



APPENDIX A - 1 : FORM FOR CONSTRUCTION OF BUILDING OR LAYOUT OF BUILDINGS / GROUP HOUSING

Application for permission for development under Section 18 / 44 / 58 / 69 of The Maharashtra Regional and Town Planning Act, 1966 read with any other Act governing the Planning Authority,* if any.

From _____ (Name of the owner)

To,

The Authority (Name of the Authority)

Sir,

I intend to carry out the under mentioned development in the site/plot of land, on Plot No.
Revenue S.No. / Gat No. / Khasara No. / City Survey No. / Final Plot No.
Mauje situated at Road / Street Society in accordance with Section
18/44/58/69 of the Maharashtra Regional and Town Planning Act, 1966 read with Section (*) ----- of
----- Act.

I forward herewith the following plans and statements (Item i to x), wherever applicable, in quadruplicate, signed by me (Name in block letters) and the Architect / Licensed Engineer / Supervisor (License No.), who has been engaged by me and has prepared the plans, designs and a copy of other statements / documents as applicable.

- i)** Key Plan (Location Plan), (to be shown on first copy of the set of plans)
- ii)** Site Plan showing the surrounding land and existing access to the land proposed to be developed; (to be shown on first copy of the set of plans)
- iii)** A detailed building plan showing the plan, section/s and elevation/s of the proposed development work along with existing structure to be retained / to be demolished, if any;
- iv)** Particulars of development in Form enclosed (excluding individual Residential building);
- v)** Copy of sanctioned layout plan if any;
- vi)** An extract of record of rights, property register card (any other document showing ownership of land to be specified)
- vii)** In case of revised permission, document of consent as per Regulation No.2.2.3(v).
- viii)** Attested copy of receipt of payment of scrutiny fees;
- ix)** Latest property tax receipt;
- x)** No Objection Certificate(s), wherever required.

I request that the proposed development / construction may be approved and permission be accorded to me to execute the work. I hereby undertake that I shall carry out the work according to the approved plan.

Signature of Owner

Name of Owner

Address of Owner.

Contact No.

Dated.

CERTIFICATE

The above mentioned Plans are prepared by me as per UDCPR.

Signature of the Architect / Licensed Engineer /
Supervisor.

Name.

License No.

Contact No.

Dated

(*) Name of the Act of the Planning Authority, if any, be mentioned.

Form giving Particulars of Development		
(Item iv of Appendix A - 1)		
1.	(a) (i) Full Name of Applicant	
	(ii) Address of applicant	
	(iii) e-mail ID	
	(iv) Contact / Mobile No.	
	(i) Name and address of Architect / licensed Engineer / Supervisor.	
	(ii) No. and date of issue of License	
2.	(a) Is the plot of, a City Triangulation Survey Number, Revenue Survey Number or Hissa Number of a Survey Number or a Final Plot Number of a Town Planning Scheme or a plot of an approved layout ?	
	(b) Please state Sanction Number and Date of Sub-division / Layout.	
	(c) Whether the land is situated in Congested Area (Core Area) or Outside Congested Area ?	
3.	(a) What is the total area of the plot according to the i) Ownership document ? ii) Measurement plan ?	
	(b) Does it tally with the Revenue / CTS Record ?	Yes / No
	(c) What is the actual area available on site measured by Architect / licensed Engineer / Supervisor ? (The permission shall be based on the area whichever is minimum.)	
	(d) Minimum area of 3(a)(i), (ii) and 3 (c) above	
	(e) Is there any deduction in the original area of the plot on account of i) D.P. Roads, or ii) Reservation(s) If so, are they correctly marked on the site plan ? Please state the total area of such deductions ?	Yes / No Area ----- Yes / No Area ----- Yes / No Total Area -----
	(f) Is there any water stream in the land? State the area of such land.	Yes / No Area -----
	(g) What is the area remained for development after above deduction(s) ?	Area -----
	(h) What is the area proposed for recreational open space ?	Area ----- Sq.m.
	(i) i) Whether amenity space as required under Regulation No.3.5 is left ? OR ii) Whether amenity space as required under Regulation No.4.8.1 is left ? (applicable in case of I to R provision)	Yes / No Area ----- Yes / No Area -----
	(j) What is the net plot area as per Regulation No.3.9 ? (excluding (i) above)	Area -----

4.	Are all plans as required under Regulation No.2.2 enclosed ?	Yes / No
5.	(a) In what zone does the plot fall ?	
	(b) For what purpose the building is proposed ? Is it permissible according to the land use classification ?	----- Yes / No
6.	(a) Is road available as an approach to the land ? What is the average existing width of the road ? (If the plot abuts on two or more roads, the above information in respect of all roads should be given)	Yes / No Existing Width -----
	(b) Is the land fronting on D.P. road ? If so, width of the D.P. road	Yes / No Width -----
	(c) Is the land fronting on National or State highway ? If so, is the Building line / control line maintained ? Please state the distance.	
	(c) What is the height of the building above the average ground level of the plot ?	Height -----
	(d) Is it within permissible limit of height specified in Regulation No. ⁽¹⁾ 6.10 ?	Yes / No
	(e) Is height approved by Chief Fire Officer / Director of Fire Services, M.S. ? (In case of ⁽¹⁾ Special Buildings mentioned in Regulation Number 1.3.93(xiv))	Yes / No
7.	Is the land subject to restrictions of blue / red flood line, airport, railway, electric line, land fill sites, archaeology, etc. ? Please state the details along with 'No objection certificate', if any.	Yes / No -----
8.	(a) If there are existing structures on the plot	Yes / No
	(i) Are they correctly marked and numbered on the site plan ?	Yes / No
	(ii) Are those proposed to be demolished immediately and hatched in yellow colour ?	Yes / No
	(iii) What is the plinth area and total floor area of all existing structures to be retained ? (Please give details confirming to the plan submitted)	
9.	(a) Please state the total built up area on the basis of outer line of construction (including balconies, double height terraces and deducting voids) (existing + proposed)	
	(b) What is the basic permissible F.S.I. of the zone according to front road width ?	
	(c) What is the premium FSI proposed to be utilised ?	
	(d) What is the area of TDR proposed to be utilised ?	
	(e) What is the additional FSI proposed to be utilised ?	
	(f) Please state the overall F.S.I. utilised in the proposal ?	
	(g) Is carpet area of each apartment mentioned on the plan ?	

⁽¹⁾ Substituted vide Corrigendum / Addendum No. CR 121/21, dt. 02nd December, 2021.

10.	Whether area for inclusive housing is required as per Regulation No.3.8 ? Please state the details.			
11.	(a) What is the width of the front marginal distance(s) ? If the building abuts two or more roads, does the front marginal distance comply with Regulation ?			
13.	(a) What is :	Permissible	Proposed	
	(i) the front set-back(s) ?			
	(ii) the side marginal distance(s) ?			
	(iii) the rear marginal distance(s) ?			
	(vi) the distance between buildings ?			
14.	(a) What are the dimensions of the inner or outer chowk ?			
	(b) Is / are room(s) dependent for its light and ventilation on the chowk ? If so, are the dimensions of the chowk as required ?			
15.	(a) Whether use of every room / part mentioned on the plan ?			
	(b) Whether every room derives light and ventilation required under the regulations ?			
16.	If the height of the building is more than 15 meter above the average ground level, is provision for lifts made ?			
	(a) If so, give details of lift.	Passenger Capacity	No. of Lifts	
	(b) Details of Fire Lift.	Passenger Capacity	No. of Lifts	
17.	(a) Does the building fall under purview of Special Building Regulation No.2.2.8 ?			
	(b) If so, is fire escape staircase provided in addition to regular staircase?	Yes / No		
	(c) Whether the ramps to the basement are provided leaving 6.0 m. marginal distance for movement of fire fighting vehicle ?	Yes / No.		
	(d) If podiums are proposed, does it allow the movement of fire fighting vehicle properly ?	Yes / No.		
18.	(a) What are the requirements of parking spaces under the Regulation No.8.0 ? How many are proposed ?		Required	Proposed
		Car		
		Scooter		
	(b) (i)			
	(ii) If so, what is the requirement ?			
	(iii) How many are proposed ?			
19.	Is the sanitary arrangement provided as per the regulation ?			
20.	Details of the source of water to be used in the construction ?			
21.	Distance from the sewer line. (if sewerage system is available)			

22.	Please explain in detail in what respect the proposal does not comply with the Unified Development Control and Promotion Regulations and the reasons there for, attaching a separate sheet if necessary.	
	I hereby declare that I am the Architect / licensed Engineer / Supervisor employed for the proposed work and that the statements made in this form are true and correct to the best of my knowledge.	
	Date : / /	Signature of the Architect / licensed Engineer / Supervisor employed.

Form of Statement 1 (to be printed on plan) [Sr.No.8(a)(iii)] Existing Building to be retained				
Existing Building No.	Floor No.	Plinth Area	Total Floor Area of Existing Building	Use / Occupancy of Floors.
(1)	(2)	(3)	(4)	(5)

Form of Statement 2 (to be printed on plan) [Sr.No.9(a)] Proposed Building		
Building No.	Floor No.	Total Built-up Area of floor, as per outer construction line.
(1)	(2)	(3)
	Total	

Form of Statement 3 (to be printed on plan) [Sr.No.9(g)] Area details of Apartment					
Building No.	Floor No.	Apartment No.	Carpet area of apartment	Area of Balcony attached to Apartment	Area of Double height terraces attached to flat.
1	2	3	4	5	6
Note : Above statements may vary, wherever required.					

Proforma - I : Area Statement (At Right Hand top Corner of Plans)	
PROPOSED ----- COMPLEX ON C.T.S. NO. / PLOT NO. / S.NO. / GAT NO. / F.P.NO. ----- OF VILLAGE MAUJE -----	Drawing Sheet No.: X / Y
Stamps of Approval of Plans :	
AREA STATEMENT	
1. Area of plot <i>(Minimum area of a, b, c to be considered)</i>	
(a) As per ownership document (7/12, CTS extract)	
(b) as per measurement sheet	
(c) as per site	
2. Deductions for	
(a) Proposed D.P. / D.P. Road widening Area / Service Road / Highway widening	
(b) Any D.P. Reservation area	
(Total a + b)	
3. Balance area of plot (1 - 2)	
4. Amenity Space (if applicable)	
(a) Required -	
(b) Adjustment of 2(b), if any -	
(c) Balance Proposed -	
5. Net PlotArea (3 - 4(c))	
6. Recreational Open space (if applicable)	
(a) Required -	
(b) Proposed -	
7. Internal Road area	
8. Platable area (if applicable)	
9. Built up area with reference to Basic F.S.I. as per front road width <i>(Sr.No.5 x basic FSI)</i>	
10. Addition of FSI on payment of premium	
(a) Maximum permissible premium FSI - based on road width / TOD Zone.	
(b) Proposed FSI on payment of premium.	
11. In-situ FSI / TDR loading	
(a) In-situ area against D.P. road $[2.0 \times \text{Sr.No.2(a)}]$, if any	

(b) In-situ area against Amenity Space if handed over [2.00 or 1.85 x Sr.No.4(b) and /or (c)],						
(c) TDR area						
(d) Total in-situ / TDR loading proposed (11 (a) + (b) + (c))						
12. Additional FSI area under Chapter No.7						
13. Total entitlement of FSI in the proposal						
(a) [9 + 10(b) + 11(d)] or 12 whichever is applicable.						
(b) Ancillary Area FSI upto 60% or 80% with payment of charges.						
(c) Total entitlement (a + b)						
14. Maximum utilization limit of F.S.I. (building potential) Permissible as per Road width {(as per Regulation No.6.1 or 6.2 or 6.3 or 6.4 as applicable) x 1.6 or 1.8}						
15. Total Built-up Area in proposal.(excluding area at Sr.No.17 b)						
(a) Existing Built-up Area.						
(b) Proposed Built-up Area (as per 'P-line')						
(c) Total (a + b)						
16. F.S.I. Consumed (15 / 13) (should not be more than serial No.14 above.)						
17. Area for Inclusive Housing, if any						
(a) Required (20% of Sr.No.5)						
(b) Proposed						
Certificate of Area: Certified that the plot under reference was surveyed by me on _____ and the dimensions of sides etc. of plot stated on plan are as measured on site and the area so worked out tallies with the area stated in document of Ownership / T.P. Scheme Records / Land Records Department / City Survey records. Signature (Name of Architect / Licensed Engineer / Supervisor.)						
Owner's Declaration – I / We undersigned hereby confirm that I / We would abide by plans approved by Authority / Collector. I / We would execute the structure as per approved plans. Also I / We would execute the work under supervision of proper technical person so as to ensure the quality and safety at the work site. Owner(s) name and signature						
Architect / Licensed Engineer / Supervisor name and signature						
Job No.	Drawing No.	Scale	Drawn by	Checked by	Registration No. of Architect / License no. of Licensed Engineer / Supervisor	

APPENDIX A - 2 : FORM FOR SUB-DIVISION OF LAND AS PLOTTED LAYOUT

Application for permission for development under Section 18 / 44 / 58 / 69 of The Maharashtra Regional and Town Planning Act, 1966 read with any other Act governing the Planning Authority, if any.*

From _____ (Name of the owner)

To,
The Authority, (Name of the Authority.)

Sir,

I intend to carry out the under mentioned development in the site/plot of land, bearing S.No. / Gat No. / City Survey No. / Final Plot No., Mouje, situated at Road / Street in accordance with Section 18 / 44 / 58 / 69 of The Maharashtra Regional and Town Planning Act, 1966 read with Section (*)----- of ----- Act.

I forward herewith the following plans and statements (Item 1 to 7), wherever applicable, in quadruplicate, signed by me (Name in block letters) and the Architect / Licensed Engineer / Supervisor (Registration / License No.....), who has been engaged by me and has prepared the plans, designs and a copy of other statements / documents as applicable.

- (1) Key Plan (Location Plan); (to be shown on first copy of the set of plans)
- (2) Site Plan showing the surrounding land and existing access to the land included in the layout;(to be shown on first copy of the set of plans)
- (3) A layout plan showing,
 - (i) sub-divisions of the land or plot with dimensions and area of each of the proposed sub-divisions and its use according to prescribed regulations;
 - (ii) width of the proposed streets; and
 - (iii) dimensions and area of recreational open spaces provided in the layout.
 - (iv) dimensions and area of amenity space provided in the layout.
- (4) An extract of record of rights, property register card (any other document showing ownership of land to be specified)
- (5) In case of revised permission, document of consent as per Regulation No.2.2.3(v).
- (6) Particulars of development in Form enclosed.
- (7) Attested copy of Receipt for payment of scrutiny fees.

(8) No Objection Certificate, wherever required. I request that the proposed Sub-division / layout may please be approved and permission accorded to me to execute the work.

Signature of Owner

Name of Owner

Address of Owner

Contact No.

Dated:

CERTIFICATE

The above mentioned Plans are prepared by me as per UDCPR.

Signature of the Architect / Licensed
Engineer / Supervisor.

Name

License No.

Contact No.

Dated

(*) Name of the Act of the Planning Authority, if any, be mentioned.

Form giving Particulars of Development

(Part of Appendix A - 2, Item 6)

1.	(a) (i) Full Name of Applicant	
	(ii) Address of applicant	
	(iii) e-mail ID	
	(iv) Mobile No.	
	(b) (i) Name and address of Architect / licensed Engineer / Supervisor employed.	
	(ii) No. and date of issue of License (Registration No. in case of Architect.)	
2.	(a) Is the plot of, a City Triangulation Survey Number, Revenue Survey Number or Hissa Number of a Survey Number or a Final Plot Number of a Town Planning Scheme ?	Yes / No. -----
	(b) Whether the land is situated in Congested (core) Area or outside Congested Area ?	Yes / No.
3.	(a) What is the total area of the plot according to the ownership document and measurement plan ?	Area -----
	(b) Does it tally with the Revenue / CTS Record	Yes / No.
	(c) What is the actual area available on site measured by Architect / licensed Engineer / Supervisor ? (The permission shall be based on the area whichever is minimum.)	Area -----
	(d) Is there any deduction in the original area of the plot on account of D.P. Roads or reservation(s). If so, are they correctly marked on the site plan ? Please state the total area of such deductions ?	Yes / No. D.P. Road / widening Area ----- Reservation Area -----
	(e) Is there any water stream in the land? State the area of such land and state whether it is excluded ?	Yes / No. Area -----
	(e) What is the area remained for development after above deduction(s) ?	Area -----
	(f) What is the area proposed for recreational open space ? (For minimum original holding as mentioned in Regulation No.3.4)	Area -----
	(g) Whether amenity space as required under Regulation No.3.5 is left? Please mention the area.	Yes / No. Area -----
	(h) What is the net plot area as per Regulation No.3.9 ?	Area -----
4.	Are all plans as required under Regulation No.2.2 enclosed ?	Yes / No.

5.	(a) In what zone does the plot / land fall ?	
	(b) For what purpose the layout is proposed ? Is it permissible according to the land use classification ?	
6.	(a) Is road available as an approach to the land ? What is the average existing width of the road ? (If the plot abuts on two or more roads, the above information in respect of all roads should be given)	Yes / No. Width -----m.
	(b) Is the land fronting on D.P. road ? If so, width of the D.P. road	Yes / No. Width -----m.
	(c) Is the land fronting on National or State highway ? If so, is the Building line / control line maintained ? Please state the distance.	Yes / No. -----
7.	Is the land subject to restrictions of blue / red flood line, airport, railway, electric line, land fill sites, archaeology, etc. ? Please state the details along with 'No objection certificate', if any.	Yes / No.
8.	Whether the internal roads proposed in the layout conform to the Regulation No.3.3 ?	Yes / No.
9.	Whether roads in the layout are co-ordinated with the roads in the surrounding layout ?	Yes / No.
10.	Whether the area and dimensions of plots are proposed as per prescribed regulations ?	Yes / No.
11.	Whether area for inclusive housing is required as per Regulation No.3.8 ? Please state the details.	Yes / No.

I hereby declare that I am the Architect / Licensed Engineer / Supervisor employed for the proposed work and that the statements made in this form are true and correct to the best of my knowledge.

Date : / /

Signature of the
Architect / Licensed
Engineer / Supervisor
employed.

Proforma - I : Area Statement

(At Right Hand top Corner of Plans)

Proposed ----- Layout on C.T.S. No. / Plot No. / S.No. / Gat. Drawing Sheet
No. / F.P.No. ----- of Village Mauje ----- No.: X / Y

Stamps of Approval of Plans :

Area Statement	
Area of Plot (<i>Minimum area of a, b, c to be considered</i>)	
a) As per ownership document (7/12, CTS extract)	
b) as per measurement sheet	
(c) as per site	
2. Deductions for	
(a) Proposed D.P. / D.P. Road widening Area / Service Road / Highway widening	
(b) Any D.P. Reservation area	
(Total a + b)	
3. Balance area of plot (1 - 2)	
4. Amenity Space (if applicable)	
(a) Required -	
(b) Adjustment of 2(b), if any -	
(c) Balance Proposed -	
5. Net Plot Area (3 - 4(c))	
6. Recreational Open space (if applicable)	
(a) Required -	
(b) Proposed -	
7. Internal Road area	
8. Service road and Highway widening	
9. Platable area	
10. Pro-rata factor for FSI calculation on layout plots = (5 / 9)	
11. Area for inclusive housing	
(a) Required -	
(b) Proposed -	
Certificate of Area : Certified that the plot under reference was surveyed by me on _____ and the dimensions of sides etc. of plot stated on plan are as measured on site and the area so worked out tallies with the area stated in document of Ownership / T.P. Scheme Records / Land Records Department / City Survey records.	

Area Statement**Signature**

(Name of Architect / Licensed Engineer / Supervisor.)

Owner(s) name and signature**Architect / Licensed Engineer / Supervisor name and signature****Statement of distribution of FSI on each plot**

(to be printed at suitable place on plan)

Plot No.	Plot area (Sq.m.)	Corner Rounding area of Road (if any) (Sq.m.)	Remaining Plot area (b-c) (Sq.m.)	Pro-Rata FSI factor	Built up area on pro-rata basis i.e. (d x e) *	Front Road width (m.)	Basic FSI	Permissible Built-up area on Basic FSI ⁽¹⁾ (f x h) (Sq.m.)
(a)	(b)	(c)	(d)	(e)	(f)	(g)	(h)	(i)

* This factor may not be applied in case of individual plot, if quantum of FSI to be apportioned on various plots is varied. In such case, column (e) shall read as "quantum of pro-rata FSI to be utilised" and total of this column shall be equal to or less than the quantum at Sr. No.5.

⁽¹⁾ Substituted vide Corrigendum / Addendum No. CR 121/21, dt. 02nd December, 2021.

APPENDIX 'B' : FORM FOR SUPERVISION

To,
The Authority
(Name of the Authority)
Sir,

I hereby certify that the development/erection/re-erection/demolition or material alteration in / or Building No. _____ on / in Plot No. _____ in Block No. _____ situated at Road / street _____ Revenue S.No. / Gat No. / Khasara No. / City Survey No. / Final Plot No. shall be carried out under my supervision and I certify that all the materials (types and grade) and the workmanship of the work shall be generally in accordance with the general specifications and that the work shall be carried out according to the sanctioned plans. I shall be responsible for the execution of the work in all respects.

Date : _____ Signature and name of the Architect or Licensed Engineer / Site Engineer / Supervisor. *
Registration / License No. _____

* Strike out whichever is not applicable.

CERTIFICATE

** I hereby certify that the structural drawings for the above mentioned work are prepared by me / us and ⁽¹⁾ the work, as far as structural drawings are concerned, shall be carried ⁽¹⁾ out as specified in Appendix 'C'. I shall be responsible for the ⁽¹⁾ adequacy of the Structural Designs far as structural drawings are concerned.

Signature and name of the Structural Engineer / Architect / Licensed Engineer. ***
Registration / License No. _____
Date : _____

** Wherever applicable.

*** Strikeout whichever is not applicable.

⁽¹⁾ **CERTIFICATE**

⁽¹⁾ ** I hereby certify that the work of structural elements for the above mentioned work shall be carried under my supervision as per the above mentioned structural drawings after due verification by concerned Structural Engineer. I shall be responsible for the execution of the work, quality of material used and quality of workmanship as per the above mentioned Structural Design and structural drawings.

Date : _____ Signature and name of the Architect or Licensed Engineer / Site Engineer / Supervisor. *
Registration / License No. _____

** Wherever applicable.

* Strikeout whichever is not applicable.

⁽¹⁾ Substituted vide Corrigendum / Addendum CR 121/21, dt. 02nd December, 2021.

APPENDIX – C

QUALIFICATION, COMPETENCE, DUTIES AND RESPONSIBILITIES ETC. OF LICENSED TECHNICAL PERSONNEL OR ARCHITECT FOR DEVELOPMENT PERMISSION AND SUPERVISION

C-1 GENERAL

- C-1.1** The qualifications of the technical personnel and their competence to carry out different jobs for development permission and supervision for the purpose of licensing by the Authority shall be as given in Regulation No.C-2 to C-6. The procedure for licensing the technical personnel is given in Regulation No.C-7. In the event, the services of the technical personal is discontinued by the owner / developer or such technical personal resigns from the services, he shall forthwith intimate to the authority and owner / developer shall immediately appoint another technical person on the project.

C-2 ARCHITECT

C-2.1 Qualifications -

The minimum qualifications for an architect shall be the qualifications as provided in the Architects Act, 1972 and should be registered with the Council of Architecture with valid membership. Such registered Architects shall not be required to again register their names with the Authority. However, he shall submit the registration certificate to the Authority.

C-2.2 Competence of Architect -

To carry out work related to development permission as given below and shall be entitled to submit -

- i) All plans and technical information connected with designs and plans of development permission.
- ii) Structural details and calculations for building on plot up to 500 Sq.m. and up to 3 storeys or 11.0 m. height and
- iii) Certificate of architectural supervision and completion for all buildings.

C-2.3 Duties and Responsibilities

- i) Design as per Client's requirements and site conditions.
- ii) Prepare and submit plans as per the Regulations and shall be responsible for correctness of the calculations and dimensions mentioned on the plan and shall be liable for consequences arising thereof.
- iii) Represent before the Authority for scrutiny of drawings.
- iv) Prepare and issue working drawings details in conformity with approved plans.
- v) Advise client to appoint Site Engineer / Supervisor, in case he himself is not undertaking the supervision work.
- vi) Inform Authority about Commencement of work on site.
- vii) To verify the work at obligatory stages of plinth completion, completion of RCC structure and superstructure completion to ensure work progress in conformity of approved drawings and dimensions.
- viii) Inform Authority about reaching relevant stage of work where stage-wise approval from the authority is required.
- ix) Issue completion / part completion certificate for submission to the authority.

- x) Inform in writing to the Authority in case of violation by Client during the period of appointment
- xi) To assist and co-operate with the Authority and other officers in carrying out and enforcing the provisions of Maharashtra Regional and Town Planning Act, 1966 and of any regulations for the time being in force under the same.
- xii) The above mentioned Architect's scope and responsibilities shall be similarly applicable for Landscape / Heritage & Conservation Consultant, if any.

C-3 ENGINEER

C-3.1 Qualifications -

- i) The qualifications for Licensing Engineer shall be the corporate membership (Civil) of the Institution of Engineers or such Degree or Diploma in Civil or Structural Engineering or equivalent; **or**
- ii) Diploma in Civil Engineering or Diploma in Architectural Assistance ship or equivalent qualification, having experience of 10 years in the field of land and building planning.

C-3.2 Competence -

To carry out work related to development permission as given below and shall be entitled to submit-

- i) All plans and related information connected with development permission.
- ii) Structural details and calculations for building on plot up to 500 Sq.m. and up to 3 storeys or 11.0 m. height, and
- iii) Certificate of supervision and completion for all buildings.

C-3.3 Duties and Responsibilities -

Duties and Responsibilities of the Engineer shall be as mentioned in C-2.3 above within the competency mentioned in Clause - C-3.2.

C-4 STRUCTURAL ENGINEER

C-4.1 Qualifications -

- i) Graduate in Civil Engineering of recognised Indian or Foreign University and Chartered Engineer or Associated Member in Civil Engineering Division of Institution of Engineers (India) or equivalent Overseas Institution with minimum 3 years of experience of structural engineering practice in designing and related field work; **or**
- ii) Post graduate degree in structural engineering with 2 years' experience; **or**
- iii) Doctorate in structural engineering with 1 year experience.

C-4.2 Competence -

The structural engineer shall be competent.

- i) To prepare the structural design, calculations and details of all buildings and carry out verification of reinforcement as per stages of work.
- ii) To carry out structural audit / structural condition survey of the existing / old buildings.

C-4.3 Duties and Responsibilities of Structural Engineer

- i) All structural layouts and structural design related with plan and development on the basis of details received from architect / owner / builder / developer / geo technical consultant.

- ii) Wherever required, structural engineer shall avail the services / advice of Geotechnical Engineer.
- iii) Provide lists of tests to be carried out at each stage of work and allow the further work only after satisfying with the same.
- iv) To verify the structural elements in compliance with structural drawings.
- v) To document the site visit report mentioning therein the deviation / lapses, if any, in respect of structural elements designed by him and inform the same to the site engineer, owner / developer, architect / licensed personnel for rectification required.
- vi) He shall be responsible for the adequacy of the structural design in compliance with BIS code and plans received from architect / owner / builder / developer.
- vii) The structural engineer will advise owner / builder / developer to appoint formwork co-coordinator (FWC) and same shall be employed by the owner / builder / developer for the project.
- viii) Certificate of structural design adequacy at the time of completion ⁽¹⁾ shall be in the following format :-

⁽¹⁾ **PRAPTRA -1**

CERTIFICATE AS PER APPENDIX C-4.3(viii)

Structural Design Adequacy

(to be submitted at the time of completion)

To,

The Authority

(Name of the Authority)

Sir,

I / we have been appointed as Structural Engineer by M/s. ----- for preparing the structural design and drawings for the New structure consisting of ----- floors, construction of ----- additional floors over existing structure with ----- floors, as described in my enclosed Design base report, based on the Architectural drawings and other utilities and services requirements given by the Owner / Developer of the development work of building in Plot No. _____ in Block No. _____ situated at Road / street _____ Revenue S.No. / Gat No. / Khasara No. / City Survey No. / Final Plot No., Tal. -----, District -----.

The following listed firms / persons are associated with the work as appointed by M/s. -----.

Architect : -----

Owner / Developer :-----

Licensing Engineer :-----

Site Engineer :-----

I / we hereby certify and confirm adequacy of the structural design for intended use represented through my structural drawing issued from time to time.

I / we further confirm that the structural design structural drawings and details of the building which has been done by me/us, satisfy the structural safety requirements for all situations including natural disasters, as applicable, as stipulated in National Building Code of India and its Part 6 - Structural Design and other relevant Codes, considering the report of Subsurface investigations, where applicable.

⁽¹⁾ Inserted vide Corrigendum / Addendum No. CR 121/21, dt. 02nd December, 2021.

⁽¹⁾ I / we enclosing herewith undertaking of Site Engineer / licensed Engineer, Owner regarding compliance with structural drawings and adherence to standard construction practices while executing the construction work.

On the basis of this I / we hereby certify that to the best of my Knowledge and belief the said structure is structurally fit for the intended purpose.

As a Structural Engineer for design my responsibilities are limited to providing structural design structural drawings and details in accordance with the provisions of relevant prevailing Indian Standard codes, and visits to site at specified stages called for by the Supervising Structural Engineer / Supervising Engineer / site Engineer for verification of reinforcement laid. All issues related to Supervision, Materials, Workmanship and execution are the sole responsibility of the Supervising Structural Engineer/Supervising Engineer / site Engineer. Visit made by me as Structural Engineer are not for Supervision since, I / we are not responsible for supervision and quality of work. This certificate is issued on the clear understanding that my overall design responsibility for safe and proper performance of structural design ceases, the moment any addition and / or alteration or any damage to the structural frame is caused by accident or by tampering with the geometrical sections of structural members for any purpose whatsoever or due to overloading of the structure or lack of maintenance or any act that is detrimental to the structure as a whole.

This certificate is issued in conjunction with the certificate of the licensed Engineer and owner certifying the quality of work.

Enclosure -

- 1)
- 2)
- 3)

Date :

Signature and name of the Licensed Structural Engineer

Registration / License No.

C-5 SUPERVISOR

C-5.1 Qualification

(a) For Supervisor - 1 :-

- i) Three years architectural assistantship or intermediate in architecture with two years experience, or
- ii) Diploma in Civil engineering or equivalent qualifications with two years experience, or
- iii) Draftsman in Civil Engineering from ITI or equivalent qualifications with Ten years experience out of which five year shall be under Architect / Engineer.

(b) For Supervisor - 2 :-

- i) Draftsman in Civil Engineering from ITI or equivalent qualifications with five years experience under Architect / Engineer.

C-5.2 Competence

(a) For Supervisor - 1 : He shall be entitled to submit -

- i) All plans and related information connected with development permission on plot up to 500 sq.m.; and
- ii) Certificate of supervision of buildings on plot up to 500 Sq.m. and completion thereof.

⁽¹⁾ Inserted vide Corrigendum / Addendum No. CR 121/21, dt. 02nd December, 2021.

(b) For Supervisor - 2 : He shall be entitled to submit -

- i) All Plans and related information up to 200 sq.m. built up area, and
- ii) Certificate of supervision for limits at (i) above and completion thereof.

C-5.3 Duties and Responsibilities

Duties and Responsibility of the Engineer shall be as mentioned in C-2.3 above within the competency mentioned in Clause C-5.2.

C-6 TOWN PLANNER**C-6.1 Qualification**

Graduate or Post-graduate degree in Town and country planning, urban planning, planning, regional planning or equivalent.

C-6.2 Competence

- i) All plans and related information connected with development permission.
- ii) Issuing certificates of supervision for development of all lands.

C-6.3 Duties and Responsibilities

- i) Design as per Client's requirements and site conditions.
- ii) Prepare and submit plans as per the Regulations and shall be responsible for correctness of the calculations and dimensions mentioned on the plan and shall be liable for consequences arising thereof.
- iii) Represent before the Authority for scrutiny of drawings.
- iv) Advise client to appoint Site Engineer / Supervisor, in case he himself is not undertaking the supervision work.
- v) Inform Authority about Commencement of work on site.
- vi) Inform Authority about reaching relevant stage of work where stage-wise approval from the authority is required.
- vii) Inform in writing to the Authority in case of violation by Client during the period of appointment.
- viii) To assist and co-operate with the Authority and other officers in carrying out and enforcing the provisions of Maharashtra Regional and Town Planning Act, 1966 and of any regulations for the time being in force under the same.

C-7 LICENSING**C-7.1 ⁽⁺⁾ Technical Personnel to be licensed :-**

The Qualified technical personnel or group as given in regulations No.⁽¹⁾ (--) C-3, C-4, C-5, C-6 shall be licensed with the Authority or ⁽¹⁾ Directorate Office of Town Planning Department and the license shall be valid for three calendar years ending 31st December after which it shall be renewed every three years. The technical person registered with the Authority shall be entitled to work within Authority's jurisdiction and those registered with ⁽¹⁾ Directorate Office shall be entitled to work within jurisdiction of all Authorities as well as regional plan area ⁽¹⁾ (--).

^(#) Fees for Licensing - The annual licensing fees shall be as follows :-

C-7.2	For Engineer, Structural Engineer and Town Planner.	Rs.3000/- For three years.
	For Supervisor (1) and For Supervisor (2)	Rs.1500/- For three years. .

These fees shall be increased by 10% for every three years.

⁽¹⁾ Substituted / deleted vide Corrigendum / Addendum No. CR 121/21, dt. 02nd December, 2021.

⁽⁺⁾ Order issued by Director of Town Planning vide Order No. 5729, dt., 8th December, 2021.

^(#) Clarification issued vide Order No. CR 236/18 (Part 2), dt. 23rd December, 2021.

C-8 DUTIES AND RESPONSIBILITIES OF OTHER TECHNICAL PERSONS / OWNER**C-8.1 SITE ENGINEER****C- Qualifications :**

- 8.1.1** The “Site Engineer” must hold a minimum diploma in Civil / Construction Engineering / Construction Management or any other equivalent qualification in the field of Civil Engineering.

C- Duties and Responsibilities :

- 8.1.2**
- i) To carry out day to day supervision in order to ensure that the work on site is carried out in accordance with the development permissions, approved plans, drawings given by Licensed personnel / Architect of the project, structural drawings given by structural engineer.
 - ii) Enforce construction methodology; Ensure the quality of work as per the specifications and keep site records.
 - iii) To make necessary arrangement for the temporary structures / formwork / shuttering required for the execution of the building as per the design and drawing with the help of owner / developer.
 - iv) To organise the all activities related to construction and development in coordination with Architect / Engineer / Structural Engineer and Owner / Developer.
 - v) To take necessary measures to ensure the safety of workers on site.

C-8.2 GEOTECHNICAL ENGINEER**C- Qualifications :**

- 8.2.1**
- i) Graduate in civil engineering or geotechnical engineering or Member of Civil Engineering Division of Institution of Engineers (India), and with minimum 3 year experience in geotechnical engineering practice in designing and field work, **or**
 - ii) Post graduate in civil engineering or geotechnical engineering with minimum 2 year experience in geotechnical engineering practice in designing and field work **or**
 - iii) Doctorate in civil engineering or geotechnical engineering with minimum 1 year experience in geotechnical engineering practice in designing and field work.

C- Duties and Responsibilities of Geotechnical Engineer :

- 8.2.2**
- i) Geotechnical investigation by exploring necessary field tests and visual inspection, taking samples and testing in certified / authorized Laboratory.
 - ii) Prepare the Geotechnical Report certifying the Geotechnical conditions, advise on safe bearing capacity, required depth for foundation, stability of excavated slopes and safety of the adjoining structures to the Structural Engineer by considering all relevant affecting / governing aspects.
 - iii) Certify the strata and sub soil conditions before laying the foundation.

C-8.3 OWNER / DEVELOPER**C- Duties and Responsibilities.**

- 8.3.1**
- i) The applicant owner / developer shall be responsible for title of the property.
 - ii) The applicant owner / developer shall be responsible for truthfulness and validity of orders, NOCs, certificates obtained by him.
 - iii) Communicate with the consultants on reaching various stages of work in order to facilitate them to get clearances for further action.
 - iv) Appoint professional / consultant / supervisors / site engineer / technical personnel / staff required for carrying out the work.

- v) Provide necessary resources as may be required by the professionals / consultants / supervisors / technical personnel / Staff.
- vi) Commence work at various stages only after obtaining required approval to the plans from the Authority or clearances under the law.
- vii) To comply with any instructions, directions and orders by any Statutory Authority.
- viii) Ensure that no work in violations of the sanctioned plan is carried out at any stage of the work and even after Occupation certificate is obtained.
- ix) To ensure overall safety during construction by engaging various technical persons, site engineer, formwork coordinator etc.

C-8.4 DUTIES AND RESPONSIBILITIES OF THE OFFICERS OF THE AUTHORITY

In addition to the duties and responsibilities assigned to the post of the officers of the Authority dealing with the development permission, following duties shall also be performed.

- i) The application of development permission shall be scrutinised and shall be disposed off within the time limit specified in the Act / DCPR or Right to Services Act.
- ii) The concerned officer shall make site inspection/s as and when required.
- iii) If any complaint is received in respect of any on-going work for which development permission has been granted, he should take the cognizance of the said complaint and do the needful within 15 days.
- iv) On receipt of complaint, the officer of the Authority shall investigate thoroughly and do the needful as per provisions of law and regulations. He shall not act arbitrarily on complaint and issue stop work notice to on-going work.

C-8.5 TECHNICAL FACT FINDING COMMITTEE

In case of any accident at site during construction on account of failure of any component of building / structure, the reason for the same shall be ascertained by the following technical fact finding committee.

Committee for Planning Authority Area		
Sr. No.	Members	Post
1	Collector of the concerned District	Chairman
2	Deputy Commissioner of Police or Police Officer of the equivalent rank.	Member
3	Assistant Director of Town Planning of the District.	Member
4	Superintending Engineer of P.W.D. (Building Design Division) of the State.	Member
5	Chief Fire Officer of the concerned Authority. In absence of such officer at the Authority, representative of Director of Fire Services, Maharashtra State.	Member
6	Representative of Labour Commissioner not below the rank of Class-A officer.	Member
7	Representative of Indian Society of Structural Engineers of local / nearby centre.	Member
8	Representative of Indian Institute of Architects of local / nearby centre.	Member.
9	Representative of CREDAI of the concerned district / city.	Member.
10	In-charge Officer of the department of the concerned Authority, granting the development permission.	Member Secretary.

Committee for Regional Plan Area		
Sr. No.	Members	Post
1	Divisional Commissioner of the Concerned Division.	Chairman
2	Joint Director of Town Planning of the concerned Division.	Member
3	Collector of the concerned District	Member
4	Deputy Superintendent of Police or Police Officer of the equivalent rank.	Member
5	Superintending Engineer of P.W.D. (Building Design Division) of the State.	Member
6	Representative of Director of Fire Services, Maharashtra State.	Member
7	Representative of Labour Commissioner not below the rank of Class-A officer.	Member
8	Representative of Indian Society of Structural Engineers of local / nearby centre.	Member
9	Representative of Indian Institute of Architects of local / nearby centre.	Member.
10	Representative of CREDAI of the concerned district / city.	Member.
11	Assistant Director of Town Planning / Town Planner of the concerned area.	Member Secretary.

In case of accident mentioned above, the concerned Authority shall intimate to the concerned committee along with relevant documents. The Committee shall convene the meeting of the committee immediately and shall send the report of its primary findings within 3 working days to the concerned Authority for further necessary action. The committee shall submit final report within 10 working days if detailed investigations are required. The committee shall be at liberty to take the help of experts, if required. It may give hearing to the concerned persons, if required.

_*_*_*_*_*_*

APPENDIX 'D - 1'
FORM FOR SANCTION OF BUILDING PERMISSION AND COMMENCEMENT
CERTIFICATE

To,

Sir,

With reference to your application No. _____, dated _____ for the grant of sanction of ⁽¹⁾ Building Permission Commencement Certificate under Section 18 / 44 of The Maharashtra Regional and Town Planning Act, 1966 read with Section (*)----- of ----- Act, to carry out development work / Building on Plot No. Revenue S.No. / Gat No. / Khasara No. / City Survey No. / Final Plot No. Mauje _____ situated at Road / Street _____, Society _____, the Commencement Certificate / Building Permit is granted under Section 18 / 45 of the said Act, subject to the following conditions :

1. The land vacated in consequence of the enforcement of the set-back rule shall form part of the public street in future.
2. No new building or part thereof shall be occupied or allowed to be occupied or used or permitted to be used by any person until occupancy certificate is granted.
3. The Commencement Certificate / Building permit shall remain valid for a period of one year commencing from the date of its issue ⁽¹⁾ if the work is not commenced within the valid period.
4. This permission does not entitle you to develop the land which does not vest in you.

⁽¹⁾ **Note 1** - At the time of building permission, the Planning Authority may add the necessary conditions regarding compliance of these regulations.

Note 2 - At the time of Commencement Certificate, the Planning Authority may add the necessary one or two conditions regarding compliance of the conditions of sanctioned Building Permission and these regulations.

Office No.

Office Stamp

Date :

Yours faithfully,

Authority or an officer appointed by it

(*) Name of the Act of the Planning Authority, if any, be mentioned or concerned sentence be deleted.

(Specimen of Stamp of Approval to be marked on building plan)

OFFICE OF THE **----- Building Permit No. ----- Date : -----. SANCTIONED. Signature of the Authority

** Name of the Municipal Corporation / Council / Nagar Panchayat / Collector shall be mentioned.

⁽¹⁾ Substituted / Inserted vide Corrigendum / Addendum No. CR 121/21, dt. 02nd December, 2021.

APPENDIX 'D - 2'
FORM FOR TENTATIVE APPROVAL FOR DEMARCATION OF LAND /
SUB-DIVISION LAYOUT

To,

Sir,

With reference to your application No. _____, dated _____ for the land sub-division approval, under Section 18 / 44 of The Maharashtra Regional and Town Planning Act, 1966 read with Section (*)----- of ----- Act, to carry out development work in respect of land bearing Plot No. Revenue S.No. / Gat No. / Khasara No. / City Survey No. / Final Plot No., Mauje it is to inform you that, land sub-division layout is hereby tentatively approved and recommended for demarcation, subject to the following conditions :

1. You will get the land sub-division layout demarcated on the site by the Land Records Department and submit the certified copy to that effect for final approval.
2. It shall be the responsibility of the owner to carry out all the development work including construction of roads, sewer lines, water supply lines, culverts, bridges, street lighting, etc. and hand it over to the Authority after developing them to the satisfaction of the Authority.
3. If you wish that the Authority has to carry out these development works, then you will have to deposit the estimated expenses to the Authority in advance, as decided by the Authority.
4. You will have to handover the amenity space to the Authority before approval of final layout as per Regulation No.3.5. (applicable in case where owner is not allowed to develop)
5. This permission does not entitle you to develop the land which does not vest in you.

Office No.

Yours faithfully,

Office Date

Authority or an officer appointed by it

Office Stamp

(*) Name of the Act of the Planning Authority, if any, be mentioned or concerned sentence be deleted.

(Specimen of Stamp of Approval to be marked on Layout plan)

OFFICE OF THE **----- Letter No. ----- Date : -----. LAYOUT RECOMMENDED FOR DEMARCATION. Signature of the Authority

** Name of the Municipal Corporation / Council / Nagar Panchayat / Collector shall be mentioned.

APPENDIX 'D - 3'**FORM FOR FINAL APPROVAL TO THE LAND SUB-DIVISION / LAYOUT**

To,

Sir,

With reference to your application No. _____, dated _____ for the land sub-division approval, under Section 18 / 44 / 69 of The Maharashtra Regional and Town Planning Act, 1966 read with Section (*)----- of ----- Act, to carry out development work in respect of land bearing Plot No. Revenue S.No. / Gat No. / Khasara No. / City Survey No. / Final Plot No., Mauje the land sub-division layout is finally approved as demarcated, under Section 18 / 45 / 69 of the Maharashtra Regional & Town Planning Act, 1966, subject to the following conditions :

1. It shall be the responsibility of the owner to carry out all the development work including construction of roads, sewer lines, water supply lines, culverts, bridges, street lighting, etc. and hand it over to the Planning Authority /Collector after developing them to the satisfaction of the Authority.
2. If you wish that the Planning Authority / Collector should carry out these development works, then you will have to deposit the estimated expenses to the Planning Authority /Collector in advance, as decided by the Authority.
3. As per the undertaking submitted by you in respect of recreational open space as stipulated in Regulation No.3.4, the said open space admeasuring ----- Sq.m. stand vested in the name of plot holders of the layout or society of the plot holders and you have no right of ownership or interest in the said recreational open space.
4. This permission does not entitle you to develop the land which does not vest in you.
5. -----

Yours faithfully,

Office Stamp

Authority or an officer appointed by it

(*) Name of the Act of the Planning Authority, if any, be mentioned or concerned sentence be deleted.

(Specimen of Stamp of Approval to be marked on Layout plan)

OFFICE OF THE **----- Letter No. ----- Date : ----- LAYOUT SANCTIONED Subject to conditions mentioned in the said letter. Signature of the Authority

** Name of the Municipal Corporation / Council / Nagar Panchayat / Collector shall be mentioned.

APPENDIX 'E - 1'**FORM FOR REFUSAL OF BUILDING PERMIT / COMMENCEMENT CERTIFICATE**

Office No.

Office Date

To,

Sir,

With reference to your application No. _____ dated _____ for the grant of sanction for the development work / the erection of a building / execution of work on Plot No. Revenue S.No. / Gat No. / Khasara No. / City Survey No. / Final Plot No. Mauje _____, I regret to inform you that the proposal has been refused under Section 18 / 45 / 69 of the Maharashtra Regional and Town Planning Act, 1966, on the following grounds.

- 1.
- 2.
- 3.
- 4.
- 5.
- 6.

Yours faithfully,

Office Stamp

Authority or an officer appointed by it

Note - While refusing the permission, the Authority shall mention the Regulation number, provision of which is not complied within the development proposal.

(Specimen of Stamp of rejection to be marked on building plan)

Letter No. -----

Date : -----.

REJECTED

APPENDIX 'E - 2'
FORM FOR REFUSAL OF LAND SUB-DIVISION / LAYOUT

Office No.

Date

To,

Sir,

With reference to your application No. _____ dated _____ for the grant of sanction for the development work bearing Plot No. Revenue S.No. / Gat No. / Khasara No. / City Survey No. / Final Plot No. Mauje _____, I regret to inform you that the proposal has been refused under Section 18 / 45 / 69 of the Maharashtra Regional and Town Planning Act, 1966, on the following grounds.

1. -----
2. -----
3. -----
4. -----
5. -----
6. -----

Stamp

Yours faithfully,

Authority or an officer appointed by it

Note - While refusing the permission, the Authority shall mention the Regulation number, provision of which is not complied within the development proposal.

(Specimen of Stamp of rejection to be marked on Layout plan)

Letter No. -----
 Date : -----.

REJECTED

APPENDIX 'F'**FORM FOR INTIMATION OF COMPLETION OF WORK UP TO PLINTH LEVEL***

To,

The Authority,
Planning Authority / Collector

Sir,

The construction up to plinth / column up to plinth level has been completed in Building No _____ Plot No. Revenue S.No. / Gat No. / Khasara No. / City Survey No. / Final Plot No., Mouje situated at Road / Street _____, Society _____ in accordance with your permission No. _____ dated _____ under my architectural / technical supervision and construction is carried out strictly in accordance with the sanctioned plan upto plinth level.

This is for information to you and we are proceeding further with the remaining construction work.

Yours faithfully

Signature of Architect / Licensed Engineer / Supervisor

Name : _____

(In Block Letters)` _____

Address : _____

E-mail ID: _____

Mobile No.: _____

Date: _____

APPENDIX 'G'

FORM FOR COMPLETION CERTIFICATE

To,

The Authority,
Planning Authority / Collector

Sir,

I hereby certify that the erection / re-erection or part / full development work in / on building / part building No. _____ Plot No. Revenue S.No. / Gat No. / Khasara No. / City Survey No. / Final Plot No., Mouje has been supervised by technical person and has been completed on _____ without any departures of substantial nature according to the plans sanctioned, vide office communication No. _____ dated _____. The work has been completed as per sanctioned plan. No provisions of the Act or the building Regulations, no requisitions made, conditions prescribed or orders issued thereunder have been transgressed, except * a few changes made within the internal layout of residential or commercial units, which do not violate FSI or other regulations, in the course of the work. I am enclosing three copies of the completion plans. The building is fit for occupancy for which it has been erected / re-erected or altered, constructed and enlarged.**

⁽¹⁾ All premium charges which are permitted to be paid in instalments with interest as per Regulation No.2.2.14 are fully paid.

I have to request you to arrange for the inspection & grant permission for the occupation of the building.

Yours faithfully

(Signature of Owner)

Encl : As above.

Name of Owner (in Block Letters)

Date :

Signature and name of Architect / Licensed
Engineer / Supervisor

* Wherever applicable.

** Delete whichever is not applicable.

⁽¹⁾ Inserted vide Corrigendum / Addendum No. CR 121/21, dt. 02nd December, 2021.

APPENDIX 'H'
FORM FOR FULL / PART OCCUPANCY CERTIFICATE

Office No.

Date

To,

i) Owner:

ii) Architect, Licensed Engineer , Structural Engineer / Supervisor :

Sir,

The full / part development work / erection re-erection / or alteration in of building / part building No _____ Plot No. Revenue S.No. / Gat No. / Khasara No. / City Survey No. / Final Plot No., Mouje completed under the supervision of _____ Architect / Licensed Engineer / Structural Engineer / Supervisor / License No _____ may be occupied on the following conditions.

1. -----
2. -----
3. -----
4. -----

A set of certified completion plans is returned herewith.

Encl : As above.

Office Stamp

Yours faithfully,

Authority or an officer appointed by it

(Specimen of Stamp to be marked on the plan)

OFFICE OF THE **----- Letter No. ----- Date : ----- OCCUPATION GRANTED Signature of the Authority

OFFICE OF THE **----- Letter No. ----- Date : ----- PART OCCUPATION GRANTED Signature of the Authority

** Name of the Municipal Corporation / Council / Nagar Panchayat / Collector shall be mentioned.

APPENDIX 'I'
FORM FOR REFUSAL OF OCCUPANCY CERTIFICATE

Office No.

Date

To,

i) Owner :

ii) Architect / Licensed Engineer / Structural Engineer / Supervisor

Sir,

The part / full development work / erection re-erection / or alteration in of building / part building
 No. _____ Plot No. Revenue S.No. / Gat No. / Khasara No. / City Survey
 No. / Final Plot No., Mouje completed under the supervision of
 _____ Architect, Licensed Engineer / Supervisor / License
 No. _____ is not allowed to be occupy because of the following reasons -

1. The construction carried out by you does not conform to the sanctioned plans.

2. _____

3. _____

A set of completion plan is retained with the Authority and remaining sets are regretfully returned
 herewith.

Encl : As above.

Office Stamp

Yours faithfully,

Authority or an officer appointed by him

(Specimen of Stamp of rejection to be marked on the plan)

Letter No. -----

Date : -----.

O.C. REJECTED

APPENDIX 'J'**FORM OF INDEMNITY FOR PART OCCUPANCY CERTIFICATE****(On Stamp Paper)**

(Of such value as decided by the Authority.)

To,

The Authority,

Subject:-**Sir,**

While thanking you for letting me occupy a portion of the above building before acceptance of the Completion Certificate of the whole building for the plans approved in communication No. _____, dated _____. I hereby indemnify the Authority against any risk, damage and danger which may occur to occupants and users of the said portion of the building and also undertake to take necessary security measures for their safety. This undertaking will be binding on me /us, our heirs, administrators and our assignees.

Yours faithfully,

Signature and name of Owner

Witness:

Address:

Date:

APPENDIX 'K' APPROVALS OF BUILDING PERMISSION BASED ON RISK BASED CATEGORIZATION			
Sr. No.	Parameters to be considered for Risk Base	Risk Category	
		Low Risk Category	Moderate Risk Category
1	Plot area	Building on a Plot Area upto 150 Sq.m.	Buildings on a Plot Area more than 150 Sq.m. and upto 300 Sq.m.
2	Plot status	Plot should be from sanctioned layout released for construction or regularised under Gunthewari Act, if plot is from congested area / gaothan it should have undivided original City Survey Number / original Property Card Number / Independent 7/12 abstract. (Plot should not be from un-authorised sub-division.)	Plot should be from sanctioned layout released for construction or regularised under Gunthewari Act, if plot is from congested area / gaothan it should have undivided original City Survey Number / original Property Card Number / Independent 7/12 abstract. (Plot should not be from un-authorised sub-division.)
3	Buildability of Plot	Plot should be buildable in view of the provisions in Regulation No.3.1.	Plot should be buildable in view of the provisions in Regulation No.3.1.
4	Zone in Development Plan	Residential or Commercial Zone or in a zone wherein Residential development is allowed.	Residential or Commercial Zone or in a zone wherein Residential development is allowed.
5	Type of Building	Residential or Residential with shop on ground floor.	Residential or Residential with shop on ground floor or mixed use.
6	Front, side and rear open spaces, access, parking and other requirements.	As per the provisions of UDCPR.	As per the provisions UDCPR.
7	Storeys allowed.	G. F. + 2 or Stilt + 3 floors.	G.F. + 2 or Stilt + 3 floors.
8	FSI	Construction should be within basic FSI + Premium FSI along with ancillary area FSI thereon	Construction should be within basic FSI + Premium FSI along with ancillary area FSI thereon
9	Submission of Application for approval.	Applicant shall submit the intimation letter as per Appendix K-1 along with i) Ownership document. ii) Copy of approved layout showing plot / measurement plan of plot. iii) Building plan showing periphery of construction (P-line) floor wise and details of property, FSI calculation as mentioned in Proforma-I with the signature of	Applicant shall submit the application as per UDCPR and all required document shall be certified and signed by the licensed personal. The licensed personal shall also submit the certificate stating that the proposal is strictly in accordance with the provisions of UDCPR.

		owner and licensed personal. iv) Copy of receipt of development charges including labour cess paid to Authority, if any v) The certificate of licensed personal stating that the proposal is strictly in accordance with the provisions of UDCPR. No more details shall be necessary.	
10	Issue of Commencement Certificate/ Approval.	The receipt of application along with the required documents and fees / charges mentioned in 9 above, by the authority shall be treated as permission for development.	After receipt of the application, the Demand Note regarding payment of Development Charges and other Charges based on the proposed Plans/ Drawing submitted, shall be given by the concerned Engineer of the authority within 10 days. After the receipt of payment, the Authority shall issue Commencement Certificate within 10 days from receipt of such plans without any scrutiny, solely based on the certificate of the licensed personal.
11	Plinth Checking	Plinth Checking shall not be required.	Plinth Checking shall not be required.
12	Occupation Certificate.	After completion of the work, the owner shall intimate to the Authority about the occupation of the building.	Licensed personal shall submit the completion certificate in Appendix - H to the Authority. The licensed personal shall not issue the completion certificate unless the construction is completed strictly as per plan. The Authority shall issue the occupation certificate within 10 days after site inspection.
13	Other Stipulations.	----	Any deficiency of documents or payments as per UDCPR shall amount to unauthorised construction and shall be liable for action under the provisions of the Act.
Note - The above procedure for permission shall not bar the owner to obtain development permission as per provisions of this UDCPR, if he so desires.			

APPENDIX 'K-1'
FORM FOR PERMISSION OF CONSTRUCTION OF BUILDING ON A PLOT
UPTO 150 SQ.M.

Application for permission for development under Section 18 / 44 of The Maharashtra Regional and Town Planning Act, 1966 read with any other Act governing the Planning Authority, if any.

From _____
 (Name of the owner)

To,

The Authority
 (Name of the Authority)

Sir,

I intend to carry out the under mentioned development in the site/plot of land, on Plot No.
 Revenue S.No. / Gat No. / Khasara No. / City Survey No. / Final Plot No., Mouje
situated at Road / Street Society in accordance with Section 18 / 44 of the
 Maharashtra Regional and Town Planning Act, 1966.

I forward herewith the following plans and statements, signed by me (Name in block letters)
 and the Architect / Licensed Engineer / Supervisor (License No.), who has prepared the
 plans.

- i) Key Plan (Location Plan) and Site Plan (to be shown on the plan);
- ii) A building plan showing the periphery of construction line (P-line) floor wise. No details of internal room sizes and other details including section / elevation are to be shown. The height of building shall be mentioned. Existing structure to be retained / to be demolished, if any, shall be shown;
- iii) Copy of sanctioned layout plan, if any;
- iv) An extract of record of rights, property register card (any other document showing ownership of land to be specified);
- v) Attested copy of receipt of payment of Charges; (*give details of proposed Area, FSI, Charges.*);
- vi) Copy of latest property tax receipt;

Please treat this intimation as permission for development.

Signature of Owner

Name of Owner

Address of Owner

Contact No.

Dated

The above mentioned P-line plans are prepared by me.

Signature of the Architect / Licensed Engineer / Supervisor.

Name

License No.

Contact No.

Dated

⁽¹⁾ APPENDIX – ‘K - 2’

APPROVALS OF BUILDING PERMISSION FOR CONSTRUCTION UPTO 8 ROOMS FOR AGRO TOURISM CENTER AND ALLIED ACTIVITIES AS PER TOURISM POLICY - 2016

Sr. No.	Parameters to be considered	Description	
1	Agricultural Plot area and No. of Rooms	Plot Area	No. of Rooms
		(i) Upto 0.8 ha. (ii) 0.8 ha. upto 1.6 ha. (iii) 1.6 ha. & above	(i) Max. 04 (ii) Max. 06 (iii) Max. 08 & 2 Dormitories.
2	Buildability of Plot	Plot should be buildable in view of the provisions in Regulation No.3.1 of UDCPR.	
3	Zone in Development Plan / Regional Plan	Agricultural Zone.	
4	Type of Building	Residential & Allied Amenities for Agro Tourism Centre.	
5	Front, side and rear open spaces, access, parking and other requirements.	As per the provisions of UDCPR.	
6	Storeys allowed	G.F. + 1 floor	
7	FSI	Area of rooms should be minimum 150 Sq.m. and Area of dormitories should be minimum 65 Sq.m. to 75 Sq.m. However, total construction should be within maximum FSI of 0.2 of gross plot area along with ancillary area FSI thereon.	
8	Submission of Application for approval.	Applicant shall submit the intimation letter as per appendix K - 1 of UDCPR along with – i) Ownership document. ii) Copy of measurement plan of plot. iii) Building plan showing periphery of construction (P-line) floorwise and details of property, FSI calculation as mentioned in Proforma - I with the signature of owner and licensed personal. iv) Copy of receipt of development charges including labour cess paid to Authority, if any. v) The certificate of licensed personal stating that the proposal is strictly in accordance with the provisions of UDCPR. No more details shall be necessary.	
9	Issue of Commencement Certificate / Approval.	The receipt of application along with the required documents and fees / charges mentioned in 8 above, by the authority shall be treated as permission for development.	
10	Plinth Checking	Plinth Checking shall not be required.	

11	Occupation Certificate	After completion of the work, the owner shall intimate to the Authority about the occupation of the building. ⁽¹⁾
⁽¹⁾ Note – The above procedure for permission shall not bar the owner to obtain development permission as per provisions of this UDCPR, if he so desires.		
- Notwithstanding anything mentioned above, if number of rooms exceeds 8 in Agro Tourism Centre, it shall be considered as commercial enterprises and for such proposal it shall be necessary to obtain development permission as per sanction Unified Development Control and Promotion Regulations from concerned Authorities. - All other provisions and terms / conditions mentioned in Government Resolution of Department of Tourism and Cultural Affairs No.TDS-2018/CR.514/Tourism, dated 28/09/2020 shall be applicable. ⁽¹⁾		

****_

⁽¹⁾ Inserted Vide Directives u/s 154 No. CR 04/2022 dt. 2nd June 2022.

APPENDIX - 'L'			
HERITAGE LISTCARD (TOWN & REGION)			
	Location	Pin / MH 09	Heritage listing of the city
	Photo w.r.t.Landmark (min. 4 side black and white photos)	Site photo (black and white)	Card No.
			Grade
			Zone
			Zone reference
			Geological co-ordinate
			Village / CTS / Survey / Plot No.
			Postal Address
			GTS R.L. Survey
A	Name of the Property		
i)	Name		
ii)	Historic name		
iii)	Built inAge		
B	Built Form		
i)	Number of floors		
C	Area (sq.m.)		
i)	Plot Area		
ii)	Built-up area		
D	Approach		
i)	Access		
ii)	Distance from Rly. Station		
E	Ownership		
i)	Past owner(s)		
ii)	Present owner(s)		
iii)	Lease status		
F	Uses		
i)	Past uses		
ii)	Present uses		
G	Listing criteria and reference		
i)	Historic / Archaeological Significance		

ii)	Value for architectural, historical or cultural reasons	
iii)	Architectural	
iv)	Historical	
v)	Cultural	
vi)	The date and / or period and / or design and / or unique use of the building or artefact	
vii)	Period	
viii)	Design	
ix)	Use	
x)	Relevance to social or economic history	
xi)	Association with well-known persons or events.	
xii)	A building or groups of buildings and/or areas of a distinct architectural design and / or style, historic period or way of life having sociological interest and / or community value.	
xiii)	The unique value of a building or architectural features or artefact and / or being part of a chain of architectural development that would be broken if it is lost.	
xiv)	Its value as a part of a group of buildings.	
xv)	Representing forms of technological development.	
xvi)	Vistas of natural / scenic beauty or interest, including water front areas, distinctive and / or planned lines of sight, street line, skyline or topographical features.	
xvii)	Special details related to services like sanitation, plumbing, water supply system, drainage system, electrical, wind scoops, rainwater harvesting, etc.	

xviii)	Open spaces sometimes integrally planned with their associated areas having a distinctive way of life and for which they have the potential to be areas of recreation.	
ix)	Industrial sites of historical interest	
xx)	Archaeological sites	
xxi)	Natural heritage sites	
xxii)	Sites of scenic beauty	
xxiii)	Architectural Description (As-Built drawings)	
xxiv)	Ecological Significance	
xxv)	Final grade	
xxvi)	Lister / reviewer	
H	Architectural Systems in the Structure with Images / Photos	
i)	Foundation and Plinth	
ii)	Walls	
iii)	Floor	
iv)	Roof	
v)	Openings	
vi)	Steps	
vii)	Decorative elements / Interiors	
ANNEXURE I		
Transformation over the years in		
i)	Form	
ii)	Structure	
iii)	Finishes	
ANNEXURE II		
Ecological and Environmental Features in and upto 500 m. from the Site		
i)	No. of trees	
ii)	Type of trees	
iii)	Topography	

ANNEXURE III		
A	Cultural Aspect	
i)	Folk cultural	
ii)	Social, Traditional Festivals	
B	Historical Aspect	
i)	Renewal time of form – every 5 years	
C	Present Structural Status	
i)	Structural Stability Audit every 5 years	
ii)	Maintenance Level	
D	Remarks	
i)	Conservation and Development - Methodology	
ii)	Any other Significant Aspect	

Name and Signature of Heritage
Conservationist


_*_*_*_*_

APPENDIX - 'M'


TYPICAL PLANS & CROSS SECTIONS OF ROAD

- PLAN 1 : 18M Wide
- PLAN 2 : 24M Wide
- PLAN 3 : 30M Wide
- PLAN 4 : 36M Wide
- PLAN 5 : 45M Wide
- PLAN 6 : 60M Wide












PLAN 3





CROSS SECTION

30 MTS. D.P. ROAD











PLAN 6



60 MTS. D.P. ROAD



CONSTRUCTION OF FOOTPATHS AT PROPERTY ENTRANCES



Plan A - Nallahs identified for Cycle Track in Nashik Municipal Corporation Area.



महाराष्ट्र शासन

नगर विकास विभाग

४ था मजला, मुख्य इमारत, मंत्रालय,

मादाम कामा मार्ग, हुतात्मा राजगुरु चौक, मंत्रालय, मुंबई - ४०० ०३२

दुरध्वनी क्र.०२२-२२७९४१९६

Email ID : kishor.gokhale@gov.in

क्र.टिपीएस-१८१८/प्र.क्र.२३६/१८(भाग-२)/नवि-१३

दि.१४/०१/२०२१

प्रति,

१. आयुक्त, पुणे महानगरपालिका, पुणे.
२. आयुक्त, पिंपरी-चिंचवड महानगरपालिका, पिंपरी, पुणे.
३. महानगर आयुक्त तथा मुख्य कार्यकारी अधिकारी,
पुणे महानगर प्रदेश विकास प्राधिकरण, पुणे.

विषय :- एकत्रिकृत विकास नियंत्रण व प्रोत्साहन नियमावली (UDCPR)

मंजूर नियमावलीमधील विनियम क्र.१४.२.१ संदर्भात स्पष्टीकरण देणेबाबत.

महोदय,

एकत्रिकृत विकास नियंत्रण व प्रोत्साहन नियमावली मंजूर करताना विनियम क्र.१४.२.१-Transit Oriented Development for Pune Municipal Corporation area हा विनियम प्रलंबित ठेवण्यात येत असल्याचे उल्लेखासह सदर नियमावली मंजूर करण्यात आली आहे. या मंजूर UDCPR मध्ये उक्त विनियम प्रलंबित ठेवण्यात आला असल्याने त्याचे अंमलबजावणी संदर्भात प्रश्न उपस्थित होत असल्याचे शासनाच्या निदर्शनास आले आहे.

वर नमूद केल्यानुसार उपस्थित होत असलेल्या प्रश्नाचे निराकरण होण्याच्या दृष्टीने उक्त विनियम क्र.१.९(v) अंतर्गत खालीलप्रमाणे स्पष्टीकरण देण्याचे मला आदेश आहेत.

"मंजूर एकत्रिकृत विकास नियंत्रण व प्रोत्साहन नियमावली (UDCPR) मधील विनियम क्र.१४.२.१ Transit Oriented Development for Pune Municipal Corporation area हा प्रलंबित ठेवण्यात आला आहे. तथापि, यापूर्वी पुणे महानगरपालिकेच्या मंजूर विकास नियंत्रण व प्रोत्साहन नियमावली-२०१७ मधील विनियम २४.८ मध्ये फेरबदल करण्यासाठी शासनाने महाराष्ट्र प्रादेशिक नियोजन व नगर रचना अधिनियम, १९६६ चे कलम ३७(१कक) अन्वये सूचना क्र.टिपीएस-१८१८/१५०/प्र.क्र.१५८/१९/नवि-१३, दि.३०/०६/२०२० द्वारे सुधारित विनियम प्रसिध्द केला असून सदर सुधारित विनियम दि.३०/०६/२०२० रोजीच्या कलम १५४ अन्वयेच्या निदेशानुसार तातडीने लागू केला आहे. सबब सद्यस्थितीत सदर निदेशानुसार लागू करण्यात आलेला विनियम अंमलात राहील, म्हणजेच TOD चे मंजूर विनियम पूर्वीप्रमाणेच कार्यरत राहतील."

आपला,



(किशोर गोखले)

अवर सचिव, महाराष्ट्र शासन

- प्रत :- १) संचालक, नगर रचना, महाराष्ट्र राज्य, पुणे.
२) सहसंचालक, नगर रचना, पुणे विभाग, पुणे.
३) सहायक संचालक, नगर रचना, पुणे शाखा, पुणे.



महाराष्ट्र शासन
नगर विकास विभाग,

चौथा मजला, मुख्य इमारत, मंत्रालय,

मादाम कामा मार्ग, हुतात्मा राजगुरु चौक, मुंबई - ४०० ०३२.

दूरध्वनी क्र :- ०२२-२२७९४१९६

Email ID : kishor.gokhale@gov.in

क्रमांक:टिपीएस-१८२१/३४०/प्र.क्र.६८/२०२१/नवि-१३

दिनांक : १०.०५.२०२१

प्रति,

✓ मा. सहसंचालक, नगर रचना,
पुणे विभाग, पुणे

विषय- एकत्रिकृत विकास नियंत्रण व प्रोत्साहन नियमावलीतील विनियम क्र.६.२.२ मधील Table No.६E(६) नुसार वर्गीकृत रस्त्यावरील पेट्रोल पंपाचेसाठी जंक्शन पासून सोडावयाच्या अंतराबाबत.

संदर्भ:- आपले पत्र क्र. १९५, दि.०२.०२.२०२१

महोदय,

प्रस्तुत प्रकरणी आपल्या संदर्भित पत्राचे कृपया अवलोकन करावे. सदर पत्रान्वये, एकत्रिकृत विकास नियंत्रण व प्रोत्साहन नियमावलीतील विनियम क्र.६.२.२ मधील Table No.६E(६) नुसार वर्गीकृत रस्त्यावरील पेट्रोल पंपाचेसाठी जंक्शन पासून सोडावयाच्या अंतराबाबतचा प्रस्ताव शासनास सादर केला आहे.

०२. प्रस्तुत प्रकरणी आपणांस खालीलप्रमाणे कळविण्याचे मला निर्देश आहेत -

मंजूर एकत्रिकृत विकास नियंत्रण व प्रोत्साहन नियमावलीतील विनियम क्र.६.२.२ Other Buildings मधील Table No.६E मधील अ.क्र.६ मध्ये नमूद अटीनुसार पेट्रोल पंप अनुज्ञेय करावयाचा आहे. सदर विनियमानुसार जर Fuel stations चा भूखंड प्रादेशिक योजना क्षेत्रात वर्गीकृत रस्त्यावर स्थित असेल, तर अशा भूखंडात पेट्रोलपंप अनुज्ञेय होणेसाठी सदर भूखंडाचे वर्गीकृत रस्त्याच्या जंक्शनपासूनचे अंतर हे IRC १२-२००९ व MoRTH चे दि.२५.०९.२००३ मधील मार्गदर्शक सूचनांनुसार असणे आवश्यक आहे. याशिवाय शासनाच्या सार्वजनिक बांधकाम विभागाने त्यांचे दि.२८.०६.२०१७ रोजीच्या परिपत्रकाद्वारे IRC १२-२००९ च्या विहीत तरतुदीनुसार कार्यवाही करण्याचे व त्यामध्ये शिथिलता देण्याचे प्रस्ताव शासनास सादर करू नयेत असे कळविले आहे.

पेट्रोल पंप वितरीत (allot) करतवेळी त्याचे स्थान IRC 12-2009 मधील मार्गदर्शक सूचनांशी सुसंगत असणेबाबत खबरदारी घेणेबाबतच्या सूचना सर्व संबंधितांस देण्याची विनंती, राज्य शासनाच्या नगर विकास विभागाने दि.२२.०६.२०२० रोजी केंद्र शासनाच्या पेट्रोलियम मंत्रालयास करण्यात आलेली आहे. मात्र IRC १२-२००९ व MoRTH चे दि.२५.०९.२००३ मधील मार्गदर्शक सूचनांनुसार वर्गीकृत रस्त्याच्या जंक्शनपासून सोडावयाच्या विहित अंतराची पूर्तता होत नसताना काही Fuel stations चे वाटप करण्यात आलेले आहे. आणि अशा प्रकरणांमध्ये पेट्रोल

पंपाचे जंक्शनपासून सोडावयाचे अंतरात सवलत देण्याची प्रकरणे विभागीय कार्यालयास प्राप्त झालेली आहेत. त्याबाबत सार्वजनिक बांधकाम विभागाशी सल्लामसलत करून, धोरण निश्चित करून मार्गदर्शन करणेची धिनंती सहसंचालक नगर रचना, पुणे विभाग, पुणे यांनी केली आहे.

वास्तविक मंजूर UDCPR मधील तरतुद स्पष्ट आहे. त्यानुसार वर्गिकृत रस्त्यावर स्थित भूखंडावर पेट्रोलपंप अनुज्ञेय करताना, रस्त्याच्या जंक्शनपासूनचे अंतर हे IRC/MoRTH यांनी नमूद केलेल्यानुसार विचारात घ्यावयाचे आहे. त्यामुळे पेट्रोलपंप अनुज्ञेय करताना मंजूर नियमावलीतील तरतुदी विचारात घेणे आवश्यक आहे. जंक्शनपासूनचे अंतर हे सार्वजनिक बांधकाम विभागाच्या अख्यत्यारीतील विषय असून मंजूर नियमावलीतील तरतुदीप्रमाणे IRC/MoRTH यांनी नमूद केलेल्या अंतरामध्ये शिथिलता देण्याचे अधिकार सार्वजनिक बांधकाम विभागाचे असून अशा अंतरामध्ये त्या विभागाने शिथिलता दिल्यास त्याप्रमाणेचे अंतर विचारात घेऊन परवानगी देणे अपेक्षित आहे.

त्यामुळे उपरोक्त वस्तुस्थिती विचारात घेऊन त्यानुसार आपल्या स्तरावरून पुढील कार्यवाही करण्यात यावी, असे आपणांस कळविण्याचे मला निर्देश आहेत.

आपला,


(किशोर वि. गोखले)

अवर सचिव, महाराष्ट्र शासन.

प्रति:-

संचालक, नगर रचना, महाराष्ट्र राज्य, पुणे.

/- वरीलप्रमाणेच्या सूचना सर्व विभागीय सहसंचालक, नगर रचना, जिल्हाधिकारी व सर्व शाखा अधिकारी यांना आपल्या स्तरावरून देण्यात याव्यात.



महाराष्ट्र शासन

नगर विकास विभाग

मादाम कामा मार्ग, हुतात्मा राजगुरु चौक, मंत्रालय, मुंबई - ४०० ०३२.

क्रमांक:- टिपीएस-१२२१/९९०/प्र.क्र.४४/२१/नवि-१२

दिनांक :- १० जून, २०२१

प्रति,

आयुक्त,

ठाणे महानगरपालिका, ठाणे.

विषय : एकत्रिकृत विकास नियंत्रण व प्रोत्साहन नियमावली (UDCPR) मधील विनियम ११.२.५ नुसार बांधीव सुविधा अंतर्गत विकास हक्क हस्तांतरण संदर्भातील बाबींच्या अंमलबजावणीकामी मार्गदर्शन मिळणेबाबत.

संदर्भ : १. आयुक्त, ठाणे महानगरपालिका यांचे पत्र क्र. ठामपा/आयुक्त/३२४/२०२१ दि. १५.०३.२०२१
२. आयुक्त, ठाणे महानगरपालिका यांचे पत्र क्र. ठामपा/आयुक्त/२२/२०२१ दि. १२.०५.२०२१

महोदय,

आपले संदर्भीय पत्रास अनुसरून खालील प्रमाणे आपणास कळविण्याचे मला आदेश आहेत.

- 1) UDCPR २०२० विनियम ११.२.५ नुसार Amenity Construction TDR देण्याबाबतची तरतूद आहे. यापूर्वी पत्र क्र. टिपीएस-१२२१/४०३/२१/नवि-१२, दि. १७.०३.२०२१ मध्ये स्पष्ट केल्याप्रमाणे अनिवार्य / अपरिहार्य काम असल्यास त्याचा Construction TDR अनुज्ञेय करता येईलच, त्या व्यतिरिक्त -
 - i) MRTP कलम 2 (2) नुसार Amenity मध्ये "Drainage" चा समावेश होतो. त्यामुळे हा विनियम त्यास लागू राहील.
 - ii) जागा ज्याच्या मालकीची आहे त्यास / विकास हक्क धारण करणाऱ्यास किंवा भाडेकरू असल्यास त्यास जागेचा व बांधकामाचा TDR देय आहे.
 - iii) चालू कामाचा Scope वाढून नाल्याचा समावेश झाल्यास किंवा नव्याने काम घेतल्यास त्याचा TDR देता येईल.
 - iv) विनियम २.७.१ मध्ये Commencement बाबतचे स्पष्टीकरण देण्यात आले आहे. प्रस्तुत प्रकरणी Drainage चे काम जेव्हा चालू होईल, आणि जरी ते यापूर्वीच्या रस्त्याचा भाग असेल तरी, स्वतंत्रपणे विचारार्थ घेता येवू शकेल व त्यास प्रचलित नियमावलीनुसार 2 चा गुणाकार अनुज्ञेय असेल.

2) UDCPR विनियम २.७.१ मध्ये Commencement ची व्याख्या दिली आहे. इमारतीच्या बांधकामाची सुरुवात (Commencement) त्यानुसार upto Plinth Level अशी आहे. UDCPR मध्ये Plinth Certificate देण्याबाबतची तरतूद नसली तरी विकासकाने मनपास Plinth Completion ची सूचना दिल्याचा दिनांक हा संदर्भ म्हणून गृहीत धरता येईल. विनियम २.७.१ व ११.२.५ यांचा एकत्रितरित्या विचार करता खालील बाबी स्पष्ट होतात:-

- i) Construction TDR साठी बांधकाम Commencement झाल्याच्या तारखेला असणारी प्रचलित नियमावलीतील तरतूद लागू होते, म्हणजेच UDCPR लागू झाल्यानंतरच्या संदर्भाकित दिनांकास Plinth पूर्ण होवून पुढील काम चालू असल्यास, त्यास UDCPR मधील तरतुदी लागू पडतील.
- ii) अशा प्रकरणी Plinth पुढील सर्व कामांकरिता प्रचलित नियमावलीतील तरतुदीनुसार 2 च्या गुणाकाराने TDR अनुज्ञेय राहिल. मात्र Plinth च्या पूर्वी झालेल्या कामांकरिता तत्कालीन नियमानुसार जुना गुणक देय राहिल.
- iii) UDCPR - table ११-A मधील ix ही तरतूद यापूर्वी Accommodation Reservation (A.R.) करिता देण्यात आलेल्या परवानग्या या सदर मंजूरीप्रमाणेच पुढेही चालू राहतील, याची शाश्वती / बंधन देण्यासाठी आहे. परंतु Construction TDR कसा व किती द्यावा, याकरिता विनियम ११.२.५ च लागू राहिल. म्हणजेच, विनियम ११.१ हा आरक्षित भूखंड कसे विकसित करावे (A.R.) याच्या तपशीलाबाबत आहे, तर त्याचा TDR मोबदला देण्यासाठी ११.२.५ विनियम विचारात घेणे आवश्यक आहे.

3) UDCPR मधील टेबल ११-अ खाली नमूद अट ix - अशी आहे - In cases, where permission for development under accommodation reservation principle is already granted as per earlier regulations, the same shall continue to be valid till completion of construction.

ज्यावेळेस समावेशक आरक्षणाची योजना मंजूर झाली त्यावेळेस, अस्तित्वात असणाऱ्या नियमावलीनुसारच पुढे चालू राहिल. सदर तरतूद ही, आरक्षण हे समायोजित आरक्षणाच्या माध्यमातून करताना भूखंडाचे प्रमाण (टक्केवारी) व त्यावर बांधून हस्तांतरीत करावयाचे बांधीव क्षेत्र ठरविण्यासाठी देखील अंमलात राहिल, म्हणजेच नवीन UDCPR प्रमाणे ५०% ऐवजी ४० % भूखंडाचे देण्याची मागणी मान्य करता येणार नाही.

आपका



(सु.म.शिंदे)

कार्यासन अधिकारी

प्रत माहितीसाठी:

१) संचालक, नगर रचना, महाराष्ट्र राज्य, पुणे.



महाराष्ट्र शासन

नगर विकास विभाग

मादाम कामा मार्ग, हुतात्मा राजगुरु चौक, मंत्रालय, मुंबई - ४०० ०३२.

क्रमांक:-टिपीएस-१२२१/१०३९/प्र.क्र.४२/२१/नवि-१२

दिनांक :- १४ जून, २०२१

प्रति,

१. आयुक्त, नवी मुंबई महानगरपालिका, नवी मुंबई.

२. आयुक्त, पनवेल महानगरपालिका, पनवेल

विषय : सिडको प्राधिकरणाकडून पनवेल महानगरपालिकेकडे वर्ग झालेल्या भूखंडावर मंजूर एकत्रिकृत विकास नियंत्रण व प्रोत्साहन नियमावलीनुसार (UDCPR) बांधकाम परवानगी देतेवेळी अनुसरावयाच्या पध्दतीचे मार्गदर्शन मिळणेबाबत.

संदर्भ : पनवेल महानगरपालिका यांचेकडील पत्र क्र.प.महा./नरवि/६६९/२०२१ दि.२५.०३.२०२१

महोदय,

उपरोक्त पत्रान्वये आयुक्त, पनवेल महानगरपालिका यांनी सिडको प्राधिकरणाकडून पनवेल महानगरपालिकेकडे वर्ग झालेल्या भूखंडावर मंजूर एकत्रिकृत विकास नियंत्रण व प्रोत्साहन नियमावलीनुसार (UDCPR) बांधकाम परवानगी देतेवेळी अनुसरावयाच्या पध्दतीचे मार्गदर्शन मिळणेबाबत शासनास विनंती केली आहे. पनवेल महानगरपालिका यांनी उपस्थित केलेले मुद्द्याची वस्तुस्थिती ही नवी मुंबई महानगरपालिकेमध्ये देखील असल्याने मंजूर एकत्रिकृत विकास नियंत्रण व प्रोत्साहन नियमावलीतील विनियम क्र. १.९ (V) अन्वये दोन्ही महानगरपालिकांना खालीलप्रमाणे मार्गदर्शन देण्याचे मला आदेश आहेत.

अ.क्र.	पनवेल महानगरपालिकेचे मुद्दे	मुद्द्यावरील मार्गदर्शन
१.	एकत्रिकृत विकास नियंत्रण व प्रोत्साहन नियमावलीतील मुद्दा क्र.२.१.१४ प्रमाणे एकूण प्रिमियम शुल्कापैकी सामायिक हिस्सा शासनास ५० टक्के व नियोजन प्राधिकरणास ५० टक्के देण्याचे नमूद आहे. वरील नमूद केल्याप्रमाणे सिडको जरी जमिन मालक	नियोजन प्राधिकरण हे त्या क्षेत्रामध्ये सार्वजनिक सेवा सुविधा/ पायाभूत सुविधा देणार असल्यामुळे त्याठिकाणी एकूण अधिमुल्य रक्कमेपैकी ५०% अधिमुल्याची रक्कम ही पायाभूत सुविधा देणा-या नियोजन प्राधिकरणाकडे म्हणजेच पनवेल महानगरपालिकेकडे व उर्वरीत अधिमुल्य रक्कमेपैकी २५% अधिमुल्य हे जमिन मालक म्हणून सिडको यांचेकडे व उर्वरीत २५% अधिमुल्य हे शासनाकडे भरणा करणे आवश्यक राहिल, तसेच पनवेल महानगरपालिका क्षेत्रामध्ये ज्या ठिकाणी सिडको नवनगर

	असले तरी सेवा सुविधा पुरविण्याची जबाबदारी पनवेल महानगरपालिकेची आहे. त्यामुळे प्रिमियम शुल्क व अन्विलरी शुल्क पनवेल महानगरपालिकेमध्ये जमा होणे आवश्यक आहे, असे मत आहे.	विकास प्राधिकरण /नियोजन प्राधिकरण आहे त्याठिकाणी जमिनीच्या विकास परवानगीवेळी प्राप्त होणा-या रक्कमेपैकी ५०% रक्कम ही सिडकोकडे व उर्वरीत रक्कमेपैकी २५% रक्कम ही पनवेल महानगरपालिकेस व २५% रक्कम ही शासनास भरणे करणे आवश्यक राहिल. सदरचे अधिमूल्य वाटपाचे प्रमाण हे नवी मुंबई महानगरपालिका क्षेत्राकरीता सुध्दा लागू राहिल.
२.	एकात्रिकृत विकास नियंत्रण नियमावली व प्रोत्साहन नियमावली -२०२० मधील नियम क्र.२.२.३ नुसार भूखंडधारक सिडको प्राधिकरण असल्यामुळे भाडेपट्टेदार यांना नियमावलीतील नियम क्र.६.३ नुसार प्राप्त होणा-या FSI on payment of premium व Ancillary Area तसेच नियम क्र.७.६ नुसार धोकादायक इमारतीकरीता १० टक्के अतिरिक्त चटई क्षेत्र निर्देशांक व नियम क्र.१०.१०.१ टिप-३ नुसार प्राप्त होणारे In-situ FSI अनुज्ञेय आहे. सदरील बाबी भाडेपट्टेदार यांना द्यावयाचे झाल्यास जमिनमालक संस्था (सिडको) व भाडेपट्टेदार यांचे करारातील मान्य FSI व कात्मिक बांधकाम नियंत्रण व प्रोत्साहन नियमावलीतील तक्ता क्र.६A व ६G मधील FSI यापैकी कमी असलेला रकाना ३ मधील Basic FSI विचारात घेऊन जमीनमालक या नात्याने सिडकोचे ना-हरकत प्रमाणपत्र न घेता विहित शुल्क भरून घेऊन रकाना क्र.४ मधील जादा FSI व नोट १ व २ प्रमाणे लाभ अनुज्ञेय करता येईल अशी धारणा आहे.	एकात्रिकृत विकास नियंत्रण व प्रोत्साहन नियमावलीतील विनियम २.२.३ मधील तरतुदीनुसार विकास परवानगीचे वेळी मालकीहक्काबाबत सादर करावयाच्या दस्तावेजा अंतर्गत जर एखादी जमिन ही शासन /स्थानिक प्राधिकरण यांनी भाडेपट्टा कराराने दिलेली असल्यास व भाडेपट्टा करारामध्ये काही बदल झाल्यास तसेच भाडेपट्टा करारामधील चटई क्षेत्र निर्देशांकाव्यतिरीक्त जास्त चटई क्षेत्र निर्देशांक प्रस्तावित असल्यास बांधकाम परवानगीचेवेळी संबंधित जमिनीसाठी शासनाचे /संबंधित संस्थेचे ना-हरकत आवश्यक आहे. त्यामुळे भाडेपट्टा करारामधील चटई क्षेत्र निर्देशांकाव्यतिरीक्त जास्तीचे चटई क्षेत्र निर्देशांक प्रस्तावित असल्यास विनियम ६ मधील तक्ता ६A, ६G मधील किमान चटई क्षेत्र निर्देशांक विचारात न घेता सिडकोच्या करारनाम्याचे अनुषंगाने सिडकोचे ना-हरकत घेऊन विनियम १०.१०.१ मधील टिप -३ नुसार कार्यवाही होणे आवश्यक राहिल, तसेच वाढीव चटई क्षेत्र निर्देशांकासाठी आकारले जाणारे अधिमूल्य यांचा भरणे हा मुद्दा क्र.१ मध्ये अंतिम होणा-या तरतुदीप्रमाणे भरणे करणे आवश्यक राहिल. तक्ता ६G खालील टिप १ मधील अधिमूल्य हे झोपडपट्टी पुनर्वसन प्राधिकरण क्षेत्र वगळता इतर सर्व क्षेत्रामध्ये लागू असल्यामुळे त्यांचे देखिल अधिमूल्य उक्त नमूद प्रमाणे भरणे करणे आवश्यक राहिल तसेच टिप २ ही ज्या ठिकाणी नियोजन प्राधिकरण नाही तेथे टीडीआर अनुज्ञेय होत नाही. थोडक्यात टिप २ ही प्रादेशिक योजना क्षेत्रामधील जागेसाठी लागू होईल. तथापि पनवेल महानगरपालिका ही नियोजन प्राधिकरण असल्याने महानगरपालिका क्षेत्रासाठी टिडीआरची तरतूद लागू होते. सिडकोच्या मालकीच्या भूखंडामधून टिडीआर निर्माण होत नसला तरी महानगरपालिका क्षेत्रामधील इतर भूखंड/आरक्षणांच्या माध्यमातून निर्माण होणारा टिडीआर पनवेल महानगरपालिका नियोजन प्राधिकरण असलेल्या क्षेत्रातील सिडकोच्या मालकीच्या भूखंडावर वापरता येईल. त्याचप्रमाणे,



		i). ज्या भूखंडावर सिडकोची थकबाकी आहे, याची यादी सिडकोने एका महिन्यात दोन्ही महापालिकांना उपलब्ध करून द्यावी. ii). या यादीमधील भूखंडावर वाढीव चटईक्षेत्र किंवा बांधकाम परवानगी देताना सिडकोचे 'ना-हरकत' प्रमाणपत्र बंधनकारक राहील. iii). या यादीमध्ये नसणान्या भूखंडावर वाढीव चटईक्षेत्र अथवा बांधकाम परवानगी देताना सिडकोच्या ना-हरकत प्रमाणपत्राची आवश्यकता राहणार नाही. संबंधित महापालिकांनी नियमानुसार पुढील कार्यवाही करावी.
३.	सिडको प्राधिकरणाकडून शैक्षणिक, वैद्यकीय, औद्योगिक व सामाजिक वापराकरीता यापूर्वी भूखंड भाडेपट्ट्याने देणेत आले आहेत. सदर भूखंडाकरीता सिडको विकास नियंत्रण नियमावली १९७५ मधील नियम क्र.१६.३ नुसार सदरील भूखंडावर २ चटई क्षेत्र निर्देशांक (FSI) अनुज्ञेय असून एकत्रिकृत विकास नियंत्रण नियमावली व प्रोत्साहन नियमावली-२०२० मंजूर होण्यापूर्वी भाडेपट्टा करार करण्यात आलेले आहेत. सदर बाबत एकत्रिकृत विकास नियंत्रण नियमावली व प्रोत्साहन नियमावली-२०२० नियम क्र.६.३ मधील तरतुदीनुसार Basic FSI १.१० व इतर अनुषंगिक बाबी अनुज्ञेय आहे. त्यामुळे भाडेपट्टेदार यांस सिडको भाडेपट्टा करारानुसार २.०० FSI द्यावयाचा झाल्यास त्याबाबत सुस्पष्ट निर्देश आवश्यक असून तक्ता ६A व ६G मधील सुत्राव्यतिरीक्त FSI देण्याबाबत नियमावलीच्या अनुषंगाने तरतूद आवश्यक आहे.	शैक्षणिक, वैद्यकीय व सामाजिक वापरासाठी मुळ चटई क्षेत्र निर्देशांक (Basic FSI) १.०० असून वाढीव चटई क्षेत्र निर्देशांक १.०० आणि धर्मिक कारणासाठी वाढीव ०.५ चटई क्षेत्र निर्देशांक हा सिडकोच्या पुर्व मान्यतेने व वाढीव चटई क्षेत्र निर्देशांकाचे अधिमुल्य भरणा केलेनंतर एकत्रित चटई क्षेत्र निर्देशांक हा अनुक्रमे २.०० व १.५ इतका अनुज्ञेय होत होता. सदरस्थितीत एकत्रिकृत विकास नियंत्रण व प्रोत्साहन नियमावलीमधील विनियम ६ मधील तक्ता ६-A, ६-G व विनियम ७ मधील तक्ता ७ A मधील मुळ चटई क्षेत्र निर्देशांक (Basic FSI) हा सिडकोच्या तत्कालिन विकास नियंत्रण नियमावलीतील मुळ चटई क्षेत्र निर्देशांकापेक्षा जास्तीचा असून त्यामध्ये वाढीव चटई क्षेत्र निर्देशांक हा अधिमुल्य भरणा करून अनुज्ञेय केलेला आहे. सदरचा एकत्रित (मुळ + वाढीव) चटई क्षेत्र निर्देशांक हा सिडकोच्या तत्कालिन विकास नियंत्रण नियमावलीतील विनियम १६.३ च्या तरतुदीमधील चटई क्षेत्र निर्देशांकापेक्षा जास्तीचा असल्यामुळे उक्त वापराच्या भूखंडामध्ये भाडेपट्टेदार यांचेसाठी नियमावलीमध्ये वेगळी सुस्पष्टता / निर्देश देण्याची आवश्यकता नाही.

४.	एकत्रिकृत विकास नियंत्रण व प्रोत्साहन नियमावली २०२० मधील व्याख्या क्र.९३ (xiv) (i) नुसार २४ मी.वरील इमारतींना स्पेशल बिल्डींग असे संबोधले जाते व त्याकरीता फायर एनओसी घेणे बंधनकारक आहे. तसेच १५ मी.पेक्षा जास्त उंची असलेल्या इमारतीसाठी नियम क्र.९.२९.८ नुसार एक लिफ्ट ही फायर लिफ्ट असावी असे नमूद आहे. तसेच नॅशनल बिल्डींग कोडचे फायर तरतुदीनुसार १५ मी.उंचीवरील इमारतीसाठी फायर एनओसी घेणे बंधनकारक आहे. त्यामुळे १५ मी.उंचीवरील इमारतीकरीता फायर एनओसी घ्यावी किंवा कसे याबाबत मार्गदर्शन होणेस विनंती.	एकत्रिकृत विकास नियंत्रण व प्रोत्साहन नियमावलीमधील विनियम १.९ मधील ९३ (xiv) (i, ii, iii) मध्ये विशेष इमारत (Special Building) याबाबत स्पष्टता आहे. तसेच विनियम ९.२८.७ व ९.२९.८ यांचा एकत्रित विचार करता तळ मजल्यापेक्षा जास्त मजल्याच्या इमारतीस जी विनियम १.३.९३ (xiv) (i, ii, iii) तरतुदीनुसार विशेष इमारत नाही, अशा इमारतीस एक जिना व १५ मी. उंचीपेक्षा जास्त उंचीच्या इमारतीस एक अग्निशमन जिना (Fire Lift) आवश्यक आहे. त्यामुळे अग्निशमन जिना (Fire Lift) ही २४.०० मी. उंचीपेक्षा कमी (जी विशेष इमारत नाही) उंचीच्या इमारतीस सोडावयाचे प्रयोजन असले तरी त्यास अग्निशमन विभागाचे ना-हरकत आवश्यक नाही. परंतु याबाबत विनियम २.२.११ मध्ये नमूद नुसार जर एखादी इमारत ही विनियम क्र.१.३. ९३ (xiv) (i, ii, iii) मधील तरतुदीमध्ये बसत असल्यास सदर इमारतीस अग्निशमन विभागाचे ना-हरकत घेणे बंधनकारक आहे, अशी स्पष्ट तरतुद विनियमामध्ये असल्याने नॅशनल बिल्डींग कोड मधील तरतुद विचारात न घेता एकत्रिकृत विकास नियंत्रण व प्रोत्साहन नियमावलीमधील तरतुदीनुसार इमारतीस अग्निशमन विभागाचे ना-हरकत घेणे आवश्यक राहिल.
५.	संदर्भ क्र.४ च्या पत्रातील पुरकपत्र क्र.११ The Indian Institute of Architects यांच्या पत्रातील मुद्दा क्र.१ नुसार सिडकोच्या १२.५% योजनेमधील ५०० चौ.मी. क्षेत्रापेक्षा कमी भूखंडावर नविन एकत्रित नियंत्रण व प्रोत्साहन नियमावली नुसार पार्किंग, इमारतीची उंची, सामासिक अंतर मुळे विकास/ भूखंडधारकास विकास करतेवेळी अनुज्ञेय चटई क्षेत्र निर्देशांक क्षेत्राचा पूर्णपणे वापर करता येत नाही. त्यामुळे सदर बाबत वरीष्ठ स्तरावर विचार होणेस विनंती.	एकत्रिकृत विकास नियंत्रण व प्रोत्साहन नियमावलीमधील विनियम ६.२ मधील तक्ता ६.D व ६.E मध्ये रस्त्याच्या रुंदीनुसार त्यास सन्मुख भूखंडाचे किमान क्षेत्र व त्यावर अनुज्ञेय होणा-या इमारतीच्या उंची नुसार सामासिक अंतरे सोडावयाची तरतुद असून सदरची तरतुद ही या तक्त्यामधील स्तंभ ८ मध्ये नमूद केल्यानुसार पार्किंग मजल्यासाठीची उंची वगळून उर्वरीत इमारतीच्या उंचीकरीता आहे. सदर तक्त्यामधील इमारत उंचीपेक्षा जास्त उंचीच्या इमारतीसाठी आवश्यक सामासिक अंतरे हे विनियम ६.२.३ नुसार प्रस्तावित करणे आवश्यक आहे. सिडकोच्या तत्कालिन सर्वसाधारण विकास नियंत्रण नियमावलीमध्ये सिडकोच्या प्रकल्पग्रस्तासाठी वाटप केलेल्या १२.५ टक्के योजनेअंतर्गत ४५० चौ.मी. पेक्षा कमी क्षेत्राच्या भूखंडामध्ये Semi detached Buildings व रो हाऊसेस १३ मी.उंचीच्या मर्यादित अनुज्ञेय होत्या तसेच एकत्रिकृत विकास नियंत्रण व प्रोत्साहन नियमावलीतील विनियम ३.७ मधील तक्ता क्र.३D नुसार भूखंडाचे किमान क्षेत्र व त्यामध्ये अनुज्ञेय विकास नमूद असून सदर विकास हा पुर्व मंजूर रेखांकनामध्ये नमूद मंजूर रेखांकनामधील तरतुदीनुसार किंवा

		भविष्यामधील मंजूर रेखांकनानुसार अनुज्ञेय आहे. तसेच तक्ता क्र.६D नुसार रस्त्याच्या रुंदीनुसार किमान भूखंडाचे क्षेत्र. इमारतीपासून सोडावयाचे सामासिक अंतर व इमारत उंची नमूद असून त्याखालील नोट क्र.१३ नुसार पुर्व मंजूर रेखांकनामधील विकास हा पुर्व मंजूर रेखांकनानुसार करावयाचा आहे. त्यामुळे सिडकोच्या १२.५% भूखंडासाठी सामासिक अंतराबाबत वेगळ्या विनियमाची आवश्यकता नाही. तसेच संपूर्ण अनुज्ञेय चटई क्षेत्र निर्देशांक वापरणे बंधनकारक नाही.

आपला



(पु.म.खंदे)

कार्यासन अधिकारी

प्रत माहितीसाठी व उचित कार्यवाहीसाठी:

- १) व्यवस्थापकीय संचालक, सिडको, सिडको भवन, बेलापूर, नवी मुंबई.
- २) संचालक, नगर रचना, महाराष्ट्र राज्य, पुणे.
- ३) सहसंचालक, नगर रचना, कोकण विभाग, नवी मुंबई.
- ४) सहायक संचालक, नगर रचना, अलिबाग शाखा, रायगड.



महाराष्ट्र शासन
नगर विकास विभाग

४ था मजला, मुख्य इमारत, मंत्रालय,
मादाम कामा मार्ग, हुतात्मा राजगुरु चौक, मंत्रालय, मुंबई - ४०० ०३२

क्र.टिपीएस-१८२१/प्र.क्र.१०३/२०२१/नवि-१३

दि.०२/०८/२०२१

प्रस्तावना :- शासनाने दि.०२.१२.२०२० रोजीच्या अधिसूचनेद्वारे मंजूर एकत्रिकृत विकास नियंत्रण व प्रोत्साहन नियमावली मंजूर केली असून ती दि.०३.१२.२०२० पासून अंमलात आली आहे. सदर नियमावली उक्त अधिसूचनेत नमूद क्षेत्र वगळता राज्यातील सर्व प्राधिकरणे व प्रादेशिक योजना क्षेत्राकरिता लागू आहे. सदर नियमावलीतील विनियम २.२.१४(ii) हा Fire Infrastructure Charges बाबत असून यामध्ये These charges shall be decided by the Government from time to time अशी तरतुद आहे.

महाराष्ट्र आग प्रतिबंधक व जीवसंरक्षक उपाययोजना अधिनियम, २००६ हा महाराष्ट्र राज्यासाठी दि.०६.१२.२००८ पासून लागू करण्यात आला आहे. या अधिनियमामध्ये अग्निशमन सेवेच्या अनुषंगाने वसूल करावयाचे शुल्क, त्यामध्ये वाढ अथवा घट करणे, असे शुल्क स्वतंत्र निधीमध्ये ठेऊन त्याचा विनियोग कशाप्रकारे करावा याबाबत सविस्तर तरतुदी करण्यात आल्या आहेत.

उक्त अधिनियम संपूर्ण राज्यासाठी लागू झाला असल्याने त्यातील तरतुदी व त्यानुसार आकारावयाचे शुल्काची मंजूर एकत्रिकृत विकास नियंत्रण व प्रोत्साहन नियमावलीमध्ये Fire Infrastructure Charges बाबत करण्यात आलेल्या तरतुदींमध्ये पुनरावृत्ती होत असल्याचे शासनाच्या निर्दर्शनास आले असल्याने मंजूर एकत्रिकृत विकास नियंत्रण व प्रोत्साहन नियमावलीतील विनियम २.२.१४(ii) मधील तरतुदीच्या अनुषंगाने आकारावयाच्या Fire Infrastructure Charges बाबत खालीलप्रमाणे आदेश पारित करण्यात येत आहेत.

आदेश

मंजूर एकत्रिकृत विकास नियंत्रण व प्रोत्साहन नियमावलीतील विनियम २.२.१४(ii) मधील तरतुदीनुसार Fire Infrastructure Charges ची आकारणी वेगळ्याने करण्याची आवश्यकता नाही. मात्र महाराष्ट्र आग प्रतिबंधक व जीवसुरक्षा अधिनियम, २००६ मधील तरतुदीनुसार आवश्यक ती फी / शुल्क आकारणी करण्यात यावी व त्याचा विनियोग सदर अधिनियमातील तरतुदीनुसार करण्यात यावा.



(किशोर गोखले)

अवर सचिव, महाराष्ट्र शासन

प्रत :-

१. मा.मुख्यमंत्री महोदय यांचे प्रधान सचिव, मंत्रालय, मुंबई.
२. मा.उप मुख्यमंत्री महोदय यांचे सचिव, मंत्रालय, मुंबई.
३. मा.मंत्री, नगर विकास यांचे खाजगी सचिव, मंत्रालय, मुंबई.
४. मा.राज्यमंत्री, नगर विकास यांचे खाजगी सचिव, मंत्रालय, मुंबई.

५. मा.विरोधी पक्षनेता, विधानपरिषद / विधानसभा, महाराष्ट्र विधानमंडळ सचिवालय, मुंबई.
६. मा.उपसभापती, महाराष्ट्र विधानपरिषद, महाराष्ट्र विधानमंडळ सचिवालय, मुंबई.
७. मा.उपाध्यक्ष, महाराष्ट्र विधानसभा, महाराष्ट्र विधानमंडळ सचिवालय, मुंबई.
८. प्रधान सचिव (नवि-१), नगर विकास विभाग, मंत्रालय, मुंबई.
९. प्रधान सचिव (नवि-२), नगर विकास विभाग, मंत्रालय, मुंबई.
१०. संचालक (नगर रचना) तथा सह सचिव, नगर विकास विभाग, मंत्रालय, मुंबई.
११. सह सचिव तथा सहसंचालक (नगर रचना), नगर विकास विभाग, मंत्रालय, मुंबई.

प्रति :-

- १) संचालक, नगर रचना, महाराष्ट्र राज्य, पुणे.
/- सदर आदेश नगर रचना संचालनालयाच्या संकेतस्थळावर प्रसिध्द करावेत.
- २) संचालक, महाराष्ट्र अग्निशमन सेवा, मुंबई.
- ३) सर्व विभागीय सहसंचालक, नगर रचना.
- ४) सर्व विभागीय आयुक्त.
- ५) सर्व जिल्हाधिकारी.
- ६) आयुक्त, सर्व संबंधित महानगरपालिका.
- ७) महानगर आयुक्त, सर्व महानगर प्रदेश विकास प्राधिकरणे.
- ८) सर्व विशेष नियोजन प्राधिकरणे.
- ९) व्यवस्थापक, शासकीय मध्यवर्ती मुद्रणालय, चर्नी रोड, मुंबई.
/- त्यांना विनंती करण्यात येते की, सोबतची शासकीय आदेश महाराष्ट्र शासनाच्या असाधारण राजपत्रामध्ये राज्यस्तरावर प्रसिध्द करून त्याच्या प्रत्येकी १० प्रती नगर विकास विभागास व सर्व कार्यालयांना पाठवाव्यात.
- १०) मुख्य कार्यकारी अधिकारी, कोल्हापूर नागरी क्षेत्र विकास प्राधिकरण, कोल्हापूर.
- ११) सर्व नवनगर विकास प्राधिकरणे.
- १२) सहायक संचालक, नगर रचना / नगर रचनाकार, नगर रचना व मूल्यनिर्धारण विभाग, सर्व शाखा कार्यालये.
- १३) मुख्य कार्यकारी अधिकारी, सर्व जिल्हापरिषद.
- १४) मुख्य अधिकारी (सर्व नगरपरिषदा / नगरपंचायती)
- १५) अवर सचिव, नवि-११/नवि-३०, कक्ष अधिकारी, नवि-९/नवि-१२, नगर विकास विभाग, मंत्रालय, मुंबई.
- १६) कक्ष अधिकारी (नवि-२९), नगर विकास विभाग, मंत्रालय, मुंबई.
/- सोबतचे आदेश या विभागाच्या संकेतस्थळावर प्रसिध्द करावेत.
- १७) कक्ष अधिकारी, माहिती व तंत्रज्ञान विभाग, मंत्रालय, मुंबई.
/- सदरचे आदेश शासनाच्या संकेतस्थळावर प्रसिध्द करावेत.
- १८) निवडनस्ती, कार्यासन (नवि-१३).



नगर विकास विभाग

मादाम कामा मार्ग, हुतात्मा राजगुरु चौक, मंत्रालय, मुंबई - ४०० ०३२

Email ID : kishor.gokhale@gov.in

दि. १७.०९.२०२१

मा.आयुक्त,
पुणे महानगरपालिका, पुणे.

विषय :- मंजूर एकत्रिकृत विकास नियंत्रण व प्रोत्साहन नियमावली (UDCPR) प्रमाणे भूखंडाच्या कमाल बांधकाम क्षमतेच्या गणनेसंदर्भात येणाऱ्या अडचणींबाबत मार्गदर्शन मिळणेबाबत

संदर्भ :- आपलेकडील पत्र क्र.७८२९, दि.०२.०९.२०२१ रोजीचे पत्र.

उपरोक्त विषयानुषंगाने, विनियम ६.३, नुसारची तरतूद आणि विनियम ११.२.७(iii) नुसारची तरतूद यामध्ये संविधता असल्याने मुद्दे उपस्थित झाल्याचे नमूद करून त्याबाबत शासनाचे मार्गदर्शन अपेक्षिते आहे.

या अनुषंगाने आपणास खालीलप्रमाणे कळविण्याच्या मला सूचना आहेत.

०१. विनियम ६.३, टेबल ६-G खालील नोट (xiv) आणि विनियम ११.२.७(iii) या तरतुदी वेगवेगळ्या असून त्या स्वयंस्पष्ट आहेत.

विनियम ६.३ व त्या अंतर्गतचे टेबल ६-G मधील तरतुदी ह्या, एखाद्या भूखंडावर कमाल बांधकाम क्षमता किती अनुज्ञेय होईल याबाबत आहेत. यातील नोट (xiv) नुसार, एखाद्या भूखंडाच्या एकूण क्षेत्रामधून विकास योजना रस्ता/रस्तारुंदी, सुविधा जागा/आरक्षण याखालील क्षेत्र वगळून शिल्लक राहणाऱ्या निव्वळ भूखंड क्षेत्रावर मूळ चटई क्षेत्र निर्देशांक (Basic FSI) अनुज्ञेय राहिल. तर विकास योजना रस्ता/रस्तारुंदी किंवा सुविधा जागा/आरक्षण याखालील क्षेत्र प्राधिकरणास हस्तांतरित केलेले असल्यास, त्यासहचे भूखंडाचे एकूण क्षेत्र विचारात घेऊन अशा एकूण भूखंड क्षेत्रानुसार Premium FSI & TDR loading ची क्षमता अनुज्ञेय राहिल.

०२. विनियम ११.२.७ हा TDR चा प्रत्यक्ष वापर करण्यासंदर्भात असून यातील अ.क्र.(i) नुसार, एखाद्या भूखंडावर कमाल अनुज्ञेय बांधकाम क्षमता आणि TDR चा वापर विनियम ६.१, ६.२, ६.३ मधील तरतुदीनुसार अनुज्ञेय आहे. तर अ.क्र.(iii) नुसार, भूखंडाच्या एकूण क्षेत्रामधून विकास योजना रस्ता/रस्तारुंदी, आरक्षण/मानवीआरक्षण (सुविधा जागा) या प्रस्तावांनी बांधीत होणारे क्षेत्र घगळल्यानंतर शिल्लक राहणाऱ्या भूखंड क्षेत्रावर TDR चा प्रत्यक्ष वापर अनुज्ञेय आहे.

०३. उक्ता दोन तरतुदीपैकी विनियम ६.३, टेबल ६-G, नोट (xiv) मधील तरतुदीनुसार, एखाद्या भूखंडावर अनुज्ञेय कमाल बांधकाम क्षमता ठरविताना वरील मुद्दा ०१ मध्ये नमूद केल्यानुसार भूखंड क्षेत्र विचारात घ्यावयाचे आहे. तर विनियम ११.२.७(iii) मधील तरतुदीनुसार, कमाल बांधकाम क्षमतेचा / TDR चा प्रत्यक्ष वापर वरील मुद्दा ०२ मध्ये नमूद केल्यानुसार भूखंड क्षेत्रावर करणे आवश्यक आहे.

आपला,


(किशोर गोखले)

अवर सचिव, महाराष्ट्र शासन

प्रत :-

मा.संचालक, नगर रचना, महाराष्ट्र राज्य, पुणे



महाराष्ट्र शासन
नगर रचना आणि मूल्यनिर्धारण विभाग,
नगर रचना संचालनालय, तळमजला,
मध्यवर्ती इमारत, पुणे ४११ ००१

दुरध्वनी क्र. ०२०-२६१२९४९४

Email ID : dtdpvd.pune@maharashtra.gov.in/

ddtp.uro@maharashtra.gov.in

कार्यालयीन आदेश

विषय : मंजूर UDCPR मधील काही तरतुदींच्या प्रभावी अंमलबजावणीमध्ये येणाऱ्या अडचणीबाबत सुधारणा करणेसंदर्भात विनियम क्र.१.१० अन्वये मंजूर नियमावलीस शुध्दीपत्रक / पुरकपत्रानुसार कार्यवाही होणेबाबत.

संदर्भ : शासनाच्या नगर विकास विभागाकडील शासन निर्णय क्र.टिपीएस १८२०/६१४/प्र.क्र.७९/२०२१/नवि-१३, दि. ०२/१२/२०२१.

शासनाने दि. ०२/१२/२०२० रोजी मंजूर केलेल्या UDCPR मधील काही तरतुदींच्या प्रभावी अंमलबजावणीमध्ये येणाऱ्या अडचणीबाबत सुधारणा करणेसंदर्भात विनियम क्र.१.१० अन्वये मंजूर नियमावलीस संदर्भित शासन निर्णयान्वये शुध्दीपत्रक / पुरकपत्र निर्गमित केले आहे. या शुध्दीपत्रकातील अ.क्र. ५६ येथे Appendix-C, C-७.१ Technical Person to License मध्ये सुधारणा केली आहे.

या सुधारणेनुसार UDCPR मधील Appendix-C अंतर्गत C-३ Engineer, C-४ Structural Engineer, C-५ Supervisor, C-६ Town Planner यांना संबंधित प्राधिकरणाकडील अथवा नगर रचना संचालनालयाकडील परवाना आवश्यक आहे. उपरोक्त सुधारणेनुसार संचालनालयाकडे नोंदणी केलेल्या परवानाधारकास संपूर्ण राज्यातील सर्व निवोजन प्राधिकरणाच्या तसेच प्रादेशिक योजना क्षेत्रात काम करण्यास परवानगी असेल.

सबब, UDCPR मधील Appendix-C अंतर्गत C-३ Engineer, C-४ Structural Engineer, C-५ Supervisor, C-६ Town Planner यांना नगर रचना संचालनालयाच्या स्तरावरील परवाना निर्गमित करणे व त्यांची नोंदणी करणे यासाठीची आवश्यक सर्व कार्यवाही करण्यासाठी सहसंचालक, नगर रचना, अंमलबजावणी यांना प्राधिकृत करण्यात येत आहे. त्यानुसार सदरची कार्यवाही त्यांनी मा.संचालक, नगर रचना, महाराष्ट्र राज्य, पुणे यांच्या मान्यतेने करावी.

(मसुदा मा.संचालक यांनी मान्य केला असे.)

जा.क्र. UDCPR/Appendix-C/परवाना/५७२८

दिनांक २८/१२/२०२१.

(रा.म.पवार)

संचालक, नगर रचना,
महाराष्ट्र राज्य, पुणे करिता

प्रत

- १) मा. प्रधान सचिव (नवि-१), नगर विकास विभाग, मंत्रालय, मुंबई-३२
- २) संचालक, नगर रचना तथा सहसचिव, नगर विकास विभाग, मंत्रालय, मुंबई (सरनेह)
- ३) संचालक, नगर रचना तथा मुख्य नियोजनकार, मजीविन, मुंबई (सरनेह)

- ४) सहसंचालक, नगर रचना तथा सहसचिव, नगर विकास विभाग, मंत्रालय, मुंबई-३२
- ५) सहसंचालक, नगर रचना, अ.क., पुणे यांना माहिती व आवश्यक त्या कार्यवाहीसाठी.
- ६) सहसंचालक, नगर रचना, पुणे / कोकण / नाशिक / औरंगाबाद / नागपूर / अमरावती. त्यांनी सदरचे आदेश सर्व शाखा कार्यालयाना अवगत करावेत.

प्रत माहिती व योग्य त्या कार्यवाहीसाठी-

- १) उपसंचालक, नगर रचना, मुख्य कार्यालय, पुणे / नागरी संशोधन घटक, पुणे / वृहन्मुंबई.
- २) कार्यासन अधिकारी, कार्यासन क्र. १/२/३/४/५/६/७.
- ३) श्री. पालकर, स्वि.स. / श्रीमती हुपरे / श्री. चंद्रस (उच्चश्रेणी लघुलेखक)
- ४) परिपत्रक नस्ती.



महाराष्ट्र शासन

नगर विकास विभाग

४ था मजला, मुख्य इमारत, मंत्रालय,

मादाम कामा मार्ग, हुतात्मा राजगुरु चौक, मंत्रालय, मुंबई - ४०० ०३२

दुरध्वनी क्र.०२२-२२७९४१९६

Email ID : kishor.gokhale@gov.in

आदेश

क्र.टिपोएस-१८१८/प्र.क्र.२३६/१८(भाग-२)/नवि-१३

दि.२३/१२/२०२१

विषय :- एकत्रिकृत विकास नियंत्रण व प्रोत्साहन नियमावली (UDCPR)

मंजूर नियमावलीमधील विनियम क्र.१.९(v) अन्वये स्पष्टीकरण देणेबाबत.

ज्याअर्थी, शासनाने अधिसूचना क्र. टिपोएस १८१८/प्र.क्र.३३६/१८/कलम ३७(१कक)(ग) व कलम २०(४)/ नवि-१३, दि.०२/१२/२०२० अन्वये राज्यातील सर्व नियोजन प्राधिकरणे (काही अपवाद वगळता) आणि प्रादेशिक योजना क्षेत्राकरिता एकत्रिकृत विकास नियंत्रण व प्रोत्साहन नियमावली मंजूर केली असून ती दि.०३/१२/२०२० पासून अमलात आली आहे;

आणि ज्याअर्थी, उक्त नियमावलीतील विनियम क्र.१.९ मध्ये अ.क्र. (v) या तरतुदीनुसार UDCPR मधील विविध तरतुदींच्या अन्वयार्थ संदर्भात उपस्थित प्रश्न/मुद्द्याच्या अनुषंगाने शासनातर्फे आदेश देणेबाबत तरतुद आहे ;

आणि ज्याअर्थी, या शासनाने उपरोक्त तरतुदीच्या अनुषंगाने खेळोवळी निर्गमित आदेशान्वये संबंधितांना मार्गदर्शन केलेले आहे.

आणि ज्याअर्थी, उक्त नियमावलीतील अन्य काही तरतुदींची अंमलबजावणी करण्यासंदर्भात येणाऱ्या अडचणींच्या अनुषंगाने विनियमातील तरतुदींचा अन्वयार्थ स्पष्ट करणेसंदर्भात नियोजन प्राधिकरणांकडून तसेच अन्य काही संस्थांकडून शासनाकडे निवेदने प्राप्त झाली आहेत;

आणि ज्याअर्थी, उक्त विविध निवेदने विचारात घेता आणि जनहिताच्या दृष्टीने, उक्त नियमावलीची प्रभावी अंमलबजावणी होण्यासाठी उक्त नियमावलीतील काही तरतुदींबाबत व्यवहार्यता तपासून अशा तरतुदींचे पुनरावलोकन करून विनियम क्र.१.९ मधील (v) नुसार शासनाकडून अशा तरतुदींबाबत स्पष्टीकरण करणे आवश्यक असल्याचे शासनाचे मत झाले आहे;

आता त्याअर्थी, उक्त नियमावलीतील उक्त तरतुदीस अनुसरून काही तरतुदींबाबत सोबतच्या परिशिष्टामध्ये नमूद केल्यानुसार सविस्तर स्पष्टीकरणात्मक सूचना पुढील कार्यवाहीसाठी निर्गमित करण्यात येत आहेत.



Kishor Gokhale
(किशोर गोंखले)

अवर सचिव, महाराष्ट्र शासन

प्रत :-

१. मा.मुख्यमंत्री महोदय यांचे प्रधान सचिव, मंत्रालय, मुंबई.
२. मा.उप मुख्यमंत्री महोदय यांचे सचिव, मंत्रालय, मुंबई.
३. मा.मंत्री, नगर विकास यांचे खाजगी सचिव, मंत्रालय, मुंबई.
४. मा.राज्यमंत्री, नगर विकास यांचे खाजगी सचिव, मंत्रालय, मुंबई.
५. मा.विरोधी पक्षनेता, विधानपरिषद / विधानसभा, महाराष्ट्र विधानमंडळ सचिवालय, मुंबई.
६. मा.उपसभापती, महाराष्ट्र विधानपरिषद, महाराष्ट्र विधानमंडळ सचिवालय, मुंबई.
७. मा.उपाध्यक्ष, महाराष्ट्र विधानसभा, महाराष्ट्र विधानमंडळ सचिवालय, मुंबई.
८. प्रधान सचिव (नवि-१), नगर विकास विभाग, मंत्रालय, मुंबई.
९. संचालक (नगर रचना) तथा सह सचिव, नगर विकास विभाग, मंत्रालय, मुंबई.
१०. सह सचिव तथा सहसंचालक (नगर रचना), नगर विकास विभाग, मंत्रालय, मुंबई.

प्रति :-

- १) संचालक, नगर रचना, महाराष्ट्र राज्य, पुणे.
/- सदरचे **आदेश** नगर रचना संचालनालयाच्या संकेतस्थळावर प्रसिध्द करावेत.
- २) सर्व विभागीय सहसंचालक, नगर रचना.
- ३) सर्व विभागीय आयुक्त.
- ४) सर्व जिल्हाधिकारी.
- ५) आयुक्त, सर्व संबंधित महानगरपालिका.
- ६) महानगर आयुक्त, सर्व महानगर प्रदेश विकास प्राधिकरणे.
- ७) सर्व विशेष नियोजन प्राधिकरणे.
- ८) मुख्य कार्यकारी अधिकारी, कोल्हापूर नागरी क्षेत्र विकास प्राधिकरण, कोल्हापूर.
- ९) सर्व नवनगर विकास प्राधिकरणे.
- १०) सहायक संचालक, नगर रचना / नगर रचनाकार, नगर रचना व मूल्यनिर्धारण विभाग, सर्व शाखा कार्यालये.
- ११) मुख्य कार्यकारी अधिकारी, सर्व जिल्हापरिषद.
- १२) जवर सचिव, नवि-११/नवि-३०, कक्ष अधिकारी, नवि-९/नवि-१२, नगर विकास विभाग, मंत्रालय, मुंबई.
- १३) मुख्यअधिकारी (सर्व नगरपरिषदा / नगरपंचायती)
- १४) कक्ष अधिकारी (नवि-२९), नगर विकास विभाग, मंत्रालय, मुंबई.
/- सोबतचे **आदेश** या विभागाच्या संकेतस्थळावर प्रसिध्द करावेत.
- १५) कक्ष अधिकारी, माहिती व तंत्रज्ञान विभाग, मंत्रालय, मुंबई.
/- सोबतचे **आदेश** शासनाच्या संकेतस्थळावर प्रसिध्द करावेत.
- १६) निवडनस्ती, कार्यासन (नवि-१३).



परिशिष्ट

अ. क्र.	विनियम क्र.	मंजूर UDCPR मधील तरतुद	विनियम क्र.१९(iv) अन्वये स्पष्टीकरण
१	२	३	४
१	10.4	10.4 Nagpur Metropolitan Region Development Authority 10.4.1 Development along Ring Road: 250 m. Residential Zone/ Residential Belt proposed along the 60 m. wide Outer Ring Road as a corridor development is sanctioned, subject to payment of premium. The development in this 250 m. corridor is permitted on payment of premium as decided by the Government on the total area of land under development or building permission. Such premium shall be deposited with the concerned Authority.	सदर तरतुदीमध्ये शासन ठरवेल त्यानुसार अधिमूल्य आकारून विकास परवानगी अनुज्ञेय करणेबाबत तरतुद आहे. शासनाने यापूर्वी आदेश क्र.टिपोएस-२४१६/प्र.क्र.१२२(भाग-३)/ २०१६/नवि-९, दि.२०/११/२०१८ अन्वये, मंजूर नागपूर महानगर प्रदेश विकास योजना व विकास नियंत्रण व प्रोत्साहन नियमावलीमध्ये, ६० मी. बाह्यवळण रस्त्याचे दोन्ही बाजूस प्रस्तावित २५० मी. रहिवास विभाग/रहिवास पट्ट्यात विकास परवानगी देताना जाकारजवयाच्या अधिमूल्याचा दर १५% निश्चित करण्यात आला आहे. सद्यस्थितीत यांनुसारचाच दर सदर विनियमानुसार परवानगी देताना लागू राहील.
२	2.2	2.2 Procedure for Obtaining Development Permission / Building Permission / Commencement Certificate 2.2.12 Building / Layout Permission Scrutiny Fee - The notice shall be accompanied by a self-attested copy of receipt of payment of building/ layout permission Scrutiny Fee. These fees shall be as mentioned below and shall be subject to Government orders, if any. Provided that, such fees shall not be applicable for the development proposals implemented by Government / Government Departments or Public Authorities of State or Central Government.	महाराष्ट्र प्रादेशिक नियोजन व नगर रचना अधिनियम, १९६६ च्या कलम १८(१)(ii) मधील तरतुदीनुसार प्रादेशिक योजना क्षेत्रात, गावठाण क्षेत्रातील विकास परवानगी संबंधित ग्रामपंचायतीने द्यावयाची आहे. अशी विकास परवानगी, ग्रामपंचायत अधिनियमातील सुधारणेनुसार, पंचायत समिती अथवा जिल्हापरिषद स्तरावर पदस्थापित नगर रचना अधिकार्यांची पूर्वपरवानगी घेऊन पंचायतीने परवानगी द्यावयाची आहे. तथापि, सद्यस्थितीत पंचायत समिती अथवा जिल्हापरिषद स्तरावर नगर रचना अधिकार्यांची पदस्थापन झालेली नसल्याने ग्रामपंचायतीने परवानगी देणेपूर्वी संबंधित जिल्ह्याच्या नगर रचना विभागाच्या शाखा कार्यालयाची पूर्वमंजूरी घेऊन विकास परवानगी द्यावयाची असल्याने अशा संबंधित विकास परवानगी प्रकरणांची छाननी संबंधित जिल्ह्याच्या शाखा कार्यालयाच्या स्तरावर केली जाते. त्यामुळे विनियम २.२.१२ नुसार Building / Layout Permission Scrutiny Fee ही संबंधित ग्रामपंचायतीऐवजी संबंधित नगर रचना विभागाच्या शाखा कार्यालयाकडे जमा करणे आवश्यक राहील.
३	2.2	2.2.13 Development Charges Development charges as required under Section 124 A of the Maharashtra Regional and Town Planning Act, 1966 shall be deposited with the Authority before issue of development permission/ commencement certificate. Such charges shall be calculated for area of each land parcel included in the development permission considering the rates in ASR and provisions mentioned in the said Act. Provided that, i) to ix) -----	विकास शुल्क भरून घेतलेली विकास परवानगी व्यपगत झाली असेल तर सुधारित परवानगीकडील सदरचे शुल्क समायोजित करण्याची तरतुद आहे. विकास परवानगीवेळी भरून घेण्यात येणारे विकास शुल्क हे संबंधित जागेचा / बांधकामाचा वापर व त्याचे क्षेत्र यावर अवलंबून असून मालकी हक्काशी संबंधित नाही. त्यामुळे कोणत्याही विकास परवानगीमध्ये वसूल केलेले विकास शुल्क हे त्या जागेशी निगडित असल्याने सदरची जागा मुळ मालकाने विकली तरी नवीन मालकास देखील सदरचे शुल्क समायोजित करता येऊ शकेल.



४	2.2	2.2.14-Premium Charges and Fire Infrastructure Charges. i) Premium Charges - Premium charges as may be required to be recovered under these regulations shall be paid to the Authority ----- ----- collected by the Authority shall be kept in a separate account and it shall be utilized for development of civic amenities and infrastructure. In case of Regional Plan area, 100% premium charges shall be paid to Government through the District offices of Town Planning and Valuation Department.	UDCPR मधील तरतुदीनुसार विकास परवानगी देताना प्राधिकरणाने आकारावयाच्या कोणत्याही अधिमूल्यतातील (Premium charges) शासनाचा हिस्सा विनियम २.२.१४ नुसार ५०% शासनाकडे जमा करणेबाबत तरतुद आहे. UDCPR मधील कोही तरतुदीमध्ये असा शासनाचा हिस्सा, शासन वेळोवेळी ठरवेल त्यानुसार राहील, असे नमूद आहे. उदा.विनियम ६.३, टेबल ६-G, नोट (viii) मध्ये Apportionment of such amount between Authority and Government shall be as decided by Government from time to time. असे नमूद आहे. संबंध, UDCPR मध्ये ज्या-ज्या ठिकाणी प्राधिकरणाने आकारावयाच्या कोणत्याही अधिमूल्यतातील (Premium charges) शासनाच्या हिस्स्याबाबत स्पष्टपणे टक्केवारी नमूद केलेली नसेल, त्या-त्या ठिकाणी शासनाचा हिस्सा विनियम २.२.१४ नुसार ५०% शासनाकडे जमा करणे आवश्यक राहील.								
५	2.7	2.7 Commencement of Work 2.7.1 - Commencement The commencement certificate/development permission, as approved, shall remain valid for 4 years in the aggregate but ----- Provided that, no such renewal shall be necessary if the work is commenced within the period of valid permission and such permission shall remain valid till the work is completed. For the purpose of this regulation, "Commencement" shall mean as under :- <table><tr><td>For a building work including additions and alterations.</td><td>Upto plinth level or where there is no plinth upto upper level of lower basement or still as the case may be.</td></tr><tr><td>For bridges and overhead tanks construction</td><td>Foundation and work up to the base floor/ underground floor</td></tr><tr><td>For underground works/</td><td>Foundation and work upto floor of underground floor.</td></tr><tr><td>For layout, sub-division and amalgamation</td><td>Final demarcation and provision of water bound macadam roads complete.</td></tr></table>	For a building work including additions and alterations.	Upto plinth level or where there is no plinth upto upper level of lower basement or still as the case may be.	For bridges and overhead tanks construction	Foundation and work up to the base floor/ underground floor	For underground works/	Foundation and work upto floor of underground floor.	For layout, sub-division and amalgamation	Final demarcation and provision of water bound macadam roads complete.	विनियम २.७.१ येथील तरतुदीचा मुख्य उद्देश हा, एखाद्या इमारतीचे विकासकाम सुरु झाल्याच्या पृष्ठवर्ष कोणता काळ विचारात घ्यावी, हा आहे. सुप हीसिंग प्रकल्पामधील सर्वच इमारतींची विकासकामे एकाच वेळी सुरु करून ती निश्चित कालमर्यादेमध्ये Plinth पर्यंत पूर्ण करणे, हे ह्या विनियमानुसार अपेक्षित नाही. त्यामुळे अशा प्रकारे विकास परवानगी मंजूर झाल्यानंतर एका वर्षामध्ये त्यामधील एखाद्या इमारतीचे बांधकाम Plinth पर्यंत पूर्ण झाले तरी, त्या प्रकल्पाचा विकासनाची सुरुवात (Commencement) झाल्याचे समजणे अपेक्षित आहे. सदर परवानगी ही संपूर्ण प्रकल्पासाठीची एकच परवानगी असल्याने ती भाग्यः अथवा काही इमारतीपुरती व्यपगत (Lapse) होण्याचा प्रश्न उद्भवत नाही.
For a building work including additions and alterations.	Upto plinth level or where there is no plinth upto upper level of lower basement or still as the case may be.										
For bridges and overhead tanks construction	Foundation and work up to the base floor/ underground floor										
For underground works/	Foundation and work upto floor of underground floor.										
For layout, sub-division and amalgamation	Final demarcation and provision of water bound macadam roads complete.										
६	3.3	3.3 Regulations for Land Sub-division and Layout 3.3.8 Access from the highways / classified roads (b) Width of roads to be considered while granting development permissions, unless indicated otherwise in Development Plan/ Regional Plan/ Planning Proposal / T.P. Scheme shall be as mentioned in table below:-	विनियम ३.१.६ नुसार नागरी स्वराज्य संस्थांच्या महणजेच महानगरपालिका/नगरपालिका/नगरपंचायती यांच्या हद्दीतून जाणारे सर्व वर्गीकृत रस्ते हे शहरस्तरीय रस्ते म्हणून विचारात घेणेबाबत तरतुद आहे. विनियम ३.३.८(ब) मधील तरतुदीनुसार, त्याखालील तक्त्यामध्ये नमूद केलेले विविध वर्गीकृत रस्ते व त्यांची रुंदी विकास योजना / प्रादेशिक योजना / नियोजन प्रस्ताव / नगर रचना योजना यांवर नमूद नसेल तर, सदर विनियमामध्ये नमूद केलेली विविध वर्गीकृत रस्त्यांची रुंदी विचारात घ्यावयाची आहे.								



		3.1.6 Development along Highways / Classified Roads The development along the highways shall be subject to the provisions of State Highways Act, 1965 and National Highway Act, 1956 and orders issued by Public Works Department, directives issued by Urban Development Department vide Resolution No.TPS-1819/UOR-36/19/UD-13, dated 5.8.2019 in this regard, from time to time. The highways passing through the cities shall be treated as city roads.	विकास योजना / नगर रचना योजना तयार करतवेळी आवश्यकतेनुसार रस्त्यांना रेंदीकरण दर्शविण्यात येते. या पार्श्वभूमीवर विनियम ३.३.८(ब) मधील तरतुदीनुसार, नगर विकास योजना / प्रादेशिक योजना / नियोजन प्रस्ताव / नगर रचना योजना यांमध्ये जाहीर केलेल्या रस्त्यांची विद्यमान रेंदी / रेंदीकरण दर्शविले असेल तर, अशावेळी त्याप्रमाणेची रेंदी अथवा रेंदीकरण विचारात घेण्याबाबत अन्यथा अशी रेंदी / रेंदीकरण दर्शविले नसेल तर, विनियम ३.३.८(ब) खालील तक्त्यामध्ये नमूद रेंदी विचारात घेणे आवश्यक राहिल.
७	4.11	4.11 Agricultural Zone ix) Farm houses shall be permitted subject to following conditions:- a) Minimum plot area for above use shall be 0.4 Ha. However, one farmhouse per land holding shall be permitted, irrespective of size of the land holding. d) The FSI shall not exceed 0.04 subject to a maximum built up area of 400sq.m. in any case. Only ground +1 floor structure with height not exceeding 9m. shall be permissible.	प्रस्तुत तरतुदीनुसार One farmhouse per land holding अनुज्ञेय आहे. त्यासाठी एकूण निव्वळ क्षेत्राच्या ०.०४ एकरा चढई क्षेत्र निर्देशांक (तथापि, कमाल बांधकाम क्षेत्र ४०० चौ.मी. च्या पर्यायित) अनुज्ञेय आहे. शेतधरामध्ये रहिवासी वापराबरोबर धान्य/छतसाख, शेतीची औजार, गुरांचा गोठा इ. अनुषंगीक (Accessory Buildings) वापरासाठी देखील बांधकामे करणे अपरिहार्य असते. बऱ्याचदा रहिवास व अन्य अनुषंगीक वापर हे स्वतंत्र इमारतींमध्ये करणे गरजेचे असते. विनियम ४.११(ix) नुसार शेतधरासाठी कमाल किती बांधकाम अनुज्ञेय होईल याबाबत तरतुद असून या बांधकामासाठीचा चढई क्षेत्र निर्देशांक एकाच इमारतीमध्ये वापरणे आवश्यक आहे, असे बंधन नाही. ही बाब विचारत येता कमाल अनुज्ञेय बांधकाम क्षेत्रापेकी रहिवास वापरासाठीचे बांधकाम एका इमारतीमध्ये व अनुषंगीक वापरासाठीचे बांधकाम त्या जागेमध्ये अन्य इमारतीमध्ये अनुज्ञेय करता येईल.
८	6.2	6.2 Regulations for Outside Congested Area (Non-Congested Area). 6.2.3 -Marginal distances for buildings of heights more than mentioned in Table No.6-D of Regulation No.6.2.1 (a) Front Margin - Front margin shall be as given in Table No. 6-D shall be applicable to a building irrespective of its height. 2.2.3- Building plans for Special Buildings The following additional information shall be furnished / indicated in the Building Plans in addition to the items (i) to (xv) of Regulation No. 2.2.7; a) Access to fire appliances/vehicles with details of vehicular turning circle and clear motorable access way around the building of minimum 6 m. width;	पुढील सामासिक अंतर व बाजूची / मागील सामासिक अंतरे यांमध्ये येणारे तरतुदीनुसार करणे आहे. विनियम ६.२.३(अ) नुसार, विशेष इमारतीसाठी (Special Building), अशा इमारतीची उंची विचारात न घेता पुढील (रस्त्याचे बाजूचे) सामासिक अंतर, इमारत रेषेमध्ये एकसुत्रता राहण्याच्या दृष्टीने, टेबल ६-ड मध्ये नमूद केल्यानुसार विचारात घ्यावयाचे आहे. तर पुढील सामासिक अंतर वागळता विनियम २.२.८(अ) व विनियम ३.३.९ नुसार बाजूची / मागील सामासिक अंतर किमान ६.०० मी. विचारात घेणे आवश्यक आहे.
९	6.2	6.2 Regulations for Outside Congested Area (Non-Congested Area). 6.2.3 (b) Side or rear marginal distance 9.31-ADDITIONAL REQUIREMENTS IN CASE OF HOUSING SCHEMES Following amenities shall be provided in any housing scheme and shall be counted in FSI. i) Fitness Centre, Crèche, society office cum letter box room, measuring area of about 20 sq.m.in scheme having minimum 100 flats and thereafter	विनियम क्र.६.२.३(ब) नुसार इमारतीची उंची भोक्तेवेळी ६.० मी. पर्यंतची स्टोल्ड पाकौंगची उंची वागळणेबाबत तरतुद आहे. पाकौंगमध्ये विनियम ९.३१ (i) ते (iii) नुसार अनुज्ञेय असलेली बांधकामे पाकौंगच्या वागात असल्यास, सधरचा वापर पाकौंग अनुषंगीक गृहीत धरून इमारतीच्या उंचीची गणना करतवेळी अशी पाकौंगची उंची वागळणेस बाधा नाही.



		additional 20 sq.m. area for every 300 flats. ii) Sanitary block for servants having maximum area of 3 sq.m. in schemes having minimum 100 flats and thereafter additional 3 sq.m. area for every 200 flats. iii) Drivers room of size 12 sq.m. with attached toilet in schemes having minimum 100 flats and thereafter additional 10 sq.m. area for every 300 flats iv) ----- v) -----	
१०	9.13	9.13 PODIUM Podium for parking of the vehicles and ---- may be permitted with following requirements / conditions: ii) Podium may be allowed at a distance of 6m. from front, side and rear of the plot boundary in case of special building, subject to provisions of Regulation No. 6.2.3.(c).	विनियम ६.२.३(अ) मधील तरतुदीच्या अनुषंगाने देण्यात आलेल्या स्पष्टीकरणानुसार, विशेष इमारतीकरिता (Special Building) पुढील (रस्त्याचे बाजूने) सामासिक अंतर, टेबल ६-D मध्ये नमूद केल्यानुसार सोडल्यानंतर तर अन्य बाजूनी ६.० मी. अंतर सोडल्यानंतर पोदीयमचे बांधकाम अनुज्ञेय करता येईल. तर Non- Special Building करिता विनियमानुसार आवश्यक किमान सामासिक अंतरे सोडून त्यानंतर पोदीयमचे बांधकाम अनुज्ञेय होईल.
११	9.27	9.27-PROVISION OF LIFT 9.27.1-Planning and Design At least one lift -----, it will not be necessary to raise the existing lift to the additional floor. 9.29.8 Fire lift Where applicable, fire lifts ----- consideration various factors like building population, floor area, compartmentation, etc.	सद्य विनियमानुसार १५.० मी. पेक्षा जास्त व २४.० मी. पर्यंत उंचीच्या इमारतीसाठी १ फायर लिफ्ट ठेवणेबाबत तरतुद आहे. अशा फायर लिफ्टव्यतिरिक्त सर्वसामान्य वापरासाठी अन्य अतिरीक्त लिफ्टची आवश्यकता नाही. तथापि, अशा फायर लिफ्टकरिता Fire NOC आवश्यक राहिल.
१२	9.28	9.28 Exit Requirements 9.28.8 Width of Stair Case –Table 9G 1. Residential Buildings. d. Multi-storied Residential Building above 24 m. height - 1.5 m.	UDCPR पूर्वी मंजूर झालेल्या तसेच भागशः / पूर्णतः भोगवट्या प्रमाणपत्र मिळालेल्या अथवा अद्यापि न मिळालेल्या इमारतीसाठी तत्कालिन नियमानुसार १.२० मी. रुंद जिना (Staircase) अस्तित्वात असेल आणि आता UDCPR नुसार मिळणाऱ्या चटई क्षेत्र निर्देशांकानुसार अतिरिक्त बांधकाम अनुज्ञेय होऊ शकते, परंतु इमारतीची उंची वाढून त्या उंचीसाठी सद्य विनियमातील तरतुदीनुसार १.५० मी. रुंदीचा जिना आवश्यक असेल. मात्र, Occupant load विचारात घेऊन परिगणना केल्यास, विनियम ९.२८.५ - Occupant Load व विनियम ९.२८.६ - Capacity of Exits यांमधील निकषानुसार Gross Floor Area कमाल ७५० चौ.मी. असेल, Occupant load नुसार एकूण Occupants ची संख्या विचारात घेता, १.२० मी. रुंदीच्या मर्यादित जिन्साची रुंदी वेळू शकते. अशा परिस्थितीत जागेवरील बीम्स, कॉलम्स यांच्या स्थानांमध्ये (Positions) बदल करता येणे शक्य नसल्यास, बाजूची गैरसोय दूर होण्याच्या दृष्टीने, विनियम क. ९.२८.८, टेबल ९-जी, अनु क्र. १(d) च्या प्रयोजनासाठी कोणत्याही मजल्यावरील बांधकाम क्षेत्र हे ७५० चौ.मी. पेक्षा कमी असेल तर १.२० मी. रुंदीचा जिना अनुज्ञेय होईल. तथापि, नियोजनात २४.० मी.च्या वरील विशेष इमारतीसाठी UDCPR नुसार Fire Staircase स्वतंत्रपणे प्रस्तावित असणेदेखील आवश्यक आहे.



१३	14.4	14.4 PRADHAN MANTRI AWAS YOJANA 14.4.1 For Development Plan area i) For developable zone. Conditions :- 3. The permissible FSI for such projects shall be the maximum building potential on the plot mentioned in Regulation No. 6.1 or 6.3 subject to maximum 2.5 which shall be treated as allowable basic FSI for such project. No premium FSI or TDR shall be required to be loaded for availing this FSI upto 2.5. However, where building potential as per Regulation No. 6.1 or 6.3 exceeds 2.5, in such cases permissibility of availing building potential above 2.5 shall be in the form of premium FSI or TDR or both which may be utilised for the permissible uses under this UDCPR.	UDCPR अंगणाल येणव्यापूर्वी विकसनशील विभागात PMAY योजनेकरिता मंजूर असलेल्या विनियमानुसार किमान १५.० मी. रुंद रस्त्यासन्मुख जागा असेल तर सरसकट २.५ चटई क्षेत्र निर्देशांक अनुज्ञेय होतऱा. विनियम १४.४.१ मधील अट क्र.३ नुसार PMAY साठी विनियम ६.१ किंवा विनियम ६.३ नुसार कमाल बांधकाम क्षमतेपर्यंत परंतु कमाल २.५ मर्यादपर्यंत मूळ चटई क्षेत्र निर्देशांक म्हणून अनुज्ञेय आहे. दाटवस्ती क्षेत्रात टेबल ६-A नुसार २.५ पर्यंत कमाल बांधकाम क्षमता ९ मी. व वरील रस्त्यावर तर दाटवस्ती क्षेत्राबाहेर टेबल ६-G नुसार २.५ पर्यंत कमाल बांधकाम क्षमता १५.० मी. व त्यावरील रस्त्यावर अनुज्ञेय आहे. म्हणजेच दाटवस्ती क्षेत्रात किमान ९.० मी रस्त्यावर तर दाटवस्ती क्षेत्राबाहेर किमान १५.० मी रस्त्यावर २.५ चटई क्षेत्र निर्देशांक मर्यादित PMAY अनुज्ञेय होईल. यापुढे टेबल ६-A किंवा टेबल ६-G नुसार रस्तावरील अपेक्षा अनुज्ञेय कमाल बांधकाम क्षमतेमधून असा २.५ चटई क्षेत्र निर्देशांक वजा केल्यानंतर राहणारी क्षमता प्रिमियम चटई क्षेत्र निर्देशांक अथवा टीडीआर अथवा शेन्ही बांधकाम, त्या भूखंडावर कमाल बांधकाम क्षमतेपर्यंत बांधकाम अनुज्ञेय राहील.				
१४	C-7	C-7. LICENSING 7.1 Technical Personnel to be licensed:- The Qualified technical personnel or group as given in regulations; No. C-2, C-3, C-4, C-5, C-6 shall be licensed with the Authority or District Offices of Town Planning Department and the license shall be valid for three calendar years ending 31st December after which it shall be renewed every three years. The technical person registered with the Authority shall be entitled to work within Authority's jurisdiction and those registered with district offices shall be entitled to work within jurisdiction of all Authorities as well as regional plan area of the respective district. C-7.2 Fees for Licensing- The annual licensing fees shall be as follows:- <table><tr><td>For Engineer, Structural Engineer and Town Planner.</td><td>Rs.3000/- For three years.</td></tr><tr><td>For Supervisor (1) and For Supervisor (2)</td><td>Rs.1500/- For three years.</td></tr></table>	For Engineer, Structural Engineer and Town Planner.	Rs.3000/- For three years.	For Supervisor (1) and For Supervisor (2)	Rs.1500/- For three years.	सदर विनियमात Technical Personnel च्या परवाना फी बाबत तरतुद नमूद आहे. तद्विधि, काही नियोजन प्राधिकरणांनी त्यांच्या सर्वसाधारण सभांमध्ये यापूर्वी ठरविलेली परवाना फी ही, सदर फी पेक्षा जास्त असल्याचे निदर्शनास आले आहे. आता सर्व प्राधिकरणांच्या स्तरावर बांधकाम परवाना ह्या BPMS या संगणक प्रणालीद्वारे देण्यात येणार असल्याने UDCPR नुसार संपूर्ण राज्यात एकसुत्रता राहण्याच्या दृष्टीने संबंधित महानगरपालिका / नगरपरिषदा / नगरपंचायती तसेच इतर प्राधिकरणे इ. खोली या विनियमामधील तरतुदीपेक्षा वेगळी परवाना फी आकारू नये.
For Engineer, Structural Engineer and Town Planner.	Rs.3000/- For three years.						
For Supervisor (1) and For Supervisor (2)	Rs.1500/- For three years.						
१५	2.2	2.2 Procedure for Obtaining Development Permission / Building Permission / Commencement Certificate 2.2.13 Development Charges Development charges as required under Section 124 A of the Maharashtra Regional and Town Planning Act, 1966 shall be deposited with the Authority before issue of development permission / commencement certificate. Provided that ii) in case of revised permission, where development is commenced in pursuance of earlier permission, development charges shall be levied on the	या विनियमानुसार विकास शुल्क आकारणी ही क्लिंटअप परिघावर अपेक्षित आहे. महाराष्ट्र प्रादेशिक व नगर रचना अधिनियम, १९६६ च्या कलम १२४ A ची तरतुद पाहता, ज्या विकासासाठी विकास परवानगीची आवश्यकता असते त्या सर्व विकासासाठी विकास शुल्क आकारणे अपेक्षित आहे. त्यानुसार UDCPR प्रमाणे P-line मध्ये येणारे संपूर्ण बांधकाम क्षेत्रावर (Built-up area) विकास शुल्क आकारणे आवश्यक ठरते. अधिनियमातील कलम १२४ A नुसार, ज्या विकासासाठी विकास परवानगीची आवश्यकता असते त्या सर्व विकासासाठी विकास शुल्क आकारणे अपेक्षित आहे. P-line मध्ये येणारे क्षेत्र चटई क्षेत्र निर्देशांकासाठी				



		land and built-up area, over and above the area covered in the earlier permission.	(Ancillary FSI सह) विचारात घेतले जाते. त्यामुळे चटई क्षेत्र निर्देशांकाच्या प्रमाणातच विकास शूल्क आकारणी होत आहे. त्यानुसार UDCPR प्रमाणे P-line मध्ये येणारे संपूर्ण बांधकाम क्षेत्रावर (Built-up area) विकास शूल्क आकारणे आवश्यक आहे. तसेच कालम १२४ ब (१) मध्ये जमिनी व इमारती यांच्या वापराचे वर्गीकरण करणेबाबत तरतुद आहे. त्यानुसार जमिनी व इमारती यांच्या वापराचे वर्गीकरण निश्चिंत करून, ज्या प्रधान / प्रमुख कारणासाठी त्याचा वापर प्रस्तावित आहे, त्याकरिताचे दरानुसार जमीन व इमारतीसाठी विकास शूल्क आकारणी करणे आवश्यक राहिल.
१६	6.3	6.3 PERMISSIBLE FSI Table 6G Note xii) In case plots having approach by dead end road, (point access) the potential of plot mentioned in above table shall be permissible if length of such access road does not exceed 100 m.	मुख्य रस्त्यापासून १०० मी. आत असणाऱ्या Dead end अथवा point access असणाऱ्या मिळकतीकरिता विनियम ६.३, Table 6-G, Note xii नुसार मुख्य रस्त्याप्रमाणे चटई क्षेत्र निर्देशांक अनुज्ञेय आहे. UDCPR मधील इतर तरतुदीनुसार इमारतीची उंची रस्त्यारुंदीसापेक्ष अनुज्ञेयतेबाबत विशिष्ट अशी तरतुद नाही. विनियम ३.३.९ - Access Provision for Special Buildings of Regulation No.13(93)(xiv) मधील तरतुद, इमारतीच्या उंचीबाबत विनियम ६.१०.१ मधील तरतुद, अशा तरतुदी एकत्रितपणे विचारात घेऊन परवानगी देणे आवश्यक आहे. तर पुणे महानगरपालिकेच्या बाबतीत विनियम ३.३.९ मधील तरतुद, इमारतीच्या उंचीबाबत विनियम ६.१०.१ मधील तरतुद आणि पुणे महानगरपालिका क्षेत्रासाठीचा विशिष्ट विनियम १०.१.१ येथील इमारत उंचीची तरतुद, अशा तरतुदी एकत्रितपणे विचारात घेऊन परवानगी देणे आवश्यक आहे.
१७	14.8	14.8 Urban Renewal Scheme 14.8.7 Development of Reservations contemplated in Development Plan falling in the area of URC Reg. No.14.8.14 (xvi) Any aspect of development under URS, which is not specified under this Regulation shall be governed by the relevant provisions of the UDCPR.	विनियम १४.८.७ नुसार नागरी पुनरुत्थान योजनेमधील आरक्षित जागेवर अंमलबजावणी संस्थेने बांधकाम करून महानगरपालिकेस सुविधा हस्तांतरित करणेबाबत तरतुद आहे. सदर तरतुदीनुसार बांधीव घटक त्या-त्या प्रमाणात बांधून देण्याच्या बदल्यात मोबदला कशाप्रकारे अनुज्ञेय होईल, याबाबत स्पष्टीकरण होण्याच्या दृष्टीने विनियम १४.८.१४(xvi) नुसारची तरतुद विचारात घेता, URC मधील आरक्षणातील बांधीव क्षेत्र विकसित करून हस्तांतरित करण्याच्या मोबदल्यात विनियम ११.२.५ नुसार Construction Amenity TDR अनुज्ञेय करता येईल.



(Signature)
(किशोर गोखले)

अवर सचिव, महाराष्ट्र शासन



महाराष्ट्र शासन
नगर विकास विभाग

चौथा मजला, मुख्य इमारत, मंत्रालय,
मादाम कामा मार्ग, हुतात्मा राजगुरू चौक, मुंबई - ४०० ०३२.

दूरध्वनी क्र ०२२-२२७९४१९६

Email ID : kishor.gokhale@gov.in

जा.क्र.टिपीएस-१८२१/१३३/नवि-१३

दिनांक : २३.१२.२०२१

प्रति,

✓ मा.संचालक, नगर रचना,
महाराष्ट्र राज्य, पुणे.

विषय :- एकत्रिकृत विकास नियंत्रण व प्रोत्साहन नियमावली

मंजूर एकत्रिकृत विकास नियंत्रण व प्रोत्साहन नियमावलीमधील विनियम क्र.२.५-
आरेखिय त्रुटीसंदर्भात चूक दुरुस्ती करण्याचे अधिकाराबाबत स्पष्टीकरण देणेबाबत...

संदर्भ :- आपलेकडील पत्र क्र प्र.क्र.४४/२१, दि.१५.०७.२०२१.

महोदय,

रायगड जिल्ह्यातील पेण नगरपरिषद व ठाणे जिल्ह्यातील कुळगाव-बदलापूर नगरपरिषद या दोन नगरपरिषदांच्या हद्दीमधील काही जमिनींचे अनुषंगाने मंजूर विकास योजनेमध्ये झालेल्या आरेखिकीय चूक दुरुस्तीचे प्रस्ताव संबंधित नगरपरिषदांनी संचालनालयास सादर केले असून सदर प्रस्तावांमध्ये संदर्भित पत्रान्वये मार्गदर्शन अपेक्षित आहे.

या अनुषंगाने आपणांस खालीलप्रमाणे कळविण्याच्या मला सूचना आहेत.

शासनाने बृहन्मुंबई महानगरपालिका, बृहन्मुंबई महानगरपालिका क्षेत्रातील अन्य नियोजन प्राधिकरणे आणि अन्य काही विशिष्ट क्षेत्र वगळता, राज्यातील उर्वरित सर्व नियोजन प्राधिकरणे तसेच प्रादेशिक योजना क्षेत्राकरिता (ग्रामीण भाग) एकत्रिकृत विकास नियंत्रण व प्रोत्साहन नियमावलीस (Unified DCPR) महाराष्ट्र प्रादेशिक नियोजन व नगर रचना अधिनियम, १९६६ मधील तरतुदीनुसार दि.०२/१२/२०२० रोजीच्या अधिसूचनेद्वारे अंतिम मंजूरी देऊन ती दि.०३/१२/२०२० पासून लागू करण्यात आली आहे. उक्त मंजूर एकत्रिकृत विकास नियंत्रण व प्रोत्साहन नियमावलीनुसार (विनियम क्र.२.५) आरेखिय त्रुटी संदर्भात चूक दुरुस्तीचे अधिकार विभागीय सह संचालक, नगर रचना यांना प्रदान केलेले आहेत.

काही विकास योजना मंजूरीच्या अधिसूचनांमध्ये विकास योजनेतील आरेखिकीय त्रुटीची दुरुस्ती संचालक, नगर रचना यांचे पूर्वमान्यतेने संबंधित मुख्याधिकारी यांनी करण्याबाबत टिप अंतर्भूत करण्यात आली आहे. मंजूर UDCPR मधील विनियम क्र.१.२ मधील तरतुदीनुसार अंमलात असलेल्या तत्कालीन सर्व नियमावली / विशेष विनियम रद्द होतील, अशी तरतुद आहे. मात्र आरेखिकीय त्रुटी दुरुस्तीबाबतची तरतुद ही तत्कालीन मंजूर नियमावलीतील नसून विकास योजना मंजूरीच्या अधिसूचनेतील तरतुद आहे. त्यामुळे अशी तरतुद विनियम क्र.१.२

नुसार रद्द होणार नसून अशी तरतुद अंमलात राहणार आहे. त्यामुळे विकास योजना मंजूरीच्या अधिसूचनेत आरेखकीय त्रुटी दुरुस्तीबाबत विशेष टिप अंतर्भूत असल्यास, अशा टिपेमधील तरतुदीनुसार संचालनालयाचे स्तरावरून कार्यवाही होणे अभिप्रेत व आवश्यक आहे.

ज्या विकास योजना मंजूरीच्या अधिसूचनेत आरेखकीय त्रुटी दुरुस्तीबाबतची तरतुद अंतर्भूत नसेल, अशावेळी UDCPR मधील विनियम क्र. २.५ नुसार कार्यवाही होणे अभिप्रेत आहे.

आपला,



(किशोर बि. गोखले)

अवर सचिव, महाराष्ट्र शासन

प्रत :-

१. सह संचालक, नगर रचना, पुणे/औरंगाबाद/कोकण/नागपूर/नाशिक/अमरावती विभाग.
२. सहायक संचालक, नगर रचना/नगर रचनाकार, सर्व शाखा कार्यालये.
३. अवर सचिव नवि-११/नवि-३०/कक्ष अधिकारी नवि-९/ कक्ष अधिकारी नवि-१२.



महाराष्ट्र शासन
नगर विकास विभाग,
चौथा मजला, मुख्य इमारत, मंत्रालय,
दाम फाया मार्ग, हाऊस राजगुरु चौक, मुंबई - ४०० ०३२.

Email ID: d.rahane@mah.gov.in
दिनांक: ०६ सप्टेंबर, २०२२

क्र.टिपीएस-२४२२/०३१/प्र.क्र.६७/२०२२/नवि-०९,
प्रति,
भा. महानगर आयुक्त,
नागपूर महानगर प्रदेश विकास प्राधिकरण,
नागपूर.

विषय:- एकत्रिकृत विकास नियंत्रण व प्रोत्साहन नियमावली
नागपूर महानगर प्रदेश विकास प्राधिकरणासाठी लागू असलेल्या नियम
क्र.१०.४.३ बाबत मार्गदर्शन होणेबाबत.

- संदर्भ:-१. आपले नगर रचना संचालनालयास पत्र क्र.मं.वि.यो./ना.म.क्षे/ससंनर (नामप्रविप्रा)
/६४७५, दि.०६/०१/२०२२.
२. आपले नगर रचना संचालनालयास पत्र क्र.मं.वि.यो./ना.म.क्षे/ससंनर (नामप्रविप्रा)
/२५६२, दि.०८/०३/२०२२.
३. संचालक नगर रचना, महाराष्ट्र राज्य, पुणे यांचे पत्र क्र.डिटीपी./१३१८/३१२२
टिपीव्ही-२/१९२३, दि.०६/०४/२०२२.

महोदय,

विषयांकित प्रकरणी आपण संदर्भित पत्र क्र.१ व २ च्या पत्रान्वये एकत्रिकृत विकास नियंत्रण व प्रोत्साहन नियमावलीमधील नागपूर महानगर प्रदेश विकास प्राधिकरणासाठी लागू असलेली तरतुद क्र.१०.४.३ ही फक्त ई.पी.२४९ साठी लागू आहे. किंवा सदरची तरतुद सरसकट पणे वापरता येईल, याबाबत संचालक नगर रचना, महाराष्ट्र राज्य, पुणे यांचेकडे मार्गदर्शन अपेक्षिलेले आहे.

UDCPR मधील कोणत्याही विनियमा संदर्भात संचालनालयाचे मार्गदर्शन घेणेबाबत तरतुद दिसून येत नसल्याने याबाबत त्यांचे मत नोंदवून UDCPR मधील विनियम क्र.१.९ (v) अंतर्गत शासनाकडून स्पष्टीकरणात्मक, मार्गदर्शन करण्याची विनंती शासनास केलेली आहे. या संदर्भात आपणास खालील प्रमाणे कळविण्याचे मला निदेश आहेत.

शासनाने दि.०२/१२/२०२० रोजी मंजूर केलेल्या एकत्रिकृत विकास नियंत्रण व प्रोत्साहन नियमावली मधील प्रकरण क्र.१० शहराकरीता विशिष्ट विनियम (City Specific Regulations) अंतर्भूत केलेला आहे. त्यातील नागपूर महानगर प्रदेश विकास प्राधिकरणाच्या क्षेत्रासाठी केलेल्या विनियम क्र.१०.४.३ मधील तरतुद, शासनाने नागपूर महानगर प्रदेश विकास प्राधिकरणासाठी विकास योजना मंजुरीबाबत निर्गमित अधिसूचनेतील विनियम क्र.२५.६ (xxxx) चा उल्लेख असणाऱ्या क्षेत्रासाठी लागू असल्याबाबत स्पष्ट केलेले आहे. यास्तव सदर तरतुद ही फक्त नागपूर महानगर प्रदेश विकास प्राधिकरणासाठी मंजूर विकास योजनेच्या अधिसूचनेतील ई.पी. क्र.२४९ मध्ये नमुद क्षेत्राकरिता लागू आहे.

त्याचा विचार करता, सदरचा विनियम क्र.१०.४.३ हा नागपूर महानगर प्रदेश विकास प्राधिकरणाच्या मंजूर विकास योजनेतील कृषी / हरीत विभागातील संपूर्ण क्षेत्रासाठी सरसकटपणे लागू करता येणार नाही,

आपका,


(सु. म. शिंदे)

कार्यासन अधिकारी, महाराष्ट्र शासन

प्रत:-

१. मा. संचालक नगर रचना, महाराष्ट्र राज्य, पुणे.
२. मा. सह संचालक नगर रचना, नागपूर विभाग, नागपूर.
३. मा. सहायक संचालक नगर रचना, नागपूर शाखा, नागपूर.
- ✓ ४. मा. अवर सचिव (नवि-१३), नगर विकास विभाग, मंत्रालय, मुंबई.
५. निवड नस्ती (नवि-१३)



महाराष्ट्र शासन

नगर विकास विभाग

मादाम कामा मार्गे, हुतात्मा राजगुरु चौक, मंत्रालय, मुंबई - ४०० ०३२.

Email ID : sould12-mh@mah.gov.in

आदेश क्र. ८

क्र.नांक:-टिपीएस-१८१८/प्र.क्र.२३६/१८(भाग-२)/नवि-१३ दिनांक:-२६ सप्टेंबर, २०२२.

विषय :- एकत्रिकृत विकास नियंत्रण व प्रोत्साहन नियमावली (UDCPR) मंजूर
नियमावलीमधील विनियम क्र. 1.9(v) अन्वये स्पष्टीकरण देणेबाबत.

संदर्भ :- १) शासनाचे आदेश क्र.टिपीएस-१८१८/प्र.क्र.२३६/१८(भाग-२) /नवि-१३.

दिनांक १४/१२/२०२१. (स्पष्टीकरण आदेश क्र. १)

२) शासनाचे आदेश क्र.टिपीएस-१८२१/३४०/प्र.क्र.६८/२१ /नवि-१३,

दिनांक १०/५/२०२१. (स्पष्टीकरण आदेश क्र. २)

३) शासनाचे आदेश क्र.टिपीएस-१२२१/९९०/प्र.क्र.४४/२१ /नवि-१२,

दिनांक १०/६/२०२१. (स्पष्टीकरण आदेश क्र. ३)

४) शासनाचे आदेश क्र.टिपीएस-१२२१/१०३९/प्र.क्र.४२/२१ /नवि-१२,

दिनांक १४/६/२०२१. (स्पष्टीकरण आदेश क्र. ४)

५) शासनाचे आदेश क्र.टिपीएस-१८१८/प्र.क्र.२३६/१८(भाग-२) /नवि-१३,

दिनांक १७/९/२०२१. (स्पष्टीकरण आदेश क्र. ५)

६) शासनाचे आदेश क्र.टिपीएस-१८१८/प्र.क्र.२३६/१८(भाग-२) /नवि-१३,

दिनांक २३/१२/२०२१. (स्पष्टीकरण आदेश क्र. ६)

७) शासनाचे आदेश क्र.टिपीएस-१८२१/९३३/नवि-१३, दिनांक २३/१२/२०२१.

(स्पष्टीकरण आदेश क्र. ७)

ज्याअर्थी, शासनाने अधिसूचना क्र. टिपीएस १८१८ / प्र.क्र.३३६/१८/कलम ३७(१कक) (ग)
व व लम २०(४)/नवि-१३, दि.०२/१२/२०२० अन्वये राज्यातील सर्व नियोजन प्राधिकरणे (काही
अपवाद वगळता) आणि प्रादेशिक योजना क्षेत्राकरिता एकत्रिकृत विकास नियंत्रण व प्रोत्साहन
नियमावली मंजूर केली असून ती दि. ०३/१२/२०२० पासून अंमलात आली आहे;

क्षेत्रांसाठी दाखल, पायाभूत साई सुविधा पुराव्याच्या अनुषंगान संदर्भ क्र.१ येथील शासन निदेशानुसार अधिमूल्य आकारणी करणे आवश्यक असल्याचे शासनाचे मत झाले आहे.

सबब, शासन नगर विकास विभागाने निर्गमित केलेले निदेश क्र. टिपीएस-२४१६/प्र.क्र.४३/१६/नवि-१, दि.२०/४/२०१६ मध्ये मुद्दा क्र. 'क' च्या नंतर नवीन मुद्दा क्र. 'क-१' खालीलप्रमाणे अंतर्भूत करण्यात येत आहे.

"क-१) प्राधिकरणांनी, एकत्रिकृत विकास नियंत्रण व प्रोत्साहन नियमावलीमधील विनियम क्र.२.३ (vi) च्या स्वेच्छाधिकाराच्या तरतुदीनुसार जमिन वापर विभाग हद्द सुधारीत करताना उपरोक्त 'अ' प्रमाणे अधिमूल्य वसूल करण्याची कार्यवाही करावी."

उपरोक्त सुधारीत तरतुद हो या शासन निदेशाच्या दिनांकापासून लागू लागू अंमलात आणण्यासाठी राज्यातील सर्व नियोजन प्राधिकरणे/नगर रचना विभागाची सर्व शाखा कार्यालये/सर्व जिल्हाधिकारी/इतर प्राधिकरणे यांना उक्त अधिनियमाचे कलम १५४ अन्वये निदेश देण्यात येत आहेत.

महाराष्ट्राचे राज्यपाल यांच्या आदेशानुसार व नांवाने,



(सुनिल मरठे)

सह सचिव, महाराष्ट्र शासन

प्रत :-

- १) मा.मुख्यमंत्री महोदय यांचे अपर मुख्य सचिव, मंत्रालय, मुंबई.
- २) मा.उप मुख्यमंत्री महोदय यांचे सचिव, मंत्रालय, मुंबई.
- ३) मा.विरोधी पक्षनेता, विधानपरिषद / विधानसभा, महाराष्ट्र विधानमंडळ सचिवालय, मुंबई.
- ४) मा.उपसभापती, महाराष्ट्र विधानपरिषद, महाराष्ट्र विधानमंडळ सचिवालय, मुंबई.
- ५) मा.उपाध्यक्ष, महाराष्ट्र विधानसभा, महाराष्ट्र विधानमंडळ सचिवालय, मुंबई.
- ६) अपर मुख्य सचिव (नवि-१), नगर विकास विभाग, मंत्रालय, मुंबई.
- ७) संचालक (नगर रचना) तथा सह सचिव, नगर विकास विभाग, मंत्रालय, मुंबई.
- ८) सह सचिव तथा सह संचालक (नगर रचना), नगर विकास विभाग, मंत्रालय, मुंबई.

प्रति :-

- १) संचालक, नगर रचना, महाराष्ट्र राज्य, पुणे.
- २) सर्व विभागीय आयुक्त.
- ३) सर्व विभागीय सहसंचालक, नगर रचना.
- ४) सर्व आयुक्त, महानगरपालिका.
- ५) सर्व महानगर आयुक्त, महानगर प्रदेश विकास प्राधिकरणे / विशेष नियोजन प्राधिकरणे.
- ६) मुख्य कार्यकारी अधिकारी, कोल्हापूर नागरी क्षेत्र विकास प्राधिकरण, कोल्हापूर.

७. संचालक (नगर रचना) तथा सह सचिव, नगर विकास विभाग, मंत्रालय, मुंबई.
 ८. सह सचिव तथा सह संचालक (नगर रचना), नगर विकास विभाग, मंत्रालय, मुंबई.

प्रति :-

- १) संचालक, नगर रचना, महाराष्ट्र राज्य, पुणे.
- २) सर्व विभागीय आयुक्त.
- ३) सर्व विभागीय सहसंचालक, नगर रचना.
- ४) सर्व आयुक्त, महानगरपालिका.
- ५) सर्व महानगर आयुक्त, महानगर प्रदेश विकास प्राधिकरणे / विशेष नियोजन प्राधिकरणे.
- ६) मुख्य कार्यकारी अधिकारी, कोल्हापूर नागरी क्षेत्र विकास प्राधिकरण, कोल्हापूर.
- ७) सर्व महानगर आयुक्त, नवनगर प्रदेश विकास प्राधिकरणे.
- ८) मुख्य कार्यकारी अधिकारी, सर्व जिल्हापरिषद.
- ९) मुख्य अधिकारी सर्व नगरपरिषदा / नगरपंचायती.
- १०) सर्व जिल्हाधिकारी.
- ११) सहायक संचालक, नगर रचना / नगर रचनाकार, नगर रचना व मूल्यनिर्धारण विभाग, सर्व शाखा कार्यालये.
- १२) अवसल सचिव, नवि-११ / नवि-१३ / नवि-३०, कक्ष अधिकारी, नवि-९, नगर विकास विभाग, मंत्रालय, मुंबई.
- १३) कक्ष अधिकारी (नवि-२९), नगर विकास विभाग, मंत्रालय, मुंबई.
 /- सोवतचे आदेश या विभागाच्या संकेतस्थळावर प्रसिध्द करावेत.
- १४) कक्ष अधिकारी, माहिती व तंत्रज्ञान विभाग, मंत्रालय, मुंबई.
 /- सदरचे आदेश शासनाच्या संकेतस्थळावर प्रसिध्द करावेत.
- १५) निवड नस्ती, कार्यासन (नवि-१२).



महाराष्ट्र शासन

नगर विकास विभाग

मोदाम कामा मार्ग, हुतात्मा राजगुरु चौक, मंत्रालय, मुंबई - ४०० ०३२.

Email ID : soudd12-mhv@mah.gov.in

क्रमांक:- टिपीएस-१२२२/१५४४/प्र.क्र.१२८/२२/नवि-१२ दिनांक :- २६ सप्टेंबर, २०२२.

प्रति,

आयुक्त,

वसई-विरार शहर महानगरपालिका,

विरार.

विषय :- एकात्रकृत विकास नियंत्रण व प्रोत्साहन नियमावली (UDCPR) मधील विनियम १.९ (v) नुसार स्पष्टीकरण मिळणेबाबत...

संदर्भ :- १) आपले शासनास पत्र क्र.व.वि.श.म./नर/शा/५४३/२०२२-२३,
दि.२८/६/२०२२ रोजीचे पत्र.

२) शासन स्पष्टीकरण क्रमांक टिपीएस-१२२२/१५४४/प्र.क्र.१२८/२२/
नवि-१२, दिनांक २६/९/२०२२.

३) शासन निदेश क्र.टिपीएस-१२२२/१५४४/प्र.क्र.१२८/२२/नवि-१२,
दिनांक २६/९/२०२२.

महोदय,

विषयांकित प्रकरणी संदर्भित पत्र क्र. १ अन्यथे आपण वसई-विरार उपनगराच्या मंजूर विकास योजनेमधील मौ.चुळणे येथील स.नं.८६/१ व ८६/२ या जमिनीचे ७/१२ उता-यानुसार एकूण क्षेत्र ५१६०.०० चौ.मी. असून, त्यापैकी ताब्यात नसलेले ३९.६७ चौ.मी. क्षेत्र वजा जाता उर्वरित ५१४०.०० चौ.मी. क्षेत्रापैकी २९९९.६९ चौ.मी. (५८.३६%) क्षेत्र रहिवास वापर विभागामध्ये व २१४०.०० चौ.मी. (४१.६४%) क्षेत्र हरित क्षेत्रामध्ये समाविष्ट असून, एकात्रकृत विकास नियंत्रण नियमावलीमधील विनियम क्र.२.३(vi) नुसार कार्यवाही करणेस तसेच सदरच्या तरतुदीनुसार विकास परवानगी कामी अधिमूल्य रक्कम कशा प्रकारे वसूल करून घेणेत याबा, याबाबत एकात्रकृत विकास नियंत्रण नियमावलीमधील विनियम क्र.१.९ (v) नुसार स्पष्टीकरण मिळणेस शासनास विनंती केली आहे. त्या अनुषंगाने आपणांस खालीलप्रमाणे कळविण्याचे मला आदेश आहेत.

“ एकत्रिकृत विकास नियंत्रण व प्रोत्साहन नियमावलीमधील विनियम क्र.२.३ (vi) च्या नुषंगाने शासनाने संदर्भाधिन क्र. २ अन्वये स्पष्टीकरण निर्गमित केले असून, सदर विनियमांतर्गत धिमुल्य आकारणीबाबत देखील संदर्भ क्र. ३ अन्वयेचे निदेश शासनाने पारीत केले असून, सदर तरणी त्यानुसार आपले स्तरावर पुढील प्रमाणे कार्यवाही करणेत यावी.”

आपला,



(पु.म.शिंदे)

कार्यासन अधिकारी

:-

- १) संचालक, नगर रचना, महाराष्ट्र राज्य, पुणे.
- २) सहसंचालक, नगर रचना, कोकण विभाग, कोकण भवन, नवी मुंबई.
- ३) सहाय्यक संचालक नगर रचना, पालघर शाखा, जि.पालघर.

महाराष्ट्र प्रादेशिक नियोजन व नगर रचना
अधिनियम, १९६६,
जमिन वापर बदलासाठी आकारावयाच्या
अधिमुल्यासंबंधीच्या कलम १५४ अन्वये
निदेशामध्ये सुधारणा करणेबाबत...

महाराष्ट्र शासन
नगर विकास विभाग,
घोधा मजला, मुख्य इमारत, मंत्रालय,
मादाम कामा मार्ग, हुतात्मा राजगुरू चौक,
मुंबई - ४०० ०३२.
शासन निदेश क्र. टिपीएस-१८१८/प्र.क्र.२३६/१८(भाग-२)/नवि-१३,
दिनांक :- २६ सप्टेंबर, २०२२

वाचा:- १) शासन नगर विकास विभागाकडील शासन निदेश क्र.टिपीएस-
२४१६/प्र.क्र.४३/१६/नवि-९, दि.२०/४/२०१६.
२) शासनाकडील स्पष्टीकरण क्र. टिपीएस-१८१८/प्र.क्र.२३६/१८(भाग-२)/नवि-१३,
दिनांक :- २६ सप्टेंबर, २०२२

प्रस्तावना :- मंजूर विकास योजनेमधील शेती / ना-विकास विभागातील जमिन अथवा
आरक्षणाखालील जमिन रहिवास/ वाणिज्य अथवा इतर विकसनक्षम वापर विभागामध्ये अंतर्भूत
करणेकामी, महाराष्ट्र प्रादेशिक व नगर रचना अधिनियम, १९६६ चे कलम ३७(१) अन्वयेचे
फेरबदल प्रस्ताव तसेच उक्त अधिनियमाचे कलम ५० अन्वये विकास योजनेमधील आरक्षणे
वगळून त्या जागेवर लगतच्या वापर विभागानुसार वापर अनुज्ञेय करावयाच्या प्रस्तावाच्या
अनुषंगाने फेरबदल केल्यानंतर, पायाभूत सुविधा खर्च उभा करण्याच्या दृष्टीने अधिमुल्य
आकारणीबाबत शासन नगर विकास विभागाने दि.२०/४/२०१६ रोजी उक्त अधिनियमाच्या कलम
१५४ अन्वये निदेश पारित केलेले आहेत.

०२. शासनाने दिनांक २/१२/२०२० रोजी मंजूर केलेल्या एकाग्रित विकास नियंत्रण व प्रोत्साहन
नियमावलीमधील विनियम क्र.२.३ नुसार प्राधिकरणास प्राप्त स्वेच्छाधिकार शक्तीमधील खंड (vi)
च्या तरतुदीनुसार, विकास योजनेमधील वापर विभागाच्या हद्दीच्या रेषेमुळे एखादा भूखंड विभाजित
होत असल्यास, अशा वापर विभागाची हद्द सुधारित करता येऊ शकते. यानुषंगाने अशा हद्दी
विचारात घेतांना त्या कशा रीतीने ठरावल्यात, या विषयीचा अन्वयार्थ शासनाने संदर्भ क्र.२ येथील
आदेशान्वये चिह्नित केला आहे. उपरोक्त तरतुदी अंतर्गत जमिन वापर विभागाची हद्द निश्चित
करण्यामुळे, ज्या प्रकरणांचे क्षेत्र हे विकसनक्षम विभागात नव्याने समाविष्ट होत असेल अशा

क्षेत्रांसाठी देखिल, पायाभूत सोडून सर्वांधा पूर्वावण्याच्या अनुषंगान संदर्भ क्र.१ येथील शासन निदेशानुसार अधिमूल्य आकारणी करणे आवश्यक असल्याचे शासनाचे मत झाले आहे.

सबब, शासन नगर विकास विभागाने निर्गमित केलेले निदेश क्र. टिपीएस-२४१६/प्र.क्र.४३/१६/नवि-९, दि.२०/४/२०१६ मध्ये मूढा क्र. 'क' च्या नंतर नवीन मूढा क्र. 'क-१' खालीलप्रमाणे अंतर्भूत करण्यात येत आहे.

“क-१) प्राधिकरणांनी, एकत्रिकृत विकास नियंत्रण व प्रोत्साहन नियमावलीमधील विनियम क्र.२.३ (vi) च्या स्वेच्छाधिकार्याच्या तरतुदीनुसार जमिन वापर विभाग हद्द सुधारीत करताना उपरोक्त 'अ' प्रमाणे अधिमूल्य वसूल करण्याची कार्यवाही करावी. -”

उपरोक्त सुधारीत तरतुद ही या शासन निदेशाच्या दिनांकापासून लागू लागू अंमलात आणण्यासाठी राज्यातील सर्व नियोजन प्राधिकरणे/नगर रचना विभागाची सर्व शाखा कार्यालये/सर्व जिल्हाधिकारी/इतर प्राधिकरणे यांना उक्त अधिनियमाचे कलम १५४ अन्वये निदेश देण्यात येत आहेत.

महाराष्ट्राचे राज्यपाल यांच्या आदेशानुसार व नावाने,



(सुनिल मरठे)

सह सचिव, महाराष्ट्र शासन

प्रत :-

- १) मा.मुख्यमंत्री महोदय यांचे अपर मुख्य सचिव, मंत्रालय, मुंबई.
- २) मा.उप मुख्यमंत्री महोदय यांचे सचिव, मंत्रालय, मुंबई.
- ३) मा.विरोधी पक्षनेता, विधानपरिषद / विधानसभा, महाराष्ट्र विधानमंडळ सचिवालय, मुंबई.
- ४) मा.उपसभापती, महाराष्ट्र विधानपरिषद, महाराष्ट्र विधानमंडळ सचिवालय, मुंबई.
- ५) मा.उपाध्यक्ष, महाराष्ट्र विधानसभा, महाराष्ट्र विधानमंडळ सचिवालय, मुंबई.
- ६) अपर मुख्य सचिव (नवि-१), नगर विकास विभाग, मंत्रालय, मुंबई.
- ७) संचालक (नगर रचना) तथा सह सचिव, नगर विकास विभाग, मंत्रालय, मुंबई.
- ८) सह सचिव तथा सह संचालक (नगर रचना), नगर विकास विभाग, मंत्रालय, मुंबई.

प्रति :-

- १) संचालक, नगर रचना, महाराष्ट्र राज्य, पुणे.
- २) सर्व विभागीय आयुक्त.
- ३) सर्व विभागीय सहसंचालक, नगर रचना.
- ४) सर्व आयुक्त, महानगरपालिका.
- ५) सर्व महानगर आयुक्त, महानगर प्रदेश विकास प्राधिकरणे / विशेष नियोजन प्राधिकरणे.
- ६) मुख्य कार्यकारी अधिकारी, कोल्हापूर नागरी क्षेत्र विकास प्राधिकरण, कोल्हापूर.

- ७) सर्व महानगर आयुक्त, नवनगर प्रदेश विकास प्राधिकरणे,
 ८) मुख्य कार्यकारी अधिकारी, सर्व जिल्हापरिषद,
 ९) मुख्याधिकारी सर्व नगरपरिषदा / नगरपंचायती,
 १०) सर्व जिल्हाधिकारी,
 ११) सहायक संचालक, नगर रचना / नगर रचनाकार, नगर रचना व मूल्यनिर्धारण विभाग, सर्व शाखा कार्यालये,
 १२) अवर सचिव, नवि-११ / नवि-१३ / नवि-३०, कक्ष अधिकारी, नवि-९, नगर विकास विभाग, मंत्रालय, मुंबई.
 १३) कक्ष अधिकारी (नवि-२९), नगर विकास विभाग, मंत्रालय, मुंबई.
 /- सोबतचे निदेश या विभागाच्या संकेतस्थळावर प्रसिध्द करावेत.
 १४) कक्ष अधिकारी, माहिती व तंत्रज्ञान विभाग, मंत्रालय, मुंबई.
 /- सदरचे निदेश शासनाच्या संकेतस्थळावर प्रसिध्द करावेत.
 १५) निवड नस्ती, कार्यासन (नवि-१२).



महाराष्ट्र शासन
नगर विकास विभाग

माधाम काना मार्ग, हुतात्मा राजगुरु चौक, मंत्रालय, मुंबई - ४०० ०३२.

Email ID : sould12-mb@mah.gov.in

आदेश क्र.९

क्रमांक:- टिपीएस-१८१८/प्र.क्र.२३६/१८(भाग-२)/नवि-१३ दिनांक :- १२ ऑक्टोबर, २०२२.

विषय :- एकत्रिकृत विकास नियंत्रण व प्रोत्साहन नियमावली (UDCPR) मंजूर नियमावलीमधील विनियम क्र.१९(व) अन्वये स्पष्टीकरण देणेबाबत.

संदर्भ :- १) शासनाचे आदेश क्र.टिपीएस-१८१८/प्र.क्र.२३६/१८(भाग-२)/नवि-१३, दि.१४/९/२०२१. (स्पष्टीकरण आदेश क्र.१)

२) शासनाचे आदेश क्र.टिपीएस-१८२१/३४०/प्र.क्र.६८/२०२१/नवि-१३, दि.१०/५/२०२१. (स्पष्टीकरण आदेश क्र.२)

३) शासनाचे आदेश क्र.टिपीएस-१२२१/९९०/प्र.क्र.४४/२१/नवि-१२, दि.१०/६/२०२१. (स्पष्टीकरण आदेश क्र.३)

४) शासनाचे आदेश क्र.टिपीएस-१२२१/१०३९/प्र.क्र.४२/२१/नवि-१२, दि.१४/६/२०२१. (स्पष्टीकरण आदेश क्र.४)

५) शासनाचे आदेश क्र.टिपीएस-१८१८/प्र.क्र.२३६/१८(भाग-२)/नवि-१३, दि.१७/९/२०२१. (स्पष्टीकरण आदेश क्र.५)

६) शासनाचे आदेश क्र.टिपीएस-१८१८/प्र.क्र.२३६/१८(भाग-२)/नवि-१३, दि.२३/१२/२०२१. (स्पष्टीकरण आदेश क्र.६)

७) शासनाचे आदेश क्र.टिपीएस-१८२१/९३३/नवि-१३, दि.२३/१२/२०२१. (स्पष्टीकरण आदेश क्र.७)

८) शासनाचे आदेश क्र.टिपीएस-१८१८/२३६/१८(भाग-२)/नवि-१३, दि.२६/९/२०२२. (स्पष्टीकरण आदेश क्र.८)

ज्याअर्थी, शासनाने अधिसूचना क्र. टिपीएस १८१८/प्र.क्र.३३६/१८/कलम ३७(१कक)(ग) व कलम २०(४)/नवि-१३, दि.०२/१२/२०२० अन्वये राज्यातील सर्व नियोजन प्राधिकरणे (काही अपवाद वगळता) आणि प्रादेशिक योजना क्षेत्राकरिता एकत्रिकृत विकास नियंत्रण व प्रोत्साहन नियमावली मंजूर केली असून ती दि.०३/१२/२०२० पासून अमलात आली आहे;

आणि ज्याअर्थी, शासनाने महाराष्ट्र प्रादेशिक नियोजन व नगर रचना अधिनियम, १९६६ (यापुढे ज्याचा उल्लेख "उक्त अधिनियम" असा केलेला आहे) चे कलम ३७(१कक) अन्वये दि.२/१२/२०२० रोजी सूचना प्रसिद्ध केली आहे. त्यानुसार सदरची प्रारूप नियमावली ही "सिडको



क्षेत्र (ज्यासाठी सिडको नियोजन प्राधिकरण आहे)" तसेच 'MADC' क्षेत्र यासाठी लागू करणेचा उद्देश घोषित करण्यात आला होता. त्यामधील सिडको क्षेत्राचा उल्लेख विचारात घेताना, सिडकोचे केवळ नवी मुंबई येथील क्षेत्र विचारात घ्यावे, त्याचप्रमाणे MADC चे क्षेत्र विचारात घेताना केवळ शिर्डी विमानतळ क्षेत्र घ्यावे कि ज्या - ज्या ठिकाणी MADC अधिसूचित क्षेत्र/क्षेत्रे आहेत ते विचारात घ्यावे, याबाबत स्पष्टता करण्याविषयी संचालक, नगर रचना, महाराष्ट्र राज्य, पुणे यांनी शासनास विनंती केली आहे. ;

आणि ज्याअर्थी, उक्त नियमावलीतील विनियम क्र.१.९ मध्ये अ.क्र.(v) या तरतुदीनुसार UDCPR मधील विविध तरतुदींच्या अन्वयार्थ संदर्भात उपस्थित प्रश्न / मुद्द्यांच्या अनुषंगाने शासनातर्फे आदेश देणेबाबत तरतुद आहे; आणि ज्याअर्थी, शासनाने उपरोक्त तरतुदींच्या अनुषंगाने वेळोवेळी निर्गमित आदेशान्वये संबंधितांना मार्गदर्शन केलेले आहे;

आणि ज्याअर्थी, संचालनालयाची उक्त विनंती विचारात घेता आणि जनहिताच्या दृष्टीने उक्त नियमावलीची प्रभावी अंमलबजावणी होण्यासाठी उक्त नियमावलीबाबत विनियम क्र.१.९ मधील (v) नुसार शासनाकडून स्पष्टीकरण करणे आवश्यक असल्याचे शासनाचे मत झाले आहे;

आता त्याअर्थी, उक्त अधिनियमाचे कलम ३७(१कक) अन्वये प्रसिध्द झालेल्या सूचनेच्या अनुषंगाने, उक्त नियमावलीबाबत, उक्त अधिकारान्वये खालीलप्रमाणे स्पष्टीकरणात्मक सुचना निर्गमित करण्यात येत आहेत :-

- १) उपरोक्त दि.२/१२/२०२० रोजीच्या सूचनेमध्ये ज्या ज्या ठिकाणी, 'सिडको क्षेत्र (ज्यासाठी सिडको नियोजन प्राधिकरण आहे)' असा उल्लेख आहे, त्या ठिकाणी सिडको नियोजन प्राधिकरण असलेल्या क्षेत्रासाठी सदर नियमावली लागू करणे अपेक्षित होते. राज्यामध्ये सिडको हे, काही ठिकाणी 'नवनगर विकास प्राधिकरण (NTDA)' या नात्याने नियोजन प्राधिकरण आहे. तर काही ठिकाणी सिडको हे 'विशेष नियोजन प्राधिकरण (SPA)' आहे. राज्यामध्ये ज्या क्षेत्रासाठी सिडको हे नवनगर विकास प्राधिकरण (NTDA) या नात्याने अथवा विशेष नियोजन प्राधिकरण (SPA) या नात्याने नियोजन प्राधिकरण आहे, अशा सर्व क्षेत्रांसाठी उक्त नियमावली लागू राहिल.
- २) राज्यातील ज्या - ज्या क्षेत्रांसाठी उक्त अधिनियमाचे कलम ४० अन्वये क्षेत्र अधिसूचित करून त्यासाठी MADC ची विशेष नियोजन प्राधिकरण (SPA) म्हणून नेमणूक केली आहे, अशा सर्व क्षेत्रांसाठी उक्त अधिनियमाच्या कलम १५४ अन्वये निदेशित केलेली उक्त नियमावली लागू राहिल.


(किशोर गोखले)

अवर सचिव, महाराष्ट्र शासन

प्रत :-

१. मा.मुख्यमंत्री महोदय यांचे अपर मुख्य सचिव, मंत्रालय, मुंबई.



२. मा.उप मुख्यमंत्री महोदय यांचे सचिव, मंत्रालय, मुंबई.
३. मा.अध्यक्ष, महाराष्ट्र विधानसभा, महाराष्ट्र विधानमंडळ सचिवालय, मुंबई.
४. मा.सभापती, महाराष्ट्र विधानपरिषद, महाराष्ट्र विधानमंडळ सचिवालय, मुंबई.
५. मा.विरोधी पक्षनेता, विधानसभा, महाराष्ट्र विधानमंडळ सचिवालय, मुंबई.
६. मा.विरोधी पक्षनेता, विधानपरिषद, महाराष्ट्र विधानमंडळ सचिवालय, मुंबई.
७. मा.मुख्य सचिव, महाराष्ट्र शासन, मंत्रालय, मुंबई.
८. अपर मुख्य सचिव (नवि-१), नगर विकास विभाग, मंत्रालय, मुंबई.
९. संचालक (नगर रचना) तथा सह सचिव, नगर विकास विभाग, मंत्रालय, मुंबई.
१०. सह सचिव तथा सह संचालक (नगर रचना), नगर विकास विभाग, मंत्रालय, मुंबई.

प्रति :-

- १) संचालक, नगर रचना, महाराष्ट्र राज्य, पुणे.
- २) सर्व विभागीय आयुक्त.
- ३) सर्व विभागीय सहसंचालक, नगर रचना.
- ४) सर्व आयुक्त, महानगरपालिका.
- ५) सर्व महानगर आयुक्त, महानगर प्रदेश विकास प्राधिकरणे / विशेष नियोजन प्राधिकरणे.
- ६) मुख्य कार्यकारी अधिकारी, कोल्हापूर नागरी क्षेत्र विकास प्राधिकरण, कोल्हापूर.
- ७) सर्व महानगर आयुक्त, नवनगर प्रदेश विकास प्राधिकरणे.
- ८) मुख्य कार्यकारी अधिकारी, सर्व जिल्हापरिषद.
- ९) मुख्याधिकारी सर्व नगरपरिषदा / नगरपंचायती.
- १०) सर्व जिल्हाधिकारी.
- ११) सहायक संचालक, नगर रचना / नगर रचनाकार, नगर रचना व मूल्यनिर्धारण विभाग, सर्व शाखा कार्यालये.
- १२) अवर सचिव, नवि-११ / नवि-१२ / नवि-३०, कक्ष अधिकारी, नवि-९, नगर विकास विभाग, मंत्रालय, मुंबई.
- १३) कक्ष अधिकारी (नवि-२९), नगर विकास विभाग, मंत्रालय, मुंबई.
/- सोबतचे निदेश या विभागाच्या संकेतस्थळावर प्रसिध्द करावेत.
- १४) कक्ष अधिकारी, माहिती व तंत्रज्ञान विभाग, मंत्रालय, मुंबई.
/- सदरचे निदेश शासनाच्या संकेतस्थळावर प्रसिध्द करावेत.
- १५) निवड नस्ती, कार्यासन (नवि-१३).





महाराष्ट्र शासन
नगर विकास विभाग

मादाम कामा मार्ग, हुतात्मा राजगुरु चौक, मंत्रालय, मुंबई - ४०० ०३२.

Email ID : soud12-mh@mah.gov.in

आदेश क्र.१०

क्रमांक:- टिपीएस-१८१८/प्र.क्र.२३६/१८(भाग-२)/नवि-१३ दिनांक :- १२ ऑक्टोबर, २०२२.

विषय :- एकत्रिकृत विकास नियंत्रण व प्रोत्साहन नियमावली (UDCPR) मंजूर
नियमावलीमधील विनियम क्र.१९(v) अन्वये स्पष्टीकरण देणेबाबत.

संदर्भ :- १) शासनाचे आदेश क्र.टिपीएस-१८१८/प्र.क्र.२३६/१८(भाग-२)/नवि-१३,
दि.१४/१२/२०२१. (स्पष्टीकरण आदेश क्र.१)

२) शासनाचे आदेश क्र.टिपीएस-१८२१/३४०/प्र.क्र.६८/२०२१/नवि-१३,
दि.१०/५/२०२१. (स्पष्टीकरण आदेश क्र.२)

३) शासनाचे आदेश क्र.टिपीएस-१२२१/९९०/प्र.क्र.४४/२१/नवि-१२,
दि.१०/६/२०२१. (स्पष्टीकरण आदेश क्र.३)

४) शासनाचे आदेश क्र.टिपीएस-१२२१/१०३९/प्र.क्र.४२/२१/नवि-१२,
दि.१४/६/२०२१. (स्पष्टीकरण आदेश क्र.४)

५) शासनाचे आदेश क्र.टिपीएस-१८१८/प्र.क्र.२३६/१८(भाग-२)/नवि-१३,
दि.१७/९/२०२१. (स्पष्टीकरण आदेश क्र.५)

६) शासनाचे आदेश क्र.टिपीएस-१८१८/प्र.क्र.२३६/१८(भाग-२)/नवि-१३,
दि.२३/१२/२०२१. (स्पष्टीकरण आदेश क्र.६)

७) शासनाचे आदेश क्र.टिपीएस-१८२१/९३३/नवि-१३, दि.२३/१२/२०२१.
(स्पष्टीकरण आदेश क्र.७)

८) शासनाचे आदेश क्र.टिपीएस-१८१८/२३६/१८(भाग-२)/नवि-१३,
दि.२६/९/२०२२ (स्पष्टीकरण आदेश क्र.८)

९) शासनाचे आदेश क्र.टिपीएस-१८१८/२३६/१८(भाग-२)/नवि-१३,
दि.१२/१०/२०२२ (स्पष्टीकरण आदेश क्र.९)

ज्याअर्थी, शासनाने अधिसूचना क्र. टिपीएस १८१८/प्र.क्र.२३६/१८/कलम ३७(१कक)(ग)

व कलम २०(४)/नवि-१३, दि.०२/१२/२०२० अन्वये राज्यातील सर्व नियोजन प्राधिकरणे (काही
अपवाद वगळता) आणि प्रादेशिक योजना क्षेत्राकरिता एकत्रिकृत विकास नियंत्रण व प्रोत्साहन
नियमावली मंजूर केली असून ती दि. ०३/१२/२०२० पासून अमलात आली आहे;



आणि ज्याअर्थी, उक्त नियमावलीतील विनियम क्र.१.९ मध्ये अ.क्र. (v) या तरतुदीनुसार UDCPR मधील विविध तरतुदींच्या अन्वयार्थ संदर्भात उपस्थित प्रश्न / मुद्याच्या अनुषंगाने शासनातर्फे आदेश देणेबाबत तरतुद आहे:

आणि ज्याअर्थी, या शासनाने उपरोक्त तरतुदीच्या अनुषंगाने वेळोवेळी निर्गमित आदेशान्वये संबंधितांना मार्गदर्शन केलेले आहे.

आणि ज्याअर्थी, उक्त नियमावलीतील विनियम क्र.१०.१०.१ नोट क्र.३ नुसारच्या तरतुदींची अंमलबजावणी करण्यासंदर्भात येणाऱ्या अडचणींच्या अनुषंगाने विनियमातील तरतुदींचा अन्वयार्थ स्पष्ट करणेसंदर्भात सिडकोकडून तसेच अन्य काही संस्थांकडून शासनाकडे निवेदने प्राप्त झाली आहेत;

आणि ज्याअर्थी, उक्त विविध निवेदने विचारात घेता आणि जनहिताच्या दृष्टीने, उक्त नियमावलीची प्रभावी अंमलबजावणी होण्यासाठी उक्त नियमावलीतील काही तरतुदींबाबत व्यवहार्यता तपासून अशा तरतुदींचे पुनरावलोकन करून विनियम क्र.१.९ मधील (v) नुसार शासनाकडून अशा तरतुदींबाबत स्पष्टीकरण करणे आवश्यक असल्याचे शासनाचे मत झाले आहे.

आता त्याअर्थी उक्त नियमावलीतील उक्त विनियम क्र.१०.१०.१ नोट क्र.३ च्या अनुषंगाने खालीलप्रमाणे स्पष्टीकरणात्मक सुचना निर्गमित करण्यात येत आहेत :-

- १) विनियम क्र.१०.१०.१ नोट क्र.३ - UDCPR अंमलात येण्यापूर्वी जे भूखंड १.५ चटई क्षेत्र निर्देशांकासह सिडकोने प्रकल्पप्रस्तांसाठी वाटप केले असतील, अशा भूखंडांवर UDCPR प्रमाणे परवानगी देतेवेळी टेबल क्र.६G नुसार अनुज्ञेय असलेली कमाल विकसन क्षमता (Maximum Building Potential) (म्हणजेच १.१० बेसीक चटई क्षेत्र निर्देशांक + प्रिमियम चटई क्षेत्र निर्देशांक + टिडीआर) यासह ०.५ चटई क्षेत्र निर्देशांक अनुज्ञेय आहे. तसेच UDCPR लागू करण्यापूर्वी सिडकोने जे भूखंड १.५ चटई क्षेत्र निर्देशांकासह भाडे पट्ट्याने वाटप केले आहेत, त्यासाठी देखील उक्त विनियम क्र.१०.१०.१ नोट क्र.३ मधील तरतुदी वर नमूद अर्थासह लागू राहतील.
- २) UDCPR नियमावली अंमलात आल्यापासून पुढे सिडकोने भूखंड भाडेपट्ट्याने अथवा लिलावाने वाटप करतांना त्याचा चटई क्षेत्र निर्देशांक अथवा कमाल विकसन क्षमता ही UDCPR मधील तरतुदीनुसारच ठेवणे आवश्यक आहे.


(किशोर गोखले)

अवर सचिव, महाराष्ट्र शासन

प्रत -:

१. मा.मुख्यमंत्री महोदय यांचे अपर मुख्य सचिव, मंत्रालय, मुंबई.
२. मा.उप मुख्यमंत्री महोदय यांचे सचिव, मंत्रालय, मुंबई.



३. मा.अध्यक्ष, महाराष्ट्र विधानसभा, महाराष्ट्र विधानमंडळ सचिवालय, मुंबई.
४. मा.सभापती, महाराष्ट्र विधानपरिषद, महाराष्ट्र विधानमंडळ सचिवालय, मुंबई.
५. मा.विरोधी पक्षनेता, विधानसभा, महाराष्ट्र विधानमंडळ सचिवालय, मुंबई.
६. मा.विरोधी पक्षनेता, विधानपरिषद, महाराष्ट्र विधानमंडळ सचिवालय, मुंबई.
७. मा.मुख्य सचिव, महाराष्ट्र शासन, मंत्रालय, मुंबई.
८. अपर मुख्य सचिव (नवि-१), नगर विकास विभाग, मंत्रालय, मुंबई.
९. संचालक (नगर रचना) तथा सह सचिव, नगर विकास विभाग, मंत्रालय, मुंबई.
१०. सह सचिव तथा सह संचालक (नगर रचना), नगर विकास विभाग, मंत्रालय, मुंबई.

प्रति :-

- १) संचालक, नगर रचना, महाराष्ट्र राज्य, पुणे.
- २) सर्व विभागीय आयुक्त.
- ३) सर्व विभागीय सहसंचालक, नगर रचना.
- ४) सर्व आयुक्त, महानगरपालिका.
- ५) सर्व महानगर आयुक्त, महानगर प्रदेश विकास प्राधिकरणे / विशेष नियोजन प्राधिकरणे.
- ६) मुख्य कार्यकारी अधिकारी, कोल्हापूर नागरी क्षेत्र विकास प्राधिकरण, कोल्हापूर.
- ७) सर्व महानगर आयुक्त, नवनगर प्रदेश विकास प्राधिकरणे.
- ८) मुख्य कार्यकारी अधिकारी, सर्व जिल्हापरिषद.
- ९) मुख्याधिकारी सर्व नगरपरिषदा / नगरपंचायती.
- १०) सर्व जिल्हाधिकारी.
- ११) सहायक संचालक, नगर रचना / नगर रचनाकार, नगर रचना व मूल्यनिर्धारण विभाग, सर्व शाखा कार्यालये.
- १२) अपर सचिव, नवि-११ / नवि-१२ / नवि-३०, कक्ष अधिकारी, नवि-९, नगर विकास विभाग, मंत्रालय, मुंबई.
- १३) कक्ष अधिकारी (नवि-२९), नगर विकास विभाग, मंत्रालय, मुंबई.
/- सोवतचे निदेश या विभागाच्या संकेतस्थळावर प्रसिध्द करावेत.
- १४) कक्ष अधिकारी, माहिती व तंत्रज्ञान विभाग, मंत्रालय, मुंबई.
/- सदरचे निदेश शासनाच्या संकेतस्थळावर प्रसिध्द करावेत.
- १५) निवड नस्ती, कार्यासन (नवि-१३).







महाराष्ट्र शासन
नगर विकास विभाग,
घोद्या मजला, मुख्य इमारत, मंत्रालय,
मादाम कामा मार्ग, हुतात्मा राजगुरु चौक, मुंबई - ४०० ०३२.
दूरध्वनी क्र:- ०२२-२२७९४१९६ Email ID :kishor.gokhale@gov.in

आदेश क्र.११

क्रमांक : टिपीएस-१८२१/२०२३/प्र.क्र.१०४/२०२२/नवि ३०, दि.२९.११.२०२२

विषय :- एकत्रिकृत विकास नियंत्रण व प्रोत्साहन नियमावलीतील (UDCPR) विनियम क्र.३.४.१ व विनियम क्र.३.५.१ संदर्भात स्पष्टीकरण देणेबाबत

संदर्भ :- १. शासनाचे आदेश क्र.टिपीएस-१८१८/ प्र.क्र.२३६/१८(भाग-२)/नवि-१३, दि.१४.०१.२०२१ (स्पष्टीकरण आदेश क्र.१)
२. शासनाचे आदेश क्र.टिपीएस-१८२१/३४०/ प्र.क्र.६८/२०२१/नवि-१३, दि.१०.०५.२०२१ (स्पष्टीकरण आदेश क्र.२)
३. शासनाचे आदेश क्र.टिपीएस-१२२१/९९०/प्र.क्र.४४/२१/नवि-१२, दि.१०.०६.२०२१ (स्पष्टीकरण आदेश क्र.३)
४. शासनाचे आदेश क्र.टिपीएस-१२२१/१०३९/प्र.क्र.४२/२१/नवि-१२, दि.१४.०६.२०२१ (स्पष्टीकरण आदेश क्र.४)
५. शासनाचे आदेश क्र.टिपीएस-१८१८/ प्र.क्र.२३६/१८(भाग-२)/नवि-१३, दि.१७.०९.२०२१ (स्पष्टीकरण आदेश क्र.५)
६. शासनाचे आदेश क्र.टिपीएस-१८१८/ प्र.क्र.२३६/१८(भाग-२)/नवि-१३, दि.२३.१२.२०२१ (स्पष्टीकरण आदेश क्र.६)
७. शासनाचे आदेश क्र.टिपीएस-१८२१/९३३/नवि-१३, दि.२३.१२.२०२१ (स्पष्टीकरण आदेश क्र.७)
८. शासनाचे आदेश क्र.टिपीएस-१८१८/प्र.क्र.२३६/१८(भाग-२)/नवि-१३, दि.२६.०९.२०२२ (स्पष्टीकरण आदेश क्र.८)
९. शासनाचे आदेश क्र.टिपीएस-१८१८/२३६/१८(भाग-२)/नवि-१३, दि.१२.१०.२०२२ (स्पष्टीकरण आदेश क्र.९)
१०. शासनाचे आदेश क्र.टिपीएस-१८१८/२३६/१८(भाग-२)/नवि-१३, दि.१२.१०.२०२२ (स्पष्टीकरण आदेश क्र.१०)



ज्याअर्थी, शासनाने अधिसूचना क्र.टिपीएस-१८१८/प्र.क्र.२३६/१८/वियो व प्रायो/कलम-५७(१कक)(ग) आणि कलम २०/नवि-१३, दि.०२.१२.२०२० अन्वये राज्यातील सर्व नियोजन प्राधिकरणे (कहो अपवाद वगळता) आणि प्रादेशिक योजना क्षेत्राकरिता, एकत्रिकृत विकास नियंत्रण व प्रोत्साहन

नियमावली (यापुढे "उक्त नियमावली" असे संबोधिलेले आहे) मंजूर केली असून ती दि.०३.१२.२०२० पासून अंमलात आली आहे;

आणि ज्याअर्थी, उक्त नियमावलीत विनियम क्र.१.९ मध्ये अनु क्र.(v) मधील तरतुदीनुसार, उक्त नियमावलीमधील विविध तरतुदीच्या अन्वयार्थ संदर्भात उपस्थित प्रश्न / मुद्द्यांच्या अनुषंगाने शासनाकडे आदेश देणेबाबत तरतुद आहे;

आणि ज्याअर्थी, शासनाने उपरोक्त तरतुदीच्या अनुषंगाने वेळोवेळी निर्गमित आदेशान्वये संबंधितांना मार्गदर्शन केले आहे;

आणि ज्याअर्थी, उक्त नियमावलीतील विनियम क्र.३.४.१(i) व ३.५.१ नुसारच्या तरतुदीची अंमलबजावणी करण्यासंदर्भात येणाऱ्या अडचणीच्या अनुषंगाने विनियमातील तरतुदीच्या अन्वयार्थ स्पष्ट करणेसंदर्भात अमरावती महानगरपालिका व इतर काही संस्थांकडून शासनाकडे निवेदने प्राप्त झाली आहेत;

आणि ज्याअर्थी, उक्त विविध निवेदने विचारात घेता आणि बृहत् जनहिताच्या दृष्टीने, उक्त नियमावलीची प्रभावी अंमलबजावणी होण्यासाठी उक्त नियमावलीतील काही तरतुदीबाबत व्यवहार्यता तपासून अशा तरतुदीचे पुनरावलोकन करून विनियम क्र.१.९ मधील (v) नुसार शासनाकडून अशा तरतुदीबाबत स्पष्टीकरण करणे आवश्यक आहे, असे शासनाचे मत झाले आहे;

आता त्याअर्थी, उक्त नियमावलीतील विनियम क्र.३.४.१ (i) व विनियम क्र.३.५.१ च्या अनुषंगाने खालील सारणीतील स्पष्टीकरणात्मक सूचना निर्गमित करण्यात येत आहेत -

आता, त्याअर्थी उक्त नियमावलीतील उक्त विनियम क्र.३.४.१(i) व ३.५.१ च्या अनुषंगाने खालीलप्रमाणे स्पष्टीकरणात्मक सूचना निर्गमित करण्यात येत आहेत.

अनु क्र.	मुद्दे	शासनाचे स्पष्टीकरण
१	उक्त नियमावलीतील नियम क्र.३.५.१ मधील तरतुदीनुसार, यापूर्वी प्रस्तावित नकाशाखालील जागेचे क्षेत्र ०.४० हे. आर पेक्षा जास्त असल्याने, नियमानुसार सुविधा क्षेत्र प्रस्तावित करण्यात येवून अभिन्यासना सिमांकनाकरीता सुधारीत मंजूरी प्रदान करण्यात आली आहे. आता सुधारीत तरतुदीनुसार Amenity space रद्द करून सुधारीत अभिन्यास दाखल होत आहेत, अशा प्रकारे सादर होणाऱ्या सुधारीत अभिन्यासना सिमांकनाकरीता	महाराष्ट्र प्रादेशिक नियोजन व नगर रचना अधिनियम, १९६६ द्वारे जमिनीचा विकास व वापर यांचे नियोजन करणेसाठी तरतुदी करण्यात आल्या असून सदर अधिनियम दि.११ जानेवारी, १९६७ पासून अंमलात आला आहे. त्यामुळे दि.११ जानेवारी, १९६७ नंतर एखाद्या जमिनीचे, सक्षम प्राधिकरणाची परवानगी न घेता, अनधिकृत तुकडे पडले असतील आणि अशा तुकड्यांचे क्षेत्र २.० हे. पेक्षा जरी कमी असेल तरी, अशा अनधिकृत तुकड्यांचे क्षेत्र विचारात न घेता अशा जमिनीचे ७/१२ उताऱ्यानुसारचे एकूण क्षेत्र विचारात घेऊन



	सुधारित मंजूरी देता येईल किंवा कसे?	प्रचलित विनियमानुसार आवश्यकतेप्रमाणे सुविधा क्षेत्र सोडणे आवश्यक राहिल.
२	उक्त नियमावली लागू होण्यापूर्वी 'ड' वर्ग महानगरपालिकेस लागू असलेल्या नियमावलीतील तरतुदीनुसार Amenity space राखीव ठेवून अभिन्यास सिसांकनाकरीता तात्पुरती मंजूरी प्रदान करण्यात आली आहे. अशा प्रकरणांना देखिल सिसांकनाकरीता सुधारित मंजूरी देता येईल किंवा कसे?	उक्त नियमावली मधील विनियम ३.५.१ मधे दि.१६.०६.२०२१ रोजीच्या अधिसूचनेद्वारे मंजूर फेरबदलानुसार २०००० चौ. मी. किंवा त्यापेक्षा जास्त क्षेत्राच्या रेखांकन / उपविभागणी मधे ५% सुविधा क्षेत्र सोडणे आवश्यक आहे. या दिनांकापूर्वी म्हणजेच दि.१६.०६.२०२१ पूर्वी मंजूर असणाऱ्या रेखांकन / उपविभागणी प्रस्तावांमध्ये (तात्पुरते अथवा अंतिम रेखांकन) तत्कालीन नियमावलीप्रमाणे सोडण्यात आलेले सुविधा क्षेत्र असे रेखांकन उक्त नियमावलीनुसार सुधारित करताना विनियम ३.५.१(viii) मधील तरतुदी विचारात घेता, कमी करता येणार नाही.
३	उक्त नियमावली दि.०३.१२.२०२० पासून लागू झाली असल्याने या तारखेनंतर ०.४ हेक्टर आर पेक्षा कमी क्षेत्राचे तुकडे पाडून अभिन्यास मंजूरीसाठी सादर होणाऱ्या प्रकरणांना एकत्रित विकास नियंत्रण व प्रोत्साहन नियमावली मधील नियम क्र. ३.४.१(i) मध्ये (a), (b), (c) हे पर्याय लागू राहणार किंवा कसे?	दि.११.०१.१९६७ नंतर एखाद्या जमिनीचे, सक्षम प्राधिकरणाची परवानगी न घेता, अनाधिकृत तुकडे पडले असतील आणि अशा तुकड्याचे क्षेत्र ०.४० हे. पेक्षा कमी असेल तर, अशा तुकड्याचे रेखांकन / उपविभागणी करताना खुल्या जागेच्या संदर्भात विनियम ३.४.१(i) मध्ये (a), (b), (c) असे तीन पर्याय नमूद असून यापैकी एक पर्याय निवडण्याचा अर्जदारांचा स्वेच्छाधिकार आहे. त्यानुसार संबंधित नियोजन प्राधिकरणाकडे प्राप्त होणाऱ्या प्रस्तावांमध्ये अर्जदारांनी निवडलेल्या पर्यायाचा विचार करून त्यावर नियोजन प्राधिकरणाने निर्णय घेणे आवश्यक आहे. तथापि, उक्त नियमावली व त्यातील उपरोक्त विनियम व त्यातील पर्याय दि.०३.१२.२०२० पासून



	अंमलात आले आहेत. त्यामुळे दि.११.०१.१९६७ नंतर परंतु दि.०२.१२.२०२० पर्यंत, एखाद्या जमिनीचे, सक्षम प्राधिकरणाची परवानगी न घेता, अनधिकृत तुकडे पडले असतील आणि अशा तुकड्याचे क्षेत्र ०.४० हे. पेक्षा कमी असेल तर त्याकरिता विनियम ३.४.१(i) मधील तीन पर्याय उपलब्ध राहतील. मात्र दि.०३.१२.२०२० नंतर जर असे सक्षम प्राधिकरणाची परवानगी न घेता, अनधिकृत तुकडे पडले असतील आणि त्यांचे क्षेत्र जरी ०.४० हे. पेक्षा कमी असेल तरी अशा प्रस्तावांमध्ये विनियम ३.४.१(i) मधील केवळ पर्याय (a) नुसार अशा तुकड्याच्या एकूण क्षेत्राच्या १०% अथवा किमान २०० चौ. मी. क्षेत्र खुली जागा म्हणून सोडण्याचाच पर्याय उपलब्ध राहिल. अन्य दोन (b) व (c) हे पर्याय उपलब्ध राहणार नाहीत.



(किशोर गोखले)

अवर सचिव, महाराष्ट्र शासन

प्रत —

- १) मा. मुख्यमंत्री महोदयांचे अपर मुख्य सचिव, मंत्रालय, मुंबई-४०० ०३२.
- २) मा. उपमुख्यमंत्री महोदयांचे प्रधान सचिव, मंत्रालय, मुंबई-४०० ०३२.
- ३) मा. सभापती, महाराष्ट्र विधानपरिषद, महाराष्ट्र विधानमंडळ सचिवालय, मुंबई-४०० ०३२.
- ४) मा. अध्यक्ष, महाराष्ट्र विधानसभा, महाराष्ट्र विधानमंडळ सचिवालय, मुंबई-४०० ०३२.
- ५) मा.विरोधी पक्ष नेता, विधानपरिषद/ विधानसभा, महाराष्ट्र विधानमंडळ सचिवालय, मुंबई-४०० ०३२.
- ६) मा. उपसभापती, महाराष्ट्र विधानपरिषद, महाराष्ट्र विधानमंडळ सचिवालय, मुंबई-४०० ०३२.
- ७) मा. उपाध्यक्ष, महाराष्ट्र विधानसभा, महाराष्ट्र विधानमंडळ सचिवालय, मुंबई-४०० ०३२.
- ८) अपर मुख्य सचिव (नवि-१), नगर विकास विभाग, मंत्रालय, मुंबई-४०० ०३२.
- ९) संचालक (नगर रचना) तथा सह सचिव, नगर विकास विभाग, मंत्रालय, मुंबई-४०० ०३२.
- १०) सहसंचालक (नगर रचना) तथा सह सचिव, नगर विकास विभाग, मंत्रालय, मुंबई-४०० ०३२.

प्रति,

- १) संचालक, नगर रचना, महाराष्ट्र राज्य, पुणे.

(15)
महाराष्ट्र प्रादेशिक नियोजन व नगर रचना
अधिनियम, १९६६ चे कलम १५४ अन्वये निदेश.
(भोगवटा वर्ग - २ जमिनी भोगवटादार वर्ग -१ मध्ये रुपांतरित
करण्यासंदर्भात राज्यातील ज्या नियोजन प्राधिकरणांसाठी
UDCPR नियमावली लागू आहे, अशा सर्व नियोजन
प्राधिकरणांना निदेश)

महाराष्ट्र शासन

नगर विकास विभाग,

शासन निर्णय क्र. टिपीएस-१८२३/प्र.क्र.०७/२०२३/नवि-१३,

मादाम कामा मार्ग, हुतात्मा राजगुरु चौक,

चौथा मजला, मंत्रालय, मुंबई ४०० ०३२.

दिनांक : २७.०२.२०२३

संदर्भ :- १. शासन महसूल व वन विभागाकडील शासन निर्णय क्र.जमिन-२०१५/प्र.क्र.८७/ज-१अ, दि.२७.१२.२०१८.
२. शासन महसूल व वन विभागाकडील अधिसूचना क्र.जमिन-२०१८/प्र.क्र.१०/ज-१, दि.०८.०३.२०१९.

निदेश

महाराष्ट्र प्रादेशिक नियोजन व नगर रचना अधिनियम, १९६६

प्रस्तावना -

- I) शासनाच्या महसूल व वन विभागाकडील शासन निर्णय क्र.जमिन-२०१५/प्र.क्र.८७/ज-१अ, दि.२७.१२.२०१८ अन्वये शासकीय प्रकल्प / योजना यासाठी व शासन अंगीकृत उपक्रमासाठी इनाम / वतन जमिनी (महार वतन जमिन वगळून) आणि इनाम जमिनी भूसंपादित / वाटाघाटीने संपादित करताना आकारावयाच्या नजराणा रक्कमेबाबत निदेश / नियम पारित करण्यात आलेले असून उक्त शासन निदेशानुसार राज्यातील महानगरपालिका / नगरपरिषदा / नियोजन प्राधिकरणांच्या क्षेत्रातील भोगवटा वर्ग -२ धारणाधिकाऱ्यांच्या जमिनीचा भोवदला हस्तांतरणीय विकास हक्क TDR / घटई क्षेत्र FSI च्या स्वरूपात प्रदान करण्याबाबत सविस्तर तरतुदी करण्यात आल्या आहेत.
- II) तद्नंतर शासन महसूल व वन विभागाकडील अधिसूचना क्र. जमिन-२०१८/प्र.क्र.१०/ज-१, दि.०८.०३.२०१९ च्या अधिसूचनेन्वये भोगवटादार वर्ग-२ धारणाधिकाऱ्यावर किंवा भाडेपट्ट्याने प्रदान केलेल्या जमिनीचे भोगवटादार वर्ग -१ मध्ये रुपांतरित करणेकरिता अधिमूल्य आकारण्याची तरतूद करण्यात आली आहे.
- III) मंजूर एकत्रित विकास नियंत्रण व प्रोत्साहन नियमावली (UDCPR) मधील TDR संबंधीच्या तरतुदी मधील विनियम क्र.११.४.९ (ii) नुसार वर्ग-१ व्यतिरिक्तच्या जमिनीस TDR देण्यासंबंधीची तरतूद खालीलप्रमाणे आहे. २

E:\UDCPR\नवि-१३\२.००४



ii) In case of lands having tenure other than class (I), i.e Inam Land, Tribal Lands etc., Noc from competent authority shall be produced the by the land holder at the time of submission of application for grant of TDR.

IV) सदर विषयाच्या अनुषंगाने आयुक्त, ठाणे महानगरपालिका यांनी दि.३/९/२०२० रोजीच्या पत्रान्वये ठाणे शहराच्या विकास योजनेमधील आरक्षणे, रस्ते हे वर्ग-२ च्या जमिनीवर असल्याने, सदर जमिनी भोगवटादार वर्ग-१ मध्ये रुपांतरीत करणेकामी नजराणा भरणा करणे व तदनंतर त्या जमिनीचा टिडीआर देणे शक्य नसल्याने विकास आराखड्यामधील आरक्षणे/रस्ते विकास हक्क हस्तांतरणाने महानगरपालिकेस हस्तांतरीत करताना अधिमूल्य रक्कमेऐवजी ५०% टिडीआर देणेबाबत निर्णय होण्यास शासनास विनंती केलेली आहे.

V) प्रस्तुत प्रकरणी आयुक्त, ठाणे महानगरपालिका यांनी दि.०३.०९.२०२० रोजीच्या पत्राद्वारे शासनास केलेली विनंती, महसूल व वन विभाग यांचेकडील दि.२७.१२.२०१८ रोजीचा शासन निर्णय व दि.०८.०३.२०१९ रोजीची अधिसूचना विचारात घेता, प्रस्तुत प्रकरणी राज्यामध्ये एकत्रिकृत विकास नियंत्रण व प्रोत्साहन नियमावली (UDCPR) लागू असलेल्या क्षेत्रामध्ये भोगवटादार वर्ग-२ च्या जमिनीचा टिडीआर देणेबाबत एकसुत्रता राहणेच्या दृष्टीकोनातून पुढील पर्यायांचे अनुषंगाने ज्या नियोजन प्राधिकरणासाठी UDCPR नियमावली लागू आहे अशा सर्व नियोजन प्राधिकरणांना महाराष्ट्र प्रादेशिक नियोजन व नगर रचना अधिनियम, १९६६ चे कलम १५४ अन्वयेचे निर्देश देण्याची बाब शासनाच्या विचाराधीन होती.

त्या अनुषंगाने अनुसरून राज्यामध्ये ज्या नियोजन प्राधिकरणासाठी UDCPR नियमावली लागू आहे, अशा सर्व नियोजन प्राधिकरणांना / जिल्हाधिकारी कार्यालये / महानगरपालिका / नगरपरिषदांना उक्त अधिनियमाचे कलम १५४ अन्वये प्राप्त अधिकारात शासन खालीलप्रमाणे निर्देश देत आहे.

शासन निर्देश

एकत्रिकृत विकास नियंत्रण व प्रोत्साहन नियमावली (UDCPR) लागू असलेल्या क्षेत्रामध्ये भोगवटादार वर्ग-२ च्या जमिनीचा टिडीआर देतेवेळी राज्यातील सर्व नियोजन प्राधिकरणांना / जिल्हाधिकारी कार्यालये / महानगरपालिका / नगरपरिषदांनी खालील पर्याय विचारात घेऊन कार्यवाही करावी.

पर्याय क्र.०१. महसूल व वन विभागाकडील शासन निर्णय क्र.जमिन/२०१५/प्र.क्र.८७/ज-१, दि.२७.१२.२०१८ मधील अ.क्र.२ (ब) अन्वये महानगरपालिका / नगरपरिषदा यांचे मंजूर विकास आराखड्यातील आरक्षित असलेल्या जमिनी (भोगवटादार वर्ग -२ या धारणाधिकाराच्या जमिनी) संपादित होत असल्यास जमिनधारकाच्या विनंती नंतर अशा आरक्षणाखालील जमिनीचा (महार वतन जमिन वगळून) तसेच इतर भोगवटादार वर्ग -२ धारणाधिकाराच्या जमिनीचा मोबदला विकास हक्क हस्तांतरण (TDR) चटई क्षेत्र निर्देशांकाच्या स्वरूपात प्रदान करण्यात येत असेल, अशा प्रकरणी हस्तांतरणीय विकास हक्क / चटई क्षेत्र विषयक आदेश मंजूर करण्यापूर्वी संबंधित नियोजन प्राधिकरण यांनी याबाबत संबंधित जिल्हाधिकारी यांचे ना-हरकत प्रमाणपत्र घेणे आवश्यक आहे. संबंधित जिल्हाधिकारी यांनी असे ना-हरकत प्रमाणपत्र प्रदान करताना त्यावेळी संबंधित जमिनीच्या प्रचलित बाजारमूल्याच्या १०% इतकी रक्कम नजराण्यापोटी वसूल करावी. तदनंतर संबंधित अर्जदार व्यक्ती यांना जिल्हाधिकारी यांच्याकडून ना-हरकत प्रमाणपत्र प्रदान करण्यात

UDCPR/नियमन-१.१००५



येईल. तसेच या ना-हरकत प्रमाणपत्रा आधारे संबंधित नियोजन प्राधिकरण यांना अशा प्रकरणी १००% हस्तांतरणीय विकास हक्क /चटई क्षेत्र निर्देशांक (FSI)मंजूर करता येईल.

पर्याय क्र.०२. मंजूर विकास आराखड्यातील आरक्षित असलेली जमिन (भोगवटादार वर्ग -२ या धारणाधिकाराच्या जमिन) नियोजन प्राधिकरणास सार्वजनिक हिताच्या दृष्टीने संपादन करणे आवश्यक असेल व अशा वेळी संबंधित जागा मालक पर्याय १ प्रमाणे महसूल विभागास १०% रक्कम प्रदान करण्यास नकार देत असेल, अशा परिस्थितीत संपादनप्रक्रिया पूर्ण होऊन विकास योजनेची अंमलबजावणी होण्याच्या दृष्टीने सदरची १०% इतकी रक्कम (नजराण्यापोटी) संबंधित नियोजन प्राधिकरणाने जमिन मालकाच्या संमतीने जिल्हाधिकारी कार्यालयास जमा केल्यास संबंधित जमिन मालकास अनुज्ञेय TDR / FSI पैकी १०% TDR / FSI राखून ठेवून उर्वरित ९०% हस्तांतरणीय TDR / FSI मंजूर करता येईल.

पर्याय क्र.०३. पर्याय क्र.२ प्रमाणे कार्यवाही केल्यानंतर संबंधित नियोजन प्राधिकरणाने जागा मालक यांना ९०% विकास हक्क हस्तांतरण (TDR)/ चटई क्षेत्र निर्देशांकमंजूर केल्यानंतर उर्वरित १०%TDR / FSI नियोजन प्राधिकरणाकडे शिल्लक राहणार आहे. अशा उर्वरित १०% TDR / FSIच्या बाबतीत संबंधित जागा मालकांनी नियोजन प्राधिकरणाकडे TDR / FSI मिळण्याबाबत मागणी केली असता, अशा बाबतीत संबंधित जागा मालक यांना नियोजन प्राधिकरणाने जिल्हाधिकारी कार्यालयाकडेनजराण्यापोटी रक्कम जमा केलेल्या दिनांकापासून मागणी केलेल्या दिनांकापर्यंत भरणा रक्कम व्याजासह आकारणी करून त्याबाबत एकूण रक्कमेचा भरणा संबंधित जमिन मालक यांनी नियोजन प्राधिकरणाकडे जमा केल्यानंतर संपादित जमिनीच्या अनुषंगाने उर्वरित १०% हस्तांतरणीय विकास हक्क हस्तांतरण (TDR)/ चटई क्षेत्र निर्देशांक जमिन मालक यांना प्रदान करता येईल.

सदरचे निदेश हे तात्काळ अंमलात येतील.

महाराष्ट्राचे राज्यपाल यांचे आदेशानुसार व नावाने.



Pranav Karp

(प्रणव कर्पे)

अवर सचिव, महाराष्ट्र शासन

प्रत : - आवश्यक त्या कार्यवाहीसाठी

१. जिल्हाधिकारी - सर्व जिल्हे.
२. आयुक्त, सर्व महानगरपालिका (वृहन्मुंबई महानगरपालिका वगळता)
३. मुख्याधिकारी, सर्व नगरपरिषदा / सर्व नगरपंचायती.
४. मुख्य कार्यकारी अधिकारी सर्व जिल्हापरिषदा.
५. महानगर आयुक्त, सर्व महानगर प्रदेश विकास प्राधिकरणे.
६. मुख्य कार्यकारी अधिकारी, कोल्हापूर नागरी क्षेत्र विकास प्राधिकरण, कोल्हापूर.

प्रत -

१. मा.मुख्यमंत्री महोदय यांचे अपर मुख्य सचिव, मंत्रालय, मुंबई.
२. मा.उप मुख्यमंत्री महोदय यांचे सचिव, मंत्रालय, मुंबई.
३. मा.विरोधी पक्षनेता, विधानपरिषद / विधानसभा, महाराष्ट्र विधानमंडळ सचिवालय, मुंबई.
४. मा.उपसभापती, महाराष्ट्र विधानपरिषद, महाराष्ट्र विधानमंडळ सचिवालय, मुंबई.
५. मा.उपाध्यक्ष, महाराष्ट्र विधानसभा, महाराष्ट्र विधानमंडळ सचिवालय, मुंबई.
६. अपर मुख्य सचिव (नवि-१), नगर विकास विभाग, मंत्रालय, मुंबई.
७. अपर मुख्य सचिव, महसूल व वन विभाग, मंत्रालय, मुंबई.
८. प्रधान सचिव, (नवि-२) नगर विकास विभाग, मंत्रालय, मुंबई.
९. संचालक (नगर रचना) तथा सह सचिव, नगर विकास विभाग, मंत्रालय, मुंबई.

प्रत माहितीस्तव व कार्यवाहीसाठी -

- १) संचालक, नगर रचना, महाराष्ट्र राज्य, पुणे.
- २) विभागीय सहसंचालक, नगर रचना, पुणे / नागपूर / अमरावती / कोकण / औरंगाबाद / नाशिक.
- ३) विभागीय आयुक्त, पुणे / नागपूर / अमरावती / कोकण / औरंगाबाद / नाशिक.
- ४) सहायक संचालक, नगर रचना / नगर रचनाकार, नगर रचना व मूल्यनिर्धारण विभाग, सर्व शाखा कार्यालये.
- ५) अवर सचिव, नवि-११ / नवि-३०, कक्ष अधिकारी, नवि-९ / नवि-१२, नगर विकास विभाग, मंत्रालय, मुंबई.
- ६) कक्ष अधिकारी (नवि-२९), नगर विकास विभाग, मंत्रालय, मुंबई.
-/सदर आदेश विभागाच्या संकेतस्थळावर प्रसिध्द करण्यात यावेत.
- ✓ ७) कक्ष अधिकारी, माहिती व तंत्रज्ञान विभाग, मंत्रालय, मुंबई.
-/सदर आदेश शासनाच्या संकेतस्थळावर प्रसिध्द करण्याबाबत कार्यवाही करण्यात यावी.
- ८) निवड नस्ती, कार्यासन (नवि-१३).





महाराष्ट्र शासन
नगर विकास विभाग,

घोद्या मजला, मुख्य इमारत, मंत्रालय,

मादाम कामा मार्ग, हुतात्मा राजगुरु चौक, मुंबई - ४०० ०३२.

दूरध्वनी क्र:- ०२२-२२७९४९९६

Email ID : jsdtp.ud-mh@gov.in

शुद्धीपत्रक (आदेश क्र.११ संदर्भात)

क्रमांक : टिपीएस-१८२१/२०२३/प्र.क्र.१०४/२०२२/नवि ३०, दि.०२.०६.२०२३

विषय :- एकत्रिकृत विकास नियंत्रण व प्रोत्साहन नियमावलीतील (UDCPR) विनियम क्र.३.४.१ व विनियम क्र.३.५.१ संदर्भात स्पष्टीकरण देणेबाबत -

संदर्भ :- शासनाने आदेश क्र.टिपीएस-१८२१/२०२३/प्र.क्र.१०४/२०२२/नवि-३०, दि.२९.११.२०२२ (स्पष्टीकरण आदेश क्र.११)

शासनाने अधिसूचना क्र.टिपीएस-१८१८/प्र.क्र.२३६/१८/वियो व प्रायो/कलम ३७(१कक)(ग) आणि कलम २०/नवि-१३, दि.०२.१२.२०२० अन्वये राज्यातील सर्व नियोजन प्राधिकरणे (काही अपवाद वगळता) आणि प्रादेशिक योजना क्षेत्राकरिता, एकत्रिकृत विकास नियंत्रण व प्रोत्साहन नियमावली (यापुढे "उक्त नियमावली" असे संबोधिलेले आहे) मंजूर केली असून ती दि.०३.१२.२०२० पासून अंमलात आली आहे;

उक्त नियमावलीत विनियम क्र.१.९(v) मधील तरतुदीनुसार, उक्त नियमावलीमधील विविध तरतुदींच्या अन्वयार्थ संदर्भात उपस्थित प्रश्न / मुद्द्यांच्या अनुषंगाने शासनातर्फे आदेश देणेबाबत तरतुद आहे. या तरतुदींच्या अनुषंगाने शासनाने संदर्भित आदेशान्वये, उक्त नियमावलीतील विनियम क्र.३.४.१(i) व ३.५.१ नुसारच्या तरतुदींची अंमलबजावणी करण्यासंदर्भात येणाऱ्या अडचणींच्या अनुषंगाने विनियमातील तरतुदींचा अन्वयार्थ स्पष्ट करणेसंदर्भात संबंधितांना मार्गदर्शन केले आहे;

उक्त नमूद संदर्भित शासन आदेश क्र.११ अन्वये निर्गमित करण्यात आलेल्या स्पष्टीकरणातील अ.क्र.१ व २ मध्ये देण्यात आलेल्या सदर स्पष्टीकरणातून, उपस्थित करण्यात आलेल्या मूळ मुद्द्यांची पूर्णतः स्पष्टता होत नसून अपेक्षित नसलेला अर्थ ध्वनीत होताना दिसत असल्याची बाब निदर्शनास येत आहे.

वरील बाब विचारात घेता दि.२९.११.२०२२ रोजीच्या आदेशातील अ.क्र.१ व २ मधील स्पष्टीकरणाऐवजी या दोन मुद्द्यांच्या अनुषंगाने एकत्रित सुधारीत स्पष्टीकरण खालीलप्रमाणे देणे आवश्यक असून त्याकरिता शुद्धीपत्रक निर्गमित करणे आवश्यक आहे, असे शासनाने मत झाले असल्याने त्याबाबत खालीलप्रमाणे शुद्धीपत्रक निर्गमित करण्यात येत आहे. :

अ.क्र.	मुद्दा	घाएवजी (संदर्भित आदेशानुसारचे स्पष्टीकरण)	असे वाचावे (सुधारीत स्पष्टीकरण)
१	उक्त नियमावलीतील नियम क्र.३.५.१ मधील यापूर्वी तरतुदीनुसार,	महाराष्ट्र प्रादेशिक नियोजन व नगर रचना अधिनियम, १९६२ द्वारे जमिनीचा विकास व, यापुढे, यांचे	अ) उक्त नियमावलीमधील विनियम ३.५.१ मध्ये दि.१६.०६.२०२१ रोजीच्या



	प्रस्तावित नकाशाखालील जागेचे क्षेत्र ०.४० हे. आर पेक्षा जास्त असल्याने, नियमानुसार सुविधा क्षेत्र प्रस्तावित करण्यात येवून अभिन्यासांना सिमांकनाकरीता सुधारीत मंजूरी प्रदान करण्यात आली आहे. आता सुधारीत तरतुदीनुसार Amenity space रद्द करून सुधारीत अभिन्यास दाखल होत आहेत, अशा प्रकारे सादर होणाऱ्या सुधारीत अभिन्यासांना सिमांकनाकरीता सुधारीत मंजूरी देता येईल किंवा कसे?	नियोजन करणेसाठी तरतुदी करण्यात आल्या असून सदर अधिनियम दि.११ जानेवारी, १९६७ पासून अंमलात आला आहे. त्यामुळे दि.११ जानेवारी, १९६७ नंतर एखाद्या जमिनीचे, सक्षम प्राधिकरणाची परवानगी न घेता, अनधिकृत तुकडे पडले असतील आणि अशा तुकड्यांचे क्षेत्र २.० हे. पेक्षा जरी कमी असेल तरी, अशा अनधिकृत तुकड्यांचे क्षेत्र विचारात न घेता अशा जमिनीचे ७/१२ उतान्यानुसारचे एकूण क्षेत्र विचारात घेऊन प्रचलित विनियमानुसार आवश्यकतेप्रमाणे सुविधा क्षेत्र सोडणे आवश्यक राहील.	अधिसूचनेद्वारे मंजूर फेरबदलानुसार २०००० चौ. मी. किंवा त्यापेक्षा जास्त क्षेत्राच्या रेखांकन / उपविभागणीमध्ये ५% सुविधा क्षेत्र सोडणे आवश्यक आहे. या दिनांकापूर्वी म्हणजेच दि.१६.०६.२०२१ पूर्वी तत्कालीन नियमावलीप्रमाणे मंजूरी देण्यात आलेल्या रेखांकन/उपविभागणी प्रस्तावांमध्ये (तात्पुरते अथवा अंतिम रेखांकन) प्रस्तावित करण्यात आलेले सुविधा क्षेत्र, सुधारित तरतुदीनुसार रद्द करता येणार नाही. असे सुविधा क्षेत्र कायम ठेवून सुधारित रेखांकनास मंजूरी देता येईल. असे रेखांकन उक्त नियमावलीनुसार सुधारित करताना विनियम ३.५.१(viii) मधील तरतुदी विचारात घेता, तत्कालीन विनियमाप्रमाणे प्रस्तावित करण्यात आलेले सुविधा क्षेत्र कमी करता येणार नाही.
२	उक्त नियमावली लागू होण्यापूर्वी 'ड' वर्ग महानगरपालिकेस लागू असलेल्या नियमावलीतील तरतुदीनुसार Amenity space राखीव ठेवून अभिन्यासास सिमांकनाकरीता तात्पुरती मंजूरी प्रदान करण्यात आली आहे. अशा प्रकरणांना देखिल सिमांकनाकरीता सुधारित मंजूरी देता येईल किंवा कसे?	उक्त नियमावली मधील विनियम ३.५.१ मध्ये दि.१६.०६.२०२१ रोजीच्या अधिसूचनेद्वारे मंजूर फेरबदलानुसार २०००० चौ. मी. किंवा त्यापेक्षा जास्त क्षेत्राच्या रेखांकन / उपविभागणी मध्ये ५% सुविधा क्षेत्र सोडणे आवश्यक आहे. या दिनांकापूर्वी म्हणजेच दि.१६.०६.२०२१ पूर्वी मंजूर असणाऱ्या रेखांकन / उपविभागणी प्रस्तावांमध्ये (तात्पुरते अथवा अंतिम रेखांकन) तत्कालीन नियमावलीप्रमाणे सोडण्यात आलेले सुविधा क्षेत्र असे रेखांकन उक्त नियमावलीनुसार सुधारित करताना विनियम ३.५.१(viii) मधील तरतुदी विचारात घेता, कमी करता येणार नाही.	ब) दि.१६.०६.२०२१ नंतर प्राप्त होणाऱ्या नवीन प्रस्तावांमध्ये ७/१२ उतान्यानुसारचे एकूण क्षेत्र विचारात घेऊन प्रचलित विनियमानुसार आवश्यकतेप्रमाणे सुविधा क्षेत्र सोडणे आवश्यक राहील.




 (प्रतिभा भदानी)
 सह सचिव, महाराष्ट्र शासन



प्रत -

- १) मा. मुख्यमंत्री महोदयांचे अपर मुख्य सचिव, मंत्रालय, मुंबई-४०० ०३२.
- २) मा. उपमुख्यमंत्री महोदयांचे प्रधान सचिव, मंत्रालय, मुंबई-४०० ०३२.
- ३) मा. सभापती, महाराष्ट्र विधानपरिषद, महाराष्ट्र विधानमंडळ सचिवालय, मुंबई-४०० ०३२.
- ४) मा. अध्यक्ष, महाराष्ट्र विधानसभा, महाराष्ट्र विधानमंडळ सचिवालय, मुंबई-४०० ०३२.
- ५) मा. विरोधी पक्ष नेता, विधानपरिषद/ विधानसभा, महाराष्ट्र विधानमंडळ सचिवालय, मुंबई-४०० ०३२.
- ६) मा. उपसभापती, महाराष्ट्र विधानपरिषद, महाराष्ट्र विधानमंडळ सचिवालय, मुंबई-४०० ०३२.
- ७) मा. उपाध्यक्ष, महाराष्ट्र विधानसभा, महाराष्ट्र विधानमंडळ सचिवालय, मुंबई-४०० ०३२.
- ८) अपर मुख्य सचिव (नवि-१), नगर विकास विभाग, मंत्रालय, मुंबई-४०० ०३२.
- ९) संचालक (नगर रचना) तथा सह सचिव, नगर विकास विभाग, मंत्रालय, मुंबई-४०० ०३२.
- १०) उप संचालक (नगर रचना) तथा उप सचिव, नगर विकास विभाग, मंत्रालय, मुंबई-४०० ०३२.

प्रति,

- १) संचालक, नगर रचना, महाराष्ट्र राज्य, पुणे.
- २) सर्व विभागीय आयुक्त,
- ३) सर्व विभागीय सह संचालक, नगर रचना
- ४) सर्व आयुक्त, महानगरपालिका
- ५) सर्व महानगर आयुक्त, महानगर प्रदेश विकास प्राधिकरणे / विशेष नियोजन प्राधिकरणे
- ६) सर्व जिल्हाधिकारी
- ७) मुख्य कार्यकारी अधिकारी, कोल्हापूर नागरी क्षेत्र विकास प्राधिकरण, कोल्हापूर.
- ८) सर्व महानगर आयुक्त, नवनगर प्रदेश विकास प्राधिकरणे.
- ९) मुख्य कार्यकारी अधिकारी, सर्व जिल्हापरिषदा
- १०) मुख्याधिकारी, सर्व नगरपरिषदा / नगरपंचायती
- ११) सहायक संचालक, नगर रचना / नगर रचनाकार, नगर रचना व मूल्यनिर्धारण विभाग सर्व शाखा कार्यालये.
- १२) अवर सचिव, (नवि-११, नवि-३०) / कक्ष अधिकारी (नवि-९, नवि-१२) नगर विकास विभाग, मंत्रालय, मुंबई.
- १३) कक्ष अधिकारी (नवि-२९), नगर विकास विभाग, मंत्रालय, मुंबई.
/- प्रस्तुतचे आदेश या विभागाच्या संकेतस्थळावर प्रसिद्ध करावेत.
- १४) कक्ष अधिकारी, माहिती व तंत्रज्ञान विभाग, मंत्रालय, मुंबई.
/- प्रस्तुतचे आदेश शासनाच्या संकेतस्थळावर प्रसिद्ध करावेत.
- १५) निवड नस्ती, कार्यासन (नवि-१३)





महाराष्ट्र शासन
नगर विकास विभाग

चौथा मजला, मुख्य इमारत, मंत्रालय,

मादाम कामा मार्ग, हुतात्मा राजगुरु चौक, मुंबई - ४०० ०३२.

दूरध्वनी क्र ०२२-२२७९४९९६

Email ID : ud13-urban@mah.gov.in

क्रमांक: डिपीएस-१८२३/प्र.क्र.३९/२०२३/नवि-१३

दिनांक : २४.०७.२०२३

प्रति,

१. मा. व्यवस्थापकीय संचालक, शहर व औद्योगिक विकास महामंडळ (सिडको).

२. मा. आयुक्त, नवी मुंबई / पनवेल महानगरपालिका.

विषय :- Request to issue clarification to CIDCO regarding allow ability of 1.5 basic FSI and additional 0.50 potential in view of provisions in UDCPR.

संदर्भ :- अध्यक्ष, क्रेडाई, बी.ए.एन.एम रायगड, यांचे मा. मुख्यमंत्री महोदय यांस निवेदन दि.०९.०१.२०२३.

महोदय,

विषयांकित प्रकरणी मंजूर UDCPR कार्यक्षेत्रातील सिडको, नवी मुंबई व पनवेल महानगरपालिका नियोजन प्राधिकरण असलेल्या क्षेत्रामध्ये बेसिक चटई क्षेत्र निर्देशांक व कमाल विकसन क्षमता याबाबतच्या अंमलबजावणीत विसंगती निर्माण झाल्याने याबाबतचा उचित अन्वयार्थ करणेसंदर्भात अध्यक्ष, क्रेडाई, बी.ए.एन.एम रायगड यांनी दि.०९.०१.२०२३ रोजी शासनास विनंती वजा निवेदन सादर केले आहे.

सदर प्रस्तावामध्ये मंजूर UDCPR मधील विनियम क्र.१०.१०.१ च्या अनुषंगाने खालीलप्रमाणे स्पष्टीकरणात्मक सूचना/ मार्गदर्शन देण्यात येते.

I. मंजूर एकत्रिकृत विकास निर्व्यवण व प्रोत्साहन नियमावलीमधील विनियम क्र.१०.१०.१ नोट क्र.३ च्या अनुषंगाने, सिडकोने प्रकल्पप्रस्तांसाठी व भाडेपट्ट्याने मुळ १.५ चटई क्षेत्र निर्देशांकासह वाटप केलेल्या अशा भूखंडावर, UDCPR प्रमाणे परवानगी देतेवेळी टेबल क्र.६ G नुसार अनुज्ञेय असलेली कमाल विकसन क्षमता (Maximum Building Potential) (म्हणजेच १.१० बेसिक चटई क्षेत्र निर्देशांक + प्रिमियम चटई क्षेत्र निर्देशांक + टिडीआर) यासह अतिरिक्त ०.५ चटई क्षेत्र निर्देशांक अनुज्ञेय आहे.

II. त्यानुषंगाने विनियम क्रमांक 10.10.1 (b) मधील १००० चौ.मी. क्षेत्रापेक्षा अधिक क्षेत्र व १५.० मी पेक्षा अधिक रुंद रस्ता संमुख भूखंडाचे बाबतीत, सिडकोने प्रकल्पप्रस्तांसाठी व भाडे पट्ट्याने मुळ १.५ चटई क्षेत्र निर्देशांकानुसार वाटप केलेल्या अशा भूखंडावर UDCPR प्रमाणे परवानगी देतेवेळी अतिरिक्त ०.५ चटई क्षेत्र निर्देशांक अनुज्ञेय होत आहे.

खरीलप्रमाणे आपणांस कळविण्याचे मला आदेश आहेत.



आपला
Pranav Karp

(प्रणव कर्पे)

अवर सचिव, महाराष्ट्र शासन

प्रत :

१. मा.संचालक, नगर रचना, महाराष्ट्र राज्य, पुणे.

२. मा.सह संचालक, नगर रचना कोकण विभाग, कोकण भूवन, नवी मुंबई.

३. अध्यक्ष, क्रेडाई, बी.ए.एन.एम रायगड, 121, Sky Lark, Plot No.63, Sector 11, CBD Belapur, Navi Mumbai



महाराष्ट्र शासन
नगर विकास विभाग

मादाम कामा मार्ग, हुतात्मा राजगुरु चौक, मंत्रालय, मुंबई - ४०० ०३२.

Email ID : sould12-mh@mah.gov.in

आदेश क्र.१२

क्रमांक:-टिपीएस-१२२३/६०३/प्र.क्र.७२/२३/नवि-१२

दिनांक :- २५ ऑगस्ट, २०२३

विषय :- एकत्रिकृत विकास नियंत्रण व प्रोत्साहन नियमावली (UDCPR) मंजूर
नियमावलीमधील विनियम क्र.१९(५) अन्वये स्पष्टीकरण देणेबाबत.

संदर्भ :- (१) शासनाचे आदेश क्र.टिपीएस-१८१८/प्र.क्र.२३६/१८(भाग-२)/नवि-१३,

दि.१४/१/२०२१. (स्पष्टीकरण आदेश क्र.१)

२) शासनाचे आदेश क्र.टिपीएस-१८२१/३४०/प्र.क्र.६८/२०२१/नवि-१३,

दि.१०/५/२०२१. (स्पष्टीकरण आदेश क्र.२)

३) शासनाचे आदेश क्र.टिपीएस-१२२१/९९०/प्र.क्र.४४/२१/नवि-१२,

दि.१०/६/२०२१. (स्पष्टीकरण आदेश क्र.३)

४) शासनाचे आदेश क्र.टिपीएस-१२२१/१०३९/प्र.क्र.४२/२१/नवि-१२,

दि.१४/६/२०२१. (स्पष्टीकरण आदेश क्र.४)

५) शासनाचे आदेश क्र.टिपीएस-१८१८/प्र.क्र.२३६/१८(भाग-२)/नवि-१३,

दि.१७/९/२०२१. (स्पष्टीकरण आदेश क्र.५)

६) शासनाचे आदेश क्र.टिपीएस-१८१८/प्र.क्र.२३६/१८(भाग-२)/नवि-१३,

दि.२३/१२/२०२१. (स्पष्टीकरण आदेश क्र.६)

७) शासनाचे आदेश क्र.टिपीएस-१८२१/९३३/नवि-१३, दि.२३/१२/२०२१.

(स्पष्टीकरण आदेश क्र.७)

८) शासनाचे आदेश क्र.टिपीएस-१८१८/२३६/१८(भाग-२)/नवि-१३,

दि.२६/९/२०२२ (स्पष्टीकरण आदेश क्र.८)

९) शासनाचे आदेश क्र.टिपीएस-१८१८/२३६/१८(भाग-२)/नवि-१३,

दि.१२/१०/२०२२ (स्पष्टीकरण आदेश क्र.९)

१०) शासनाचे आदेश क्र.टिपीएस-१८१८/प्र.क्र.२३६/१८(भाग-२)/नवि-१३,

दिनांक १२/१०/२०२२. (स्पष्टीकरण आदेश क्र.१०)

११) शासनाचे आदेश क्र.१८२१/२०२३/प्र.क्र.१०४/२२/नवि-३०,

दिनांक २९/११/२०२२ व समक्रमांकाचे शुध्दीपत्रक दिनांक २/६/२०२३

ज्याअर्थी, शासनाने अधिसूचना क्र. टिपीएस १८१८/प्र.क्र.३३६/१८/कलम ३७(१कक)(ग) व
कलम २०(४)/नवि-१३, दि.०२/१२/२०२० अन्वये राज्यातील सर्व नियोजन प्राधिकरणे (काही अपवाद

स.न.र.
कुपडा स्वर्गीनी नंद छेजे.

वगळता) आणि प्रादेशिक योजना क्षेत्राकरिता एकत्रिकृत विकास नियंत्रण व प्रोत्साहन नियमावली मंजूर केली असून ती दि. ०३/१२/२०२० पासून अमलात आली आहे;

आणि ज्याअर्थी, उक्त नियमावलीतील विनियम क्र.१.९ मध्ये अ.क्र. (v) या तरतुदीनुसार UDCPR मधील विविध तरतुदींच्या अन्वयार्थ संदर्भात उपस्थित प्रश्न / मुद्याच्या अनुषंगाने शासनातर्फे आदेश देणेबाबत तरतुद आहे;

आणि ज्याअर्थी, शासनाने उपरोक्त तरतुदीच्या अनुषंगाने वेळोवेळी निर्गमित आदेशान्वये संबंधितांना मार्गदर्शन केलेले आहे.

आणि ज्याअर्थी, उक्त नियमावलीतील विनियम क्र.४.८.१(b) (xvi) नुसारच्या तरतुदींची अंमलबजावणी करण्यासंदर्भात येणाऱ्या अडचणीच्या अनुषंगाने विनियमातील तरतुदींचा अन्वयार्थ स्पष्ट करणेसंदर्भात क्रेडाई एम.सी.एच.आय.ठाणे यांचेकडून शासनाकडे निवेदन प्राप्त झाले आहेत;

आणि ज्याअर्थी, उक्त निवेदन विचारात घेता आणि जनहिताच्या दृष्टीने, उक्त नियमावलीची प्रभावी अंमलबजावणी होण्यासाठी उक्त नियमावलीतील, उक्त तरतुदींबाबत व्यवहार्यता तपासून अशा तरतुदींचे पुनरावलोकन करून विनियम क्र.१.९ मधील (v) नुसार शासनाकडून अशा तरतुदींबाबत स्पष्टीकरण करणे आवश्यक असल्याचे शासनाचे मत झाले आहे.

आता त्याअर्थी उक्त नियमावलीतील उक्त विनियम क्र. ४.८.१(b) (xvi) च्या अनुषंगाने खालीलप्रमाणे स्पष्टीकरणात्मक सुचना निर्गमित करण्यात येत आहेत :-

“ एकत्रिकृत विकास नियंत्रण व प्रोत्साहन नियमावली मधील टेबल ६A व ६G मध्ये भूखंडावर एकूण परवानगीयोग्य बांधकाम क्षेत्र व त्यावर अनुज्ञेय Ancillary area FSI बाबतच्या तरतुदी नमूद केल्या आहेत. सदर एकूण अनुज्ञेय बांधकाम क्षेत्रापैकी भूखंडावर अनुज्ञेय TDR, प्रिमियम FSI, Ancillary area FSI हे ऐच्छिक स्वरूपाचे असून ते अधिमूल्य भरून अथवा विकत घेणे आवश्यक असल्यामुळे विनियम ४.८(१)(b)(xvi) मधील सदनिर्णयाचे क्षेत्राची (२०% क्षेत्राची) आकडेमोड करण्यासाठी सदर TDR, प्रिमियम FSI, Ancillary area FSI विचारात न घेता केवळ Basic FSI चे क्षेत्र विचारात घेऊन त्यानुसार ५० चौ.मी. बांधकाम क्षेत्राची (Built up area) सदनिका (Tenement) बांधकाम करणे आवश्यक आहे.”

(निर्मलकुमार चौधरी)

उपसचिव, महाराष्ट्र शासन

प्रत :-

१. मा.मुख्यमंत्री महोदय यांचे अपर मुख्य सचिव, मंत्रालय, मुंबई.
२. मा.उप मुख्यमंत्री महोदय यांचे सचिव, मंत्रालय, मुंबई.
३. मा.अध्यक्ष, महाराष्ट्र विधानसभा, महाराष्ट्र विधानमंडळ सचिवालय, मुंबई.
४. मा.सभापती, महाराष्ट्र विधानपरिषद, महाराष्ट्र विधानमंडळ सचिवालय, मुंबई.
५. मा.विरोधी पक्षनेता, विधानसभा, महाराष्ट्र विधानमंडळ सचिवालय, मुंबई.
६. मा.विरोधी पक्षनेता, विधानपरिषद, महाराष्ट्र विधानमंडळ सचिवालय, मुंबई.
७. मा.मुख्य सचिव, महाराष्ट्र शासन, मंत्रालय, मुंबई.

नगर रचना आणि मूल्यनिर्धारण विभाग
पु.का., पुणे-१. आवक क्र.
टिपीव्ही - १/२/३/४/५/६/७
21 SEP 2023
प्रशा - १/१ अ/२ लेखा/अर्थसंकल्प
कार्यालय पु.का. अ. उ. न. र. त. १/२

महाराष्ट्र प्रादेशिक नियोजन व नगर रचना
अधिनियम, १९६६ चे कलम १५४ अन्वये निदेश.
(केंद्र शासनाच्या गृहनिर्माण व शहरी मंत्रालय विभागाने
जारी केलेल्या addendum to model building Bye-
Laws 2016 या विनियमांचा अंतर्भाव राज्यातील सर्व
नियोजन प्राधिकरणांच्या मंजूर विकास नियंत्रण
नियमावलीमध्ये करणेबाबत.)

महाराष्ट्र शासन
नगर विकास विभाग,

शासन निर्णय क्र. टिपीएस-१८२२/१८१८/प्र.क्र.१७९/२०२२/नवि-१३,

मादाम कामा मार्ग, हुतात्मा राजगुरु चौक,
चौथा मजला, मंत्रालय, मुंबई ४०० ०३२.

दिनांक : २५.०८.२०२३

आदेश

महाराष्ट्र प्रादेशिक नियोजन व नगर रचना अधिनियम, १९६६
प्रस्तावना -

केंद्र शासनाच्या गृहनिर्माण आणि शहरी व्यवहार मंत्रालयाने जारी केलेल्या Addendum to model building Bye-Laws 2016 या विनियमाचा अंतर्भाव तातडीने अंतर्भाव राज्यातील सर्व नियोजन प्राधिकरणांच्या मंजूर विकास नियंत्रण नियमावलीमध्ये करण्याचा आहे.

Addendum to model building Bye-Laws २०१६ या विनियमामधील बाबी या इमारतीच्या अंतर्गत संरक्षणासंबंधी असल्यामुळे सदर विषयी नवि-१ मार्फत कार्यवाही होणे आवश्यक असल्याने सार्वजनिक हिताच्या दृष्टीने तसेच केंद्र शासनाचे मार्गदर्शक सूचनांची अंमलबजावणी व्हावी या दृष्टीकोनातून सदरची मार्गदर्शक तत्वे व विनियम लगेच लागू करण्यासाठी सदर प्रकरणी महाराष्ट्र प्रादेशिक नियोजन व नगर रचना अधिनियम १९६६ चे कलम १५४ अन्वयेचे निदेश राज्यातील सर्व नियोजन प्राधिकरणांना देण्याची बाब शासनाच्या विचाराधीन होती.

त्यास अनुसरून विषयांकित प्रकरणी सार्वजनिक हिताच्या दृष्टीकोनातून केंद्र शासनाच्या गृहनिर्माण आणि शहरी व्यवहार मंत्रालयाने जारी केलेल्या Addendum to model building Bye-Laws 2016 या विनियमाचा अंतर्भाव तातडीने राज्यातील सर्व नियोजन प्राधिकरणांच्या मंजूर विकास नियंत्रण नियमावलीमध्ये करण्यासाठी राज्यातील सर्व नियोजन प्राधिकरणांना उक्त अधिनियमाचे कलम १५४ अन्वये प्राप्त अधिकारात शासन खालीलप्रमाणे निदेश देत आहे.



नगर रचना आणि मूल्यनिर्धारण विभाग
उपसंचालक, नगर रचना (ना.सं.व.)
आ.क्र. १३६ दिनांक-०५.१०.२३
संबंधित अधि./कम.
२२.९.२३
व.सं.न.र.

शासन निदेश

१. राज्यातील सर्व नियोजन प्राधिकरणांनी त्यांचे कार्यक्षेत्रामध्ये विकास प्रस्तावांना मंजूरी देतेवेळी केंद्र शासनाच्या गृहनिर्माण आणि शहरी व्यवहार मंत्रालयाने जारी केलेल्या Addendum to model building Bye-Laws 2016 या विनियमाची अंमलबजावणी ही सोबत जोडलेल्या परिशिष्टामधील तरतुदीनुसार करावी. तसेच सदर परिशिष्टामधील विकास नियंत्रण नियमावलीशी संबंधित तरतुदींचे परिपालन होईल याची दक्षता घ्यावी.
२. सदरचे निदेश हे तात्काळ अंमलात येत असून शासनाच्या सदर विनियमाची अंमलबजावणी राज्यातील सर्व नियोजन प्राधिकरणांनी तात्काळ सुरु करावी.

महाराष्ट्राचे राज्यपाल यांचे आदेशानुसार व नावाने.



(डॉ.प्रतिभा भदाणे)

सह सचिव, महाराष्ट्र शासन

प्रत : - आवश्यक त्या कार्यवाहीसाठी

१. आयुक्त, सर्व महानगरपालिका
२. मुख्याधिकारी, सर्व नगरपरिषदा / सर्व नगरपंचायती.
३. मुख्य कार्यकारी अधिकारी सर्व जिल्हापरिषदा.
४. महानगर-आयुक्त, सर्व महानगर प्रदेश विकास प्राधिकरणे.
५. मुख्य कार्यकारी अधिकारी, कोल्हापूर नागरी क्षेत्र विकास प्राधिकरण, कोल्हापूर.

प्रत -

१. मा.मुख्यमंत्री महोदय यांचे अपर मुख्य सचिव, मंत्रालय, मुंबई.
२. मा.उप मुख्यमंत्री महोदय यांचे सचिव, मंत्रालय, मुंबई.
३. मा.विरोधी पक्षनेता, विधानपरिषद / विधानसभा, महाराष्ट्र विधानमंडळ सचिवालय, मुंबई.
४. मा.उपसभापती, महाराष्ट्र विधानपरिषद, महाराष्ट्र विधानमंडळ सचिवालय, मुंबई.
५. मा.उपाध्यक्ष, महाराष्ट्र विधानसभा, महाराष्ट्र विधानमंडळ सचिवालय, मुंबई.
६. मा.मुख्य सचिव, महाराष्ट्र राज्य, नगर विकास विभाग, मंत्रालय, मुंबई.
७. प्रधान सचिव (नवि-१), नगर विकास विभाग, मंत्रालय, मुंबई.
८. प्रधान सचिव, (नवि-२) नगर विकास विभाग, मंत्रालय, मुंबई.
९. संचालक (नगर रचना) तथा सह सचिव, नगर विकास विभाग, मंत्रालय, मुंबई.

प्रत माहितीस्तव व कार्यवाहीसाठी -

- १) संचालक, नगर रचना, महाराष्ट्र राज्य, पुणे.
- २) विभागीय सहसंचालक, नगर रचना, पुणे / नागपूर / अमरावती / कोकण / औरंगाबाद / नाशिक.
- ३) विभागीय आयुक्त, पुणे / नागपूर / अमरावती / कोकण / औरंगाबाद / नाशिक.
- ४) सहायक संचालक, नगर रचना / नगर रचनाकार, नगर रचना व मूल्यनिर्धारण विभाग, सर्व शाखा कार्यालये.
- ५) अवर सचिव, नवि-११ / नवि-३०, कक्ष अधिकारी, नवि-९ / नवि-१२, नगर विकास विभाग, मंत्रालय, मुंबई.
- ६) कक्ष अधिकारी (नवि-२९), नगर विकास विभाग, मंत्रालय, मुंबई.
-/सदर आदेश विभागाच्या संकेतस्थळावर प्रसिध्द करण्यात यावेत.
- ७) कक्ष अधिकारी, माहिती व तंत्रज्ञान विभाग, मंत्रालय, मुंबई.
-/सदर आदेश शासनाच्या संकेतस्थळावर प्रसिध्द करण्याबाबत कार्यवाही करण्यात यावी.
- ८) निवड नस्ती, कार्यासन (नवि-१३).



परिशिष्ट

(केंद्र शासनाच्या गृहनिर्माण व शहरी मंत्रालय विभागाने जारी केलेल्या addendum to model building Bye-Laws 2016 या विनियमांचा अंतर्भाव राज्यातील सर्व नियोजन प्राधिकरणांच्या मंजूर विकास नियंत्रण नियमावलीमध्ये करणेबाबत विनियम)

Architects / Developer & Planning Authority Officer approving the plans shall ensure that the following provisions are incorporated in the building plans -

a) Plan for creation of Common Telecommunication Infrastructure including the common duct to access the common space used as telecom room inside the building is also prepared and separate set of drawings showing the inter / intra connectivity access to the building with distribution network.

b) In Building Solutions In Built Solutions (IBS) - Installation spaces : area for rooms or systems should be provided as given below :-

(I) Telecom Room Space for the building with built-up area more than 465 sq.mt.

Sr. No.	Area to be covered by IBS	Size of Telecom Room (all dimension in m.)
1	Upto 465 sq.mt	3.0 m. X 2.4 m.
2	465 sq.mt. to 930 sq.mt	3.0 m. X 3.4 m.
3	More than 930.0 sq.mt	Additional Telecom Room required with same space norms

(II) Telecom Room Space requirements for the smaller building with built-up area less than 465 sq.mt.

Sr. No.	Area to be covered by IBS	Size of Telecom Room (all dimension in m.)
1	Upto 93.0 sq.mt	Wall cabinets, Self contained enclosed cabinets
2	93.0 sq.mt. to 465.0 sq.mt.	i) Shallow Room - 0.6 m. x 2.6 m. ii) Walk - in Room 1.3 m. x 1.3 m

(III) In Building Solutions In Built Solutions (IBS) -installation spaces, so provided, should be :

- It should not susceptible to flooding
- It should not exposed to water, moisture, fumes, gases or dust
- It should be able to with stand designed equipment load (to be specified in design)
- It should be located away from any vibrations to avoid dislocation / dislodgement

c) At Layout Level -

- 1) The placement and sequence of above and below-ground utilities at the appropriate location in the right-of-way to be ensured for unconstrained movement as well as easy access for



maintenance. Empty pipes (large size Hume pipes / HDPE pipes) should be laid before planting trees in order to accommodate additional Infrastructure.

2) Design criteria and standards utilities should meet the following criteria :

Telecommunication cables should ideally be placed below the parking area or service lane, which may be dug up easily without causing major inconvenience. Where this is not possible, the cables may be placed at the outer edge of the right-of-way. Telecom boxes should be placed in easements just off the right-of-way. Where this is not possible, they should be placed within parking or landscaping areas. If cables have to be located in the pedestrian path, a space of at least 2.0 m. should be maintained for the through movement of pedestrians. Telecom boxes should never constrain the width of a Cycle Track.

- d) While preparing the building plans, properly demarcated sections within buildings and on rooftops for housing Broad Band / digital connectivity infrastructure / antenna shall be shown on plans.
- e) The layout plans should clearly indicate the telecom as Utility Infrastructure lines.
- f) While submitting the proposed Building plan seeking approval from the relevant sanctioning Authority, applicant shall also submit a complete Service Plan for In Building Solutions (IBS) -Infrastructure along with required specifications (in consultation with, and certified by a credible Telecom Networking hardware-consultant)
- g) Occupancy / Building Completion certificate to a building to be granted only after ensuring that the Common Telecommunication Infrastructure as per the prescribed standards is in place.
- h) Visit from Department of Telecom (DOT) / TRAI officials along-with joint inspection with Telecom Service Providers (TSPs) who may suggest any relevant modification in the plan may be arranged, if required by Planning Authorities.
- i) For any other necessary detailing of building components and service installations w.r.t. Common Telecom / Digital Connectivity Infrastructure, Architects / Developers and other service consultants involved in preparing building and service drawings may refer Part 8 - Section 6 : Information and communication Enabled Installations of Volume 2 of the National Building Code, 2016 and the norms of Department of Telecommunication / Information Technology or concerned Department of the Central / State Government, if any.




(डॉ. प्रतिभा भदोणे)
सह सचिव, महाराष्ट्र शासन



महाराष्ट्र शासन
नगर विकास विभाग

मादाम कामा मार्ग, हुतात्मा राजगुरु चौक, मंत्रालय, मुंबई - ४०० ०३२.

दुरध्वनी क्र.०२२-२२७९४९९६

Email ID : kishor.gokhale@gov.in

आदेश क्र. १२

क्रमांक:-टिपीएस-१८१८/प्र.क्र.५४/२०२३/नवि-१३

दिनांक:-२८.०८.२०२३.

विषय :- मंजूर एकत्रिकृत विकास नियंत्रण व प्रोत्साहन नियमावली (UDCPR)
मधील विनियम क्र.१४.२.१.२.४ संदर्भात स्पष्टीकरण देणेबाबत.

- संदर्भ :- १) शासनाचे आदेश क्र.टिपीएस-१८१८/प्र.क्र.२३६/१८(भाग-२)/नवि-१३,
दि.१४/९/२०२१. (स्पष्टीकरण आदेश क्र.१)
२) शासनाचे आदेश क्र.टिपीएस-१८२१/३४०/प्र.क्र.६८/२०२१/नवि-१३,
दि.१०/५/२०२१. (स्पष्टीकरण आदेश क्र.२)
३) शासनाचे आदेश क्र.टिपीएस-१२२१/९९०/प्र.क्र.४४/२१/नवि-१२,
दि.१०/६/२०२१. (स्पष्टीकरण आदेश क्र.३)
४) शासनाचे आदेश क्र.टिपीएस-१२२१/१०३९/प्र.क्र.४२/२१/नवि-१२,
दि.१४/६/२०२१. (स्पष्टीकरण आदेश क्र.४)
५) शासनाचे आदेश क्र.टिपीएस-१८१८/प्र.क्र.२३६/१८(भाग-२)/नवि-१३,
दि.१७/९/२०२१. (स्पष्टीकरण आदेश क्र.५)
६) शासनाचे आदेश क्र.टिपीएस-१८१८/प्र.क्र.२३६/१८(भाग-२)/नवि-१३,
दि.२३/१२/२०२१. (स्पष्टीकरण आदेश क्र.६)
७) शासनाचे आदेश क्र.टिपीएस-१८२१/९३३/नवि-१३, दि.२३/१२/२०२१.
(स्पष्टीकरण आदेश क्र.७)
८) शासनाचे आदेश क्र.टिपीएस-१८१८/२३६/१८(भाग-२)/नवि-१३,
दि.२६/९/२०२२ (स्पष्टीकरण आदेश क्र.८)
९) शासनाचे आदेश क्र.टिपीएस-१८१८/२३६/१८(भाग-२)/नवि-१३,
दि.१२/१०/२०२२ (स्पष्टीकरण आदेश क्र.९)
१०) शासनाचे आदेश क्र.टिपीएस-१८१८/२३६/१८(भाग-२)/नवि-१३,
दि.१२/१०/२०२२ (स्पष्टीकरण आदेश क्र.१०)
११) शासनाचे आदेश क्र.टिपीएस-१८२१/२०२३/प्र.क्र.१०४/२०२२/नवि-३०,
दि.२९/११/२०२२ (स्पष्टीकरण आदेश क्र.११)
१२) शासनाचे आदेश क्र.टिपीएस-१८२१/२०२३/प्र.क्र.१०४/२०२२/नवि-३०,
दि.०२/०६/२०२३ (शुध्दीपत्रक, आदेश क्र.११ संदर्भात)

ज्याअर्धी, शासनाने अधिसूचना क्र. टिपीएस १८१८/प्र.क्र.३३६/१८/कलम ३७(१कक)(ग) व कलम
२०(४)/नवि-१३, दि.०२/१२/२०२० अन्वये राज्यातील सर्व नियोजन प्राधिकरणे (काही अपवाद वगळता)
आणि प्रादेशिक योजना क्षेत्राकरिता एकत्रिकृत विकास नियंत्रण व प्रोत्साहन नियमावली मंजूर घेऊनी असून
तो दि. ०३/१२/२०२० पासून अंमलात आली आहे;

आणि ज्याअर्थी, उक्त नियमावलीतील विनियम क्र.१९ मध्ये अ.क्र. (v) या तरतुदीनुसार UDCPR मधील विविध तरतुदीच्या अन्वयार्थ संदर्भात उपस्थित प्रश्न / मुद्द्याच्या अनुषंगाने शासनातर्फे आदेश देणेबाबत तरतुद आहे:

आणि ज्याअर्थी, या शासनाने उपरोक्त तरतुदीच्या अनुषंगाने येळोवळी निर्गमित आदेशान्वये संबंधितांना मार्गदर्शन केलेले आहे.

आणि ज्याअर्थी, उक्त नियमावलीतील विनियम क्र.१४.२.१.२.४ नुसारच्या तरतुदीची अंमलबजावणी करण्यासंदर्भात येणाऱ्या अडचणीच्या अनुषंगाने, पुणे महानगर प्रदेश विकास प्राधिकरण यांचेकडून शासनाकडे निवेदन प्राप्त झाले आहे;

आणि ज्याअर्थी, उक्त निवेदन विचारात घेता आणि जनहिताच्या दृष्टीने, उक्त नियमावलीची प्रभावी अंमलबजावणी होण्यासाठी उक्त नियमावलीतील काही तरतुदीबाबत व्यवहार्यता तपासून अशा तरतुदीचे पुनरावलोकन करून विनियम क्र.१९ मधील (v) नुसार शासनाकडून अशा तरतुदीबाबत स्पष्टीकरण करणे आवश्यक असल्याचे शासनाचे मत झाले आहे.

आता त्याअर्थी उक्त नियमावलीतील उक्त विनियम क्र. १४.२.१.२.४ च्या अनुषंगाने खालीलप्रमाणे स्पष्टीकरणात्मक सूचना निर्गमित करण्यात येत आहेत :-

• विनियम क्र.१४.२.१.२.४ (ii) -

एकत्रिकृत विकास नियंत्रण व प्रोत्साहन नियमावलीचे टी.ओ.डी. संदर्भातील विनियम क्र.१४.२.१.२.४(ii) नुसार, विनियम क्र.१४.२.१.२ अन्वये रस्तारहदी सापेक्ष कमाल अनुज्ञेय घटई क्षेत्र निर्देशांकामधून बेसीक अनुज्ञेय FSI बजा केल्यानंतर, उर्वरित अतिरिक्त घटई क्षेत्र निर्देशांकामधी २५% FSI हा टी.ओ.आर च्या माध्यमातून व ७५ % FSI हा प्रिमियमच्या माध्यमातून वापरावयाचा आहे. तथापि, विशिष्ट प्रकरणी वि.पो रस्ता, आरक्षण, सुविधा क्षेत्र इ. चा in situ FSI वापरावयाचा असल्यास, कमाल अनुज्ञेय होणाऱ्या घटई क्षेत्र निर्देशांकामधून (म्हणजेच २,५०, ३,००, ३,५०, ४,०० मधून) बेसीक अनुज्ञेय FSI बजा केल्यानंतर, उर्वरित अतिरिक्त FSI मधून In-situ FSI वापरून झाल्यावर आणखी FSI शिल्लक राहीला असल्यास, २५% FSI हा टी.ओ.आर च्या माध्यमातून व ७५ % FSI हा प्रिमियमच्या माध्यमातून वापरावयाचा आहे.

तथापि, एखाद्या प्रकरणी विकास योजना रस्ता, आरक्षण, सुविधा क्षेत्र इ. चा in situ FSI चे अनुषंगाने उपलब्ध विकास हक्क (Development Rights - DR) हा बजा केल्यानंतर उर्वरित FSI चे २५% व ७५% विभागणी करणेऐवजी अनुज्ञेय होणारा in situ FSI / DR, २५% TDR च्या घटकामध्ये समायोजित करणे व उर्वरित ७५% FSI हा प्रिमियमच्या माध्यमातून वापरण्याबाबतचा पर्याय अवलंबविण्याची विनंती जमोनमालक/विकासक यांनी केली असल्यास, त्यानुसार विनंतीच्या अनुषंगाने संबंधित प्रकरणातील गुणवत्ता विचारात घेऊन, उपलब्ध in situ FSI हा DRC ची कार्यवाही न करता, सदर in situ FSI हा TDR गृहित धरून तो २५% TDR घटकामध्ये समायोजित करण्याची परवानगी देण्यास हरकत नसावी.

Handwritten signature

(प्रणय कर्पे)

अवर सचिव, महाराष्ट्र शासन

प्रत :-

- १) मा.मुख्यमंत्री महोदय यांचे अपर मुख्य सचिव, मंत्रालय, मुंबई.
- २) मा.उप मुख्यमंत्री महोदय यांचे सचिव, मंत्रालय, मुंबई.
- ३) मा.अध्यक्ष, महाराष्ट्र विधानसभा, महाराष्ट्र विधानमंडळ सचिवालय, मुंबई.
- ४) मा.सभापती, महाराष्ट्र विधानपरिषद, महाराष्ट्र विधानमंडळ सचिवालय, मुंबई.
- ५) मा.विरोधी पक्षनेता, विधानसभा, महाराष्ट्र विधानमंडळ सचिवालय, मुंबई.
- ६) मा.विरोधी पक्षनेता, विधानपरिषद, महाराष्ट्र विधानमंडळ सचिवालय, मुंबई.
- ७) मा.मुख्य सचिव, महाराष्ट्र शासन, मंत्रालय, मुंबई.
- ८) अपर मुख्य सचिव (नवि-१), नगर विकास विभाग, मंत्रालय, मुंबई.
- ९) संचालक (नगर रचना) तथा सह सचिव, नगर विकास विभाग, मंत्रालय, मुंबई.
- १०) सह सचिव तथा सह संचालक (नगर रचना), नगर विकास विभाग, मंत्रालय, मुंबई.

प्रति :-

- १) संचालक, नगर रचना, महाराष्ट्र राज्य, पुणे.
- २) सर्व विभागीय आयुक्त.
- ३) सर्व विभागीय सहसंचालक, नगर रचना.
- ४) सर्व आयुक्त, महानगरपालिका.
- ५) सर्व महानगर आयुक्त, महानगर प्रदेश विकास प्राधिकरणे / विशेष नियोजन प्राधिकरणे.
- ६) मुख्य कार्यकारी अधिकारी, कोल्हापूर नागरी क्षेत्र विकास प्राधिकरण, कोल्हापूर.
- ७) सर्व महानगर आयुक्त, नवनगर प्रदेश विकास प्राधिकरणे.
- ८) मुख्य कार्यकारी अधिकारी, सर्व जिल्हापरिषद.
- ९) मुख्याधिकारी सर्व नगरपरिषदा / नगरपंचायती.
- १०) सर्व जिल्हाधिकारी.
- ११) सहायक संचालक, नगर रचना / नगर रचनाकार, नगर रचना व मूल्यनिर्धारण विभाग, सर्व शाखा कार्यालये.
- १२) अपर सचिव, नवि-११ / नवि-१२ / नवि-३०, कक्ष अधिकारी, नवि-९, नगर विकास विभाग, मंत्रालय, मुंबई.
- १३) कक्ष अधिकारी (नवि-२९), नगर विकास विभाग, मंत्रालय, मुंबई.
/- सोबतचे निदेश या विभागाच्या संकेतस्थळावर प्रसिध्द करावेत.
- १४) कक्ष अधिकारी, माहिती व तंत्रज्ञान विभाग, मंत्रालय, मुंबई.
/- सदरचे निदेश शासनाच्या संकेतस्थळावर प्रसिध्द करावेत.
- १५) निवड नसती, कार्यासन (नवि-१३).



महाराष्ट्र शासन
नगर विकास विभाग

मादाम कामा मार्ग, हुतात्मा राजगुरु चौक, मंत्रालय, मुंबई - ४०० ०३२.

Email ID : soud12-mh@mah.gov.in

आदेश क्र.१३

क्रमांक:-टिपीएस-१२२१/२१७४/प्र.क्र.५८/२२/नवि-१२

दिनांक :- ४ सप्टेंबर, २०२३.

विषय :- एकत्रिकृत विकास नियंत्रण व प्रोत्साहन नियमावली (UDCPR) मंजूर
नियमावलीमधील विनियम क्र.१.१(४) अन्वये स्पष्टीकरण देणेबाबत.

संदर्भ :- १) शासनाचे आदेश क्र.टिपीएस-१८१८/प्र.क्र.२३६/१८(भाग-२)/नवि-१३,
दि.१४/१/२०२१. (स्पष्टीकरण आदेश क्र.१)

२) शासनाचे आदेश क्र.टिपीएस-१८२१/३४०/प्र.क्र.६८/२०२१/नवि-१३,
दि.१०/५/२०२१. (स्पष्टीकरण आदेश क्र.२)

३) शासनाचे आदेश क्र.टिपीएस-१२२१/९९०/प्र.क्र.४४/२१/नवि-१२,
दि.१०/६/२०२१. (स्पष्टीकरण आदेश क्र.३)

४) शासनाचे आदेश क्र.टिपीएस-१२२१/१०३९/प्र.क्र.४२/२१/नवि-१२,
दि.१४/६/२०२१. (स्पष्टीकरण आदेश क्र.४)

५) शासनाचे आदेश क्र.टिपीएस-१८१८/प्र.क्र.२३६/१८(भाग-२)/नवि-१३,
दि.१७/९/२०२१. (स्पष्टीकरण आदेश क्र.५)

६) शासनाचे आदेश क्र.टिपीएस-१८१८/प्र.क्र.२३६/१८(भाग-२)/नवि-१३,
दि.२३/१२/२०२१. (स्पष्टीकरण आदेश क्र.६)

७) शासनाचे आदेश क्र.टिपीएस-१८२१/९३३/नवि-१३, दि.२३/१२/२०२१.
(स्पष्टीकरण आदेश क्र.७)

८) शासनाचे आदेश क्र.टिपीएस-१८१८/२३६/१८(भाग-२)/नवि-१३,
दि.२६/९/२०२२ (स्पष्टीकरण आदेश क्र.८)

९) शासनाचे आदेश क्र.टिपीएस-१८१८/२३६/१८(भाग-२)/नवि-१३,
दि.१२/१०/२०२२ (स्पष्टीकरण आदेश क्र.९)

१०) शासनाचे आदेश क्र.टिपीएस-१८१८/प्र.क्र.२३६/१८(भाग-२)/नवि-१३,
दिनांक १२/१०/२०२२. (स्पष्टीकरण आदेश क्र.१०)

११) शासनाचे आदेश क्र.१८२१/२०२३/प्र.क्र.१०४/२२/नवि-३०,
दिनांक २९/११/२०२२ व समक्रमांकाचे शुध्दीपत्रक दिनांक २/६/२०२३.

१२) शासनाचे आदेश क्र.टिपीएस-१२२३/६०३/प्र.क्र.७२/२३/नवि-१२,
दिनांक २५/८/२०२३ (स्पष्टीकरण आदेश क्र.१२)

ज्याअर्थी, शासनाने अधिसूचना क्र. टिपीएस १८१८/प्र.क्र.२३६/१८/कलम ३७(१कक)(ग) व
कलम २०(४)/नवि-१३, दि.०२/१२/२०२० अन्वये राज्यातील सर्व नियोजन प्राधिकरणे (काही अपवाद

वगळता) आणि प्रादेशिक योजना क्षेत्राकरिता एकात्रिकृत विकास नियंत्रण व प्रोत्साहन नियमावली मंजूर केली असून ती दि. ०३/१२/२०२० पासून अंमलात आली आहे;

आणि ज्याअर्थी, उक्त नियमावलीतील विनियम क्र.१९ मध्ये अ.क्र. (v) या तरतुदीनुसार UDCPR मधील विविध तरतुदीच्या अन्वयार्थ संदर्भात उपस्थित प्रश्न / मुद्द्याच्या अनुषंगाने शासनातर्फे आदेश देणेबाबत तरतुद आहे;


आणि ज्याअर्थी, शासनाने उपरोक्त तरतुदीच्या अनुषंगाने वेळोवेळी निर्गमित आदेशांन्वये संबंधितांना मार्गदर्शन केलेले आहे.

आणि ज्याअर्थी, महाराष्ट्र महानगरपालिका अधिनियम, १९४९ अन्वये प्रस्तावित केलेल्या रस्त्याच्या विकासाकरिता Construction Amenity TDR देणेच्या अनुषंगाने, उक्त नियमावलीतील विनियम क्र.११.२.५ नुसार तरतुदीची अंमलबजावणी करण्यासंदर्भात येणाऱ्या अडचणीच्या अनुषंगाने विनियमातील तरतुदीचा अन्वयार्थ स्पष्ट करणेसंदर्भात नियोजन प्राधिकरणाकडून शासनाकडे निवेदन प्राप्त झाले आहे;

आणि ज्याअर्थी, उक्त निवेदन विचारात घेता आणि जनहिताच्या दृष्टीने, उक्त नियमावलीची प्रभावी अंमलबजावणी होण्यासाठी उक्त नियमावलीतील, उक्त तरतुदीबाबत व्यवहार्यता तपासून अशा तरतुदीचे पुनरावलोकन करून विनियम क्र.१९ मधील (v) नुसार शासनाकडून अशा तरतुदीबाबत स्पष्टीकरण करणे आवश्यक असल्याचे शासनाचे मत झाले आहे.

आता त्याअर्थी उक्त नियमावलीतील उक्त विनियम क्र. ११.२.५ च्या अनुषंगाने खालीलप्रमाणे स्पष्टीकरणात्मक सूचना निर्गमित करण्यात येत आहेत :-

“ज्या प्रकरणी मंजूर विकास योजनेतील प्रस्तावित रस्ता अथवा महापालिका, नगरपालिका अधिनियमांतर्गत प्रस्तावित रस्ता त्याच जागेच्या मालकाने रस्त्याखालील जागा प्राधिकरणास हस्तांतरित करणे व त्याचा विकास करणे, त्यासाठी जमिनमालकास विनियम क्र.११.२.२ नुसार जागेचा व विनियम क्र.११.२.५ नुसार बांधकामाचा अशा दोन्ही प्रकारचा टिडीआर अनुज्ञेय आहे. मात्र ज्या प्रकरणी प्रस्तावित रस्त्याखालील जागेच्या जमिनमालका व्यतिरिक्त त्रयस्थ विकासकर्ते अशा रस्त्याचे बांधकाम करून घेण्यात येत असल्यास त्याबाबतची तरतुद फक्त विकास योजना रस्त्यापुरती मर्यादित आहे.”


(निर्मलकुमार चौधरी)

उपसचिव, महाराष्ट्र शासन

प्रत :-

१. मा.मुख्यमंत्री महोदय यांचे अपर मुख्य सचिव, मंत्रालय, मुंबई.
२. मा.उप मुख्यमंत्री महोदय यांचे सचिव, मंत्रालय, मुंबई.
३. मा.अध्यक्ष, महाराष्ट्र विधानसभा, महाराष्ट्र विधानमंडळ सचिवालय, मुंबई.
४. मा.सभापती, महाराष्ट्र विधानपरिषद, महाराष्ट्र विधानमंडळ सचिवालय, मुंबई.
५. मा.विरोधी पक्षनेता, विधानसभा, महाराष्ट्र विधानमंडळ सचिवालय, मुंबई.



२१/१२/२०२३
१३

**महाराष्ट्र शासन
नगर विकास विभाग**

मादाम कामा मार्ग, हुतात्मा राजगुरु चौक, मंत्रालय, मुंबई - ४०० ०३२,

Email ID : soundd12-mh@mah.gov.in

आदेश क्र.१४

क्रमांक:-टिपीएस-१२२३/१०५/प्र.क्र.१००/२३/नवि-१२ दिनांक :- १८ ऑक्टोबर, २०२३.

विषय :- एकत्रिकृत विकास नियंत्रण व प्रोत्साहन नियमावली (UDCPR) मंजूर
नियमावलीमधील विनियम क्र.१.१(v) अन्वये स्मार्टीकरण देण्याबत.

संदर्भ :- १) शासनाचे आदेश क्र.टिपीएस-१८१८/प्र.क्र.२३६/१८(भाग-२)/नवि-१३,
दि.१४/१/२०२१. (स्मार्टीकरण आदेश क्र.१)

२) शासनाचे आदेश क्र.टिपीएस-१८२१/३४०/प्र.क्र.६८/२०२१/नवि-१३,
दि.१०/५/२०२१. (स्मार्टीकरण आदेश क्र.२)

३) शासनाचे आदेश क्र.टिपीएस-१२२१/११०/प्र.क्र.४४/२१/नवि-१२,
दि.१०/६/२०२१. (स्मार्टीकरण आदेश क्र.३)

४) शासनाचे आदेश क्र.टिपीएस-१२२१/१०३९/प्र.क्र.४२/२१/नवि-१२,
दि.१४/६/२०२१. (स्मार्टीकरण आदेश क्र.४)

५) शासनाचे आदेश क्र.टिपीएस-१८१८/प्र.क्र.२३६/१८(भाग-२)/नवि-१३,
दि.१७/९/२०२१. (स्मार्टीकरण आदेश क्र.५)

६) शासनाचे आदेश क्र.टिपीएस-१८१८/प्र.क्र.२३६/१८(भाग-२)/नवि-१३,
दि.२३/१२/२०२१. (स्मार्टीकरण आदेश क्र.६)

७) शासनाचे आदेश क्र.टिपीएस-१८२१/१३३/नवि-१३, दि.२३/१२/२०२१.
(स्मार्टीकरण आदेश क्र.७)

८) शासनाचे आदेश क्र.टिपीएस-१८१८/२३६/१८(भाग-२)/नवि-१३,
दि.२६/१/२०२२ (स्मार्टीकरण आदेश क्र.८)

९) शासनाचे आदेश क्र.टिपीएस-१८१८/२३६/१८(भाग-२)/नवि-१३,
दि.१२/१०/२०२२ (स्मार्टीकरण आदेश क्र.९)

१०) शासनाचे आदेश क्र.टिपीएस-१८१८/प्र.क्र.२३६/१८(भाग-२)/नवि-१३,
दिनांक १२/१०/२०२२, (स्मार्टीकरण आदेश क्र.१०)

११) शासनाचे आदेश क्र.१८२१/२०२३/प्र.क्र.१०४/२२/नवि-३०,
दिनांक २९/११/२०२२ व समक्रमांकाचे शुद्धीपत्रक दिनांक २/६/२०२३.

१२) शासनाचे आदेश क्र.टिपीएस-१२२३/६०३/प्र.क्र.७२/२३/नवि-१२,
दिनांक २५/८/२०२३ व टिपीएस-१८१८/प्र.क्र.५४/२३/नवि-१३
दि.२८/८/२०२३ (स्मार्टीकरण आदेश क्र.१२)

१३) शासनाने आदेश क्र.टिपीएम-१२२३/२१७४/प्र.क्र.५८/२२/नवि-१२,

दिनांक ४/९/२०२३ (सगरीकरणे आदेश क्र.१३)

ज्याअर्थी, शासनाने अधिसूचना क्र. टिपीएस २८१८/प्र.क्र.३३६/१८/कलम ३७(१कक)/ग) व कलम २७(४)/नवि-१३, दि.०२/१२/२०२० अन्वये सन्यातील सर्व नियोजन प्राधिकरणे (काही अपवाद वगळता) आणि प्रादेशिक योजना क्षेत्राकरिता एकत्रित विकास नियंत्रण व प्रोत्साहन नियमावली संजूर केली असून ती दि. ०३/१२/२०२० पासून अंमलात आली आहे;

आणि ज्याअर्थी, उक्त नियमावलीतील विनियम क्र.१.९ मध्ये अ.क्र. (v) या तरतुदीनुसार UDCPR मधील विविध तरतुदीच्या अन्वयार्थ संदर्भात उपस्थित प्रश्न / मुद्द्याच्या अनुषंगाने शासनाने आदेश देण्यात तरतुद आहे;

आणि ज्याअर्थी, शासनाने उपरोक्त तरतुदीच्या अनुषंगाने चेळोवळी निर्गमित आदेशान्वये संबंधितांना मार्गदर्शन केलेले आहे;

आणि ज्याअर्थी, उक्त नियमावलीमधील विनियम क्र.७.७ (Development of Housing for EWS/LIG in Residential Zone) नुसारच्या तरतुदीची अंमलबजावणी करण्यासंदर्भात येणाऱ्या अडचणीच्या अनुषंगाने विनियमातील तरतुदीचा अन्वयार्थ स्पष्ट करणेसंदर्भात नियोजन प्राधिकरणाकडून शासनाकडे निवेदन प्राप्त झाले आहे;

आणि ज्याअर्थी, उक्त निवेदन विचारात घेता आणि जनहिताच्या दृष्टीने, उक्त नियमावलीची प्रभावी अंमलबजावणी होण्यासाठी उक्त नियमावलीतील, उक्त तरतुदीबाबत व्यवहार्यता तपासून अशा तरतुदीचे पुनरावलोकन करून विनियम क्र.१.९ मधील (v) नुसार शासनाकडून अशा तरतुदीबाबत स्पष्टीकरण करणे आवश्यक असल्याचे शासनाने मत झाले आहे;

आता त्याअर्थी उक्त नियमावलीतील उक्त विनियम क्र. ७.७ च्या अनुषंगाने खालीलप्रमाणे सगरीकरणात्मक सूचना निर्गमित करण्यात येत आहेत :-

“विनियम क्र.७.७ Development of Housing for EWS/LIG अंतर्गतच्या विकास परवानगी प्रकरणी विनियम क्र.७.७.१(i) नुसार, विनियम क्र.७.७.१ मध्ये नमूद केलेनुसार, टेबल क्र.६A व ६G मधील रकमा क्र.६ व ९ नुसार कमाल अनुज्ञेय बांधकाम क्षमतेपेकी येसीक चटई क्षेत्र निर्देशांकाव्यतिरीक्त, उर्वरित चटई क्षेत्र निर्देशांक हा चालू बाजारमूल्य दराच्या १५% अधिमूल्य रकमेचा भरणा केल्यानंतर बापरात आणता येवू शकतो, असा अन्वयार्थ असल्यामुळे, टेबल क्र.६A व ६G नुसार रस्त्याच्या रुंदीसापेक्ष अनुज्ञेय होणा-या कमाल चटई क्षेत्र निर्देशांकामधून येसीक चटई क्षेत्र निर्देशांक घजा जाता उर्वरित (TDR तसेच Premium FSI) चटई क्षेत्र निर्देशांक हा बाजारमूल्य दराच्या १५% अधिमूल्य रकमेचा भरणा करून बापरात आणता येवू शकेल.”

(निर्मलकुमार चौधरी)

उपसचिव, महाराष्ट्र शासन

प्रत :-

१. मा.मुख्यमंत्री महोदय यांचे अपर मुख्य सचिव, मंत्रालय, मुंबई.
२. मा.उप मुख्यमंत्री महोदय यांचे सचिव, मंत्रालय, मुंबई.



सर्व तांत्रिक अधिवासी
मंजी नोद ह्यावी

महा विद्यापीठ अर्थशास्त्र विभाग
उपशाखा, नवी दिल्ली (म.स.घ.)
आ.क.
संख्या: अर्थ. / नवी. महाविद्यालयीन सेवा
११/११/२२-११-२२
११.११.२२

महाराष्ट्र शासन
नगर विकास विभाग

मादाम कामा मार्ग, हुतात्मा राजगुरु चौक, मंत्रालय, मुंबई - ४०० ०३२.

Email ID : soudd12-mh@mah.gov.in

क्रमांक:-टीपीएस-१२२३/१४८०/प्र.क्र.१२२/२३/नवि-१२ दिनांक :- २६ ऑक्टोबर, २०२३

प्रति,
मुख्य नियोजनकार,
महाराष्ट्र राज्य रस्ते विकास महामंडळ,
नेपियन्सी रोड, प्रियदर्शनी पार्कच्या बाजुस,
मुंबई - ४०००३६.

सर्व कर्मा
अधिकारी
नेंद प्रवाही

नगर रचना आणि मुख्याधिकारण विभाग
मु.जा., पुणे-१. जावन क्र. _____
दिनांक - १२/११/२०२३
20 NOV 2023
प्रशा-१/१३/२/लेखा/अर्थसंकल्प
सहायक मुख. प्र. व. उ. त. न. र. / त. न. र.

विषय :-Regarding the Recreational Open Space within Green Belt Zone and River Protection Belt as per Regulation No.3.4.5 and 4.12 of UDCPR.

संदर्भ :- आपलेकडील क्र. MSRDC/SPA/२०२३/१६५८,
दि. ०३/१०/२०२३ रोजीचे शासनास पत्र

महोदय,

वरील विषयांकित प्रकरणी आपण संदर्भाधिर्न पत्रान्वये एकत्रिकृत विकास नियंत्रण व प्रोत्साहन नियमावलीमधील विनियम क्र.३.४.५ व विनियम क्र.४.१२ च्या अनुषंगाने Green Belt/River Protection Belt यामध्ये खुले क्षेत्र प्रस्तवित करता येवु शकेल अशी धारणा व्यक्त करुन ती कायम करण्यास शासनास विनंती केली आहे. त्याअनुषंगाने आपणास खालील प्रमाणे कळविण्याच्या मला सूचना आहेत.

“एकत्रिकृत विकास नियंत्रण व प्रोत्साहन नियमावलीमधील (UDCPR) विनियम क्र.३.१.३(i)(a) नुसार नदी किनारा ते निळी पुरेबा यामधील क्षेत्र Prohibited Zone क्षेत्र असताना सदरच्या क्षेत्रामध्ये खुल्या स्वरूपाचे वापर जसे Open Space, Garden, Lawns इत्यादी वापर अनुज्ञेय आहेत, तर Green Belt किंवा River Protection Belt हे वापर विभाग देखील नदी/नालाच्या किना-या लगत प्रस्तावित असताना, त्यामध्ये विनियम क्र. ४.१२.१(ii) नुसार खुले स्वरूपाचे वापर सदरचे १५ मी. व ९.० मी. अंतरे विचारात न घेता अनुज्ञेय आहेत तर विनियम क्र. ४.१२(v) व ४.१२(vii) नुसार सदरच्या वापर विभागामध्ये नदीपासून १५ मी. व नाल्यापासून ९.०० मी. अंतर सोडून Recreational Open Space सोडणेबाबत तरतुद असून, सदर दोन्ही विनियमामध्ये नमुद क्षेत्र हे नदी/नाला या लगत असताना, त्यामध्ये विकास परवानगीच्या अनुषंगाने प्रस्तावित करावयाच्या Recreational Space / Open Space च्या स्थानांच्या अनुषंगाने दोन्ही

तरतुदीमध्ये विसंगती आहे. त्यामुळे सदरची विसंगती दूर करणे आवश्यक असल्याने, विनियम क्र.३.१.३ नुसार नदी किनारा ते निळी पुररेषा यांमध्ये अनुज्ञेय असलेले खुले क्षेत्र (Open Space) तसेच विनियम क्र. ४.१२.१(ii) मध्ये नमूद Recreational open space हे River Protection Belt / Green Belt या बापर विभागामध्ये विकास परवानगीवेळी उपरोक्त नमूद अंतरे विचारात न घेता नदी/नाल्या लागत प्रस्तावित करता येवू शकतील, तथापि, असे प्रस्तावित खुले क्षेत्र हे नियमावलीमधील तरतुदीनुसार योग्य आकारमानाचे असणे आवश्यक राहिल तसेच अशा प्रस्तावित Open Space, Recreations open spaces क्षेत्रामध्ये नदीपासून १५.०० मी. व नाल्यापासून ९.०० मी. अंतरे सोडून तसेच विनियम क्र.३.१.३ मधील तरतुदीनुसार पुररेषा विचारात घेऊन सदरच्या प्रस्तावित खुल्या क्षेत्रामध्ये UDCPR मधील तरतुदीनुसार विकास अनुज्ञेय राहिल.



आपला,

(निर्मलकुमार चौधरी)


उपसचिव महाराष्ट्र शासन,

प्रत माहितीस्वरूप व आवश्यक त्या कार्यवाहीस्तव :-

- १) संचालक, नगर रचना, महाराष्ट्र राज्य, पुणे.
- २) सर्व विभागीय आयुक्त.
- ३) सर्व विभागीय सहसंचालक, नगर रचना.
- ४) सर्व आयुक्त, महानगरपालिका.
- ५) सर्व महानगर आयुक्त, महानगर प्रदेश विकास प्राधिकरणे / विशेष नियोजन प्राधिकरणे.
- ६) मुख्य कार्यकारी अधिकारी, कोल्हापूर नागरी क्षेत्र विकास प्राधिकरण, कोल्हापूर.
- ७) सर्व महानगर आयुक्त, नवनगर प्रदेश विकास प्राधिकरणे.
- ८) मुख्य कार्यकारी अधिकारी, सर्व जिल्हापरिषद.
- ९) मुख्याधिकारी सर्व नगरपरिषदा / नगरपंचायती.
- १०) सर्व जिल्हाधिकारी.
- ११) सहायक संचालक, नगर रचना / नगर रचनाकार, नगर रचना व मूल्यविधोरण विभाग, सर्व शाखा कार्यालये.
- १२) अवर सचिव, नवि-१३/नवि-३०, कक्ष अधिकारी, नवि-९, नगर विकास विभाग, मंत्रालय, मुंबई.



महाराष्ट्र शासन
नगर विकास विभाग



मादाम कामा मार्ग, हुतात्मा राजगुरु चौक, मंत्रालय, मुंबई - ४०००३२.

Email ID : soudl12-mh@mah.gov.in

आदेश क्र.१५

क्रमांक:-टिपीएस-१२२३/१३१२/प्र.क्र.१४०/२३/नवि-१२ दिनांक :- २१ फेब्रुवारी, २०२४.

विषय :- एकत्रिकृत विकास नियंत्रण व प्रोत्साहन नियमावली (UDCPR) मंजूर
नियमावलीमधील विनियम क्र.१९(व) अन्वये स्पष्टीकरण देणेबाबत.

संदर्भ :-१) शासनाचे आदेश क्र.टिपीएस-१८१८/प्र.क्र.२३६/१८(भाग-२)/नवि-१३,

दि.१४/१/२०२१. (स्पष्टीकरण आदेश क्र.१)

२) शासनाचे आदेश क्र.टिपीएस-१८२१/३४०/प्र.क्र.६८/२०२१/नवि-१३,

दि.१०/५/२०२१. (स्पष्टीकरण आदेश क्र.२)

३) शासनाचे आदेश क्र.टिपीएस-१२२१/९९०/प्र.क्र.४४/२१/नवि-१२,

दि.१०/६/२०२१. (स्पष्टीकरण आदेश क्र.३)

४) शासनाचे आदेश क्र.टिपीएस-१२२१/१०३९/प्र.क्र.४२/२१/नवि-१२,

दि.१४/६/२०२१. (स्पष्टीकरण आदेश क्र.४)

५) शासनाचे आदेश क्र.टिपीएस-१८१८/प्र.क्र.२३६/१८(भाग-२)/नवि-१३,

दि.१७/९/२०२१. (स्पष्टीकरण आदेश क्र.५)

६) शासनाचे आदेश क्र.टिपीएस-१८१८/प्र.क्र.२३६/१८(भाग-२)/नवि-१३,

दि.२३/१२/२०२१. (स्पष्टीकरण आदेश क्र.६)

७) शासनाचे आदेश क्र.टिपीएस-१८२१/९३३/नवि-१३, दि.२३/१२/२०२१.

(स्पष्टीकरण आदेश क्र.७)

८) शासनाचे आदेश क्र.टिपीएस-१८१८/२३६/१८(भाग-२)/नवि-१३,

दि.२६/९/२०२२ (स्पष्टीकरण आदेश क्र.८)

९) शासनाचे आदेश क्र.टिपीएस-१८१८/२३६/१८(भाग-२)/नवि-१३,

दि.१२/१०/२०२२ (स्पष्टीकरण आदेश क्र.९)

१०) शासनाचे आदेश क्र.टिपीएस-१८१८/प्र.क्र.२३६/१८(भाग-२)/नवि-१३,

दिनांक १२/१०/२०२२.(स्पष्टीकरण आदेश क्र.१०)

११) शासनाचे आदेश क्र.१८२१/२०२३/प्र.क्र.१०४/२२/नवि-३०,

दिनांक २९/११/२०२२ व समक्रमांकाचे शुध्दीपत्रक दिनांक २/६/२०२३.

१२) शासनाचे आदेश क्र.टिपीएस-१२२३/६०३/प्र.क्र.७२/२३/नवि-१२,

दिनांक २५/८/२०२३ व टिपीएस-१८१८/प्र.क्र.५४/२३/नवि-१३

दि.२८/८/२०२३ (स्पष्टीकरण आदेश क्र.१२)

- १३) शासनाचे आदेश क्र.टिपीएस-१२२३/२१७४/प्र.क्र.५८/२२/नवि-१२,
दिनांक ४/९/२०२३ (स्पष्टीकरणे आदेश क्र.१३)
१४) शासनाचे आदेश क्र.टिपीएस-१२२३/९०५/प्र.क्र.१००/२३/नवि-१२,
दिनांक १८/१०/२०२३ (स्पष्टीकरणे आदेश क्र.१४)

ज्याअर्थी, शासनाने अधिसूचना क्र. टिपीएस १८१८/प्र.क्र.३३६/१८/कलम ३७(१कक)(ग) व कलम २०(४)/नवि-१३, दि.०२/१२/२०२० अन्वये राज्यातील सर्व नियोजन प्राधिकरणे (काही अपवाद वगळता) आणि प्रादेशिक योजना क्षेत्राकरिता एकत्रिकृत विकास नियंत्रण व प्रोत्साहन नियमावली मंजूर केली असून ती दि. ०३/१२/२०२० पासून अमलात आली आहे;

आणि ज्याअर्थी, उक्त नियमावलीतील विनियम क्र.१.९ मध्ये अ.क्र. (v) या तरतुदीनुसार UDCPR मधील विविध तरतुदींच्या अन्वयार्थ संदर्भात उपस्थित प्रश्न / मुद्द्याच्या अनुषंगाने शासनातर्फे आदेश देणेबाबत तरतुद आहे;

आणि ज्याअर्थी, शासनाने उपरोक्त तरतुदीच्या अनुषंगाने वेळोवेळी निर्गमित आदेशान्वये संबंधितांना मार्गदर्शन केलेले आहे;

आणि ज्याअर्थी, उक्त नियमावलीमधील विनियम क्र.१०.१४.२ Regulation For Land Compensation Scheme and Rehabilitation Pocket in Navi Mumbai ची तरतुद असून, सदर विनियमाच्या खंड १०.१४.२(ii) नुसारच्या तरतुदीची अंमलबजावणी करण्यासंदर्भात येणाऱ्या अडचणींच्या अनुषंगाने आवश्यक त्या मार्गदर्शन सुचना/निदेश देण्यासंदर्भात नियोजन प्राधिकरणाकडून शासनाकडे निवेदन प्राप्त झाले आहे;

आणि ज्याअर्थी, उक्त निवेदन विचारात घेता आणि जनहिताच्या दृष्टीने, उक्त नियमावलीची प्रभावी अंमलबजावणी होण्यासाठी उक्त नियमावलीतील, उक्त तरतुदीबाबत व्यवहार्यता तपासून अशा तरतुदींचे पुनरावलोकन करून विनियम क्र.१.९ मधील (v) नुसार शासनाकडून अशा तरतुदीबाबत स्पष्टीकरण करणे आवश्यक असल्याचे शासनाचे मत झाले आहे;

आता त्याअर्थी उक्त नियमावलीतील उक्त विनियम क्र.१०.१४.२(ii) संदर्भात खालीलप्रमाणे स्पष्टीकरणात्मक सुचना निर्गमित करण्यात येत आहेत :-

“विनियम क्र.१०.१४.२(ii) नुसार अनुज्ञेय एकूण चटई क्षेत्र निर्देशांकाचेवर विनियम क्र.६.३, तक्ता क्र.६-जी नुसार रस्ता रुंदीसापेक्ष कमाल बांधकाम क्षमतेपर्यंतचा चटई क्षेत्र निर्देशांक पुष्पक नोड मधील भाडेपट्ट्यातील मूळ चटई निर्देशांकाव्यतिरीक्त अतिरीक्त चटई क्षेत्र निर्देशांक भूखंडावर अधिमूल्य आकारणीसह अनुज्ञेय होईल.”



(निर्मलकुमार चौधरी)

उपसचिव, महाराष्ट्र शासन

प्रत :-

१. मा.मुख्यमंत्री महोदय यांचे अपर मुख्य सचिव, मंत्रालय, मुंबई.
२. मा.उप मुख्यमंत्री महोदय यांचे सचिव, मंत्रालय, मुंबई.
३. मा.अध्यक्ष, महाराष्ट्र विधानसभा, महाराष्ट्र विधानमंडळ सचिवालय, मुंबई.



महाराष्ट्र शासन
नगर विकास विभाग

चौथा मजला, मुख्य इमारत, मंत्रालय,

मादाम कामा मार्ग, हुतात्मा राजगुरू चौक, मुंबई - ४०० ०३२.

दुरध्वनी क्र ०२२ २२७९४१९६

E mail ID : ud13-urban@mah.gov.in

क्रमांक:टिपीएस-१८२३/१७२/प्र.क्र.४२/२०२३/नवि-१३

दिनांक : ०३.०४.२०२४

प्रति,

१. संचालक, नगर रचना, महाराष्ट्र राज्य पूर्ण,
२. सर्व विभागीय सहसंचालक, नगर रचना, पूर्ण / नाशिक / नागपूर / कोकण / छत्रपती संभाजीनगर / अमरावती विभाग,
३. सर्व विभागीय आयुक्त, पूर्ण / नाशिक / नागपूर / कोकण / छत्रपती संभाजीनगर / अमरावती विभाग,
४. सर्व जिल्हाधिकारी,
५. मुख्याधिकारी, सर्व नगरपालिका / नगरपालिका
६. आयुक्त, सर्व संबंधित महानगरपालिका, (चुनवट महानगरपालिका वगळता),
७. महानगर आयुक्त, सर्व महानगर प्रवेश विकास प्राधिकरण,
८. सर्व विशेष नियोजन प्राधिकरण,
९. सर्व नवनगर विकास प्राधिकरण,
१०. व्यवस्थापकीय संचालक, सिडको, सिडको भवन, सोबीटो बेंलापूर, नवी मुंबई- ४०० ४१६,
११. मुख्य कार्यकारी अधिकारी, पिंपरी चिंचवड नवनगर विकास प्राधिकरण, निगडो, पूर्ण,
१२. उपाध्यक्ष तथा व्यवस्थापकीय संचालक, महाराष्ट्र राज्य ग्राम विकास महामंडळ, मुंबई.

विषय : महाराष्ट्र प्रादेशिक नियोजन व नगर रचना अधिनियम, १९६६

मंजूर विकास नियंत्रण व प्रोत्साहन नियमावलीतील विनियम क्र.१०.१५ चे तरतुदींमध्ये सुधारणा करणंसंदर्भात कलम १५.४(१) खालील निर्देश

संदर्भ : १. शासन निर्णय क्र.टिपीएस-१८२३/१७२/प्र.क्र.४२/२०२३/नवि-१३, दि.०४.०१.२०२४,

२. मा.उच्च न्यायालय, मुंबई यांचे जनहित याचिका क्र.२८/२०२४ मध्ये आदेश दि.०६.०३.२०२४

३. मा.सरकारी वकील, उच्च न्यायालय, मुंबई यांचे पत्र क्र.GP WP PPK 5718/2024, dt.28.03.20

विषयार्थित प्रकरणी शासनाने मंजूर विकास नियंत्रण व प्रोत्साहन नियमावलीतील (UDCPR) विनियम क्र.१०.१५ चे तरतुदींमध्ये सुधारणा करणंसंदर्भात संदर्भ क्र.१ अन्वये महाराष्ट्र प्रादेशिक नियोजन व नगर रचना अधिनियम, १९६६ चे कलम ३७(१कक) अन्वये सूचना व त्यासह उक्त अधिनियमाच्या कलम १५.४(१) अन्वयेचे निर्देश पारित केले आहेत.

तथापि, सदर विषयाच्या अनुषंगाने शासनाने दि.०४.०१.२०२४ अन्वये पारित केलेल्या महाराष्ट्र प्रादेशिक नियोजन व नगर रचना अधिनियम, १९६६ चे कलम १५.४(१) अन्वयेचे निर्देशास मा.उच्च न्यायालयात जनहित याचिका क्रमांक २८/२०२४ द्वारे आव्हान देण्यात आले आहे.

सदर जनहित याचिकेमध्ये दि.०६.०३.२०२४ रोजी उच्च न्यायालयात मुनावणी होऊन सदर मुनावणी अंती मा.उच्च न्यायालयाने दि.०६.०३.२०२४ रोजी शासनाने पारित केलेल्या आदेशानुसार शासनाने दि.०४.०१.२०२४ रोजी उक्त विषयाच्या अनुषंगाने महाराष्ट्र प्रादेशिक नियोजन व नगर रचना अधिनियम, १९६६ चे कलम १५४(१) अन्वये पारित केलेले निर्देशानुसार प्रस्तावित केलेल्या फेरबदलाच्या अंमलबजावणीस मा.उच्च न्यायालयाचे पुढील आदेश हाईपर्यंत र्थागती देण्यात आली आहे.

मा.उच्च न्यायालयाचे दि.०६.०३.२०२४ रोजीच्या आदेशाची छायाप्रत सोबत जोडली आहे. मा.उच्च न्यायालयाचे उक्त आदेशानुसार शासनाने दि.०४.०१.२०२४ रोजी उक्त विषयाच्या अनुषंगाने महाराष्ट्र प्रादेशिक नियोजन व नगर रचना अधिनियम, १९६६ चे कलम १५४(१) अन्वये पारित केलेले निर्देशानुसार प्रस्तावित केलेल्या फेरबदलाच्या अंमलबजावणीस मा.उच्च न्यायालयाचे पुढील आदेश हाईपर्यंत शासनाची र्थागती देण्यात येते.

वरीलप्रमाणे आपणांस कळविण्याच्या मला सूचना आहेत.



(डॉ.प्रतिभा भदाणे)

सह सचिव, महाराष्ट्र शासन

प्रत माहितीसाठी :

१. मा. प्रधान सचिव, नगर विकास विभाग (नवि-१) यांचे स्वीस सहायक, मंत्रालय, मुंबई-३२
२. मा. संचालक, नगर रचना तथा सहसचिव, नगर विकास विभाग (नवि-१) यांचे स्वीस सहायक, मंत्रालय, मुंबई-३२.
- ✓ ३. मा. सरकारी वकील, अपिलेट शाखा, उच्च न्यायालय, मुंबई
४. निवड नस्ती (नवि-१३)



महाराष्ट्र शासन
नगर विकास विभाग

मादाम कामा मार्ग, हुतात्मा राजगुरु चौक, मंत्रालय, मुंबई - ४०० ०३२.

Email ID : soudd12-mh@mah.gov.in

आदेश क्र.१६

क्रमांक:-टिपीएस-१२२२/१३९८/प्र.क्र.११७/२२/नवि-१२ दिनांक :- २२ ऑगस्ट, २०२४.

विषय :- एकत्रिकृत विकास निवंत्रण व प्रोत्साहन नियमावली (UDCPR) मंजूर
नियमावलीमधील विनियम क्र.१९(v) अन्वये स्पष्टीकरण देणेबाबत.

संदर्भ :- १) शासनाचे आदेश क्र.टिपीएस-१८१८/प्र.क्र.२३६/१८(भाग-२)/नवि-१३,

दि.१४/९/२०२१. (स्पष्टीकरण आदेश क्र.१)

२) शासनाचे आदेश क्र.टिपीएस-१८२१/३४०/प्र.क्र.६८/२०२१/नवि-१३,

दि.१०/५/२०२१. (स्पष्टीकरण आदेश क्र.२)

३) शासनाचे आदेश क्र.टिपीएस-१२२१/९९०/प्र.क्र.४४/२१/नवि-१२,

दि.१०/६/२०२१. (स्पष्टीकरण आदेश क्र.३)

४) शासनाचे आदेश क्र.टिपीएस-१२२१/१०३९/प्र.क्र.४२/२१/नवि-१२,

दि.१४/६/२०२१. (स्पष्टीकरण आदेश क्र.४)

५) शासनाचे आदेश क्र.टिपीएस-१८१८/प्र.क्र.२३६/१८(भाग-२)/नवि-१३,

दि.१७/९/२०२१. (स्पष्टीकरण आदेश क्र.५)

६) शासनाचे आदेश क्र.टिपीएस-१८१८/प्र.क्र.२३६/१८(भाग-२)/नवि-१३,

दि.२३/१२/२०२१. (स्पष्टीकरण आदेश क्र.६)

७) शासनाचे आदेश क्र.टिपीएस-१८२१/९३३/नवि-१३, दि.२३/१२/२०२१.

आणि मूल्यानिर्धारण विभागाच्या स्पष्टीकरण आदेश क्र.७)

क्र.नगर रचना (ना.सं.२) शासनाचे आदेश क्र.टिपीएस-१८१८/२३६/१८(भाग-२)/नवि-१३,

दिनांक- दि.२६/९/२०२२ (स्पष्टीकरण आदेश क्र.८)

१) शासनाचे आदेश क्र.टिपीएस-१८१८/२३६/१८(भाग-२)/नवि-१३,

दि.१२/१०/२०२२ (स्पष्टीकरण आदेश क्र.९)

२) शासनाचे आदेश क्र.टिपीएस-१८१८/प्र.क्र.२३६/१८(भाग-२)/नवि-१३,

दिनांक १२/१०/२०२२. (स्पष्टीकरण आदेश क्र.१०)

११) शासनाचे आदेश क्र.१८२१/२०२३/प्र.क्र.१०४/२२/नवि-३०,

दिनांक २९/११/२०२२ व समक्रमांकाचे शुध्दीपत्रक दिनांक २/६/२०२३.

१२) शासनाचे आदेश क्र.टिपीएस-१२२३/६०३/प्र.क्र.७२/२३/नवि-१२,

दिनांक २५/८/२०२३ व टिपीएस-१८१८/प्र.क्र.५४/२३/नवि-१३

दि.२८/८/२०२३ (स्पष्टीकरण आदेश क्र.१२)

१३) शासनाचे आदेश क्र.टिपीएस-१२२३/२१७४/प्र.क्र.५८/२२/नवि-१२,



- दिनांक ४/९/२०२३ (स्पष्टीकरणे आदेश क्र.१३)
 १४) शासनाचे आदेश क्र.टिपीएस-१२२३/१०५/प्र.क्र.१००/२३/नवि-१२,
 दिनांक १८/१०/२०२३ (स्पष्टीकरणे आदेश क्र.१४)
 १५) शासनाचे आदेश क्र.टिपीएस-१२२३/१३१२/प्र.क्र.१४०/२३/नवि-१२,
 दिनांक २१/०२/२०२४ (स्पष्टीकरणे आदेश क्र.१५)

ज्याअर्थी, शासनाने अधिसूचना क्र. टिपीएस १८१८/प्र.क्र.३३६/१८/कलम ३७(१कक)(ग) व कलम २०(४)/नवि-१३, दि.०२/१२/२०२० अन्वये राज्यातील सर्व नियोजन प्राधिकरणे (काही अपवाद वगळता) आणि प्रादेशिक योजना क्षेत्राकरिता एकत्रिकृत विकास नियंत्रण व प्रोत्साहन नियमावली मंजूर केली असून ती दि. ०३/१२/२०२० पासून अंमलात आली आहे;

आणि ज्याअर्थी, उक्त नियमावलीतील विनियम क्र.१.९ मध्ये अ.क्र. (v) या तरतुदीनुसार UDCPR मधील विविध तरतुदींच्या अन्वयार्थ संदर्भात उपस्थित प्रश्न / मुद्द्याच्या अनुषंगाने शासनातर्फे आदेश देणेबाबत तरतुद आहे;

आणि ज्याअर्थी, शासनाने उपरोक्त तरतुदीच्या अनुषंगाने वेळोवेळी निर्गमित आदेशांचे संबंधितांना मार्गदर्शन केलेले आहे;

आणि ज्याअर्थी, उक्त नियमावलीमधील विनियम क्र. ५.१.१ Development Permissible Adjacement to Gaathan ची तरतुद असून, सदर विनियमाच्या खंड ५.१.१(vi) मध्ये गांवठाणापासूनच्या ५०० मी.परीघ क्षेत्रामध्ये रहिवास बापर अनुज्ञेय करण्याअनुषंगाने आकारावयाच्या अधिमुल्याबाबत आहे आणि विनियम क्र.५.१.६ मध्ये रेल्वे स्थानकाच्या ५००मी.परीघस्त क्षेत्रात शेती विभागात रहिवास बापर अनुज्ञेय करण्याअनुषंगाने आकारावयाच्या अधिमुल्याबाबत आहे.

आणि ज्याअर्थी, सदर विनियम क्र.५.१.१ (vi) व विनियम क्र.५.१.६ या दोन्ही विनियमानुसार येणा-या परीघस्त क्षेत्रातील जमिनीवरील प्राप्त विकास प्रस्तावामध्ये आकारावयाच्या अधिमुल्य आकारणीसंदर्भात येणाऱ्या अडचणीच्या अनुषंगाने आवश्यक ते स्पष्टीकरण/ मार्गदर्शन देण्याची विनंती संचालक नगर रचना, महाराष्ट्र राज्य, पुणे यांनी शासनास केली आहे;

आणि ज्याअर्थी, उक्त निवेदन विचारात घेता आणि जनहिताच्या दृष्टीने, उक्त नियमावलीची प्रभावी अंमलबजावणी होण्यासाठी उक्त नियमावलीतील, उक्त तरतुदीबाबत व्यवहार्यता तपासून अशा तरतुदींचे पुनरावलोकन करून विनियम क्र.१.९ मधील (v) नुसार शासनाकडून अशा तरतुदीबाबत स्पष्टीकरण करणे आवश्यक असल्याचे शासनाचे मत झाले आहे;

आता त्याअर्थी उक्त नियमावलीतील उक्त विनियम क्र. ५.१.१(vi) व ५.१.६ संदर्भात खालीलप्रमाणे स्पष्टीकरणात्मक सूचना निर्गमित करण्यात येत आहेत :-

"एकत्रिकृत विकास नियंत्रण व प्रोत्साहन नियमावलीमधील विनियम क्र.५.१.१ नुसार प्रादेशिक योजना क्षेत्रामध्ये गावामध्ये विशिष्टपणे रहिवास विभाग दर्शविला नसेल तेथे गावठाणापासून नमूद केल्या असलेल्या ठरावीक क्षेत्रापासून लोकसंख्यासापेक्ष १५% अधिमुल्य आकारून विकास अनुज्ञेय आहे तर विनियम क्र. ५.१.६ मध्ये अस्तित्वातील रेल्वे स्थानकापासून ५०० मी. परिघ क्षेत्रामध्ये ३०% अधिमुल्य आकारून विकास अनुज्ञेय आहे. तथापि, एखादे क्षेत्र गावठाण तसेच रेल्वे स्थानक अशा दोन्हीच्या परीघस्त क्षेत्रात अंतर्भूत होत असेल तर अशा Overlapping क्षेत्राकरीता गावठाणापासून

NR

लोकसंख्यासापेक्ष अंतराचे परीघात विनियम क्र.५.१.१ नुसार १५% प्रमाणे अधिमूल्य आकारणी करावी. या व्यतिरीक्त स्टेशन परिघस्त क्षेत्रात विनियम क्र.५.१.६ नुसार ३०% प्रमाणे अधिमूल्य आकारण्यात यावे."



(निर्मलकुमार चौधरी)

उपसचिव, महाराष्ट्र शासन

प्रत :-

- १) मा.मुख्यमंत्री महोदय यांचे अपर मुख्य सचिव, मंत्रालय, मुंबई.
- २) मा.उप मुख्यमंत्री महोदय यांचे सचिव, मंत्रालय, मुंबई.
- ३) मा.अध्यक्ष, महाराष्ट्र विधानसभा, महाराष्ट्र विधानमंडळ सचिवालय, मुंबई.
- ४) मा.सभापती, महाराष्ट्र विधानपरिषद, महाराष्ट्र विधानमंडळ सचिवालय, मुंबई.
- ५) मा.विरोधी पक्षनेता, विधानसभा, महाराष्ट्र विधानमंडळ सचिवालय, मुंबई.
- ६) मा.विरोधी पक्षनेता, विधानपरिषद, महाराष्ट्र विधानमंडळ सचिवालय, मुंबई.
- ७) मा.मुख्य सचिव, महाराष्ट्र शासन, मंत्रालय, मुंबई.
- ८) प्रधान सचिव (नवि-१), नगर विकास विभाग, मंत्रालय, मुंबई.
- ९) संचालक (नगर रचना) तथा सह सचिव, नगर विकास विभाग, मंत्रालय, मुंबई.
- १०) उपसचिव (नगर रचना), नगर विकास विभाग, मंत्रालय, मुंबई.

प्रति :-

- १) संचालक, नगर रचना, महाराष्ट्र राज्य, पुणे.
- २) सर्व विभागीय आयुक्त.
- ३) सर्व विभागीय सहसंचालक, नगर रचना.
- ४) सर्व आयुक्त, महानगरपालिका.
- ५) सर्व महानगर आयुक्त, महानगर प्रदेश विकास प्राधिकरणे / विशेष नियोजन प्राधिकरणे.
- ६) मुख्य कार्यकारी अधिकारी, कोल्हापूर नागरी क्षेत्र विकास प्राधिकरण, कोल्हापूर.
- ७) सर्व महानगर आयुक्त, नवनगर प्रदेश विकास प्राधिकरणे.
- ८) मुख्य कार्यकारी अधिकारी, सर्व जिल्हापरिषद.
- ९) मुख्याधिकारी सर्व नगरपरिषदा / नगरपंचायती.
- १०) सर्व जिल्हाधिकारी.
- ११) सहायक संचालक, नगर रचना / नगर रचनाकार, नगर रचना व मूल्यनिर्धारण विभाग, सर्व शाखा कार्यालये.
- १२) अवर सचिव, नवि-११ / नवि-१३ / नवि-३०, कक्ष अधिकारी, नवि-९, नगर विकास विभाग, मंत्रालय, मुंबई.
- १३) कक्ष अधिकारी (नवि-२९), नगर विकास विभाग, मंत्रालय, मुंबई.
/- सोबतचे निदेश या विभागाच्या संकेतस्थळावर प्रसिध्द करावेत.
- १४) कक्ष अधिकारी, माहिती व तंत्रज्ञान विभाग, मंत्रालय, मुंबई.
/- सदरचे निदेश शासनाच्या संकेतस्थळावर प्रसिध्द करावेत.
- १५) निवड नस्ती, कार्यासन (नवि-१२).



महाराष्ट्र शासन
नगर विकास विभाग

मादाम कामा मार्ग, हुतात्मा राजगुरु चौक, मंत्रालय, मुंबई

Email ID : soude12-mah@mah.gov.in

नगर रचना आणि मूल्यनिर्धारण विभाग
उपसंचालक, नगर रचना (ना.सं.घ.)
आ.क्र. दिनांक-
संग्रहित अधि./कर्म.
४०० ०३२.
३.१
७.स.न.र.

आदेश क्र.१७

क्रमांक:-टिपीएस-१२२४/१२०५/प्र.क्र.७०/२४/नवि-१२

दिनांक :- २६ सप्टेंबर, २०२४.

विषय :- एकत्रिकृत विकास नियंत्रण व प्रोत्साहन नियमावली (UDCPR) मंजूर
नियमावलीमधील विनियम क्र.१९(५) अन्वये स्पष्टीकरण देणेबाबत.

संदर्भ :-१) शासनाचे आदेश क्र.टिपीएस-१८१८/प्र.क्र.२३६/१८(भाग-२)/नवि-१३,
दि.१४/१२/२०२१. (स्पष्टीकरण आदेश क्र.१)

२) शासनाचे आदेश क्र.टिपीएस-१८२१/३४०/प्र.क्र.६८/२०२१/नवि-१३,
दि.१०/५/२०२१. (स्पष्टीकरण आदेश क्र.२)

३) शासनाचे आदेश क्र.टिपीएस-१२२१/९९०/प्र.क्र.४४/२१/नवि-१२,
दि.१०/६/२०२१. (स्पष्टीकरण आदेश क्र.३)

४) शासनाचे आदेश क्र.टिपीएस-१२२१/१०३९/प्र.क्र.४२/२१/नवि-१२,
दि.१४/६/२०२१. (स्पष्टीकरण आदेश क्र.४)

५) शासनाचे आदेश क्र.टिपीएस-१८१८/प्र.क्र.२३६/१८(भाग-२)/नवि-१३,
दि.१७/९/२०२१. (स्पष्टीकरण आदेश क्र.५)

६) शासनाचे आदेश क्र.टिपीएस-१८१८/प्र.क्र.२३६/१८(भाग-२)/नवि-१३,
दि.२३/१२/२०२१. (स्पष्टीकरण आदेश क्र.६)

७) शासनाचे आदेश क्र.टिपीएस-१८२१/९३३/नवि-१३, दि.२३/१२/२०२१.
(स्पष्टीकरण आदेश क्र.७)

८) शासनाचे आदेश क्र.टिपीएस-१८१८/२३६/१८(भाग-२)/नवि-१३,
दि.२६/९/२०२२ (स्पष्टीकरण आदेश क्र.८)

९) शासनाचे आदेश क्र.टिपीएस-१८१८/२३६/१८(भाग-२)/नवि-१३,
दि.१२/१०/२०२२ (स्पष्टीकरण आदेश क्र.९)

१०) शासनाचे आदेश क्र.टिपीएस-१८१८/प्र.क्र.२३६/१८(भाग-२)/नवि-१३,
दिनांक १२/१०/२०२२.(स्पष्टीकरण आदेश क्र.१०)

११) शासनाचे आदेश क्र.१८२१/२०२३/प्र.क्र.१०४/२२/नवि-३०,
दिनांक २९/११/२०२२ व समक्रमांकाचे शुद्धीपत्रक दिनांक २/६/२०२३.

१२) शासनाचे आदेश क्र.टिपीएस-१२२३/६०३/प्र.क्र.७२/२३/नवि-१२,



Handwritten signature

- दिनांक २५/८/२०२३ व टिपीएस-१८१८/प्र.क्र.५४/२३/नवि-१३
 दि.२८/८/२०२३ (स्पष्टीकरण आदेश क्र.१२)
 १३) शासनाचे आदेश क्र.टिपीएस-१२२३/२१७४/प्र.क्र.५८/२२/नवि-१२,
 दिनांक ४/९/२०२३ (स्पष्टीकरण आदेश क्र.१३)
 १४) शासनाचे आदेश क्र.टिपीएस-१२२३/९०५/प्र.क्र.१००/२३/नवि-१२,
 दिनांक १८/१०/२०२३ (स्पष्टीकरण आदेश क्र.१४)
 १५) शासनाचे आदेश क्र.टिपीएस-१२२३/१३१२/प्र.क्र.१४०/२३/नवि-१२,
 दिनांक २१/०२/२०२४ (स्पष्टीकरण आदेश क्र.१५)
 १६) शासनाचे आदेश क्र.टिपीएस-१२२२/१३९८/प्र.क्र.११७/२२/नवि-१२,
 दिनांक २२/८/२०२४ (स्पष्टीकरण आदेश क्र.१५)

ज्याअर्थी, शासनाने अधिसूचना क्र. टिपीएस १८१८/प्र.क्र.३३६/१८/कलम ३७(१कक)(ग) व कलम २०(४)/नवि-१३, दि.०२/१२/२०२० अन्वये राज्यातील सर्व नियोजन प्राधिकरणे (काही अपवाद वगळता) आणि प्रादेशिक योजना क्षेत्राकरिता एकत्रिकृत विकास नियंत्रण व प्रोत्साहन नियमावली (यापुढे ज्याचा उल्लेख "उक्त नियमावली" असा करण्यात आला आहे.) मंजूर केली असून ती दि. ०३/१२/२०२० पासून अंमलात आली आहे;

आणि ज्याअर्थी, उक्त नियमावलीतील विनियम क्र.१.९ मध्ये अ.क्र. (v) या तरतुदीनुसार UDCPR मधील विविध तरतुदीच्या अन्वयार्थ संदर्भात उपस्थित प्रश्न / मुद्द्याच्या अनुषंगाने शासनातर्फे आदेश देणेबाबत तरतुद आहे;

आणि ज्याअर्थी, शासनाने उपरोक्त तरतुदीच्या अनुषंगाने वेळोवेळी निर्गमित आदेशांन्वये संबंधितांना मार्गदर्शन केलेले आहे;

आणि ज्याअर्थी, उक्त नियमावलीच्या विनियम ५.१.४ मध्ये आरेखित नुटी दुरुस्त करण्याची तरतुद असून, सदर विनियमाच्या खंड ५.१.४ (ii) (यापुढे ज्याचा उल्लेख "उक्त तरतुद" असा करण्यात आला आहे.) मध्ये ज्या खाजगी जमिनी चुकून संरक्षण विभाग, वन विभाग, इत्यादी प्रतिबंधनात्मक वापर विभागात दर्शविलेल्या असतील अशा जमिनी संबंधित प्राधिकारी यांनी अभिलेख तपासणी व जागेवरील वस्तुस्थिती तपासून, सहसंचालक नगर रचना, यांच्या पुर्व मंजूरीने दुरुस्त करण्याची तरतुद आहे;

आणि ज्याअर्थी, उक्त तरतुद शासकीय जमिनीकरीता लागू करण्याअनुषंगाने संचालक नगर रचना, महाराष्ट्र राज्य, पुणे यांचेकडून दिनांक २६/६/२०२४ च्या पत्रान्वये शासनास संदर्भ प्राप्त झाला आहे;

आणि ज्याअर्थी, जनहिताच्या दृष्टीने, उक्त नियमावलीची प्रभावी अंमलबजावणी होण्यासाठी उक्त नियमावलीतील, उक्त तरतुद शासकीय जमिनीकरीतासुद्धा अनुज्ञेय करणे उचित होईल व त्याकरीता उक्त नियमावलीच्या विनियम क्र.१.९ मधील (v) नुसार शासनाकडून स्पष्टीकरण निर्गमित करणे आवश्यक असल्याचे शासनाचे मत झाले आहे;

आता त्याअर्थी, उक्त नियमावलीच्या विनियम ५.१.४ मधील खंड ५.१.४(ii) संदर्भात खालीलप्रमाणे स्पष्टीकरणात्मक सूचना निर्गमित करण्यात येत आहेत.



“एकत्रिकृत विकास नियंत्रण व प्रोत्साहन नियमावलीमधील विनियम ५.१.४ च्या खंड (ii) मध्ये नमूद केल्यानुसारच्या मंजूर प्रादेशिक योजनेमधील आरेखित वृद्धी दुरुस्त करण्याची तरतूद ही खाजगी जमिनीसह शासकीय जमिनींना सुद्धा लागू राहील.”



(निर्मलकुमार चौधरी)
उपसचिव, महाराष्ट्र शासन

प्रत :-

- १) मा.मुख्यमंत्री महोदय यांचे अपर मुख्य सचिव, मंत्रालय, मुंबई.
- २) मा.उप मुख्यमंत्री महोदय यांचे सचिव, मंत्रालय, मुंबई.
- ३) मा.अध्यक्ष, महाराष्ट्र विधानसभा, महाराष्ट्र विधानमंडळ सचिवालय, मुंबई.
- ४) मा.सभापती, महाराष्ट्र विधानपरिषद, महाराष्ट्र विधानमंडळ सचिवालय, मुंबई.
- ५) मा.विरोधी पक्षनेता, विधानसभा, महाराष्ट्र विधानमंडळ सचिवालय, मुंबई.
- ६) मा.विरोधी पक्षनेता, विधानपरिषद, महाराष्ट्र विधानमंडळ सचिवालय, मुंबई.
- ७) मा.मुख्य सचिव, महाराष्ट्र शासन, मंत्रालय, मुंबई.
- ८) प्रधान सचिव (नवि-१), नगर विकास विभाग, मंत्रालय, मुंबई.
- ९) संचालक (नगर रचना) तथा सह सचिव, नगर विकास विभाग, मंत्रालय, मुंबई.
- १०) उपसचिव (नगर रचना), नगर विकास विभाग, मंत्रालय, मुंबई.

प्रति :-

- १) संचालक, नगर रचना, महाराष्ट्र राज्य, पुणे.
- २) सर्व विभागीय आयुक्त.
- ३) सर्व विभागीय सहसंचालक, नगर रचना.
- ४) सर्व आयुक्त, महानगरपालिका.
- ५) सर्व महानगर आयुक्त, महानगर प्रदेश विकास प्राधिकरणे / विशेष नियोजन प्राधिकरणे.
- ६) मुख्य कार्यकारी अधिकारी, कोल्हापूर नागरी क्षेत्र विकास प्राधिकरण, कोल्हापूर.
- ७) सर्व महानगर आयुक्त, नवनगर प्रदेश विकास प्राधिकरणे.
- ८) मुख्य कार्यकारी अधिकारी, सर्व जिल्हापरिषद.
- ९) मुख्याधिकारी सर्व नगरपरिषदा / नगरपंचायती.
- १०) सर्व जिल्हाधिकारी.
- ११) सहायक संचालक, नगर रचना / नगर रचनाकार, नगर रचना व मूल्यनिर्धारण विभाग, सर्व शाखा कार्यालये.
- १२) अवर सचिव, नवि-११ / नवि-१३ / नवि-३०, कक्ष अधिकारी, नवि-९, नगर विकास विभाग, मंत्रालय, मुंबई.
- १३) कक्ष अधिकारी (नवि-२९), नगर विकास विभाग, मंत्रालय, मुंबई.
- / सोबतचे निदेश या विभागाच्या संकेतस्थळावर प्रसिध्द करावेत.
- १४) कक्ष अधिकारी, माहिती व तंत्रज्ञान विभाग, मंत्रालय, मुंबई.
- / सदरचे निदेश शासनाच्या संकेतस्थळावर प्रसिध्द करावेत.
- १५) निवड नस्ती, कार्यासन (नवि-१२).

(शासन नगर विकास विभागाकडील अधिसूचना क्र. टिपीवी टिपीवी ४३२२/१०/प्र.क्र.४५/२०२२/
नवि-११, दिनांक :- १० ऑक्टोबर, २०२४ सोबतचे परिशिष्ट.)

Annexures of Regulation No.13.6

ANNEXURE – A

Checklist for calculation of Risk Assessment of buildings vulnerable to man-made disasters

1. Threat Assessment (TA)

Parameter	Rating Out of	Assigned Score	Remarks
Inputs from various Government, Quasi or Semi Government or even private sources.	60		0—if no specific input 60—if specific input is received
Historical data and evidence of such threats to a structure or a structure type can provide the basis for identifying the threat type.	40		0—no previous inputs or incidences or threats 20—in past inputs 40—previous incidence and specific inputs
Total (TA)	100		

2. Consequence Assessment (CA)

Parameter	Rating Out of	Assigned Score	Remarks
Human Impact (public health and safety): Effects on human life and physical well-being (e.g., fatalities, injuries).	30		0—no approvable impacts 30—very high number of casualties and injuries
Economic Impact: Direct and indirect effects on the economy with respect to the building and its functions (e.g., cost to rebuild assets, cost to respond to and recover from the attack, downstream costs resulting from the disruption of operations or services, long-term costs due to environmental damage).	25		0—no effect on the economy; very low asset recreation cost. 25—very high impact on economy; very high asset reconstruction cost.
Public Confidence (psychological): Effect on public morale and trust in the government and critical infrastructure. This encompasses those changes in perceptions emerging after a significant incident that affected the public's sense of safety and well-being.	25		0—no effect on public confidence or non-critical infrastructure. 25—very high impact on public confidence or critical infrastructure.
Government Functionality (Governance): Effect on the local government's ability to maintain order, deliver minimum essential public services, ensure public health and safety, and carry out security-related	20		0—no effect on government function. 10—impact on local-area governance. 20—very high effect on government functioning at the national level.
Total (TA)	100		

3. Vulnerability Assessment (VA)

3.1 Site (VA-1)

Parameter		Rating Out of	Assigned Score	Remarks
i. Distance to unsecured vehicle	Setting of the building, giving it adequate protection against any unsecured vehicle. 5 ft being the minimum and 75 ft being ideal.	3		0—unsecured vehicle beyond 75 feet. 3—unsecured vehicle can come within 5 feet of the building.
ii. Perimeter boundary	What kind of perimeter protection in place for any vehicle/ person trying to enter the plot—type of wall, other barriers etc	4		0—very secured boundaries, not possible for vehicle entry or intrusion. 4—not secured boundaries capable of stopping vehicles and infrared.
iii. Unobstructed view (5 ft to 30 ft)	Visibility for counter- surveillance activity. 5 ft being minimum and 30 ft being best.	2		0—more than 30 ft 2—less than 5 ft
iv. Unsecured underground access	Unsecured underground access through any tunnel/ drain/ culvert of some other infrastructure. Eg.—getting into a building through the sewage drain passing below it	3		0—no underground access 3—underground unscreened access near the site
v. Storage of hazardous material (none to high)	Whether the structure has stores of any kind of material that is explosive thereby causing secondary fliers / can emit toxic releases	3		0—no hazardous/ explosive material. 3—hazardous and explosive material at site likely.
Total (VA-1)		15		

3.2 Architecture (VA-2)

Parameter		Rating Out of	Assigned Score	Remarks
i. Building Height - 20 ft to 200 ft	The greater the height of the building, the greater the risk of a collapse due to its own weight and higher the challenges of a timely evacuation. Low risk – Upto 30m Moderate risk – Upto 70m High risk– More than 70m	2		0–20 feet height or less 2–200 feet height or more
ii. Height/Least Lateral Dimension	Slender buildings are more prone to progressive and catastrophic collapses. Low risk– <5 Medium risk– 5-10 High risk– >10	2		H/B Ratio < 5=0, 5< H/B Ratio <9=1 H/B Ratio>9=2
iii. Building configuration (shape etc.)	Influence of a shock wave gets enhanced due to sharp corners and concave shape. Low risk–circular and convex Moderate risk– rectangular boxes High risk–re-entrant corners and concave shapes	2		0.0–circular and convex corners 1.0–rectangular boxes 2.0–concave/rectangular/sharp corners
iv. Overhang	The larger the overhang, the greater the risk of sudden collapse. Low risk–0-2 High risk–2 and above	1		0–overhang 0.75m or below, 1–overhang of 2m or above.
v. Lobby/Retail location/ Parking with respect to main building	Whether the structure allows visitors to be alienated from the main structure. Independent being safest Integrated being most dangerous.	3		0–independent lobby where secured screening happens 3–secured screening in the building
vi. Vehicular penetration of exterior envelope	Defines the angles at which vehicles can be driven into the complex and rammed into the structure at high speeds. 90 degrees (right-angle turn) is the best protection. 180 degree (straight drive) is the most dangerous.	3		0–no possibility of vehicle driver 3–very easy to drive into the envelope at high speed and breach the envelope.
vii. Evacuation Risk	Exit Adequacy	2		0–quick evacuation arrangement at exits. 2–difficult to evacuate due to narrow/insufficient exit
Total (VA-2)		15		

3.3 Building Envelope (VA-3)

Parameter		Rating Out of	Assigned Score	Remarks
i. Percentage of Window/ structural wall/ glazing area to total façade area	Low risk—20% Moderate risk—20-80% High risk—more than 80%	4		0—20% (safe) 2—20-80% (moderate risk) 4—more than 80% (high risk)
ii. Window support type	How well-secured are the windows/ structural wall/ glass façade to the main structure	1		0—secured 1—unsecured
iii. Glass/ window type	Is the glass/ window blast resistant Safest—laminated glass Moderately safe—security film - safe tempered Risky—heat strengthening Most risky—annealed	2		0—glass is blast resistant 2—ordinary glass
iv. Wall type	Safest—RCC Moderate—curtain wall Risky—pre-cast panels Most risky—unreinforced masonry structure	8		0—RCC (safest) 3—curtain wall (moderate) 5—pre-cast panels (risky) 8—unreinforced masonry structure (most risky)
Total (VA-3)		15		

Note: Robust unreinforced structure for low rise will be equivalent to RCC

3.3 Building Envelope (VA-3)

Parameter		Rating Out of	Assigned Score	Remarks
Structural System	i. Defines the Load-Carrying Structure			
	A. Redundancy and Robustness	8		
	B. Degree of redundancy in main-frame thereby allowing redistribution of load.	4		0—20% (safe) 2—20-80% (moderate risk) 4—more than 80% (high risk)
	C. Column vulnerability due to large spacing (10m, higher height -9m and above)	5		
	D. Public Accessibility to the column	8		
Total (VA-4)		25		

3.5 Security Systems (VA-5)

Parameter	Rating Out of	Assigned Score	Remarks
i. Intrusion Detection	2		0—robust detection 2—no system
ii. Video Surveillance and Assessment	4		0—system with AI detection and robustness. 2—system available 4—no system
iii. Security Guards	6		0—robust multi-level security with trained professionals
iv. Security Lighting	2		0—adequate lighting 2—no lights
v. Vehicle Access Control and Screening	6		0—boom barriers and bollard belly view camera 6—no screening of vehicle
vi. Pedestrian Access and Screening	6		0—X-ray metal detector and sniffing dogs 3—manual screen with metal detector 6—person can just walk in unscreened with no detectors.
vii. Package Screening	2		0—specific package X-ray screening provided 2—no package screening until an unscreened package is in the lobby.
viii. Public address (PA) system	2		0—adequate system provided 1—system inadequate 2—no system adequate
Total (VA-5)	30		

Parameter	Rating (out of 100)	Assigned Score
Site (VA-1)	15	
Architecture (VA-2)	15	
Building Envelope (VA-3)	15	
Structural Components and Systems (VA-4)	25	
Security Systems (VA-5)	30	
Total (VA)	100	

Based on the criterion mentioned above, risk assessment is calculated with the following formula:

Risk = Threat Assessment (TA) x Consequence Assessment (CA) x Vulnerability Assessment (VA)

Risk assessment will be scored out of 10,00,000z

Up to 1,25,000	Low Risk
From 1,25,000 to 4,50,000	Moderate Risk
From 4,50,000 and above	High Risk

ANNEXURE B

Mitigation measures to be provided for the safety of buildings vulnerable to man-made disasters as per Risk Assessment.

Risk Assessment as per checklist		Low Risk		Moderate Risk		High Risk	
A. General requirements		New Building	Existing Building	New Building	Existing Building	New Building	Existing Building
1	Open Spaces for "The Buildings Vulnerable to Terrorist Attack" shall be provided with a safe perimeter or blast standoff distance delineated with positive barriers and systems that prevent any attackers from approaching within that zone.	NA	NA	A	NM	A	NM
2	Marginal Distances required are as follows: As per the building line prescribed for National Highway/State Highway/ Major Road from the boundary of the road or as per provisions in that respect in DCPR 2034 and UDCPR 2020 as may be modified from time to time.	NA	NA	A	NM	A	NM
3	Compound wall shall be of 2.0m in height or as specified in these regulations (the height may be reduced to 0.75m if line of sight gets affected in which case the balance height shall be made up of vertical strong steel rods).	A	NM	A	A	A	A
4	At the corner plot, the boundary wall for a length of 10m on the front and side of the intersection shall be constructed of masonry/ concrete up to a height of 0.75m and the balance height shall be made of iron mesh or a railing of suitable size and thickness. However, this provision shall not be applicable to the boundary walls of jails.	A	NM	A	NM	A	NM
5	The approach to the building shall be provided with sufficient restraints to prevent any direct movement of vehicles towards the structures. There shall not be ordinarily more than two entry points, one for persons and the other for materials. The outer perimeter except the porch and the entrance area of the structure shall be protected with an RCC kerb of height not less than 600mm and thickness not less than 450mm.	NA	NA	A	NM	A	A
6	An additional standoff shall be provided to reduce the effect of an explosion at a closer distance of not less than that approved by the competent authority of the Police Department.	NA	NA	A	NM	A	A
7	Parking shall not be provided in the minimum marginal open spaces.	NA	NA	NM	NM	A	NM
8	A Security Outpost with the following requirements shall be provided near the entry control of the building having size not more than 45 sq.m. a. Fire-resistant material with two hours fire rating shall be used for construction. b. Latest electronic system for surveillance purpose shall be provided.	NA	NA	A	NM	A	A

Risk Assessment as per checklist		Low Risk		Moderate Risk		High Risk	
A. General requirements		New Building	Existing Building	New Building	Existing Building	New Building	Existing Building
9	A Control room with following requirements shall be provided for use by the owner/ occupier for controlling and monitoring various Security and Surveillance operations having size not more than 45 sq m.	NM	NM	A	A	A	A
	a. The Control room shall be centrally located but shall be away from the main entrance of the building.	NM	NM	A	A	A	A
	b. Control rooms shall be provided with escape routes at suitable locations.	NM	NM	A	A	A	A
	c. Control rooms shall be designed as blast-resistant strong rooms and shall be self-sustaining with full independent provisions for water, electricity, and communications. These rooms shall be provided with essential survival kits for at least a 72-hour period.	NM	NM	A	A	A	A
	d. The walls of the control room shall have adequate blast resistance.	NM	NM	A	NM	A	NM
	e. The door shall be provided with steel guard bars or grills. The main entry room or the control area shall be provided with steel armored gates having a minimum thickness of 12mm.	NM	NM	A	A	A	A
	f. The control room should also house the centralized control system of the building. Any window for ventilation shall be suitably protected with bulletproof glass and shatterproof membranes.	NM	NWMM	A	A	A	A
	g. The control room shall be suitably ventilated, and care taken to ensure foolproof safety of this ventilation arrangement.	NM	NM	A	A	A	A
	h. The control room should not be located near other highly-inflammable areas.	NM	NM	A	A	A	A
	i. Adequate water discharging capacity and provisions shall be made to prevent flooding in case of damage to overhead water tanks, water supply lines etc.	NM	NM	A	NM	A	A
	j. A proper access control from the terrace to the building shall be provided in the form of a locked door with proximity control to be activated and deactivated from the control room.	NM	NM	A	A	A	A

Note:

- 1) 'A' mentioned in the above chart means 'Applicable'.
- 2) 'NA' mentioned in the above chart means 'Not Applicable'
- 3) 'NM' mentioned in the above chart means 'Not Mandatory / At the option of owner'
- 4) NM in High risk and Moderate risk may include feasible alternative mitigation measure.

Risk Assessment as per checklist		Low Risk		Moderate Risk		High Risk	
B. Requirements for Electrical and Electronic Systems		New Building	Existing Building	New Building	Existing Building	New Building	Existing Building
1	Electronic Surveillance Systems shall be installed at various locations both inside and outside the building as may be required and with previous approval of the Appropriate Authority of Police Department having regard to the degree of perceived risk. A suitable control room shall be provided within the premises for monitoring, as mentioned above.	A	A	A	A	A	A
2	CCTV coverage of all important locations and vital installations shall be done including the main gate, reception, utility areas, and common open areas on floors, lifts, lobbies, and the compound. Perimeter lighting outside the building shall be adequate with focus at critical areas and movable search lights at corners.	A	A	A	A	A	A
3	All electronic systems, electrical systems, security systems and minimum services to the control room shall be provided with a three-tier system arrangement consisting of: (i) main supply (ii) standby generating system, (iii) Inverter or UPS system, to have continuous and uninterrupted power supply and shall comply with the provisions of IS codes, Indian Electricity Rules, 1956 and the National Building Code.	A	A	A	A	A	A
4	All provisions of the National Building Code in respect of electrification shall be applicable. In addition, the following requirements shall also apply regarding the illumination levels etc. in different areas in respect of security	A	A	A	A	A	A
5	Maximum to average ratio of luminance should not be more than 3:1.	A	A	A	A	A	A
6	Luminance level for vertical illumination at 1.5m above ground should be equal to horizontal luminance level at that point to enable clear detection.	A	A	A	A	A	A
7	The design should be such that uniform lux level is maintained considering the utility of the area which is dependent on the following points and is to be decided by its previous history and the environment.	A	A	A	A	A	A
	• Crime status of area • Nature of site (business, malls, restaurant) • Degree of obstruction (landscape designs, building configuration) • Ambient brightness of surrounding area. • Impacts on the surrounding area (stray light from security lighting, trespass).						

Risk Assessment as per checklist		Low Risk		Moderate Risk		High Risk	
B. Requirements for Electrical and Electronic Systems		New Building	Existing Building	New Building	Existing Building	New Building	Existing Building
7	In controlled sites, public spaces, important places, the illumination levels for different areas may be maintained as per Table No. 4 in Section 1 of part 8 (building services) of the National Building Code.	A	A	A	A	A	A
8	Light Controls: These should be of timer clock, photo control, dimmers, and motion detectors. Lighting control should be energized lighting when the ambient natural light level is less than 1.6 times the minimum horizontal security luminance value or 15 lux whichever is higher.	A	A	A	A	A	A
9	For façade lighting, the illumination level on building faces should be kept as required with an arrangement to increase or reduce this whenever essential depending on the situation and vital nature of the building. There should be rotating searchlights/ floodlights for very important buildings.	A	A	A	A	A	A
10	For vital buildings, on the compound wall or on the fence, electrical fencing of lower voltage (below 30 volts) can be proposed with a sensor arrangement.	NA	NA	A	NM	A	A
11	In addition to the main supply to the licensee through a transformer and/ or a standby generating system to fulfill minimum basic requirements in case of failure of the main supply, an inverter or UPS system for the centralized security system and for access control shall be provided. The generating system and transformer should preferably be provided outside the building with necessary security and the electrical cables should be underground/ metallic covered.	A	NM	A	NM	A	A
12	The usual provisions for maintenance of the Power Supply System and luminaires shall be properly scheduled for periodical servicing, tests, inspections, repairs, security audits for electrical installations, etc.	A	A	A	A	A	A

Note:

- 1) 'A' mentioned in the above chart means 'Applicable'.
- 2) 'NA' mentioned in the above chart means 'Not Applicable'
- 3) 'NM' mentioned in the above chart means 'Not Mandatory / At the option of owner'
- 4) NM in High risk and Moderate risk may include feasible alternative mitigation measure.

Risk Assessment as per checklist		Low Risk		Moderate Risk		High Risk	
C. Requirements for quick evacuation during emergencies		New Building	Existing Building	New Building	Existing Building	New Building	Existing Building
1	Adequate provisions within the building for quick and safe evacuation shall be made in accordance with standards of the National Building Code, if provision in this respect is not available in prevailing DCPR. This includes the number and width of exit doors, passages to be used as escape routes, staircases, longitudinal and cross-aisle and passages in the offices with built up furniture.	NM	NM	A	NM	A	NM
2	All external cladding shall be provided with shatterproof membranes for the glass walls and operable shutters at intervals for access for the rescue teams and to release air pressure due to any blast.	A	NM	A	NM	A	A
3	Maps of exit routes shall be displayed at various spots within the building.	A	A	A	A	A	A
4	Emergency light operation on UPS or inverters lasting for 48 hours shall be provided.	A	A	A	A	A	A
5	A trained safety squad shall be provided for monitoring quick and safe evacuation in case of emergency. Every building shall have a building-specific safety manual to be approved by the Fire Officer and Police Department containing the duties and responsibilities of various squad members/ floor marshals, etc.	NM	NM	A	A	A	A
6	In respect of quick and safe evacuation during emergencies, outside the building and within the compound of the premises, additional exits/ exit routes are to be provided on the rear side, which can be normally kept closed and used only during emergencies.	NM	NM	A	NM	A	NM

Note:

- 1) 'A' mentioned in the above chart means 'Applicable'.
- 2) 'NA' mentioned in the above chart means 'Not Applicable'
- 3) 'NM' mentioned in the above chart means 'Not Mandatory / At the option of owner'
- 4) NM in High risk and Moderate risk may include feasible alternative mitigation measure.

Risk Assessment as per checklist:		Low Risk		Moderate Risk		High Risk	
D. Blast-resistant design of buildings		New Building	Existing Building	New Building	Existing Building	New Building	Existing Building
1	The buildings shall be designed for blast resistance in accordance with the guidelines given in IS 4991-1968 and the following requirements shall be considered in their planning and design:	NM	NM	A	NM	A	NM
	a. Provision of optimal combination of mass and stiffness in the building, structure, enough structural redundancy in the buildings, member strength proportioned as per capacity design concept, consideration of reversal of loading, strong connections, etc.	A	NM	A	NM	A	A
	b. The wall facing a direct vehicular approach shall be of RCC, 45cm thick and suitably reinforced.	A	A	A	A	A	A
	c. The minimum thickness of stilt members on the ground floor and floors below shall be of fire resistance of 3 hours as specified in I.S.456.	A	A	A	A	A	A
	d. The various architectural controls shall be so provided that the building is away from hub activities. Roads should not lead straight into the building in question. The number of roads to the building must be minimum. Provision for effective entry control for persons, vehicles and materials, provision of spikes to puncture tyres, thereby preventing inbound vehicles from using outbound lanes, provision of passive and active barriers, etc. shall be made.	NA	NA	A	NM	A	NM
	e. Orientation of the building should be such that walls with glazing are perpendicular to the street side façade. Re-entrant corners must be avoided on the building exterior.	NA	NA	A	NM	A	NM

Note:

- 1) 'A' mentioned in the above chart means 'Applicable'.
- 2) 'NA' mentioned in the above chart means 'Not Applicable'
- 3) 'NM' mentioned in the above chart means 'Not Mandatory / At the option of owner'
- 4) NM in High risk and Moderate risk may include feasible alternative mitigation measure.

Risk Assessment as per checklist		Low Risk		Moderate Risk		High Risk	
		New Building	Existing Building	New Building	Existing Building	New Building	Existing Building
E. Other Provisions							
A	a. All existing buildings considered vulnerable (with Protection level High) to terrorist attacks shall also make provisions for compliance with these regulations except those which are not applicable or feasible or possible to be complied with, in the opinion of the Planning authority. This includes retrofitting as may be required to comply with these provisions. b. In case of buildings considered vulnerable with Moderate Protection level, the project proponent will finalize the appropriate norms to be complied with in consultation with the Planning authority. c. Low Risk buildings—Guidelines of FEMA 426, 452, 455 will be recommended to the owner to follow.						
B	Owner/Occupier of the Medium and High-Risk building premises, shall have his own security management administration with trained personnel for execution, procedures for fire and evacuation drills, security audits and a manual containing various requirements and procedures for security control with properly-defined duties in line of control and directions, which shall be already-approved by the Police Department.						
C	Proper monitoring and periodic security audits of systems in Medium and High-risk buildings shall be done, and these reports shall be submitted to the Specified Authority of the Police Department. The owners/occupiers of such specified buildings shall assist the Police and State authorities in arranging and carrying out third-party security audits at specified intervals as directed, preferably every 5 years. The Protection level shall be reassessed every 5 years, and building/s are to be dealt with accordingly.						
D	Pending standardization of Reference Manuals and procedures for Maharashtra, the provisions in FEMA-426, 452, and 455 may be used as a guide and security arrangements made accordingly.						
E	For Special class of institutional viz; Bridges, Dams, and buildings viz; critical Industry, Refinery, BARC, Water Treatment Plant, Energy providers, RBI, BSE, NSE, Data centers, Operational infrastructure and control rooms of all essential services including but not limited to airways, railway, metro and port transportation, data and telecom providers etc. detailed security guidelines should be declared by the respective authority.						
F	The information regarding Risk Assessment mentioned in Annexure 4.1 being very sensitive information, the authorities should keep this information out of the public domain and only the emergency response department will have access to such details.						

Note:

- 1) 'A' mentioned in the above chart means 'Applicable'.
- 2) 'NA' mentioned in the above chart means 'Not Applicable'
- 3) 'NM' mentioned in the above chart means 'Not Mandatory / At the option of owner'
- 4) NM in High risk and Moderate risk may include feasible alternative mitigation measure.

ANNEXURE - D - Fire Break Water Tank System for High-Rise Buildings of Height 90m and above

Current Issues for Fire Hydrant Systems:

1. Use of Pressure Release Valves (PRVs) to limit line pressure up to 12 Bar.
2. Cost effectiveness of PRVs and their maintenance.
3. Effectiveness of Multistage Pump sets and their reliability.
4. Maintenance of such complex Pumping systems by Residential/Commercial Owners.
5. High pressure pumping and valves availability.

A schematic for a high-rise building 90m and above up to 200mt, the intent of the schematic meets the following:

Design Parameters:

1. Common Pumping for Hydrant and Sprinkler
2. Diesel Engine Standby Pump only at ground level
3. Standby pumps on floors are all electrical and fed by Diesel Generator
4. Sprinkler density considered is 4.1 LPM over 140 sq. mt.
5. Hydrant flow of 3 hydrants operating at 3.5 Bar (630 LPM x 3)
6. Total Pumping considered is 2500 LPM at 10 Bar—Duty Point—Standard Single outlet pump
7. Storage tanks at levels such that line pressure does not go beyond 12 Bar
8. Gravity feed is also considered for sprinklers
9. Redundant riser also considered for sprinklers
10. Filling of above tanks through FF Pumps at ground level.

Advantages:

- Redundant Pumps and Risers
- Gravity feed at all times in case the pumps do not function.
- No pump sets over 10 Bar pressure, and shutoff below 12 bar.
- Zoned system at 55m
- All valves below 16 bar PN 16
- NO PRV required
- NO Multi-outlet pump required
- Low on maintenance as all are low pressure.
- Utility floor every 65m, breaks the vertical fire (check floor concept)
- Additional space for refuge on these utility floors



ANNEXURE E Qualifications, duties, and responsibilities of the Electrical Professional (Electrical Engineer/Consultant)

i. Qualification

An Electrical Engineer having a bachelor's degree in electrical engineering with two years working experience in a similar field and knowledge of related standards, codes, and regulations. Or

An Electrical Engineer having a diploma degree with five years working experience in a similar field and knowledge of related standards, codes, and regulations.

ii. Duties

The Electrical Engineer shall check electrical requirements in architectural plans. He shall prepare electrical designs and provide material specifications. He shall scrutinize and validate plans, designs, drawings, and material specifications if taken from external sources. He shall supervise and certify work, produce information as required in prescribed checklists, process all regulatory compliances related to verification/inspection and testing along with applicable NOCs/Permissions from respective authorities.

iii. Responsibilities

To check compliance with the latest Indian Standards, National Electrical Code (NEC), related sections from the National Building Code (NBC), and Statutory Provisions applicable under Rules framed by government, Regulations framed by the Central Electricity Authority, pertaining to related sections from the Electricity Act 2003. He shall be responsible for the quality of work and related documents (electrical plans, single line diagrams, design sheets, specifications). He shall give stagewise **declarations for design, construction and verification and testing** in the prescribed formats given under **Annexure E-4** which will be a mark of his responsibility and further accountability.

ANNEXURE E-1 Appointment of Electrical Professional (Electrical Engineer/ Consultant) and Contractor

Standard Procedures for Executing Electrical Work in Buildings						
Check List No.1						
Planning – Preliminaries						
Ref.	CEA Reg. 5A, 29/2010					
Name of Project / Work						
Site Address						
Name of Owner / Builder						
Contact details						
Sl No.	Appointments – Electrical Professional (Electrical Engineer/ Consultant) / Electrical Contractor					Remarks
1	Appointment of MEP Consultant					Yes No N.A.
1.1	If yes, Name					
	Date of appointment					
2	Name of Electrical Consultant/CESE					Yes No N.A.
2.1	Contact Details					
2.2	Registration No. if CESE					
3	Appointment of Electrical Contractor 1*					Yes No
3.1	If yes, Name					
3.2	Contact Details					
3.3	Date of appointment					
3.4	License No.					Validity
3.5	Agreement & Under-taking					See format of declaration and model conditions of agreement
3.6	Name of Supervisor(s) -1					
3.6.1	Permit No.					
3.7	Name of Supervisor(s) -2					
3.7.1	Permit No.					
* for subsequent change(s) in Electrical Contractor, repeat 4 below						
4A	Re-appointment of Electrical Contractor 2*					Yes No
4.1	If yes, Name					
4.2	Contact Details					
4.3	Date of appointment					
4.4	License No.					Validity
4.5	Agreement & Under-taking					See declaration under Annexure B and model conditions of agreement under Annexure M
4.6	Name of Supervisor(s) -1					
4.6.1	Permit No.					
4.7	Name of Supervisor(s) -2					
4.7.1	Permit No.					
4B	Re-appointment of Electrical Contractor 3*					Yes No
Repeat 4.1 through 4.7.1, when applicable						
Signatures of the stakeholders as applicable with date	MEP Consultant		Electrical Professional / Engineer / Consultant			
	Electrical Contractor (outgoing)	Electrical Contractor (new)	Owner / Builder			

ANNEXURE E-1**Forms of Declarations from Electrical Professional
(Electrical Engineer/ Consultant)**

[Corresponding to Annex E IEC 60364-6:2016]

Form 1 – Declaration for Design of Electrical Installation**Details of Building**

Owner/Builder: _____

Contact details [Phone No(s), email]: _____

Name of the Building / Project: _____

Address: _____

Wing: _____

No. of Floors: _____ Height: _____

Details of flats/tenements/blocks: _____

Type (Residential / Commercial / Other (specify) _____

1. Declaration for Design

I/We being person(s) responsible for design of the electrical installation, particulars and location as described above, having exercised reasonable skill and care when carrying out the design hereby DECLARE that the design work for which I/we have been responsible, is to the best of my/our knowledge and belief in accordance with the latest Standards and Codes published by the BIS and in compliance with the CEA (measures relating to Safety and Electric Supply) Regulations, 2010; with the latest amendments.

I/We hereby declare that:

1 I have a valid electrical contractor's license. [Tick if yes and provide details]

2 License No. _____

3 I am a Chartered Electrical Safety Engineer (CESE). [Tick if yes and provide details]

My Registration No. is _____

I am a registered electrical engineer/professional as per DCPR [Tick if yes and provide details]

My qualifications are _____

My experience in the field is _____ (months/years)

My Registration No. is _____

Signature of the Designer/
Electrical Professional
(Electrical Engineer/ Consultant)

Signature of the LEC
(if applicable)

(Name & Stamp)
Date

(Name & Stamp)
Date

ANNEXURE



FORM 2- Declaration for Construction of Electrical Installation

Details of Building

Promoter / Developer / Owner: _____

Contact details [Phone No(s), email]: _____

Name of the Building / Project: _____

Address: _____

Wing: _____

No. of Floors: _____ Height: _____

Details of flats/tenements/blocks:

Type (Residential / Commercial / Other (specify) _____

2. Declaration

I/We being person(s) responsible for construction of the electrical installation at the location described above, having exercised reasonable skill and care when carrying out the installation work; hereby DECLARE that the said work* for which I/we have been responsible, is to the best of my/our knowledge and belief, constructed in accordance with the latest Standards and Codes published by the BIS and in compliance with the CEA (measures relating to Safety and Electric Supply) Regulations, 2010, with the latest amendments.

Signature of the Supervisor

Signature of the LEC

(Name)
Date

(Name)
Date

Signature of Electrical Professional (Electrical Engineer/ Consultant)

(Name)
Date

* If there is a change of contractor before completion of the project, the stage of work shall be recorded and mentioned with handing over and taking over documents to be signed jointly and attached with this document.

Report of the Expert Committee:

ANNEXURE E-2.3**FORM 3- Declaration for Inspection and Testing of Electrical Installation****Details of Building**

Promoter / Developer / Owner: _____

Contact details [Phone No(s)-, email]: _____

Name of the Building / Project: _____

Address: _____

Wing: _____

No. of Floors: _____ Height: _____

Details of flats/tenements/blocks:

Type (Residential / Commercial / Other (specify) _____

3. Declaration for Inspection and Testing

I/We being person(s) responsible for Inspection and Testing of the electrical installation at the location described above, having exercised reasonable skill and care when carrying out the inspection and testing, hereby DECLARE that the said work for which I/we have been responsible, is to the best of my/our knowledge and belief, inspected and tested in accordance with the latest Standards and Codes published by the BIS and in compliance with the CEA (measures relating to Safety and Electric Supply) Regulations, 2010; with the latest amendments.

Signature of the Supervisor

Signature of the LEC

Testing agency /
Chartered Electrical Safety Engineer(Name)
Date(Name)
Date(Name)
Date

Signature of Electrical Professional (Electrical Engineer/ Consultant)

(Name)
Date

ANNEXURE F - Building clearances from Electric Line (OH/UG) & Earth Work

Standard Procedures for Executing Electrical Work in Buildings					
Check List No.2					
Planning – Design Part 1 – Architectural and Construction related Preliminaries					
Ref.	Reg. 12, 58, 60, 63, 64, 65, NEC-1/7/4.2, IS 732-4.1.4, 4.1.3.1.2, 4.1.3.12				
Name of Project / Work					
Site Address					
Name of Owner / Developer					
Contact details					
Sl No.	Land / Site Survey				Remarks
1	Does the electrical overhead line exist on site?	Yes	No		
1.1	If yes, mention voltage level		kV		
1.2	Did you check with power utility or concerned if UG line exists within plot	Yes	No		
1.3	If UG line exists, mention voltage level		kV		
1.4	If UG or OH line exists, did you check compliance with CEA Reg. 63:2010.	Yes	No	NA	
Construction activities					
2	From the location of existing electrical overhead or underground line, will there be:				
2.1	Blasting within 300m	Yes	No		
2.2	Cutting of soil within 10m	Yes	No		
2.3	Brick kiln, or any polluting unit within 500 m	Yes	No		
2.4	Storage / temporary shed below electrical lines	Yes	No		
2.5	If yes, did you check compliance with CEA Reg. 64 & 65:2010	Yes	No	NA	
Signatures of stakeholders & Dates		Electrical Professional Engineer/ Consultant		Electrical Contractor	

ANNEXURE G – Requirements related to Civil Construction

Standard Procedures for Executing Electrical Work					
Check List No.4					
Planning – Design Part 2 – Civil Construction for Electrical Work					
Ref.	Standards, Codes (NEC, NBC), CEA Regulations				
Name of Project / Work					
Site Address					
Name of Owner / Developer					
Contact details					
Sl No.	Civil Construction activities Plans, Material, Specifications	Yes	No	NA	Remarks
1	Adequate ventilation arrangement done for electrical equipment	Yes	No	NA	
1.1	Fire Rating of rooms as per standard provided?	Yes	No	NA	
1.2	Fire Rating of doors, partitions at a minimum of 2 hours?	Yes	No	NA	
1.3	Fire Rating of electrical shaft, segregation at a minimum of 2 hours?	Yes	No		
1.4	Fire Rating of baffle wall between transformers at a minimum of 4 hours?	Yes	No	NA	
1.5	Doors opening outside?	Yes	No	NA	
1.6	Sizes/Cross section of ducts, cable chambers satisfactory?	Yes	No	NA	
1.7	Access to Earthing stations maintained?	Yes	No		
1.8	In case of structural earthing activity coordinated with electrical	Yes	No	NA	
1.9	In case of heavy electrical equipment with static/dynamic load, structural stability confirmation received?	Yes	No	NA	
1.10	Provision of entries kept in RCC work to avoid core cutting	Yes	No	NA	
1.11	Required vertical clearances below beam soffit/ceiling slab satisfactory?	Yes	No	NA	
1.12	Adequate clearances maintained between electrical & other UG services in Plans?	Yes	No	NA	
1.13	Construction of room for DSS – Plan satisfactory?	Yes	No	NA	
Signatures of the stakeholder	Electrical Professional / Engineer/ Consultant	Electrical Contractor		Civil Contractor	

ANNEXURE H - Assessment of Electrical Load requirement

Standard Procedures for Executing Electrical Work in Buildings					
Check List No. 3					
Planning – Design Part 3					
Ref.	Reg. 12, NEC Part2 Section 1				
Name of Project / Work					
Site Address					
Name of Owner / Developer					
Contact details					
Sl No.	Electrical Load, Supply (Primary Assessment)				
1	Assessment of Electrical Load				
1.1	Assessment done?	Yes	No		
1.2	If yes, anticipated capacity	Power from Utility Provider		kVA / kW	
1.3		Electrical Supply	HT	LT	
1.4		Power from Standby Supply		kVA / kW	
1.5		Genset		kVA	NA
1.6		UPS		kVA	NA
2	Assessment of space allocation required for electrical equipment, system in Architectural Planning				
2.1	CSS/DSS required?	Yes	No		
2.1.1	If yes,	Required space, room, location suitable?	Yes	No	NA
2.2	Genset required?	Yes	No	NA	
2.2.1	If yes,	Required space, location suitable?	Yes	No	NA
2.3	Distribution cables	Yes	No	NA	
2.3.1	Does the drawing show,	Marking of routes in plot?	Yes	No	NA
2.3.2		Separate cable shaft in building?	Yes	No	NA
2.4	Rooms				
2.4.1	As per drawing,	Meter room(s) suitable?	Yes	No	
2.4.2		Elect Panel/control rooms, etc., suitable?	Yes	No	NA
2.4.3		UPS, batteries' location, room suitable?	Yes	No	NA
2.5	Lightning Protection System	Risk analysis done as per IS/IEC 62305-2	Yes	No	NA
2.5.1	If yes, as per the drawing,	Location of air-terminations, down conductor satisfactory?	Yes	No	NA
2.6	Earthing stations – system drawings	Locations and access for maintenance satisfactory?	Yes	No	
2.7	Construction and Post completion facility	Routes, corridors, access for transportation, maintenance; satisfactory?	Yes	No	
Signatures of stakeholders & dates		Electrical professional / Engineer / Consultant	Electrical Contractor		
	Chartered Electrical Safety Engineer				

ANNEXURE I Layouts and drawings – Equipment and Internal Electrical Installation

Standard Procedures for Executing Electrical Work					
Check List No. 5					
Planning – Design Part 4 – Electrical Drawings & Layouts					
Ref.	Standards, Codes (NEC, NBC), CEA Regulations				
Name of Project / Work					
Site Address					
Name of Owner / Developer					
Contact details					
Sl No.	Layouts Drawings for Equipment / Apparatus	Yes	No	NA	Remarks
1	Drawing of Transformer substation prepared?				
1.1	If yes approval received from Electrical Inspector				
2	Drawing of standby supply arrangement from Genset prepared?				
2.1	If yes approval received from Electrical Inspector				
3	Drawing of standby supply arrangement with UPS & Battery prepared?				
3.1	Does it comply with codes				
4	Drawing of Meter room prepared?				
4.1	Does it comply with codes				
5	Any other? specify				
5.1	Does it comply with respective standard/code/Regulation				
Internal Layouts drawings of Individual Tenement (Flat/Block)					Remarks
6	Internal layout drawing prepared?				
6.1	Does it comply with the requirements in respect of minimum No. of points				
6.2	Does it comply with the requirements in respect of location of switch boards & DBs				
External Electrical Layouts, Drawings					Remarks
7	External layout prepared for streetlights?				
7.1	Does it comply with the requirements of Lux level				
8	Layout of Pump rooms prepared? Does it comply with the requirements of Lux level				
8.1	Does it comply with the requirements of respective authority				
Internal Layouts drawings for Hospital Buildings					Remarks
9.1	Have the areas been classified as A0, A1, and A2 as per IS 17512				
Signatures of the stakeholders and Dates		Electrical professional / Engineer / Consultant		Electrical Contractor	
	Civil Contractor				

ANNEXURE J - Single Line Diagrams

Standard Procedures for Executing Electrical Work					
Check List No. 6					
Planning - Design Part 5 - Electrical Drawings - Distribution, Single Line Diagram					
Ref.	Standards, Codes (NEC, NBC), CEA Regulations				
Name of Project / Work					
Site Address					
Name of Owner / Developer					
Contact details					
Sl No.	SLDs for Common Services	Yes	No	NA	Remarks
1	SLD prepared for supply from tapping point to individual service connection?				
1.1	Critical services bifurcation done?			NA	
1.2	Precise selection of HFFR/FS cable made?				
1.3	Does the cross section and conductor type conform to IS 732?				
1.4	Provision of Fire Switch made?			NA	
1.5	If a high-rise building, approval from the Electrical Inspector taken?			NA	
2	System-wise SLD prepared for common services in accordance with above?			NA	
	SLDs for Individual Services	Yes	No	NA	Remarks
3	Individual consumer-wise SLD prepared for each tenement?				
4	Do the SLDs show complete details of load, cable size, DBs and protections at every stage of distribution?				
5	Is the type of conductor and minimum cross section of cables as prescribed and precise w.r.t load, current carrying capacity considering situation and derating factors as recommended under IS 732?				
6	Are the protections precise to prevent installation from				
6.1	Overload / Short circuit / Earth fault				
6.2	Leakage current				
6.3	Over voltages / Surges			NA	
6.4	Arc fault			NA	
7	Any other - APFC, Harmonic Filter panels			NA	
8	Do the above SLDs conform to the various provisions under standards codes & regulations?				
Signatures of the stakeholders	Electrical Professional / Engineer / Consultant	Electrical Contractor	Civil Contractor		

ANNEXURE K – Coordination in Activities

Standard Procedures for Executing Electrical Work					
Check List No. 8					
Construction – Electrical Installation 1					
Ref.	Standards, Codes				
Name of Project / Work					
Site Address					
Name of Owner / Developer					
Contact details					
Sl No.	Coordination between construction activities				Remarks
1	Has the bar chart been prepared?	Yes	No		
2	Does the bar chart include all activities of civil, electrical, and other building services?	Yes	No	NA	
3	Is there mutual agreement between the civil engineer and Technical Person related to other building services in respect of activities and the bar chart?	Yes	No		
4	Has the responsibility been assigned to the project management personnel/engineer for monitoring the progress of work as per bar chart?	Yes	No		
5	Are the corridors, routes, spaces, clearances, access for construction, maintenance, transport of material / equipment assigned for respective services being observed and monitored?	Yes	No	NA	
6	In case of any damage to the work of other services, are there arrangements to resolve the issues?	Yes	No	NA	
Signatures of the stakeholders with dates		PMC		Civil Contractor	
	Electrical Professional/ Engineer/ Consultant	Electrical Contractor			

ANNEXURE C – Points to be observed in Construction Work

Standard Procedures for Executing Electrical Work					
Check List No. 9					
Construction – Electrical Installation 2					
Ref.	Standards, Codes (NEC, NBC), CEA Regulations				
Name of Project / Work					
Site Address					
Name of Owner / Developer					
Contact details					
Sl No.	Electrical Installation – General				Remarks
1	Has the proper agreement been executed with the electrical contractor making him aware of his duties and responsibilities?			Yes	No
2	Have the various conditions mentioned in the checklist under the planning section, been verified, conformed to, and being monitored?			Yes	No
3	Requirements related to NOCs concerning construction completed?			Yes	No
4	The method of construction being adopted is complying with the standards and codes as enlisted under the test report (verification & testing) format? (Ref. Annexure E-11)			Yes	No
5	Is proper record of hidden work and certification before concealing being maintained?			Yes	No
6	Is the work being supervised by an authorised person continuously?			Yes	No
Signatures of the stakeholders with dates	Electrical Professional / Engineer/ Consultant		Electrical Supervisor		Electrical Contractor

ANNEXURE **M-1** – Model format for Test Report of Electrical Works in Buildings

[Refer Annexure E-1 for Instructions to the Consultants, Contractors, Stakeholders* for providing information in Test Report]

PART-A: Particulars of Electrical Contractor and Installation*

[to be given by Promoter / Developer and LEC per service cable/meter room]

1. Electrical Contractor details

Name of the firm: _____

Contractor's name: _____

Contact details: [Phone No., email] _____

License No.: _____ Validity: _____

Supervisor's name: 1. _____ Permit No. _____

2. _____ Permit No. _____

Test Report No. HR/ _____

Date of verification and tests _____

2. Details of Multi-Storeyed Building

Promoter / Developer / Owner: _____

Contact details [Phone No(s), email]: _____

Name of the Building / Project: _____

Address: _____

Wing: _____

No. of Floors: _____ Height: _____

Details of flats: _____

Residential _____

Other (specify) _____

3. Date of appointment of contractor: _____

Stamp & Sign
(Owner/Developer/Promoter)

Stamp & Sign
(Electrical Contractor)

* In case of change of contractor before completion of project, a separate form is necessary

ANNEXURE 3 – Model format for Test Report of Electrical Works in Buildings

PART-B: Verification (Inspection and Testing)

[To be given by Licensed Electrical Contractor and Electrical Professional (Electrical Engineer/ Consultant)]

B-1 Architectural Planning and Civil Construction – Electrical Requirements

1. State if sufficient clearances maintained from overhead/underground lines and the construction is in compliance with Reg. 58, 60, 61, 63: [Yes/No/NA]
2. State if there is adequate provision of rooms, spaces and clearances as required for electrical equipment to operate, be maintained safely within the building and if it complies with the requirements as per CEA Regulations, 2010. Reg. 12(1), 37 [Yes/No]
3. State if there is provision of an independent meter / electric service room of adequate size for installation of meters and equipment with proper ventilation NBC, NEC [Yes/No]
4. State if the door openings of electrical equipment rooms are outside and are of fire resistance not less than 2 h. Reg. 12(1), NBC [Yes/No]
5. State if the meter room is free from water seepages/ leakages/water logging? Reg. 12(4) [Yes/No]
6. In respect of meter room are there any signs which show proneness to accidents? Reg. 12(1), 35(7) [Yes/No]
7. State if there is provision of a separate and independent vertical shaft/duct for distribution network of power cables/bus trunking and conveniently located adjacent to meter room. Reg. 12(1), 36(5) [Yes/No]
8. State if arrangements have been made to segregate the electrical cable duct from the other services' shafts/ducts and sealed at every floor with the material having minimum 2 h fire rating, to prevent spread of fire. Reg. 36(5) [Yes/No]
9. State if the provisions for DTC within the building are in compliance with Reg. 12(4), 44. [Yes/No/NA]
10. State in case of the oil/liquid filled transformer within the premises/building complex is filled with liquid having fire point above 300°C. NEC

B-2 Electric Supply – Details and Supplier's installation Requirements

1. State the total number of meter connections and total load in kW/kVA on service cable [Aggregate of Connected / Sanctioned load of consumer(s) on this cable]. _____
2. State if the load sanctioned is less than the standard load consideration norms set by the supply company per m² Reg. 12(1). [Yes/No]
3. Service Cable details Reg. 12(1) [type, size, construction] _____
4. State if the service cable is suitable Reg. 12(1) [Yes/No]
5. Has the supplier provided information in respect of fault level at the supply point? Reg. 12(1), Schedule V of CEA Reg. 2010 [Yes/No]
6. State if the meter room is independent and of adequate size to maintain stipulated clearances, ventilation. Reg. 12(1) [Yes/No]
7. State if the meter room is properly located, safe from external influences, and adequate care is taken to protect the supplier's equipment. Reg. 13(1), (3), NEC [Yes/No]
8. State if the supplier's distribution network has provision of multiple neutral earthings. Reg. 41(iii) [Yes/No]
9. State if the supplier has earthed the neutral of service cable at the consumer's premises (TNC-S / TNS system). Reg. 41(iii) [Yes/No]
10. State if the supplier has provided an earth terminal for consumer's use? Reg. 16(1) [Yes/No]
11. State if there is provision of separate/independent earth terminal from the consumer's side, to provide return path to leakage / fault current. (TT system) Reg. 16(1) [Yes/No] State the value of resistance _____ ohm(s).
12. Has testing been done for external Earth Fault Loop Impedance Z_e at origin of supply? [Yes/No] If yes, state the value measured. _____ ohm Reg. 41(xv)(b)
13. State if provision to isolate complete supply of building (Fire Switch) is done. Reg. 36(3) [Yes/No]
14. State if critical load requiring electrical supply during emergency is separated at the origin of supply distribution and provision of fire switch is made in accordance with IEC 30364-5-56:2018 Annex D [Yes/No].

B-3 Electric Supply – Standby supply arrangement and installation requirements

- 1 Give the list of emergency and critical services with respective load and supply restoration time No-Break (0 s), short break (< 0.5 s), medium break (< 15 s)

Sl. No.	Service	Load in kW No Break (0 s)	Load in kW Short Break (< 0.5s)	Load in kW Medium Break (< 15s)	Load in kW Long Break (>15 s)
1					
2					
Total Load					

Note – Increase no. of rows if required.

- 2 Give details of the source of standby/back-up supply arrangements corresponding supply restoration time, e.g., Genset 125 kVA with AMF (< 15 s)
- 3 State if the power rating of genset(s) conforms to standards? IS/ISO 8528-1, [Yes/No]
- 4 State if the change-over time of genset(s) conforms to standards? IS/ISO 8528-12, [Yes/No]
- 5 State if the location of the genset is safe to continue operation during emergency, (e.g., fire in the building shall not affect the working of genset). NEC [Yes/No]
- 6 Give status of permission required under Reg. 32 (received / in process)

B-4 Earthing arrangements

- 1 Do the construction of earth electrode(s) and connectivity up to Main Earthing Terminal (MET) comply with standards? IS 3043 [Yes/No]
- 2 Is there provision of a test terminal and is it accessible for testing earth resistance of individual earth electrodes? Reg. 41, 48 [Yes/No]
- 3 Are the test results of measurement of resistance of earth electrode (RE) satisfactory? IS 3043 [Yes/No/Not practicable]
- 4 Does the earthing system generally comply with requirements as mentioned, the standards, and as stipulated in the CEA Regulations? CEA Reg. 41,48:2010, IS 3043 [Yes/No]. If 'No', give details.
- 5 In case of hospitals, do the earthing arrangements comply with the requirements as per IS 17512? [Yes/No/NA]

B-5. Electrical Installation – Applicable for installations belonging to individual and common utility services**1. General/common points**

1.1	Wiring type:	Indoor [surface / concealed / mixed / hybrid] Outdoor [surface / underground / mixed / hybrid]
1.2	Material used:	Do all materials used carry the ISI mark? Reg. 12(3) [Yes/No] Where Indian Standards do not exist, do materials conform to International Standards [Yes/No]. Give details _____

1.3	Wiring/Cables:	State separately for general services and critical services requiring supply integrity: Indoor use: Make [mention] _____ Insulation. Reg. 35(6), NEC [FR/FRLSH/HFFR/FS] Conductor cross section as per IS 732 Annex S / T? Reg. 36(4) [Yes/No] Minimum 1.5 mm² copper [Yes/No] Up to 16 mm² Copper NBC, NEC [Yes/No] Above 16 mm² [Copper/Aluminium] Current-carrying capacity of conductor more than the rating of MCB? Reg. 12(1) [Yes/No] Identification by colour code as per NEC: Reg 36(4) [Yes/No] All cables are erected as per standards and protected from mechanical damages and no live parts are exposed Reg. 35(7) [Yes/No] For outdoor use: [Armoured / non armoured] [NA] Is construction of the UG cable as per IS 1255 [Yes/No/NA] In case of non armoured whether protected with mechanically strong casing / conduit / pipe (RCC/HDPE/DWC) Reg. 37(i) [Yes/No/NA] Specific for critical services: Have Fire Survival cables (FS) been used for following services having appropriate Fire Survival Category? Reg. 12(1), 36(4), IS 17505 Annex A [Yes/No]
1.4	Conduit/casing:	Make [mention] Size – adequate space factor maintained? Reg. 12(1), NEC [Yes/No]
1.5	Distribution:	A. For installation belonging to individual and common services 1. Single Line Diagram Typical SLDs attached? Reg. 12(1) [Yes/No] 2. Division of Circuits Are circuits divided adequately as per room/area, type of load light/power general/back-up? NEC [Yes/No] Do the load / points on the branch circuit exceed max. limit? Reg. 36(4), 12(1), NEC [Yes/No] 3. Cables State if the sizes of cables and their design maximum current-carrying capacities depending on the situation and derating factors are suitable to supply the load? Reg. 12(1), NEC, IS 732 [Yes/No] 4. Over-Current Protection Device (OCPD) State if the cables in each circuit are protected with MCBs having appropriate O/L and breaking capacity and instantaneous tripping characteristics as per load pattern (type B, C, D)? [Yes/No] Do such ratings of MCBs coordinate with the maximum current carrying capacity of the cable as per design suitable in particular situations? Reg. 12(1), 35(1)(4)(5) [Yes/No] State if in case of fault/short-circuit, the MCBs used have precise rating as per the loop impedance to trip in stipulated time. Reg. 35(1) [Yes/No] State if the sequence of tripping devices is coordinated. Reg. 12(1) [Yes/No]

		5. Protection from leakage currents/electric shocks State if RCDs (or RCBOs) are of appropriate types and have been provided with the appropriate rating Reg. 42 [Yes/No] 6. Protection from surges State if provision of Surge Protection Devices is made at appropriate distribution locations IS 732 (Yes/No) 7. Protection from Arc Flash State whether provision of Arc Flash Detection Device is made NEC (Yes/No) 8. Distribution Boxes / Consumer's unit State if distribution boxes are located in easily-accessible positions? Reg. 35(4), (5) [Yes/No] State if DBs, each circuit in DB and switchboards are marked with unique identifications as per the SLD and if ferruling is done at both ends of cable termination. Reg. 12(1), 24 [Yes/No] 9. Terminations State if all cable terminations have been checked and found adequate without loose contact and any possibility of overheating Reg. 12(1) [Yes/No] 8. Specific requirements in respect of common services in buildings 1. Reverify § 8-1 (12) & (13). Does the provision stand to the satisfaction as per Reg. 12(1), 36(4), IEC 60364-5-56? [Yes/No] 2. Is the arrangement of fire switch in the incoming supply distribution made as per the Annex D of IEC 60364-5-56 [Yes/No] 3. Has the provision of a ring circuit with an alternate route been made to maintain supply integrity during an emergency? Reg. 12(1), 36(4) [Yes/No]
1.6	Inverter/UPS:	Is there provision of a separate circuit with phase along with separate neutral wire for the load provided with standby supply arrangement through inverter / UPS? Reg. 12(1), Code [Yes/No] Has it been confirmed that there will be no back feeding of inverter/UPS supply to the main supply? Reg. 12(1) [Yes/No]
1.7	Point wiring:	Considering room / area / utility; are the points provided adequate in number and location to suit the functionality and ergonomics as recommended in code? Reg. 12(1), 36(4), NEC [Yes/ No] Are the locations of switch boards made as per Code? Reg. 12(1) NEC [Yes/No] Are the provisions of switches made on phase wire only? Reg. 12(1) NEC [Yes/No] Are the plug sockets 3-pin only? Are the plug sockets below 1m shuttered type? Reg. 12(1), Code [Yes/No]

1.8	Earthing	1. Does the size and type of Protective Earth (PE) conductor conform with Table 12 IS 3043: Reg. 36(4) [Yes/No] 2. State whether equipotential bonding has been done with an appropriate size of conductor? IS 3043 [Yes/No] 3. Are connections of PE conductor, equipotential bonding conductor, supplementary bonding conductors with earth terminal/metal body of electrical appliances, apparatus/mutual interconnection between PE and bonding conductors proper and mechanically strong? Reg. 41, IS 3043, IS 732 [Yes/No] Does the continuity test carried out show satisfactory results? Reg. 41, IS 732 [Yes/No] 4. Where measurement of RE is not practicable, are the values of earth fault loop impedance Z_s, satisfactory to operate protective devices within precise time (short time/instantaneous tripping)? Reg. 41, IS 3043 [Yes/No]

2. Electrical installation details and testing (List—meter/individual service connection-wise)

2.1 Attach separately in the following format.

Attach separately for each service connection in the following format.

Sr. No.	¹ Flat / Common service	² Area ft ² /m ²	Supply 1-ph / 3-ph	Sanctioned load kW	³ Mains	⁴ OCPD (main)	⁵ RCD / RCBO	Remarks
		⁶ IR test value	⁷ Continuity Test	⁸ Earth fault loop impedance Z_s	⁹ Prospective fault current / short circuit current	¹⁰ Polarity test	¹¹ Neutral looping	¹² Typical SLD Ref.

Note – Refer instructions for respective superscript

2.2 Handing over preparations made as per the format [Yes/No]

We hereby certify that the work is completed, verified, tested as per the standards, codes, CEA regulations and declare this to be safe for use.

Sign

Sign

Sign

Electrical Professional/ Electrical Engineer/ Consultant
Date

Supervisor Permit No.
Date

Electrical Contractor License No.
Date

ANNEXURE N-1 – Checklist for Handing-Over Documents to Individual Buyer

[Floor: ----- Tenement / Flat No. -----]

Sr. No.	Document	✓ or X
1	Electrical Service connection papers relating to individual energy meter, sanctioned/connected load, Security Deposit paid	
2	Copy of Test Report of the electrical installation given by the Electrical Contractor in respect of individual meters.	
3	Single Line Diagram of completed Electrical Installation	
4	Instructions / Troubleshooting chart in respect of the use, limit of maximum load, operation, safety of Electrical Installation precautions to be taken while making changes in existing installation.	
5	Users' responsibilities – Equipment to be connected to fixed wiring compliant with Standards in respect of safety, THD, EMI, no overloading, no interfering with the installation without LEC, obligations in respect of periodic inspection to be carried out as per CEA Reg. 30.2010 etc.	
6	Emergency contacts in respect of any possible problem with Electrical installation.	
Handed over:		Taken over
Promoter	LEC	Owner
Stamp	Stamp	[Name] Date

ANNEXURE N-2 – Checklist for Handing-Over Documents to the owner's Society / Association

Sr. No.	Document	✓ or X
1	Load sanctioned letter of Electric Supply Company	
2	Copies of the payments made to the Supply Company, towards proving supply	
3	Copy of Agreement with Supply Company.	
4	Electrical Service Connection papers in respect of common energy meter, sanctioned/ connected load, Security Deposit paid.	
5	Single line diagram from the tapping point of service cable to the point of supply (incoming terminal of consumers switch/MCB installed near energy meter).	
6	Copy of Test Report of the electrical installation given by the Electrical Contractor in respect of common meters.	
7	i. Copies of the approvals/permissions/licenses received from the authorities in respect of, Generating set/s (CEA Reg. 32:2010) High-rise building (CEA Reg. 36:2010) HT installation (CEA Reg. 43:2010); if installation is owned by consumer/s Lift/s (Rule 5, Mah. Lift Rules)	
8	Warranties/Guarantees and initial AMC's of Lift/s, genset, UPS and batteries and also in respect of installation handed over to the Supply Company etc. as per applicable.	
9	Instructions in respect of maintenance and operation of water pump, Lift, EV charging equipment and handling emergency. Telephone numbers of emergency services.	
10	ii. List of liabilities, responsibilities to be undertaken: • Maintaining electrical installation (related to common facilities like lights, water pump, fire fighting, common facility of EV charging equipment), in good condition so as to cause no danger. • Renewing AMC's in respect of genset, lifts after defect liability period. Due dates shall be given. • Safeguarding electrical installation belonging to the Supply Company in the premises, e.g., equipment in the Meter Room. • Communicating with the Electrical Inspector within 24 hours in respect of any electrical accident. • Any electrical related work to be done only through a license/permit holder person. • Obligations in respect of periodic inspection as per the CEA Reg. 30:2010	
Handed over		Taken over
Promoter Stamp	LEC Stamp	Secretary/ Office bearer of Society /Association Stamp & Date:

Attachment - A to Instructions under Annexure

N

Annex D (informative) [IEC 60364-5-56:2018]




Figure D.1 – Fire switch installation

Attachment - B to Instructions under Annexure 3.13

Annex A [Ref. IS 17505:2020]

APPLICATION OF FS CABLE

Sl. No. (1)	System Description (2)	Cable Fire Rating Required (°C) (3)	Time for which System Should Withstand (Minutes) (4)
i)	Fire pumps	FS (950/FWS)	180
ii)	Pressurization	FS (950/FWS)	180
iii)	Smoke venting including its ancillary systems, such as dampers and actuators	950	60
iv)	Fire-fighting shaft (staircase, lift, lift lobby)	FS (950/FWS)	180
v)	Fireman's lifts (including all lifts)	FS (950/FWS)	180
vi)	Exit signage lighting	950	120
vii)	Emergency lighting	950	120
viii)	Fire alarm system		
	a) Conventional (zone-based system)	650	60
	b) Intelligent addressable system	650	60
ix)	Public address (PA) system (related to emergency voice evacuation and annunciation)	650	60
x)	Magnetic door hold open devices	650	60
xi)	Lighting in fire command centre and security room	FS (950/FWS)	180

Attachment - C to Instructions under Annexure N

Table 12 Cross-section of Protective Conductor

Cross sectional area of Phase Conductor of the Installation S mm ²	Minimum Cross-Sectional Area of the Corresponding Protective Conductor S_p mm ²
(1)	(2)
$S \leq 16$	S
$16 < S \leq 35$	16
$S > 35^*$	See 17.2.2.1

* For these sizes alternatively formula $S/2$ may be used as per IS 732 Table 14

Cl. 17.2.2.1 of IS 3043

The cross-sectional area shall be calculated such that the current density value determined by the following formula is not exceeded (applicable only for disconnection times not exceeding 5s).

$$S = \frac{I}{k} \sqrt{t}$$

Where,

S = cross-sectional area, in square millimeters.

I = value (ac, rms) of fault current for a fault of negligible

impedance, which can flow through the protective device, in Amperes;

t = operating time of the disconnecting device, in seconds; and

NOTE — Account should be taken of the current-limiting effect of circuit impedances and the limiting capability (joule integral) of the protective device.

k = factor dependent on the material of the protective conductor, the insulation and other parts, and the initial and final temperatures. Values of k for protective conductors in various use or service for $t = 1s$ and $3s$ respectively are given in the following table which applies for insulated conductors or bare conductors touching other insulated conductors (for other conditions see Table 11 from IS 3043:2018).

Insulation	Copper			Aluminium			Steel		
	PVC	Butyl Rubber	XLPE/EPR	PVC	Butyl Rubber	XLPE/EPR	PVC	Butyl Rubber	XLPE/EPR
1 s current rating in A/mm ² (k_1)	136	160	170	90	106	112	49	58	62
3 s current rating in A/mm ² (k_3)	79	92	98	52	61	65	28	33	36

ANNEXURE



Instructions to the Electrical Professional/Engineer/Consultants, Contractors, Stakeholders for providing information in the Test Report for high-rise buildings.

The Central Electricity Authority, an apex body monitoring safety in respect of electrical supply and installations, has given the Forms I, II, III of Inspection for electrical installation in the CEA (measures relating to Safety and Electric Supply) regulations 2010. These correspond to installations having voltage up to 250V (1-ph installations), 415V (3-ph installations) and HT installations above 1kV (e.g., 11kV, 22kV, 33kV and further EHV) respectively. The forms as mentioned above are generic in nature. The National Electrical code classifies High-rise buildings under a special category (Ref. NEC 2022 Part 3 Sec. 22). In accordance with this, special parameters apply to such buildings. So, considering the high risk imposed due to the height of the building, emergency operations like evacuation and special requirements in respect of electrical installations, importance of supply integrity during emergencies like fire for the operation of critical services, there has been a need for a specific format of test report pertaining to electrical works. The instructions given below will help to provide information.

1. Declarations to streamline responsibilities of the stakeholder(s) – **Part-I**
2. Appointment of Licensed Electrical Contractor – **Part-II**
3. Checklist to verify conformation with standards, codes, and regulations – **Part-III**

PART-I: Forms of Declarations in respect of electrical work in High-rise buildings

1. Design – It is considered to be a foundation of electrical installation work and concerned persons; the designer, who may be a MEP consultant or an independent electrical consultant or an electrical contractor; his declaration in respect of design will decide his accountability for related aspects of design. The design comprising drawings, layouts, parts of electrical installation with design capacity of various material components, their specifications shall include method of construction also.

Note – Where design is prepared by the person other than the electrical contractor such as MEP consultant/electrical consultant, the contractor shall check conformation with standards, codes, regulations, etc., applicable in that regard and shall sign as a token of such consent.

Since there is no regulatory framework for giving accreditation to the electrical consultant, qualification and experience shall be given by such a person.

Note 1 – It shall be noted that the various points under the checklist are enlisted for verification at the time of completion. From these points, the following points require consideration from the design stage.

Part-I Forms of Declaration

Form-1 Declaration for Design

Part-II Particulars of Electrical Contractor

Electrical Contractor Details

Part-III Verification

A Architectural Planning and Civil Construction – Electrical Requirements

§ 1, 2, 3, 7, 10

B-1 Electric Supply – Details and Supplier's installation requirements

§ 2, 5, 6, 11, 13, 14

B-2 Electric Supply – Standby supply arrangement and installation Requirements

§ 1, 2, 3, 4, 5

B-3 Earthing Arrangements

§ 1, 4

C Electrical Installation – Applicable for installations belonging to individual and common utility services

1. General/common points

§ 1.1, 1.2, 1.3, 1.4, 1.5 A (1 to 8), 1.5 B (1 to 3), 1.6, 1.7, 1.8 (1, 2)

2. Construction – Required skill set and expertise are a very important part of workmanship. Continuous supervision and surveillance are necessary for the construction to be monitored from start to end. To get quality work output, IS 732 recommends verification during erection. Hence the declaration in respect of construction is necessary to decide responsibility for related aspects of construction work of electrical installation, it

is recommended that the concealed portion of work which remains hidden at the time of completion and not available for visual inspection, shall be certified before being concealed.

Note –1. The name of the contractor appearing in Part-II shall match with the person/agency giving this declaration.

2. Where there is a change of contractor before completion of the project, the outgoing contractor shall prepare a report of the stage of work completed and give a declaration for that portion of work. The new contractor shall agree and countersign such a report as a mark of

acceptance. In case of any non-agreement in respect of such a report, the new contractor shall report it to the appointing authority and take responsibility to clear defects, if any, from the previously executed work.

Note 2

It shall be noted that the various points in the checklist are enlisted for verification at the time of completion. From these points, the points requiring observance from the design stage are given in Note 1. During construction it is necessary that work is being executed as per the design. In addition to these points, the following points also need monitoring during the construction stage.

Part-I Forms of Declaration

Form-2 Declaration for Construction of Electrical Installation.

Part-II Particulars of Electrical Contractor

Electrical Contractor Details to be provided when there is a change of contractor in between the progress of work

Part-III Verification

A Architectural Planning and Civil Construction – Electrical Requirements

§ 4, 5, 8, 9

B-1 Electric Supply – Details and Supplier's Installation Requirements

§ 6

B-2 Earthing Arrangements

§ 2

C Electrical Installation – Applicable for installations belonging to individual and common utility services

1. General / common points

§ 1.8 (3)

2. Inspection and Testing – To decide whether an installation conforms to statutory provisions, standards, codes and is safe for use, verification which includes inspection and testing, is the pre-final step before the installation can be allowed for beneficial use (refer IS 732 § 6 Verification). Signed report of concerned persons carrying out the task is considered as an authentic document and

hence streamlines related responsibilities. The person carrying out tests shall be equipped with all required testing instruments of appropriate class and calibration certificates.

Note – Preference shall be given to third party testing

PART-II: Particulars of Electrical Contractors and Installations

- 1 It is recommended that the appointment of the electrical contractor shall be made at the planning stage to check the aspects of electrical installation in architectural plans
- 2 The contractor shall have a valid license during 555 the period of installation and till completion and testing. In case of change of contractor during the project, appropriate record of status / completed/ in progress portion of installation work shall be properly maintained with handing over and taking over notes. These shall be produced on demand.
- 3 It shall be noted that the test report is to be submitted separately for each service cable providing supply to the individual meter rooms. If within a meter room there are two service cables serving two groups of meters, then there shall be two separate test reports.
- 4 Give details of the wing of the building (if applicable).
- 5 Give details of floors distinctively, e.g., parking/ basement(s), upper floors
- 6 State height of building as per definition Cl. 2.6 Part 4 of NBC/UD DCPR
- 7 Give details of number of flats categorically, with typical area and respective numbers e.g., 450 sq.ft (1BHK) 20 Nos., 700 sq.ft. (2BHK) 24 Nos, etc. (area may be mentioned in m2 instead of sq.ft.)
- 8 This form shall be jointly signed by the promoter / developer and the electrical contractor as the information in the form pertains to both of them.
- 9 For any subsequent change in contractor, a separate form as given in Part-II, duly filled with all details shall be kept on record and submitted as and when required by an authority.

PART-III: Verification (Inspection and Testing)

A. Architectural Planning and Civil Construction – Electrical Requirements

This phase of the project on which the design and construction of electrical work relies, needs attention right from the planning stage. The developer/project manager shall appoint an electrical contractor in this regard at the beginning level. Persons involved in the design and construction of electrical installation shall check if adequate provisions are considered in architectural plans and civil work. § 1 to 9 as enlisted are most common but these provisions shall not be considered to be limited to them. §10 requires the transformer to be filled with K class insulating liquid for cooling of the transformer. Other points not covered in the list may be given in addition. If any contravention was likely to have occurred or ultimately existed even after necessary communication to the concerned, it shall be maintained as record and produced to decide responsibility.

Note – Option from Yes/No/NA, shall be ticked. Where necessary, justification may be given.

B-1 Electric Supply – Details and Supplier's installation requirements

Regulations mandate some obligations from electricity supply providers, persons carrying out electrical installation and the user. Compliance of the same shall be given in this section.

Note – In case of a user, the following points shall be noted. Electrical supply and installation is an important building service forming a part of the deliverables. It is also one of the points of compliance for issuing an occupancy certificate. When the user takes possession, the building is complete with electrical services. Hence, the responsibility of the work completed and the obligatory compliances, prior to taking over possession rests with the supplier of electricity, developer and an electrical contractor appointed by him.

Pointwise guidelines, information, examples to furnish details

- 1 Example: 1-ph meter connections 14 Nos. 4 kW each; 3-ph meter connections 7 nos. 10 kW each. Total load 125 kW

Note – Information is to be provided per service cable (inclusive parallel run with two cables feeding one group of meters). If two or more service cables provide supply in one meter room for two or more groups of meters independently, test reports shall be separate.

- 2 Example: 3.5x95 XLPE Aluminium cable in trench
- 3 Check in accordance with the sanctioned load
- 4 It is helpful in deciding breaking capacities and tripping time of breakers.

- 5 There shall be adequate length, width, and height to accommodate meters without overcrowding. Meter board at a minimum of 0.7m from the ground, 1m clearance in front and maximum height 1.8 m. of meters. All switchgears in easily accessible positions. Suitably cross ventilated.
- 6 Meter room shall be safe under all climatic conditions without any seepage, leakage accumulation of water, have restricted entry, and shall serve no other purpose than metering and housing allied electric supply equipment, cabling, etc. The area in the vicinity of the meter room, its use and nearby situation shall not endanger safety and entry approaches (e.g., use as a storeroom, nearby storage of inflammable material, hindrance of parked vehicles). Route of outgoing mains from the point of supply to vertical cable shaft if not closely adjacent, shall be safe from all external influences, with method of construction as per standards.
- 7 Multiple neutral earthings are helpful in maintaining the value of Z_n within limits, satisfactory operation of protective devices, and mitigate chances of floating neutral. The contractor is supposed to give only the status.
- 8 Earthing of neutral point of service cable in consumers premises is to ensure Z_n within limits, satisfactory operation of protective devices, mitigate chances of floating neutral. The contractor is supposed to give only the status.
- 9 Regulations stipulate provision of earthed terminal which is to conform to the TNC-S or TNS system. This obligation applies to the supplier. The contractor is supposed to give only the status.
- 10 Provide status about consumers' earth terminal, e.g., Yes. Resistance (R_e) 2 ohms
- 11 Example: Yes, $Z_n = 0.8$ ohms
- 12 Example: Yes, 200A 25kA MCCB for Building Supply (excluding critical supply)
- 13 For clarity refer **Attachment A**. Check the concept of a fire switch. Confirm separation of critical load requiring supply integrity during emergency before placing the fire switch. Example: Yes, 125A 25kA MCCB for Emergency/Critical Services Supply

B-2 Electric Supply – Details of standby supply arrangement and installation requirements


Provision of standby supply arrangement with suitable arrangement like gensets (or UPS for No break) is necessary for the operation of emergency services.

- 1 List of emergency services shall be given under column 2. It may comprise escape routes, lighting and signages, fire pumps, PA system, pressurization system, smoke venting, Fire-man's lift, security systems (door locking/opening), etc. Load shall be divided depending on allowable changeover/ supply restoration time.
- 2 Aggregate load under each category shall be considered to decide capacity(ies) of gen-set(s). Accordingly, the capacity of gen-set(s) provided shall be mentioned.

- 3 IS/ISO 8528-1 shall be followed to decide the capacity of the genset.
- 4 IS/ISO 8528-12 shall be followed to decide changeover time for the restoration of supply.
- 5 It is necessary to choose the location of the genset to be sufficiently away from other installations and to be secured to maintain trouble-free operation during an emergency.
- 6 As per applicability, the status of permission from the Electrical Inspector shall be mentioned. If permission is accorded, reference number shall be mentioned.

B-3 Earthing arrangements

For earthing systems, the guidelines given in respective clauses of IS 3043 shall be followed. Guidelines for the provision of the Main Earthing Terminal is as the Typical Diagram given below:



C-1 Electrical Installation-

Installations belonging to individuals and serving common utility services.

This section is applicable for electrical installations in individual premises as well as in common/public areas and within the possession of office bearers of society and associations of owners. While giving test reports, points not applicable in respect of individual or common installations may be marked as 'NA'. For example, UG cable work may not be applicable in respect of individual flat owners.

C-1.1 Wiring type: Wiring installations that are partly open and partly concealed (in walls/partitions/above false ceiling/below the floor or the ground), for the same service shall be considered as hybrid. Wiring of different categories for different circuits shall be considered as mixed.

C-1.2 Material used: In case of non-ISI material (standard not published by the BIS), but in conformation with international standards, the list shall be provided for such material with a corresponding international standard. In absence of both, separate lists shall be attached.

C-1.3 Wiring /Cables:


Indoor use:

For high-rise buildings, cables recommended for general use as per NEC are FRLSH or HFFR. Up to 16 mm² size, copper conductors have been recommended in NBC and NEC.

For determination of cross-section, Annex S or T of IS 732 needs to be observed.

The cross-sectional area of conductors shall be determined for both normal operating conditions and for fault conditions according to:

- a. their admissible maximum temperature;
- b. the admissible voltage drop;
- c. the electromechanical stresses likely to occur due to earth fault and short-circuit currents;
- d. other mechanical stresses to which the conductors can be subjected;
- e. the maximum impedance with respect to the functioning of the protection against fault currents; and
- f. the method of installation—for guidance following the diagram shall be observed.



Note – The items listed above concern primarily the safety of electrical installations. Cross-sectional areas greater than those required for safety, may be desirable for economic operation.

For cross-section above 16 mm², specify the conductor type (copper or aluminium) and the size.

Note – The recommendations above concern primarily the safety of the electrical installations in conjunction with inherent properties of the metal in relation with thermal management. One up size of conductor cross-section is recommended to ensure longer life of cables and accommodate/take care of future additions to certain extents.

For outdoor use:

Armoured cables shall be used for street, garden, or similar lighting. The minimum depth of the cable below ground level shall be 750mm for LT, 900mm for 11kV and 1050mm for 22/33 kV, it needs cushioning below and above with rammed soil/sand and shall be mechanically protected with bricks/ blocks or half round / full round pipe of suitable strength.

For critical services requiring supply integrity:

Systems required to be operative under emergency situations (like evacuation during fire) shall be considered as critical services and cables used shall be in accordance. Also check Annex A of IS 17505 (See Attachment B).

C-1.4 Conduit/casing: For proper dissipation of heat (considering maximum temperature rise allowed) the space factor or fill factor (corresponding to internal cross section of conduit/trunking) shall not exceed 53%, 31%, 40% for single, two, more than two cables respectively as per NEC 2022.

C-1.5 Distribution:

A. For installations belonging to individual and common services

1. Single Line Diagram - Typical SLDs depending on distribution pattern and load corresponding to flat area/ rooms/load, shall be prepared. They shall provide following details:

- electrical distribution of installation from meter to final branch circuit feeding supply to switch-board;
- distinct marking of circuits with standby supply arrangement through inverter / UPS;
- sizes of mains, sub-mains, circuits, protective earth conductor;
- details of DBs (types, ways);
- details of incoming and outgoing MCBs (poles, rating A, kA, type);

नहारे

17A-12
/20

- vi. details of RCD(s) (poles, rating mA, A);
- vii. details of other protections (e.g., SPD(s), AFDD);
- viii. load on individual final branch circuits, sub-mains, mains, at every DB, main switches;

- ix. SLD shall show identification marks to each circuit, DB, and switch board.

NOTE – If the SLD having prior approval differs with the 'as built' SLD, reasons shall be mentioned.

2. Division of Circuits - The NEC recommends an independent circuit for each room with a door to have proper control in case the door is locked. Also, separate circuits for lighting, power and circuits having standby power sources.

The limits set by the NEC on maximum load and number of points need to be observed.

3. Cables - Cable cross-sections shall be suitably selected to carry the load continuously without rise in temperature and satisfying requirements as per C-1.3. There shall be intercorrelation between the ratings of MCBs and design current-carrying capacity under particular situations. If current is 12A, the corresponding MCB will be 16A. So, the cable shall have the capacity to carry a minimum of 16A current instead of 12A.

4. Over-Current Protection Device (OCPD) - It shall be noted that for the same cross section cable capacity gets reduced by 50% depending on the situation at the place of installation and other derating factors. So, the MCB shall be selected in accordance with a rating not less than the design current which may vary for the same cross section of cable. The MCB shall also have a suitable breaking capacity of more than the anticipated short-circuit current. The selection of MCB type shall be in accordance with the load pattern. Where there is high inrush current, type B MCB will not be suitable. There shall be tripping coordination at different levels. The MCB of the corresponding final branch circuit shall trip first and the main MCB shall trip at the end.

5. Protection from leakage currents/electric shocks - As per CEA Reg. 42:2010, there shall be provision of RCD, the maximum earth leakage threshold for tripping of which shall not exceed 30mA for domestic connections and 100mA for all other installations.

NOTE – It is also recommended to provide RCD of 300mA at source to mitigate chances of initiation of fire due to heat generated by continued leakage current.

To avoid complete blackout, RCDs on local DBs/per phase isolation in TPNDs is recommended, which helps to locate fault and avoids complete blackout.

6. Protection from Surges - Provision of Surge Protection Device (SPD) prevents risks of transient over voltages and surge currents from lightning, switching surges or over voltages. Proper test class (I/II/III) shall be selected at precise points in the electrical distribution.

7. Protection from Electrical Arc Flashes - Arc Flash Detection Device (AFDD) detects initiation of arc within

electrical distribution at an early stage and trips the circuit before such occurrence. Its use is recommended in high-rise buildings above a certain height by the NEC. Such a device is of great help in preventing fire initiation due to electrical short circuit.

8. Distribution Boxes/Consumer's unit During an emergency when it is necessary to disconnect the supply immediately, immediate access to such a device is very important. Hence DBs shall be located in accessible positions without aid of any stool or ladder.

Marking of DBs and the circuits within, with provision of ferrules in the cable termination is very important from the point of view of maintenance and avoiding accidents.

9. Terminations - Loose terminations always lead to the creation of hot spots and result in initiation of fire. So, it is most important to have proper initial and periodical checks for proper tightening, and to check that there are no loose strands around.

B. Specific requirement in respect of common services in buildings

- 1 As per CEA Regulations provision of a switch to isolate complete supply of buildings is necessary. This point in most of the cases comes before the point of supply for the individual meter. Its provision shall either be made by the supplier or the building owner in coordination with the supplier.
- 2 For provision of such a switch the circuit diagram as given in **Attachment A** shall be followed.
- 3 Critical services depending on electrical supply have been identified in IS 17505 Annex A given under **Attachment B** (it shall be followed as per applicability but not be considered as being limited to).

C-1.6 Inverter/UPS: The load to be connected on the inverter supply – there shall be an independent circuit with phase and separate neutral conductor. The neutral from this circuit shall not be looped with any other circuit. Under the checklist, NA option shall be chosen if there is no inverter supply with battery backup.

C-1.7 Point wiring: The NEC provides guidelines in respect of minimum number of points depending on use of area / utility of room and the locations of switchboards for operation. Inconvenient locations and shortfall in number of points leads the user to make changes in existing installation after taking-over possession. Such subsequent work often becomes the reason for the installation becoming unsafe. Hence to mitigate possibilities, it is necessary to follow the guidelines given in the NEC. Choose an option from Yes/No or NA as observed in inspection.

C-1.8 Earthing:

- 1 Refer Attachment C to check the recommended sizes of the protective earth (PE) conductor.
- 2 Equipotential bonding is necessary to maintain exposed conductive parts and extraneous

conductive parts at the same potential. It helps to strengthen earth fault, leakage protection through automatic disconnection of supply, envisaged to prevent a touch voltage from persisting for such a duration that would be harmful to human beings.

- 3 Continuity of protective earth conductor between different points and to the MET is the most important requirement for the operation of protection. Its resistance shall not exceed 0.2 ohms.
- 4 Value of Z_S ($Z_e + R_1 + R_2$) needs to be sufficiently low to operate protective devices within the stipulated time.

C-2 Electrical Installation details and test results (List – meter-wise):

The details to be provided in this section shall be separate in respect of each service connection. The number of service connections will depend on the number of common meters, plus the number of flats within the building. It will be necessary for the testing person to follow the recommendations from Annex SS of IS 732:2019 and maintain a detailed DB-wise test results sheet ready (See Attachment D). The DB mentioned in the test result shall correspond to and be traceable in the SLD. These test results shall form the basis of the summarized information to be provided in the form given under 2.1

C-2.1

- 1 Mention Flat No. and floor, e.g., 404 first digit showing Floor No. as 4 and next digits showing flat no. 04 or alternatively 04, 4th floor. Also mention wing if applicable. In case of a common meter, mention the list of services for which supply is provided, e.g., domestic water pumps, lifts, common lighting, fire-fighting, etc.
- 2 Mention area either in sq. ft or sq. m
- 3 Mention the material (copper/aluminium) and cross-sectional area (mm²) of the line, neutral and protective earth conductor for mains (cable between point of supply in meter room and main DB); e.g., 4x6Cu+6ECu, i.e., 4 conductors for 3 phases and 1 neutral (R Y B N) of size 6mm² cross section copper and 1 conductor of size 6 mm² copper for protective earth.

- 4 OCPD – Over Current Protective Device, mention current rating, breaking capacity and poles; e.g., 32A FP MCB or 16A, 10kA DP MCB.
- 5 RCD (ELCB / RCCB) – Residual Current Device, RCBO – Residual Current Operated Circuit Breaker with over-current protection; for RCD mention nominal current rating in A, leakage current rating in mA and poles; e.g., 32A FP – 30mA. For RCBO, mention breaking capacity in addition. Test operation of RCD and mention Ok/Not Ok
- 6 IR Test– Insulation Resistance Test shall be taken with 500V DC Tester at origin/point of supply between L-N, L-E, N-L for 1-ph supply, for 3-ph supply consider L1, L2, L3 in place of L and between L1-L2, L2-L3, L1-L3
- 7 Continuity Test– shall be conducted to measure resistance, R1 – resistance of line conductor and R2 – protective earth conductor (PE/CPC); between point of origin of supply to the point of utility outlet. Combined R1+R2 values may also be given.
- 8 Earth Fault Loop Impedance (Z_e) which is the combined value of $Z_e+(R_1+R_2)$ shall be tested with an appropriate instrument at every DB. This test shall be carried out and the highest value shall be mentioned.
- 9 Prospective Fault Current (I_{pf}) / Short Circuit Current (I_{sc}) – From results, the highest value shown by the respective test instrument shall be mentioned.
- 10 Polarity Test – whether all switches (1-way / 2-way) are installed in online conductors only. In case of plug socket outlets, check if the line conductor is connected to the right side of the socket only. Mention Tested OK/not OK.
- 11 Neutral Looping – check if there is an independent neutral for individual circuits and the looping of neutral is restricted within the points of the respective circuit only. Mention Tested OK / not OK.

C-2.3 Handing-Over checklist to each individual consumer shall be as per the Annexure E-12 These checklists shall be ready with details.

महाराष्ट्र प्रादेशिक व नगर रचना अधिनियम, १९६६ चे
कलम १५४ चे तरतुदीन्वये निदेश.

(मंजूर एकत्रिकृत विकास नियंत्रण व प्रोत्साहन
नियमावलीमधील (UDCPR) विनियम ५.३.१ हा Area
within Ratnagiri District हा विशिष्ट विनियम
अधिक्रमणित करण्यासाठी व त्याऐवजी रत्नागिरी जिल्ह्याची
सुधारित प्रारूप प्रादेशिक योजना प्रसिध्द होईपर्यंत रत्नागिरी
जिल्ह्यासाठी फ्री झोन कायम ठेऊन दि.०२.१२.२०२० रोजीचे
अधिसूचनेनुसार रत्नागिरी जिल्ह्यास UDCPR लागू
करण्याबाबत उक्त अधिनियमाचे कलम १५४ चे तरतुदीन्वये
निदेश.)

निदेश

महाराष्ट्र शासन
नगर विकास विभाग
मंत्रालय, मुंबई - ४०० ०३२.
दिनांक : ०१.०३.२०२४

महाराष्ट्र प्रादेशिक नियोजन व नगर रचना अधिनियम, १९६६

क्र.टिपीएस-१८२३/व्हाआयपी-५३/प्र.क्र.९४/२०२३/निदेश/नवि-१३ :-

ज्याअर्थी, महाराष्ट्र शासनाने राज्यातील बृहन्मुंबई महानगरपालिका, व काही नियोजन प्राधिकरणे वगळता
उर्वरित सर्व नियोजन प्राधिकरणे व प्रादेशिक योजना क्षेत्रांकरिता लागू करावयाच्या एकत्रिकृत विकास नियंत्रण व
प्रोत्साहन नियमावलीस (युडीसोपीआर) (यापुढे ज्याचा उल्लेख "उक्त मंजूर नियमावली" असा करण्यात आलेला
आहे) महाराष्ट्र प्रादेशिक नियोजन व नगर रचना अधिनियम, १९६६ (यापुढे ज्याचा उल्लेख "उक्त अधिनियम"
असा करण्यात आलेला आहे) मधील तरतुदीनुसार, शासन अधिसूचना क्र. टिपीएस-१८१८/प्र.क्र.२३६/१८/ वियो.
व प्रायो./कलम ३७ (१कक) (ग) व कलम २०(४)/नवि-१३, दि.०२/१२/२०२० अन्वये मंजुरी दिली असून ती
दि.०३.१२.२०२० पासून अंमलात आली आहे :

आणि ज्याअर्थी, उक्त मंजूर नियमावलीस शासनाने पूरकपत्र क्रमांक टिपीएस-१८१८/प्र.क्र.२३६/
१८/कलम ३७(१कक) आणि कलम २०(३) (भाग-१) पूरकपत्र /नवि-१३, दि.१४.०१.२०२१ अन्वये शासनाने
रत्नागिरी जिल्ह्याचे प्रादेशिक योजना क्षेत्रास उक्त मंजूर नियमावलीमधून (UDCPR) वगळले आहे. तथापि, प्रदीर्घ
कालावधीसाठी उक्त मंजूर नियमावलीचा लाभ रत्नागिरी जिल्ह्यास घेता येत नसल्याने रत्नागिरी जिल्ह्याची
सुधारित प्रारूप प्रादेशिक योजना प्रसिध्द होईपर्यंत दि.०२.१२.२०२० रोजीचे अधिसूचनेनुसार रत्नागिरी रत्नागिरी
जिल्ह्यासाठी उक्त मंजूर नियमावली (UDCPR) पुनःच लागू करण्यात यावी, अशी लोकप्रतिनिधी यांची
शासनाकडे मागणी आहे :



आणि ज्याअर्थी, उक्त विनंती विचारात घेता, व सार्वजनिक हिताचे दृष्टीने सोबतच्या परिशिष्ट-अ येथे नमूद केल्यानुसार उक्त मंजूर UDCPR मधील विनियम ५.३.१ Area within Ratnagiri District हा विशिष्ट विनियम अधिक्रमणित करून त्याऐवजी रत्नागिरी जिल्ह्याची सुधारित प्रारूप प्रादेशिक योजना प्रसिध्द होईपर्यंत दि.०२.१२.२०२० रोजीचे अधिसूचनेनुसार रत्नागिरी जिल्ह्यास UDCPR लागू करणे आवश्यक आहे, असे शासनाचे मत झाले आहे;

त्याअर्थी, शासन याद्वारे उक्त अधिनियमाचे कलम १५.४(१) अन्वये प्राप्त अधिकारात खालीलप्रमाणे निदेश देत आहेत.

शासन निदेश

- I. रत्नागिरी जिल्ह्यास एकत्रिकृत विकास नियंत्रण व प्रोत्साहन नियमावलीमधील (युडीसीपीआर) तरतुदीची अंमलबजावणी तातडीने लागू करण्याच्या दृष्टीकोनातून तसेच सार्वजनिक हिताच्या दृष्टीने रत्नागिरी जिल्ह्याची सुधारित प्रारूप प्रादेशिक योजना प्रसिध्द होईपर्यंत रत्नागिरी जिल्ह्यासाठी प्री झोन कायम ठेऊन सदर क्षेत्राकरिता एकत्रिकृत विकास नियंत्रण व प्रोत्साहन नियमावलीमधील (युडीसीपीआर) तरतुदी लागू करण्यात येत आहेत.
- II. सदरचे शासन निदेश लागू लागू होतोल.
- III. सदरचे निदेश शासनाचे संकेतस्थळ www.maharashtra.gov.in (कायदे/नियम) वर उपलब्ध राहील.

महाराष्ट्राचे राज्यपाल यांचे आदेशानुसार व नावाने



(डॉ.प्रतिभा भदाणे)
सह सचिव, महाराष्ट्र शासन.

प्रत कार्यवाहीसाठी :

१. जिल्हाधिकारी, रत्नागिरी.
२. संचालक, नगर रचना महाराष्ट्र राज्य, पुणे.
३. सहसंचालक, नगर रचना, कोकण विभाग, कोकण भूवन, कक्ष क्र.३०५, सी.वी.डी. वेंलापूर, नवी मुंबई - ४००६१४.
४. सहायक संचालक, नगर रचना रत्नागिरी शाखा कार्यालय, रत्नागिरी.

प्रत माहितीसाठी :

१. मा. मुख्यमंत्री महोदयांचे अपर मुख्य सचिव, मंत्रालय, मुंबई.
२. मा.उप मुख्यमंत्री महोदय यांचे सचिव, मंत्रालय, मुंबई.
३. मा. विरोधी पक्षनेता, विधानपरिषद / विधानसभा, महाराष्ट्र विधानमंडळ सचिवालय.
४. मा. सभापती, महाराष्ट्र विधानपरिषद / विधानसभा, महाराष्ट्र विधानमंडळ सचिवालय.
५. मा. विरोधी पक्षनेता, विधानपरिषद / विधानसभा, महाराष्ट्र विधानमंडळ सचिवालय.

रत्नागिरी प्रादेशिक योजना संदर्भाने शासनाने दि.१४.०१.२०२१ रोजी निर्गमित केलेले पूरकपत्रामधून रत्नागिरी जिल्ह्याशी संबंधित मजकूर अधिक्रमणित करण्यास व रत्नागिरी जिल्ह्याची सुधारित प्रारूप प्रादेशिक योजना प्रसिध्द होईपर्यंत रत्नागिरी जिल्ह्यासाठी फ्री झोन कायम ठेऊन सदर क्षेत्राकरिता एकत्रिकृत विकास नियंत्रण व प्रोत्साहन नियमावलीमधील (युडीसीपीआर) तरतुदी UDCPR लागू करण्यासंबंधी सुधारित पूरकपत्र

महाराष्ट्र शासन
नगर विकास विभाग

शासन शुध्दीपत्रक क्र.टिपीएस-१८२३/व्हायपी-५३/प्र.क्र.१४/२०२३/नवि-१३.

मादाम कामा मार्ग, हुतात्मा राजगुरु चौक,
चोंथा मजला, मंत्रालय, मुंबई-४०० ०३२.

दिनांक : ०१.०३.२०२४

सुधारित पूरकपत्र

संदर्भ : - शासन निर्णय क्र.टिपीएस-१८१८/प्र.क्र.२३६/१८/कलम ३७(१कक) व कलम २०(३)(भाग-१)/
पूरकपत्र/नवि-१३, दि.१४/०१/२०२१

आणि ज्याअर्थी, रत्नागिरी-सिंधुदुर्ग जिल्ह्यांची प्रादेशिक योजना शासनाने दि.२३.१२.१९८७ रोजी मंजूर केली असून ती दि.१५.०२.१९८८ पासून अंमलात आली आहे. या योजनेनुसार रत्नागिरी जिल्ह्याच्या क्षेत्राकरिता विस्तृत प्रस्तावित जमिन वापर नकाशा नाही;

आणि ज्याअर्थी, महाराष्ट्र शासनाने राज्यातील वृहन्मुंबई महानगरपालिका, व काही नियोजन प्राधिकरणे वगळता उर्वरित सर्व नियोजन प्राधिकरणे व प्रादेशिक योजना क्षेत्रांकरिता लागू करावयाच्या एकत्रिकृत विकास नियंत्रण व प्रोत्साहन नियमावलीस (युडीसीपीआर) (यापुढे ज्याचा उल्लेख "उक्त मंजूर नियमावली" असा करण्यात आलेला आहे) महाराष्ट्र प्रादेशिक नियोजन व नगर रचना अधिनियम, १९६६ (यापुढे ज्याचा उल्लेख "उक्त अधिनियम" असा करण्यात आलेला आहे) मधील तरतुदीनुसार, शासन अधिसूचना क्र. टिपीएस-१८१८/प्र.क्र.२३६/१८/ वियो. व प्रायो./कलम ३७ (१कक) (ग) व कलम २०(४)/नवि-१३, दि.०२/१२/२०२० अन्वये मंजुरी दिली असून ती दि.०३.१२.२०२० पासून अंमलात आली आहे ;

आणि ज्याअर्थी, शासन निर्णय क्र.टिपीएस-१८१८/प्र.क्र.२३६/१८/कलम ३७(१ कक) व कलम २०(३) (भाग-१)/पूरकपत्र/नवि-१३, दि.१४/०१/२०२१ अन्वये उक्त नियमावलीस शासनाने पूरकपत्र निर्गमित केले असून उक्त पूरकपत्रान्वये शासनाने रत्नागिरी जिल्ह्याचे प्रादेशिक योजना क्षेत्रास उक्त मंजूर नियमावलीमधून वगळले आहे. तथापि, प्रदीचे कालावधीसाठी उक्त नियमावलीचा लाभ रत्नागिरी जिल्ह्यास घेता येत नसल्याने रत्नागिरी जिल्ह्याची सुधारित प्रारूप प्रादेशिक योजना प्रसिध्द होईपर्यंत दि.०२.१२.२०२० रोजीचे अधिसूचनेनुसार रत्नागिरी रत्नागिरी जिल्ह्यासाठी UDCPR लागू करावे अशी लोकप्रतिनिधी यांची शासनाकडे मागणी आहे ;



आज्ञा त्याअर्थी, सार्वजनिक शिंताळा वृष्टीने रत्नागरी प्रादेशिक योजना संदर्भात शासनात दि.१४.०१.२०२१ रोजी निर्मित केलेले पुरकप्रामाधून रत्नागरी जिल्ह्याशी सर्वाधिक मजकूर अधिकांशीत करण्यात येत असून रत्नागरी जिल्ह्याची सुधारित प्रारंभ प्रादेशिक योजना प्रसिध्द झालेवरून रत्नागरी जिल्ह्यासाठी जो आन कायम ठेऊन सदर क्षेत्राकरिता एकत्रिकृत विकास नियंत्रण व प्रांत्साहून नियमावलीमधील (यु.डी.सी.पी.आर.) तरतुदी UDCPR लागू करण्यात येत आहेत.

प्रतः :-

१. मा. मुख्यमंत्री महादयाधे अपर मुख्य सचिव, मंत्रालय, मुंबई.
२. मा. उपा. मुख्यमंत्री महादय पांचे सचिव, मंत्रालय, मुंबई.
३. मा. विरोधी पक्षनेता, विधानपरिषद / विधानसभा, महाराष्ट्र विधानमंडळ सचिवालय.
४. मा. सभापती, महाराष्ट्र विधानपरिषद / विधानसभा, महाराष्ट्र विधानमंडळ सचिवालय.
५. मा. विरोधी पक्षनेता, विधानपरिषद / विधानसभा, महाराष्ट्र विधानमंडळ सचिवालय.
६. मा. अध्यक्ष, महाराष्ट्र विधानसभा, महाराष्ट्र विधानमंडळ सचिवालय, मुंबई.
७. मा. उपाध्यक्ष, महाराष्ट्र विधानसभा, महाराष्ट्र विधानमंडळ सचिवालय, मुंबई.
८. मा. उपसभापती, महाराष्ट्र विधानसभा, महाराष्ट्र विधानमंडळ सचिवालय, मुंबई.
९. अपर मुख्य सचिव, महसूल व धन विभाग, मंत्रालय, मुंबई.
१०. प्रधान सचिव (नवि-१), नगर विकास विभाग, मंत्रालय, मुंबई.
११. संचालक, नगर रचना तथा सह सचिव, नगर विकास विभाग, मंत्रालय, मुंबई.

१. संचालक, नगर रचना, महाराष्ट्र राज्य, पुणे

१/- सदरचे सुधारित पुरकणव नगर रचना संचालनालयाच्या संकेतस्थळावर प्रसिध्द करण्यात यावे

२. सहसंचालक, नगर रचना, कोकण विभाग, कोकण भुवन, कक्ष क्र. ३०५, सो.बी. डी. बंगलापूर, नवी मुंबई.
३. विभागीय महसूल आयुक्त, कोकण विभाग, कोकण भुवन, नवी मुंबई.
४. निष्काधिकारी, रत्नागिरी,
५. सहायक संचालक, नगर रचना, रत्नागिरी शाखा कार्यालय, रत्नागिरी.

महाराष्ट्र प्रादेशिक नियोजन व नगररचना अधिनियम, १९६६ चे कलम १५४ अन्वये निदेश.
(मंजूर एकीकृत विकास नियंत्रण व प्रोत्साहन नियमावली (UDCPR) चे विनियम क्र.६.१०.१ च्या तरतुदीमधील तक्त्यानुसार महानगर प्रदेश विकास प्राधिकरणास लागू असलेल्या उक्त विनियमातील अनुक्रमांक १ मधील इमारतीच्या केंद्राबाबतच्या तरतुदी (अग्निशमन विभागाच्या मंजूरीप्रमाणे/ना-हरकत प्रमाणपत्रास अनुसरून) राज्यातील महानगर विकास प्राधिकरणामधून नव्याने निर्माण झालेली सर्व नियोजन प्राधिकरणे (नगरपरिषदा/ नगरपंचायती) क्षेत्रासाठी अनुज्ञेय करण्याबाबत...)

महाराष्ट्र शासन

नगर विकास विभाग,

शासन निर्णय क्र. टिपीएस-१८२४/अनौस-३१/२०२४/प्र.क्र.१००/२०२४ नवि-१३,

मादाम कामा मार्ग, हुतात्मा राजगुरु चौक,

चौथा मजला, मंत्रालय, मुंबई ४०० ०३२.

दिनांक : २५.०९.२०२४

संदर्भ :- १. प्रशासक, नगरपंचायत बेसा-पिपळा यांचा शासनास प्रस्ताव पत्र क्र.न.पं. बे.पि./न.र.वो/४२०, दि.२६.०६.२०२३.

२. संचालक, नगर रचना महाराष्ट्र राज्य पुणे यांचा अहवाल पत्र क्र.डिटीपी-३१२४ /न.पं.बेसा-पिपळा/तरतूद क्र.६.१०.१/टिपीव्ही-०२/३३२८, दि.२६.०६.२०२४.

आदेश

महाराष्ट्र प्रादेशिक नियोजन व नगर रचना अधिनियम, १९६६

प्रस्तावना - ज्याअर्थी, महाराष्ट्र शासनाने राज्यातील बृहन्मुंबई महानगरपालिका, व काही नियोजन प्राधिकरणे वगळता उर्वरित सर्व नियोजन प्राधिकरणे व प्रादेशिक योजना क्षेत्रांकरिता लागू करावयाच्या एकीकृत विकास नियंत्रण व प्रोत्साहन नियमावलीस (युडीसीपीआर) (यापुढे ज्याचा उल्लेख "उक्त नियमावली" असा करण्यात आलेला आहे) महाराष्ट्र प्रादेशिक नियोजन व नगर रचना अधिनियम, १९६६ (यापुढे ज्याचा उल्लेख "उक्त अधिनियम" असा करण्यात आलेला आहे) मधील तरतुदीनुसार, शासन अधिसूचना क्र. टिपीएस-१८१८/प्र.क्र.२३६/१८/ वियो. व प्रायो/कलम ३७ (१कक) (ग) व कलम २०(४)/नवि-१३, दि.०२/१२/२०२० अन्वये मंजुरी दिली असून ती दि.०३.१२.२०२० पासून अमलात आली आहे;

आणि ज्याअर्थी, उक्त नियमावलीमध्ये विनियम क्र.६.१०.१ (HEIGHT OF BUILDING) या विनियमाबाबत तरतुदी अंलभूत करण्यात आलेल्या असून (यापुढे ज्याचा उल्लेख "उक्त तरतुदी" असा करण्यात आलेला आहे) उक्त तरतुदीच्या अनुषंगाने राज्यातील महानगर विकास प्राधिकरणामधून नव्याने निर्माण झालेल्या काही नवनिर्मित नियोजन प्राधिकरणांना उक्त तरतुदीची अंमलबजावणी करताना काही अडचणी येत असल्याचे शासनाच्या निदर्शनास आले आहे;



D:\Salunkhe\UD-13\2024\बेसा - पिपळा ngrpr.docx



आणि ज्याअर्थी, राज्यातील महानगर विकास प्राधिकरणामधून नव्याने निर्माण झालेल्या काही नवनिर्मित नियोजन प्राधिकरणांनी (नगरपंचायती/नगरपरिषदा यांनी) त्यांचे कार्यक्षेत्राकरीता (यापुढे ज्याचा उल्लेख "उक्त क्षेत्र" असा करण्यात आलेला आहे) उक्त नियमावलीचे विनियम क्र.६.१०.१ मधील ५०.० मो. प्रमाणे लागू असलेली कमाल ऊंचीची मर्यादा शिथिल करण्यात यावी व त्याऐवजी तत्कालीन महानगर प्रदेश विकास प्राधिकरणाप्रमाणे अनुज्ञेय असलेली इमारतींची ऊंची विशेष बाब म्हणून उक्त क्षेत्राकरीता अनुज्ञेय करावी, या आशयाची विनंती शासनास केली आहे :

आणि ज्याअर्थी, राज्यातील महानगर विकास प्राधिकरणामधून नव्याने निर्माण झालेल्या उक्त नवनिर्मित नगरपंचायती/नगरपरिषदांच्या कार्यक्षेत्रात त्यांचे स्थापनेपूर्वी कार्यरत असलेल्या तत्कालीन महानगर प्रदेश विकास प्राधिकरणांनी प्रचलित विकास नियंत्रण नियमावलीनुसार ५०.० मो. पेक्षा अधिक उंचीच्या बांधकाम परवाने दिलेले असल्याने तसेच उक्त क्षेत्रामध्ये अनुलंब विकासास (Vertical Development) बाब आहे ही बाब विचारात घेता, तसेच या व्यतिरिक्त उक्त क्षेत्रामध्ये विकासाक जास्त उंचीचे इमारत बांधण्यास इच्छुक असल्याचे शासनाच्या निदेशनास आलेले आहे. त्यामुळे उक्त क्षेत्राचा संभवनीय विकास होण्याच्या दृष्टीकोनातून यानुषंगाने सदर प्रकरणी महाराष्ट्र प्रादेशिक नियोजन व नगर रचना अधिनियम १९६६ चे कलम १५४ अन्वये राज्यातील सर्व नवनिर्मित नगरपरिषदा/नगरपंचायती यांना आवश्यक त्या सूचना / निदेश देण्याची बाब शासनाच्या विचाराधीन होती;

सबब प्रस्तुत प्रकरणी सार्वजनिक हिताच्या दृष्टीकोनातून उक्त अधिनियमाचे कलम १५४ अन्वये प्राप्त अधिकारात शासन खालीलप्रमाणे निदेश देत आहे.

शासन निदेश

- अ) मंजूर एकत्रित विकास नियंत्रण व प्रोत्साहन नियमावली (UDCPR) चे विनियम क्र.६.१०.१ च्या तरतुदीमधील तक्त्यानुसार महानगर प्रदेश विकास प्राधिकरणास लागू असलेल्या उक्त विनियमातील अनुक्रमांक १ मधील इमारतीच्या ऊंचीबाबतच्या तरतुदी अग्निशमन विभागाच्या मंजूरीप्रमाणे व अग्निशमन विभागाच्या ना-हरकतोस अनुसरून, महानगर विकास प्राधिकरणामधून नव्याने निर्माण झालेल्या सर्व नवनिर्मित नियोजन प्राधिकरणे (नगरपालिका/नगरपंचायत) यांचे कार्यक्षेत्रामध्ये खालीलप्रमाणे विकास परवानग्या अनुज्ञेय करण्यास खालीलप्रमाणे शासनाची मान्यता देण्यात येते.

- 1) सदर नवनिर्मित नियोजन प्राधिकरणे, (नगरपालिका / नगरपंचायत) यांनी त्यांचे क्षेत्रामध्ये यापूर्वी महानगर प्रदेश विकास प्राधिकरणामार्फत देण्यात आलेल्या ५० मो. पेक्षा जास्त उंची असलेल्या इमारतींच्या सर्व विकास परवानग्या (Saving Clause) अंतर्गत कायम राहतील. तथापि, ५० मो. पेक्षा जास्तीच्या उंचीचे मंजूर प्रस्तावाकरिता लागतचे महानगर विकास प्राधिकरण उक्त वाढीव इमारतींच्या उंचीकरिता अग्निशमन सेवा पुरविण्यास तयार असल्याबाबत संबंधित महानगर विकास प्राधिकरणाकडून ना-हरकत प्रमाणपत्र दाखला प्राप्त करून घेणे बंधनकारक राहिल.



(Signature)

II) सदर नवनिर्मित नियोजन प्राधिकरणे, (नगरपालिका / नगरपंचायत) यांचे क्षेत्रामध्ये नवीन विकास प्रस्तावांना बांधकाम परवानगी देतवेळी ५०.० मी. अथवा त्यापेक्षा कमी इमारतीच्या उंचीकरिता प्रस्तावामध्ये सदर इमारतीस संबंधित नवनिर्मित नियोजन प्राधिकरण यांनी उक्त क्षेत्रामध्ये संबंधित नियोजन प्राधिकरणाने त्यांचे अग्निशमन विभागाच्या मंजूरीप्रमाणे व अग्निशमन विभागाच्या ना-हरकतीस अनुसरून, बांधकाम परवानगी देण्यास हरकत नाही.

III) सदर नवनिर्मित नियोजन प्राधिकरणे, (नगरपालिका / नगरपंचायत) यांचे क्षेत्रामध्ये नवीन विकास प्रस्तावांना बांधकाम परवानगी देतवेळी ५०.० मी. पेक्षा जास्त इमारतीच्या उंची करीता प्रस्ताव दाखल असल्यास अथवा प्राप्त झाल्यास अशा प्रस्तावामध्ये ५०.० मी. पेक्षा जास्त वाढीव इमारतीची उंची अनुज्ञेय करताना संबंधित नवनिर्मित नियोजन प्राधिकरण यांनी उक्त क्षेत्रामध्ये स्वगतचे महानगर विकास प्राधिकरण हे उक्त वाढीव इमारतीच्या उंचीकरिता अग्निशमन सेवा पुरविण्यास तयार असल्याबाबत संबंधित महानगर विकास प्राधिकरणाकडून ना-हरकत प्रमाणपत्र दाखला प्राप्त करून घेऊन तद्नंतर उक्त प्रस्तावास विकास परवानगी देणे बंधनकारक राहिल.

ब) सदरचे निर्देश तात्काळ लागू होतील.

महाराष्ट्राचे राज्यपाल यांचे आदेशानुसार व नावाने.



(डॉ.प्रतिभा भदोणे)
सह सचिव, महाराष्ट्र शासन

प्रत : - आवश्यक त्या कार्यवाहीसाठी

- १) आयुक्त, सर्व संबंधित महानगरपालिका. (वृहन्मुंबई महानगरपालिका वगळता)
- २) महानगर आयुक्त, सर्व महानगर प्रदेश विकास प्राधिकरणे.
- ३) सर्व विशेष नियोजन प्राधिकरणे.
- ४) व्यवस्थापकीय संचालक, सिडको, सिडको भवन, सोबोडी, बेलापूर, नवी मुंबई-४०० ६१४.
- ५) सर्व विशेष नियोजन प्राधिकरणे
- ६) मुख्य कार्यकारी अधिकारी, कोल्हापूर नागरी क्षेत्र विकास प्राधिकरण, कोल्हापूर.
- ७) सर्व नवनगर विकास प्राधिकरणे.
- ८) सहायक संचालक, नगर रचना / नगर रचनाकार, नगर रचना व मूल्यनिर्धारण विभाग, सर्व शाखा कार्यालये.
- ९) मुख्य कार्यकारी अधिकारी, सर्व जिल्हापरिषद.
- १०) अवर सचिव, नवि-११/नवि-३०, कक्ष अधिकारी, नवि-९/नवि-१२, नगर विकास विभाग, मंत्रालय, मुंबई.
- ११) मुख्याधिकारी (सर्व नगरपरिषदा / नगरपंचायती)
- १२) संचालक, महाराष्ट्र अग्निशमन सेवा, विद्यानगरी, हंस भुषा मार्ग, सांताक्रुझ पूर्व, मुंबई - ४०० ०९८.